

**Watauga County
Annual Retreat
February 26 & 27, 2026**



Board of Commissioners
Braxton Eggers, Chairman
Todd Castle, Vice-Chairman
Emily Greene
Tim Hodges
Ronnie Marsh



WATAUGA COUNTY

OFFICE OF THE
COUNTY MANAGER

Administration Building, Suite 205 – 814 West King Street – Boone, NC 28607 – (828) 265-8000
TDD 1-800-735-2962 – Voice 1-800-735-8262 – FAX (828) 264-3230

MEMORANDUM

TO: Watauga County Board of Commissioners
FROM: Deron Geouque
County Manager
SUBJECT: Annual Retreat
DATE: February 2, 2026

Fiscal Year 2025-2026 was the year of change for the County. Students finally occupied the Valle Crucis School and construction of the County's new Emergency Services Facility is well underway, with completion scheduled for the summer of 2026. Additionally, staff is hopeful FEMA authorization will be granted in the next month so the renovation of Old Cove Creek facility can begin with an estimated completion of winter 2026. The most significant operational change was the transition from Watauga Medics Inc., to a County run EMS system. Staff will continue to monitor and analyze the impact on the County's budget. A year's worth of data will allow for a true up of budget estimates to financial actuals. Fiscal Year 2026-2027 will see the completion of the County's reevaluation process. New valuations will be effective with the Fiscal Year 2027-2028 tax bills.

Following is the information packet for the 2026 Annual Budget Retreat. The retreat will provide a significant amount of information that will aid the Commissioners in establishing priorities for the Fiscal Year 2026-2027 budget. The purpose of the retreat is to consider where the county has been and where the Commissioners would like to direct the county moving forward. During the next two (2) days staff will record the priorities of the Commissioners based on feedback received at the retreat.

Commissioner input will be critical during the retreat process for staff to determine appropriate expenditures and funding levels. Information and reports on the county's current financial status will be provided for the retreat.

Staff will rely on the direction and guidance given by the Board at the retreat to prepare the upcoming Fiscal Year 2027 Budget. Should you have any questions or require additional information prior to or during the retreat please contact me.

TENTATIVE RETREAT AGENDA
WATAUGA COUNTY BOARD OF COMMISSIONERS
COMMUNITY ROOM
WATAUGA COUNTY COMMUNITY RECREATION CENTER, BOONE, NC
FEBRUARY 26 & FEBRUARY 27, 2026

TIME	TOPIC	PRESENTER	PAGE
THURSDAY, FEBRUARY 26, 2026			
12:00 PM	OPENING REMARKS AND LUNCH	MR. DERON GEOUQUE	
12:30 PM	WATAUGA TDA	MR. MATT VINCENT MR. WRIGHT TILLEY	
12:45 PM	MIDDLE FORK GREENWAY UPDATE	MS. WENDY PATOPRSTY	
1:00 PM	FY 2026 REVIEW AND DISCUSSION OF FY 2027 BUDGET A. Revenues B. Expenditures C. Debt Service Report D. Budget Calendar E. Special Appropriations	MS. MISTY WATSON	
1:30 PM	REVIEW OF CURRENT CAPITAL IMPROVEMENT PLAN (CIP) A. Current CIP Status Report B. 911/Medic/Emergency Services Facility C. Emergency Communications D. Library E. School Facilities 1. Parkway School Expansion 2. New Hardin Park School F. National Guard Armory Disposition G. Old Cove Creek School Park	MR. DERON GEOUQUE & MR. ROBERT MARSH	
2:00 PM	INFORMATION TECHNOLOGIES WEBSITE UPDATE	MR. DREW EGGERS	
2:15 PM	BREAK		
2:30 PM	TAX MATTERS A. 2027 Revaluation Update B. Minimal Tax Bill C. Tax Software	MR. TYLER RASH	
3:30 PM	PLANNING & INSPECTIONS MATTERS A. Watauga County Comprehensive Plan B. Planning and Development Ordinances Update	MR. JASON WALKER	
4:00 PM	APPHEALTHCARE	MS. JENNIFER GREENE	
4:15 PM	UNC HEALTH APPALACHIAN UPDATE	MR. NATHAN NIPPER	
4:45 PM	WATAUGA COUNTY EMERGENCY SERVICES MATTERS A. Update on Transition from Watauga Medics B. EMS Plans C. Communications Updates D. Franchise Ordinance Updates E. Community Paramedic Program	MR. WILL HOLT	
5:30 PM	COUNTY MANAGER'S SUMMARY	MR. DERON GEOUQUE	
6:00 PM	RECESS UNTIL FRIDAY, FEBRUARY 27 AT 9:00 AM		

FRIDAY, FEBRUARY 27, 2026

8:30 AM **BREAKFAST**

9:00 AM **EDC/CHAMBER FOUNDATION REPORT**

MR. DAVID JACKSON
MR. JOE FURMAN

9:30 AM **CALDWELL COMMUNITY COLLEGE & TECHNICAL INSTITUTE**

DR. MARK POARCH

10:00 AM **WATAUGA COUNTY SCHOOL BOARD**

DR. LESLIE ALEXANDER &
SCHOOL BOARD MEMBERS

A. FY 2027 Funding Needs

B. School's Capital Improvement Plan

11:30 AM **MISCELLANEOUS & COMMISSIONER MATTERS**

MR. DERON GEOUQUE

A. State Issues

B. Commissioner Matters

11:55 AM **WRAP UP, GOALS & OBJECTIVES, BOARD DIRECTIVES**

12:00 PM **ADJOURN**




Recreation Corridor


On the Ground

- Two Premier Trailheads
- Three Pocket Parks
- Two Miles of trail

Completed in 2026-27

- Boone Gorge Park—33 acres with 1 mile of greenway trail, 1+ mile of hiking trail, restroom, pavilion, parking, Art sculpture
- Angler Park—15 acres with stream & floodplain restoration , bridges, trailhead, greenway, river access.
- Blowing Rock segments A & C





- Completed segment
- In progress segment
- To be determined

MFG What's Completed:

~2.5 miles

1. Section 1 Trailhead
2. Section 4 Tweetsie, Mystery Hill, Sterling Creek Park
3. Section 4 321 Trailhead, asphalt section, Niley Cook Trailhead
4. Section 4 natural surface trail
5. Payne Branch Park
6. Tweetsie Underpass

What's Underway 2026-2027

~2.5 miles

1. Boone Gorge Park (5a) construction
2. Blowing Rock Phases (1A & C) construction
3. Blowing Rock Phase (1B) – BRP permitting
4. Angler Park – (3A phase 1 & 2) construction

MFG What's Left: Needs funding 2028-0000

~2 miles

1. Boone Connector (5b) – Jordan V Cook to Watauga Medical Center
2. Niley Cook to Payne Branch (5c)
3. Faithbridge Church / Three Rivers / Firethorn (2a&b)


MFG Funding	Amount
Spent so far	\$9,245,007
Awarded /To be spent 2026-27	\$10,894,620
Total	\$20,139,627

Sources	Amount	%
State & Federal Grants	\$10,006,535	50%
Watauga TDA	\$5,070,000	25%
Donors, Businesses, Foundations	\$5,063,092	25%
Total	\$20,139,627	100%



Primary County Revenues


	FY 20-21	FY 21-22	FY 22-23	FY 23-24	FY 24-25
Property Tax Totals:	\$ 38,677,716	\$ 39,147,623	\$ 44,989,124	\$ 45,337,052	\$ 46,640,180
Sales Tax Totals:	17,179,832	19,606,458	20,149,869	20,660,415	20,860,594
Other Revenues:	15,646,870	18,998,047	20,461,007	25,452,358	24,723,972
Total Revenues:	<u>\$ 71,504,418</u>	<u>\$ 77,752,128</u>	<u>\$ 85,600,000</u>	<u>\$ 91,449,825</u>	<u>\$ 92,224,746</u>



Budget Summary Report

General Fund	Actuals Thru 6-30 of Each Year			FY 2025-26		
	FY 22-23	FY 23-24	FY 24-25	Annual Budget	Actual at 12/31/2025	Percent to Date
Revenues						
Property Taxes	\$ 44,989,124	\$ 45,337,052	\$ 46,640,180	\$ 46,016,817	\$ 36,606,645	79.6%
Sales Taxes	20,149,869	20,660,415	20,860,594	21,190,300	5,755,967	27.2%
Other Taxes	1,388,052	1,405,394	1,279,302	1,135,000	746,540	65.8%
Intergovernmental	7,581,294	10,177,461	7,963,331	7,499,016	4,161,227	55.5%
Permits and Fees	979,468	945,385	848,928	758,400	440,336	58.1%
Sales and Services	3,474,521	3,611,678	3,544,077	2,329,206	1,328,648	57.0%
Miscellaneous	1,628,197	1,718,274	3,572,996	770,408	445,023	57.8%
Transfer from Other Funds	9,203,557	6,726,053	10,594,939	2,627,311	1,313,656	50.0%
Investment earnings	1,977,454	3,995,550	3,382,748	500,000	2,482,377	496.5%
Fund Balance	-	-	-	11,780,897	-	0.0%
Revenue Subtotal:	\$ 91,371,536	\$ 94,577,262	\$ 98,687,095	\$ 94,607,355	\$ 53,280,419	56.3%
Expenditures						
General Administration	\$ 1,355,434	\$ 2,116,676	\$ 1,925,828	\$ 3,139,154	\$ 956,503	30.5%
Finance	427,446	462,749	478,587	687,208	253,080	36.8%
Tax	1,626,917	1,686,685	1,808,511	2,494,347	1,007,158	40.4%
Legal	74,451	79,569	82,307	209,693	185,406	88.4%
Court Facilities	395	900	864	2,000	900	45.0%
Elections	391,466	549,740	572,564	626,895	628,716	100.3%
Register of Deeds	624,066	650,201	693,696	754,853	370,416	49.1%
Information Technology	1,131,336	1,110,683	1,387,631	1,643,438	916,478	55.8%
Maintenance/Buildings	5,631,958	9,151,480	6,095,225	5,487,495	2,764,183	50.4%
Sheriff/Jail	8,022,040	9,304,943	9,568,949	10,982,292	5,222,172	47.6%
Emergency Services	3,568,593	4,278,991	7,585,046	15,883,965	7,298,810	46.0%
Planning & Inspections	760,480	769,902	861,895	892,525	428,749	48.0%
Ambulance & Rescue	2,448,967	2,614,100	2,641,254	3,610,772	6,039,893	167.3%
Animal Control	208,287	211,556	240,577	250,909	125,307	49.9%
Transportation	272,107	272,481	265,221	82,215	140,636	171.1%
Economic Development	157,002	177,091	100,826	124,240	52,264	42.1%
Cooperative Extension	302,783	333,573	381,875	422,164	239,508	56.7%
Soil Conservation	164,922	278,468	336,111	186,917	177,610	95.0%
Public Health	945,555	1,000,000	1,030,000	1,080,000	540,000	50.0%
Mental Health	171,194	171,194	171,194	171,194	85,897	50.2%
Project on Aging	1,449,812	1,466,247	1,533,417	1,961,256	795,303	40.6%
Veteran's Service	147,388	154,136	165,112	178,243	102,967	57.8%
Special Appropriations	595,813	602,813	645,919	668,533	393,713	58.9%
WCS, Board of Education	16,153,825	16,451,088	21,073,962	18,018,880	8,757,513	48.6%
CCC&TI, Watauga Campus	1,047,793	1,097,913	1,129,350	1,239,350	619,675	50.0%
Library	741,660	776,045	818,990	846,475	423,237	50.0%
Parks & Recreation	1,790,072	1,804,502	2,128,141	2,402,143	1,050,400	43.7%
Transfers to Other Funds	17,472,571	17,510,030	18,416,719	\$ 20,560,199	10,280,100	50.0%
Expenditures Subtotal:	\$ 67,684,333	\$ 75,083,756	\$ 82,139,771	\$ 94,607,355	\$ 49,856,594	52.7%
Social Services Fund						
Revenues						
Federal/State Programs	\$ 3,325,960	\$ 3,359,789	\$ 3,933,891	\$ 3,975,119	\$ 1,450,681	36.5%
Miscellaneous	106,061	238,827	198,699	11,500	90,017	782.8%
Transfer from General Fund	2,524,622	2,141,293	2,947,627	2,825,133	1,473,814	52.2%
Fund Balance	-	-	-	446,122	-	0.0%
Revenues Subtotal:	\$ 5,956,643	\$ 5,739,909	\$ 7,080,217	\$ 7,257,874	\$ 3,014,512	41.5%
Expenditures						
Administration	\$ 3,882,657	\$ 4,250,289	\$ 4,608,481	\$ 5,084,492	\$ 2,218,787	43.6%
Child Support Enforcement Programs	171,465	179,707	196,357	224,323	93,484	41.7%
	1,375,046	1,246,770	1,251,367	1,949,059	471,941	24.2%
Expenditures Subtotal:	\$ 5,429,168	\$ 5,676,766	\$ 6,056,205	\$ 7,257,874	\$ 2,784,212	38.4%
Solid Waste Fund						
Revenues						
Intergovernmental	\$ 164,725	\$ 171,327	\$ 164,477	\$ 156,500	\$ 43,726	27.9%
Charges for Services	5,820,254	6,942,329	7,776,306	7,410,816	5,378,494	72.6%
Miscellaneous	398,519	444,346	335,512	82,400	300,951	365.2%
Fund Balance Appropriated	-	-	-	61,413	-	0.0%
Revenues Subtotal:	\$ 6,383,498	\$ 7,558,002	\$ 8,276,295	\$ 7,711,129	\$ 5,723,171	74.2%
Expenditures						
Solid Waste Operations	\$ 6,298,148	\$ 7,853,716	\$ 8,918,258	\$ 7,566,851	\$ 4,230,951	55.9%
Recycling Operations	125,437	127,041	122,619	144,278	59,264	41.1%
Expenditures Subtotal:	\$ 6,423,585	\$ 7,980,757	\$ 9,040,877	\$ 7,711,129	\$ 4,290,215	55.6%

Law Enforcement Budget History



Fiscal Years	Sheriff	Jail	Total for Law Enforcement	Percent of Change	Percent of County Budget
2025-26	\$ 7,546,154	\$ 3,374,620	\$ 10,920,774	6.40%	11.54%
2024-25	\$ 6,999,385	\$ 3,264,306	\$ 10,263,691	5.60%	11.15%
2023-24	\$ 6,653,788	\$ 3,065,165	\$ 9,718,953	8.31%	9.46%
2022-23	\$ 5,892,466	\$ 3,080,687	\$ 8,973,153	3.27%	10.29%
2021-22	\$ 5,771,307	\$ 2,917,517	\$ 8,688,824	14.18%	10.54%
2020-21	\$ 5,156,992	\$ 2,452,681	\$ 7,609,673	5.75%	11.24%
2019-20	\$ 4,839,670	\$ 2,356,496	\$ 7,196,166	13.56%	8.33%

Capital Funding Plan

Watauga County School System

	Current Capital	Capital Project Set Aside	General Assembly Public School Renovation Fund	Total Annual County Funding	Lottery Funds	Long-Term Needs	Total Capital Funding
2026-27	450,000	500,000	-	950,000	300,000	5,500,000	6,750,000
2027-28	450,000	500,000	-	950,000	300,000	5,500,000	6,750,000
2028-29	450,000	500,000	-	950,000	300,000	5,500,000	6,750,000
2029-30	450,000	500,000	-	950,000	300,000	5,500,000	6,750,000
2030-31	450,000	500,000	-	950,000	300,000	5,500,000	6,750,000
2031-32	450,000	500,000	-	950,000	300,000	5,500,000	6,750,000
2032-33	450,000	500,000	-	950,000	300,000	5,500,000	6,750,000
2033-34	450,000	500,000	-	950,000	300,000	5,500,000	6,750,000
2034-35	450,000	500,000	-	950,000	300,000	5,500,000	6,750,000
2035-36	450,000	500,000	-	950,000	300,000	5,500,000	6,750,000

Lottery Funds: Unallocated balance is \$496,218 as of January 28, 2026 with additional revenues expected in FY 25-26 of approximately \$148,956 thus netting approximately \$645,174. (Utilized the unallocated balance as the 2025-26 lottery distribution has not been released.) Unallocated repair and renovation lottery fund balance is \$583,029 as of January 28, 2026.

ADM Funds: Balance is \$7,999

Ten Year Funding Summary for Watauga County Schools

Budgeted

Current Expense

Fiscal Year	15/16	16/17	17/18	18/19	19/20	20/21	21/22	22/23	23/24	24/25	25/26
Current Operating	12,558,345	12,942,400	13,157,455	13,557,455	13,864,674	13,864,674	14,280,597	14,780,597	15,280,597	16,065,597	16,687,158
Annual Inc/(Dec)	359,936	384,055	215,055	400,000	307,219	-	415,923	500,000	500,000	785,000	621,561
	2.95%	3.06%	1.66%	3.04%	2.27%	0.00%	3.00%	3.50%	3.38%	5.14%	3.87%
WCS Unassigned Fund Balance	3,235,107	3,256,372	3,256,238	3,662,377	3,775,921	3,989,656	4,102,627	3,568,659	1,432,056	2,783,033	
Fund Bal Inc/(Dec)	(98,802)	21,265	(134)	406,139	113,544	213,735	112,971	(533,968)	(2,136,603)	1,350,977	

Capital Expense

Fiscal Year	15/16	16/17	17/18	18/19	19/20	20/21	21/22	22/23	23/24	24/25	25/26
Capital Projects Fund	375,000	400,000	500,000	500,000	500,000	500,000	500,000	500,000	500,000	500,000	-
Long Term Capital Needs	-	-	1,500,000	1,500,000	4,200,000	-	4,200,000	8,200,000	5,017,050	5,098,300	5,179,550
Lottery/ADM Projects	210,132	566,931	167,500	456,200	295,711	300,000	237,564	278,203	285,224	316,670	300,000
Current Capital	275,000	300,000	450,000	450,000	450,000	450,000	450,000	450,000	450,000	450,000	950,000
Subtotal of Capital:	860,132	1,266,931	2,617,500	2,906,200	5,445,711	1,250,000	5,387,564	9,428,203	6,252,274	6,364,970	6,429,550
Annual Inc/(Dec)	(435,608)	406,799	1,350,569	288,700	2,539,511	(4,195,711)	4,137,564	4,040,639	(3,175,929)	112,696	64,580
Debt Service	5,458,896	5,348,988	5,202,104	5,060,420	4,863,331	4,562,231	4,423,998	6,207,730	7,334,207	7,116,712	6,898,865
WCS Fund Balance	303,378	325,991	405,963	334,564	283,871	333,219	592,358	314,812	177,212	473,843	
Capital Bal Inc/(Dec)	(12,119)	22,613	79,972	(71,399)	(50,693)	49,348	259,139	(277,546)	(137,600)	296,631	

Total County Funding Excluding Debt Service and Lottery Projects	13,208,345	13,642,400	15,607,455	16,007,455	19,014,674	14,814,674	19,430,597	23,930,597	21,247,647	22,113,897	22,816,708
Annual Inc/(Dec)	534,936	434,055	1,965,055	400,000	3,007,219	(4,200,000)	4,615,923	4,500,000	(2,682,950)	866,250	702,811

Total Funding	18,877,373	19,558,319	20,977,059	21,524,075	24,173,716	19,676,905	24,092,159	30,416,530	28,867,078	29,547,279	30,015,573
Annual Inc/(Dec)	5,364,900	680,946	1,418,740	547,016	2,649,641	(4,496,811)	4,415,254	6,324,371	(1,549,452)	680,201	468,294

Change in Operating Fund Balance, last year versus 9 years ago: \$ (452,074) decrease
 Change in Capital Fund Balance, last year versus 9 years ago: \$ 170,465 increase

Debt Service Summary

Fiscal Year	2012 High School Debt (Refunded and Unrefunded)	VC SCHOOL	2018 Recreation Center	Total General Fund Debt Service
	LOBs	LOBS	LOBs	
2025-26 (P)	3,600,000	1,625,000	1,320,000	6,545,000
(I)	278,415	1,395,450	464,150	2,138,015
Total	3,878,415	3,020,450	1,784,150	8,683,015
2026-27 (P)	3,555,000	1,625,000	1,320,000	6,500,000
(I)	187,335	1,314,200	398,150	1,899,685
Total	3,742,335	2,939,200	1,718,150	8,399,685
2027-28 (P)	3,515,000	1,625,000	1,325,000	6,465,000
(I)	94,905	1,232,950	332,150	1,660,005
Total	3,609,905	2,857,950	1,657,150	8,125,005
2028-29 (P)		1,620,000	1,320,000	2,940,000
(I)		1,151,700	292,400	1,444,100
Total		2,771,700	1,612,400	4,384,100
2029-30 (P)		1,625,000	1,320,000	2,945,000
(I)		1,070,700	226,400	1,297,100
Total		2,695,700	1,546,400	4,242,100
2030-31 (P)		1,620,000	1,320,000	2,940,000
(I)		989,450	160,400	1,149,850
Total		2,609,450	1,480,400	4,089,850
2031-32 (P)		1,620,000	1,320,000	2,940,000
(I)		908,450	94,400	1,002,850
Total		2,528,450	1,414,400	3,942,850
2032-33 (P)		1,620,000	1,320,000	2,940,000
(I)		827,450	48,200	875,650
Total		2,447,450	1,368,200	3,815,650
2033-34 (P)		1,625,000		1,625,000
(I)		746,450		746,450
Total		2,371,450		2,371,450
2034-35 (P)		1,625,000		1,625,000
(I)		665,200		665,200
Total		2,290,200		2,290,200
2035-36 (P)		1,625,000		1,625,000
(I)		583,950		583,950
Total		2,208,950		2,208,950
2036-37 (P)		1,625,000		1,625,000
(I)		502,700		502,700
Total		2,127,700		2,127,700
2037-38 (P)		1,625,000		1,625,000
(I)		421,450		421,450
Total		2,046,450		2,046,450
2038-39 (P)		1,620,000		1,620,000
(I)		340,200		340,200
Total		1,960,200		1,960,200
2039-40 (P)		1,620,000		1,620,000
(I)		255,150		255,150
Total		1,875,150		1,875,150
2040-41 (P)		1,620,000		1,620,000
(I)		170,100		170,100
Total		1,790,100		1,790,100
2041-42 (P)		1,620,000		1,620,000
(I)		85,050		85,050
Total		1,705,050		1,705,050
Principal	\$10,670,000	\$27,585,000	\$10,565,000	\$48,820,000
Interest	\$560,655	\$12,660,600	\$2,016,250	\$15,237,505

Outstanding Debt at June 30

	<u>Total</u>	<u>Decrease</u>
2024-25	48,820,000	(6,570,000)
2025-26	42,275,000	(6,545,000)
2026-27	35,775,000	(6,500,000)
2027-28	29,310,000	(6,465,000)
2028-29	26,370,000	(2,940,000)
2029-30	23,425,000	(2,945,000)
2030-31	20,485,000	(2,940,000)
2031-32	17,545,000	(2,940,000)
2032-33	14,605,000	(2,940,000)
2033-34	12,980,000	(1,625,000)
2034-35	11,355,000	(1,625,000)
2035-36	9,730,000	(1,625,000)
2036-37	8,105,000	(1,625,000)
2037-38	6,480,000	(1,625,000)
2038-39	4,860,000	(1,620,000)
2039-40	3,240,000	(1,620,000)
2040-41	1,620,000	(1,620,000)
2041-42	-	(1,620,000)



Fiscal Year 2026-27 BUDGET SCHEDULE

January 2026

Capital Improvement Plan packets to departments.

January 30, 2026

Capital Improvement Program requests due back.

March 2, 2026

Requests for funding sent to outside agencies.

February 26 and 27, 2026

Board of Commissioners Retreat with staff. There are typically two sessions with some presentations.

March 2, 2026

Department head staff meeting - budget information packets emailed out. Worksheets and all supporting documents are due by email to Misty by March 13. Early submission is encouraged.

March and April 2026

Individual agency and department meetings will be during March and April with budget staff.

May 5, 2026

Staff submits recommended budget to Board of Commissioners for review prior to work sessions.

May 7 and 8, 2026


Budget work sessions held with staff and Board of Commissioners. There are two sessions planned.

May 19, 2026

Public hearing held on County Manager's proposed budget.

June 2, 2026

Budget adoption.



SPECIAL APPROPRIATIONS

	2020-21	2021-22	2022-23	2023-24	2024-25	2025-26
APPALACHIAN THEATER OF THE HC	\$ 10,000	\$ 10,000	\$ 10,000	\$ 10,000	\$ 10,000	\$ 10,000
BLOWING ROCK PARKS & REC	12,000	12,000	12,000	12,000	12,000	12,000
BLUE RIDGE MEDIATION/DRUG COURT	25,151	26,115	26,389	25,858	25,000	25,000
BOONE AREA CHAMBER OF COMMERCE	-	-	-	-	30,000	60,000
CHILDREN'S COUNCIL	50,000	50,000	50,000	50,000	30,000	-
CHILDREN'S PLAYHOUSE	2,500	6,131	7,000	7,000	7,000	7,000
COMMUNITY CARE CLINIC	25,000	25,000	25,000	25,000	25,000	25,000
FOSCOE GRANDFATHER COMM. CENTER	5,000	5,000	5,000	5,000	5,000	5,000
GREEN VALLEY COMMUNITY PARK	8,000	8,000	8,000	8,000	8,000	8,000
HOSPITALITY HOUSE - WECAN	2,500	3,000	3,000	3,000	3,000	3,000
HOSPITALITY HOUSE	10,000	10,000	10,000	10,000	10,000	-
HUNGER COALITION	9,315	10,000	10,000	10,000	10,000	10,000
MOUNTAIN ALLIANCE	10,000	10,000	10,000	10,000	10,000	10,000
OASIS	10,000	10,000	10,000	10,000	10,000	10,000
SOUTHERN APPALACHIAN HISTORICAL ASSN	22,000	22,000	22,000	22,000	22,000	22,000
VALLE CRUCIS COMMUNITY PARK	15,000	15,000	15,000	15,000	15,000	15,000
WAMY	2,500	5,000	5,000	5,000	5,000	5,000
WAMY RENTAL HOUSING PROGRAM	-	-	-	-	86,250	-
WATAUGA COUNTY ARTS COUNCIL	8,800	10,000	10,000	10,000	10,000	10,000
WATAUGA HUMANE SOCIETY	86,822	88,124	94,645	101,176	104,616	107,754
WATAUGA OPPORTUNITIES	33,000	33,000	33,000	33,000	33,000	33,000
WATAUGA HERITAGE MUSEUM	-	-	-	-	-	50,000
HOSPICE CARE	-	-	50,000	50,000	50,000	50,000
TOTALS: \$	347,588	\$ 358,370	\$ 416,034	\$ 422,034	\$ 520,866	\$ 477,754

CAPITAL PROJECTS SUMMARY

Project Description	6/30/2025 Balance	2025-26 Budget	Budget Amendments		6/30/2026 Balance
			In	Out	
Caldwell Community College	\$ 329,424	\$ 50,000	\$ -	\$ -	\$ 379,424
Information Technology Needs	504,169	-	-	-	504,169
East Annex Renovations	377,553	-	-	-	377,553
Eastern Community Center	60,509	-	-	-	60,509
Emergency Communications	4,935,967	1,800,000	-	(2,500,000)	4,235,967
Facilities Maintenance	586,632	500,000	-	(127,311)	959,321
Future County Parking Deck	3,143,773	-	-	-	3,143,773
Future County Buildings	5,775,369	1,200,000	-	-	6,975,369
EDC	378,341	50,000	-	-	428,341
LEC Future Expansion	266,805	100,000	-	-	366,805
Future Processing Plant	542,659	-	-	-	542,659
Potential Flood Mitigation	71,340	22,500	-	-	93,840
Library Expansion	84,602	50,000	-	-	134,602
Workforce Housing	50,000	-	-	-	50,000
Recreation-Facilities/Maintenance	1,903,082	100,000	-	-	2,003,082
Watauga Co. Schools-Long Term Needs	12,672,586	5,179,550	-	-	17,852,136
Watauga Co. Schools-CIP	-	-	-	-	-
Totals:	\$ 31,682,812	\$ 9,052,050	\$ -	\$ (2,627,311)	\$ 38,107,551

Project Description	Actual Additions				
	FY 2020-21	FY 2021-22	FY 2022-23	FY 2023-24	FY 2024-25
Caldwell Community College	\$ 50,000	\$ 50,000	\$ 50,000	\$ 50,000	\$ 50,000
EDC	100,000	50,000	50,000	50,000	40,000
Processing Plant	-	500,000	-	-	-
East Annex Renovations	-	-	-	-	-
Emergency Communications	1,000,000	550,000	1,800,071	1,300,000	10,775,583
Facilities Maintenance	1,500,000	785,783	500,000	500,000	500,000
LEC Future Expansion	-	-	100,000	100,000	100,000
Future County Buildings	2,900,000	2,424,583	3,700,000	9,540,715	1,442,037
Potential Flood Mitigation	-	-	22,500	22,500	22,500
Future County Parking Deck	-	5,400,000	2,500,000	-	-
Library Expansion	-	-	-	50,000	30,336
Recreation-Facilities/Maintenance	50,000	750,000	50,000	50,000	50,000
Workforce housing	-	-	-	50,000	50,000
Watauga Co. Schools-Long Term Needs	574,808	3,000,000	5,500,000	5,017,050	5,098,300
Future Valle Crucis School	-	7,545,000	2,700,000	-	-
Watauga Co. Schools-CIP	-	580,507	500,000	779,765	500,000
Totals:	\$ 6,174,808	\$ 21,635,873	\$ 17,472,571	\$ 17,510,030	\$ 18,658,756


Deron:

For the upcoming retreat, I would like to discuss the current status of our website. Specifically, I would like to talk about the new GIS site as well as the need to contract with a 3rd party vendor to design and host our primary website.

For a little background detail:

We've been taking a deep look into our websites over the last few months. Our first objective was to replace the GIS site, and this project is complete pending approval. You can view the new system here:

<https://gissvr.watgov.org/maps/>



The tax search, deeds search, and parks and recreation websites are specific to the vendors used in those areas, so they are a little less flexible than the main site and the GIS site. That said, the GIS site will likely largely replace a lot of the current tax searches with the new design. Also, if we were to change tax software in the future, that would replace the current tax search pages.

To investigate replacing the primary website, we recently conducted a survey about our website. We only had six responses, but the responses were helpful. The main request was to make the top menus not disappear quickly if the mouse moves slightly off of them. A short-term solution we have already completed was to make the menus pause for a couple seconds before disappearing.

The other item we received a couple requests on is to make the site more mobile friendly. These requests along with a more long-term solution for the menus will be best met with a site overhaul through a 3rd party vendor.

We have reached out to multiple vendors for a complete website replacement for the primary website. Two that we liked, which also seem popular with other counties in North Carolina, were Civic Plus and Revize. Currently, we feel like Revize would give us everything Civic Plus does at a lower cost.

Pricing for Revize when quoted was: \$17,000 total for the first year (\$2,300 recurring)


Pricing for Civic Plus when quoted was: \$42,799 for the first year (\$15,718 recurring)

Examples of North Carolina Counties that use Revize:


- Cleveland County, NC <https://www.clevelandcounty.com/main/>
- Martin County, NC <https://www.martincountyncgov.com/>
- Stokes County, NC <https://www.co.stokes.nc.us/>
- Franklin County, NC <https://www.franklincountync.gov/>
- Rutherford County, NC <https://www.rutherfordcountync.gov/>
- Surry County, NC <https://www.co.surry.nc.us/>
- Lee County, NC <https://leecountync.gov/>
- Edgecombe County, NC <https://www.edgecombecountync.gov/>
- Hertford County, NC <https://www.hertfordcountync.gov/>
- Polk County, NC <https://www.polknc.gov/>
- Avery County, NC <https://www.averycountync.gov/>

We have also looked at prior feedback from other counties that are using Revize and all of the feedback was positive.

This is an example of a Revize website from Edgecombe County, NC:



Here is an example from CivicPlus:



Thank you for your consideration of this request to proceed to work with a vendor on a website redesign. Please note that from start to finish, this process will be about 4-6 months.

2027 REAPPRAISAL

Summary Presentation to the Board of Commissioners

Presented by:
Joshua Kleene, Vincent Valuations LLC



February 26th, 2026

Reappraisal Process



Data Collection/Field Work



Neighborhood Delineation



Sales Analysis



Land Valuation



Building Valuation



Value Review



Appeals



2027 Reappraisal

Watauga County



How Do We Know It's Right?

Mass appraisal techniques include statistical tools used to help measure the accuracy of an appraisal

We use a sales ratio as a common measure of how closely assessed values match up with current sales prices to generate a value model

The basic sales ratio formula is:

Assessed Value ÷ Sale Price

To get an accurate sales ratio, you need to look at several normal, open-market sales. Relying on just one sale, or on sales that aren't typical (like foreclosures, auctions, short sales, or bundled properties), can give a distorted or misleading result.



Different Areas, Different Changes

In broad terms, we have seen evidence that market values around the county have changed in different ways since the 2022 reappraisal

Most areas of the county have seen a noticeable increase in value during this reappraisal cycle, while other areas have remained stagnant

Some areas or types of improvements have seen significant change in market values and others have remained steadier by comparison

The following are individual examples of these changes across the county. These sales do not necessarily reflect market changes for the assessed values of all properties in that area



F01- Foscoe Fire Service District

Year Built: 1979

2026 Assessed Value:
\$409,500

Sale Date: 01/15/2026

Sale Price: \$750,000

Market Increase of 83%



F01- Foscoe Fire Service District

Year Built: 2000

2026 Assessed Value:
\$430,500

Sale Date: 01/13/2026

Sale Price: \$533,000

Market Increase of 24%



F02- Boone Fire Service District

Year Built: 2006

2026 Assessed Value:
\$604,800

Sale Date: 01/21/2026

Sale Price: \$850,000

Market Increase of 41%



F02- Boone Fire Service District

Year Built: 1984

2026 Assessed Value:
\$248,200

Sale Date: 01/20/2026

Sale Price: \$360,000

Market Increase of 45%



F02- Boone Fire Service District

Year Built: 1973

2026 Assessed Value:
\$257,700

Sale Date: 01/09/2026

Sale Price: \$520,000

Market Increase of 102%



C03- Blowing Rock Fire Service District

Year Built: 2003

2026 Assessed Value:
\$809,900

Sale Date: 01/09/2026

Sale Price: \$1,519,000
Market Increase of 88%



C03- Blowing Rock Fire Service District

Year Built: 1965

2026 Assessed Value:
\$728,100

Sale Date: 12/16/2025

Sale Price: \$1,350,000
Market Increase of 85%



F10- Deep Gap Fire Service District

Year Built: 1992

2026 Assessed Value:
\$589,500

Sale Date: 01/14/2026

Sale Price: \$796,000

Market Increase of 35%



F10- Deep Gap Fire Service District

Year Built: 1975

2026 Assessed Value:
\$321,300

Sale Date: 12/18/2025

Sale Price: \$525,000

Market Increase of 63%



F11- Todd Fire Service District

Year Built: 2001

2026 Assessed Value:
\$350,200

Sale Date: 10/02/2025

Sale Price: \$980,000

Market Increase of 180%



F11- Todd Fire Service District

Year Built: 2004

2026 Assessed Value:
\$328,100

Sale Date: 09/15/2025

Sale Price: \$485,000

Market Increase of 48%



F11- Todd Fire Service District

Year Built: 2006

2026 Assessed Value:
\$580,700

Sale Date: 12/29/2025

Sale Price: \$920,000

Market Increase of 58%



C05- Beech Mountain Fire Service District

Year Built: 2000

2026 Assessed Value:
\$614,200

Sale Date: 12/30/2025

Sale Price: \$810,000

Market Increase of 32%



C05- Beech Mountain Fire Service District

Year Built: 1974

2026 Assessed Value:
\$399,300

Sale Date: 12/04/2025

Sale Price: \$555,000

Market Increase of 39%



Next Steps

- ▶ Spring 2026 begin desktop review
- ▶ Summer/Fall 2026 prepare, finalize and present Schedule of Values
- ▶ January 2027 run final checks
- ▶ February 2027 mail new value notices
- ▶ Spring 2027 hear taxpayer appeals
- ▶ Spring/Summer 2027 Board of Equalization and Review Hearings



Questions?





Watauga County Tax Office

Tyler Rash, Tax Administrator

Joshua Kleene, Vincent Valuations LLC

842 W King St. Ste. 21 Courthouse, Boone, NC 28607

828-265-8021

TAX ADMINISTRATION UPDATES



MINIMAL TAXES § 105-321

- ▶ (f) Minimal Taxes. - Notwithstanding the provisions of G.S. 105-380, the governing body of a taxing unit that collects its own taxes may, by resolution, direct its assessor and tax collector not to collect minimal taxes charged on the tax records and receipts.
- ▶ Minimal taxes are the combined taxes and fees of the taxing unit and any other units for which it collects taxes, due on a tax receipt prepared pursuant to G.S. 105-320 in a total original principal amount that does not exceed an amount, up to five dollars (\$5.00), set by the governing body. The amount set by the governing body should be the estimated cost to the taxing unit of billing the taxpayer for the amounts due on a tax receipt or tax notice.
- ▶ A resolution adopted pursuant to this subsection must be adopted on or before June 15 preceding the first taxable year to which it applies and remains in effect until amended or repealed by resolution of the taxing unit. A resolution adopted pursuant to this subsection shall not apply to taxes on registered motor vehicles.

SOFTWARE CONVERSION

▶ **BI-Tek LLC**

- ▶ Currently used in 43 counties
 - ▶ Including surrounding counties – Alleghany, Ashe, Avery, Caldwell
- ▶ Has completed conversions from Tyler Technologies in Jones, Moore, and Onslow Counties
- ▶ Integrates with other systems: Data can be imported from various systems use in other departments (Planning & Inspections, Finance)

ADDITIONAL FEATURES

- ▶ GIS Mapping Integration: This tool uses county GIS data in the form of shape files and aerial photos which are copied to the tax office server in order to visually display Tax Office data.
- ▶ Workflow: Workflow is highly configurable and can be used to automate the flow of work between individuals and departments.
- ▶ Query Builder: Query Builder is used to easily search and extract a variety of information from the Tax Office database.
- ▶ Online Business and Individual Personal Property Listing

IMPLEMENTATION TIMELINE

- ▶ Business and Individual Personal Property – End of 2026
- ▶ Collections – Spring 2027
- ▶ CAMA – End of 2027/after reval

COST COMPARISON


BI-Tek LLC

Item	One-Time Costs	Ongoing Annual Support
CAMA software license	\$178,750	\$35,750
ITSMobile (Tablet) software license	\$55,000	\$11,000
Billing software license	\$68,750	\$13,750
Collections software license	\$151,250	\$30,250
Data Conversion / Schedule of Values Matching	\$100,000	
Training/Implementation: 15 Days on site	Included	
Total Quote for BI-Tek Tax Office Software	\$553,750	\$90,750
Hosted Public Access (Public-facing applications for CAMA and Tax Collections information.)		\$2,400
Total Quote with Hosted Public Access	\$553,750	\$93,150
Optional Hosted (Cloud) Database Server (production operating environment)		\$33,395
Optional Hosted (Cloud) Application Server Option (production operating environment)		\$18,122
Total Quote including Hosted (Cloud) Server Production Environment		\$144,667

Tyler Technologies

Item	Annual Cost
IASWorld/CAMA	\$91,245
Munis/Tax Billing	\$36,336
Total	\$127,581

2025 Watauga County Comprehensive Plan



Acknowledgments

Watauga County Comprehensive Plan

Watauga County Board of Commissioners

Braxton Eggers, Chairman
Todd Castle, Vice Chairman
Emily Greene
Tim Hodges
Ronnie Marsh

Watauga County Manager

Deron Geouque

Watauga County Planning and Inspections Department

Jason Walker
Jennifer Storie

Watauga County Planning Board

Joel Farthing
Savva Kostis
Richard Mattar
Seth Norris
Matt Vincent
Justin Warren
Neal Winebarger
Neil Hartley*
Diane Tilson*
Marsha Walpole*
*past members

Plan Developed with Assistance from

High Country Council of Governments

Select Photographs By

High Country Council of Governments
Explore Boone



Table of Contents


Preface	page 1
Section 1: Demographics	page 10
Section 2: Physiographic Features	page 30
Section 3: Transportation	page 45
Section 4: Economic Development	page 53
Section 5: Water and Sewer	page 60
Section 6: Key Community Services	page 63
Section 7: Affordable [Workforce] Housing	page 71
Section 8: Preservation of Community	page 74
Section 9: Parks and Recreation	page 79
Section 10: Managing Change in Watauga County	page 85
Section 11: Implementation	page 98

Tables

- Table 1 – Watauga County Actual & OSBM Population Projections 1950-2050
- Table 2 – Appalachian State University Actual & Projected Enrollment 1970-2050
- Table 3 – Watauga County Municipality Populations and Population Changes 2000-2020
- Table 4 – Population Changes in County & Municipalities 2000-2010 & 2010-2020
- Table 5 – Actual County and Township Populations 1920-2020
- Table 6 – Average Decennial Population Change -1920 - 2020
- Table 7 – Median Age of Population
- Table 8 – Percent of Population 65 and Older
- Table 9 – County Population Growth and Migration 2010-2020
- Table 10 – Change in Number of Housing Units 2010-2020 - Ranked
- Table 11 – Housing Occupancy 2023
- Table 12 – Income Characteristics 1970 - 2023
- Table 13 – Employment/Wages by Industry with State for Comparison (Q2, 2024)
- Table 14 – Watauga County Tourism Revenue 2000-2023
- Table 15 – Twenty-five Largest Employers – Watauga County (2nd Quarter 2024)
- Table 16 – Watauga County Employment Characteristics 2000-2024
- Table 17 – Current Industry Structure (2nd Quarter 2024)
- Table 18 – Average Annual Unemployment Rate - Counties
- Table 19 – Average Annual Unemployment Rate - Comparison
- Table 20 – Workers Commuting to Work in Watauga County, Living in:
- Table 21 – Workers Living in Watauga County Commuting to Work in:
- Table 22 – List of County Schools with Enrollment (Spring 2025)
- Table 23 – Watauga County Recreation Facilities
- Table 24 – Other Public Recreation Facilities

Illustrations

- Illustration 1 – Watauga County Hydrology & Flood Hazard
- Illustration 2 – Topographic Characteristics
- Illustration 3 – Slope Characteristics
- Illustration 4 – Elevation Diversity
- Illustration 5 – Hill Shade View
- Illustration 6 – Protected Ridges
- Illustration 7 – Highly Erodible Land Based on Soil Characteristics
- Illustration 8 – Watauga County Significant Natural Areas
- Illustration 9 – Watauga County Drinking Water - Watersheds
- Illustration 10 – Public Lands in Watauga County
- Illustration 11 – Land Use Classification Watauga County
- Illustration 12 – Watauga County Road and Highway Network
- Illustration 13 – Proposed Widening Projects
- Illustration 14 – Daniel Boone Parkway Preliminary Alignment
- Illustration 15 – Economic Gateways
- Illustration 16 – Water and Sewer
- Illustration 17 – Schools in Watauga County
- Illustration 18 – Watauga Fire Districts and Stations
- Illustration 19 – National Historic Sites and Districts
- Illustration 20 – Parks and Recreation in Watauga County
- Illustration 21 – Summary of Natural Limitations
- Illustration 22 – Municipal Planning Jurisdictions
- Illustration 23 – Community Planning Districts
- Illustration 24 – Managing Growth in Watauga County





Preface

PREFACE

Human beings, the land on which we live, and our environment are undeniably interrelated. Sustaining an equitable balance in these relational elements is important for present and future generations.

Our individual and collective decisions and actions affect the quality of human life and the quality of our natural environment. By understanding these principles, we establish a common basis for working toward becoming a “sustainable community.”

This document is a reflection of the Watauga community’s concern for such principles. At the same time, this plan focuses on new issues that have emerged, such as “sustainability” and “green” issues, which are of great importance to the future of the Watauga community.

Sustainability Principles

This emphasis on sustainability and the efficient use of land and other natural resources is particularly relevant given the recent decline in our national and local economies. It is essential that the community acts to protect its vital economic and natural resources. Further, strategic community investments in capital improvements must be carefully weighed against the collective benefits and economic gain derived from such investments. This re-emphasis on sustainability points to the greater need to plan and prioritize to achieve strategic community goals and meet essential needs.



- ▼ A natural resource will only be available for a finite time if the depletion rate exceeds the replacement rate. Thus, unconstrained use of resources affects future generations.
- ▼ Human activity produces harmful substances, which must be mediated to maintain balance in the natural systems.
- ▼ Humans and other living creatures make up ecosystems, which are interdependent. Ecosystems are most stable when they include a diversity of species. Overuse and pollution of the natural environment has implications for maintaining the earth’s biodiversity.
- ▼ Human needs have physical, economic, environmental, cultural, social and spiritual dimensions. They can be met equitably without compromising the physical environment. To achieve social stability and the cooperation required for large-scale changes related to the first three principles, we must work together to achieve greater fairness.

BEGINNING THE PLANNING PROCESS

The Watauga County Comprehensive Plan is an update of the “Citizens’ Plan for Watauga” adopted in 2008. During that process, the Watauga County Board of Commissioners named residents from each commission’s district and the County Planning Board to the Plan Oversight Group (POG).

The 2025 update utilized the sitting Watauga County Planning Board and the Watauga County Planning and Inspections Office. Meetings with area stakeholders were held as well as a stakeholder meeting to obtain information for the plan. A survey to gain citizen input was distributed from September 2024 through January 2025.

In addition to the stakeholder and citizen input, this update includes all current demographic and economic data, updated maps, and reevaluation of all recommendations from the old plan.

During the 2025 update of the plan, the Community has the same issues and concerns as in 2008, with a few shifts in priority.

Prominent Community Issues/Concerns in Watauga:

2008

1. Traffic congestion
2. Water availability
3. Protection of natural resources
4. Farmland/large tract preservation
5. Land use divisions that are appropriate
6. Preservation of unique community identities and mountain heritage
7. Economic development/employment/affordable housing
8. Emergency services keeping pace with growth
9. Educational opportunities
10. Widespread recreational opportunities

2025

1. Traffic congestion
2. Affordable Housing
3. Emergency services keeping pace with growth
4. Water availability
5. Economic development/employment
6. Widespread recreational opportunities
7. Protection of natural resources
8. Farmland/large tract preservation
9. Preservation of unique community identities and mountain heritage
10. Educational Opportunities

WATAUGA COUNTY


Watauga County is located in northwest North Carolina. Ashe, Avery, Caldwell and Wilkes counties in North Carolina and Johnson County in Tennessee bound the County. The County has a complex geology and falls within the Unaka Mountain Range and Blue Ridge Mountain Range. The County is the headwaters for four major river basins: Yadkin, New, Watauga and Catawba; all four flow in different directions.


The human history of the area of Watauga County starts with the Native Americans, probably several thousand years B.C. In later eras, the Cherokee, Catawba and perhaps Shawnee hunted, camped and had agricultural villages here. The name Watauga is probably of Cherokee origin.

A few people of European descent were here by 1730. Later, would-be settlers had no easy access from the great wagon road of the Shenandoah Valley. As early as 1760, Daniel Boone was one of the early “long hunters,” who came here from the Yadkin River in the Piedmont.

In many ways, he was the original “tourist,” visiting regularly, staying for a while, and then passing on to what became the states of Tennessee and Kentucky. Watauga County was created in 1849, with most of its territory derived from the large County of Wilkes. The first U.S. census for the County was in 1850, which shows the population to be small in number and dedicated largely to subsistence agriculture. Most of the County’s public records were destroyed by General George Stoneman’s raid through the County near the end of the Civil War in 1865 and again with the burning of the courthouse in 1872.

Today Watauga County is a home to Appalachian State University; it has a thriving tourist economy; and is well known for its expansive outdoor recreation opportunities.





Section 1

Demographics




POPULATION TRENDS

Watauga County has experienced growth during every decade since 1960. Between 1970 and 2020, the population more than doubled from 23,404 to 54,086 according to the U.S. Census Bureau. The increase from 2010 to 2020 was 5.9%, equaling 0.8 people moving into Watauga County every day throughout the ten-year period. The N.C. Office of State Budget and Management projects a population increase of more than 17,318 new residents by 2050.

Watauga County remains an increasingly popular location within North Carolina for first and second home buyers. The projections by the N.C. Office of State Budget and Management do not include the people who are second homeowners. Although these people are not counted in the census as residents of Watauga County, they will nonetheless, directly affect the County's capacity to manage growth and deliver essential services.

The projections for future population (Table 1) do not include planned increases in Appalachian State University's student population.

Table 1
Watauga County Population
1950-2050



US Census and NC OSBM






Population Trends – Appalachian State

Appalachian State University (App State) is a major contributor to Watauga County in many ways. Student enrollment at App State is a significant contributor to overall County population. In 1970, student enrollment was 6,665. In 2020 the on-campus student enrollment was up to 18,510 (an increase of over 177%). In 2023, App State expanded and opened a campus in Hickory, North Carolina in nearby Catawba County. All data presented in this plan with regards to App State refers only to the Main Campus in Boone, North Carolina.

Projections for future growth at App State (Table 2) are more modest. The enrollment for Fall of 2004 was 18,601. Projected enrollment* from 2024 to 2030 is expected to increase by only 1.2%, with an estimate of 19,500 by 2050.

Table 2
Appalachian State University
Actual and Projected* Boone Campus Enrollment



Source: Appalachian State University - Department of Institutional Research, Assessment, and Planning



Population Trends - Watauga Municipalities

Watauga County has four municipalities: Beech Mountain, Blowing Rock, Boone and Seven Devils. Of these four towns, Boone is the only municipality that lies totally within the Watauga County boundary. Beech Mountain, Blowing Rock and Seven Devils all straddle a county line. Both Beech Mountain and Seven Devils lay partially within Avery County. Blowing Rock lies partially within Caldwell County.

Table 3 provides the populations of each town and their growth from 2000-2020. Also listed in both Table 3 and Table 4 is the portion of each town's population (in adjoining counties) that lies outside of Watauga County.

- ▼ Boone is the largest of the municipalities by population. It is the county seat of Watauga County. Appalachian State University is located within its boundaries, which adds significantly to Boone's population.
- ▼ Blowing Rock is the second largest municipality, with a population of 1,376 in 2020. During the summer, Blowing Rock's population swells to over 7,300.
- ▼ Beech Mountain is the next largest with 675 Watauga County residents in 2020. Its population increased 128% from 2010 to 2020.
- ▼ Seven Devils is the smallest town in Watauga County, with 313 Watauga County residents in 2020, an impressive increase of 90.9% from 2010. Second only to Beech Mountain's increase of 128% during the same period.


Table 3
Watauga County Municipality Populations and Population Changes 2000-2020

	POPULATION 2000	POPULATION 2010	PERCENT CHANGE 2000-2010	POPULATION 2020	PERCENT CHANGE 2010-2020
WATAUGA COUNTY					
BLOWING ROCK, TOWN (PART)	1,365	1,192	-12.7%	1,376	15.4%
BOONE, TOWN	13,472	17,122	27.1%	19,092	11.5%
BEECH MOUNTAIN, TOWN (PART)	297	296	-0.3%	675	128.0%
SEVEN DEVILS, TOWN (PART)	112	164	46.4%	313	90.9%
AVERY COUNTY					
BEECH MOUNTAIN, TOWN (PART)	13	24	84.6%	62	158.3%
SEVEN DEVILS, TOWN (PART)	17	28	64.7%	38	35.7%
CALDWELL COUNTY					
BLOWING ROCK, TOWN (PART)	35	25	-28.6%	44	76.0%

US CENSUS 2000, 2010, 2020



Table 4
Population Change
County and Municipalities



US Census 2000, 2020, 2020

Population Trends - Watauga Townships

Watauga County is divided into 15 Townships. Table 5 depicts the actual decennial population in each of Watauga County’s Townships for the past 100 years (1920 through 2020). A steady growth in the Watauga County population is reflected in each township, some healthier than others. Boone Township and New River show tremendous growth over the past decade, while one township, North Fork, has actually declined.

The two townships with the greatest population increase in the past 50 years are Blue Ridge and New River; these two townships had the largest number of new residents moving into the County. As expected, the highest growth rate in the County during the 100-year period occurred in the New River Township which averaged over 65%, Blue Ridge Township came in a close second, with an average of over 48%.

Table 6 summarizes the average percentage change in population of each township from 1970 to 2020. The Townships of New River and Brushy Fork were not established until the 1940s, first showing up in the 1950 US census. New River Township was split from Boone Township, and parts of Boone, Cove Creek, Laurel Creek, Meat Camp, and Watauga Townships were carved out to make up what is now Brushy Fork Township.

As of 2020, slightly more than 44% of the total population of the County resides in the Boone and New River Townships. This is not surprising due to the proximity of these townships to Appalachian State University, with more than 18,500 students and nearly 4,000 employees.




Table 5 Actual County and Township Populations 1920-2020

	1920	1930	1940	1950	1960	1970	1980	1990	2000	2010	2020
Bald Mountain	421	432	436	380	361	363	280	334	485	619	687
Beaverdam	1,161	1,156	1,434	1,279	944	847	1,030	1,204	1,283	1,351	1,332
Blowing Rock	734	1,001	1,167	1,042	982	1,321	2,295	2,340	2,858	2,715	2,913
Blue Ridge	738	713	818	665	644	898	1,613	2,125	3,628	4,211	4,357
Boone	2,033	3,332	4,504	2,973	3,686	8,754	10,191	12,915	8,690	9,379	10,697
Brushy Fork				1,272	1,642	2,345	2,656	3,368	3,205	4,935	4,679
Cove Creek	1,483	1,766	1,908	1,921	1,626	1,780	2,141	2,233	2,935	3,118	2,951
Elk	493	443	608	428	366	274	260	281	462	638	749
Laurel Creek	1,124	1,155	1,373	1,212	1,036	1,096	1,332	1,404	1,756	1,947	2,090
Meat Camp	1,133	1,236	1,518	1,468	1,257	1,275	1,805	2,288	2,673	3,191	3,139
New River				1,718	1,952	1,499	3,785	3,367	8,848	11,838	13,137
North Fork	347	339	378	350	261	231	207	223	222	229	202
Shawneehaw	667	630	751	655	450	390	544	574	675	765	835
Stony Fork	1,127	1,243	1,436	1,388	1,199	1,192	1,476	1,876	2,061	2,585	2,420
Watauga Township	2,016	1,719	1,783	1,591	1,123	1,139	2,051	2,420	2,914	3,558	3,898
Watauga County	13,477	15,165	18,114	18,342	17,529	23,404	31,666	36,952	42,695	51,079	54,086

US Census

Table 6 Average Decennial Population Change 1970-2020



US Census



THE CHANGING FACE OF DEMOGRAPHICS IN WATAUGA COUNTY

- ▼ The population of the nation and our state is getting older (Table 7). This is revealed in the census data for 2020 and in the estimates produced by the NC Office of State and Budget Management (NC OSBM). The median age in the United States increased from 37.2 to 38.8 from 2010 to 2020.
- ▼ The average age in North Carolina increased from 37.4 to 39.4. This trend toward an older population is also revealed in the number of people with an age of 65 years or older (Table 8).
- ▼ Watauga County's median age statistic is greatly influenced by the student population at Appalachian State University. In general, the large number of students in the 18- to 24-year-old cohorts skews the data toward a substantially lower median age.
- ▼ The percentage of persons in Watauga County over age 65 is currently less than the state's average (Table 8).
- ▼ The N.C. Office of State Budget and Management projects that the percentage of persons in Watauga County age 65 will continue to increase in 2030 but is expected to decrease by 2040 and 2050.

Watauga County experienced a growth rate of 6.1% from 2010 to 2020. The natural growth during the period declined by 129 (Table 9), indicating a death rate that exceeded the birth rate during the period. This means the growth in Watauga County resulted totally from in-migration. The neighboring mountain counties experienced population declines during this period, with deaths exceeding births and loss of population through out-migration. Ashe County had the least amount of population and out-migration decline (-1.7%), with Avery County experiencing the most with -10.5%. The neighboring foothill counties of Caldwell and Wilkes experienced population declines as well with -2.3% and -4.5% out-migration rates, respectively. In comparison, North Carolina's average in-migration growth rate was 9.3%.


Table 9
County Population Growth and Migration 2010-2020

	2010 POPULATION	2020 POPULATION	POPULATION GROWTH*	PERCENT GROWTH	BIRTHS	DEATHS	NATURAL GROWTH**	NET MIGRATION***	PERCENT NET MIGRATION
WATAUGA	51,079	54,086	3,007	5.9%	293	422	(129)	3,136	6.1%
ASHE	27,281	26,577	(704)	-2.6%	200	427	(227)	(477)	-1.7%
AVERY	19,979	17,806	(2,173)	-10.9%	139	212	(73)	(2,100)	-10.5%
CALDWELL	83,029	80,652	(2,377)	-2.9%	789	1,252	(463)	(1,914)	-2.3%
WILKES	69,340	65,969	(3,371)	-4.9%	693	976	(283)	(3,088)	-4.5%
NORTH CAROLINA	9,535,483	10,439,388	903,905	9.5%	121,577	107,975	13,582	890,323	9.3%

Source: NC Office of State Budget and Management & NC State Demographer
 *Growth = 2010 Population minus 2020 Population
 **Natural Growth = Difference of Births and Deaths




Table 7 Median Age of Population



US Census & NC OSMB

Table 8 Percent of Population 65+



US Census & NC OSMB



WATAUGA COUNTY HOUSING

North Carolina has one of the fastest growing populations in the United States. North Carolina's overall percentage increase in housing units between 2010 and 2020 was 8.8%. Table 10 summarizes the housing growth for counties exhibiting the highest rates of change, Watauga County, and its border counties.

Growth in housing units in Watauga County was well below the state average of 8.8% at 1.6%. Watauga County ranks 49th of North Carolina's 100 counties for growth in housing units, with 500 housing units constructed in the 10-year period between 2010 and 2020. The recession that began in 2007 is still affecting the rate of residential development nearly 13 years later.

Table 10
Change in number of Housing Units 2010-2020 - Ranked

	2010 US Census	2020 US Census	Percent Change	Ranking
North Carolina	4,327,528	4,708,710	8.80%	
Johnston County	67,682	84,340	24.60%	1
Wake County	371,836	462,582	24.40%	2
Onslow County	68,226	84,180	23.40%	3
Cabarrus County	71,937	87,410	21.50%	4
Durham County	120,217	144,559	20.20%	5
Mecklenburg County	398,510	478,966	20.20%	6
Chatham County	28,753	33,947	18.10%	7
Iredell County	69,013	79,372	15.00%	8
Union County	72,870	83,788	15.00%	9
Brunswick County	77,482	88,330	14.00%	10
Watauga County				
Watauga County	32,137	32,637	1.60%	49
Cleveland County	43,373	43,630	0.60%	50
Person County	18,193	18,284	0.50%	51
Camden County	4,104	4,119	0.40%	52
Haywood County	34,954	34,889	-0.20%	53
Avery County	13,890	13,827	-0.50%	54
Rockingham County	43,696	43,431	-0.60%	55
Perquimans County				
Perquimans County	6,986	6,866	-1.70%	62
Caldwell County	37,659	36,931	-1.90%	63
Chowan County	7,289	7,131	-2.20%	64
Yadkin County	17,341	16,946	-2.30%	65
Ashe County	17,342	16,935	-2.30%	66
Beaufort County	24,688	24,090	-2.40%	67
Greene County				
Greene County	8,213	7,846	-4.50%	78
Wilkes County	33,065	31,545	-4.60%	79





SEASONAL AND ABSENTEE OWNER POPULATION

The 2023 American Community Survey recognized 33,028 total housing units in Watauga County (Table 11). Approximately 9,292 housing units are considered seasonal, recreational or for occasional use. Thus, 28.1% of all housing, or 78.5% of all vacant housing in Watauga County is considered seasonal.

Arriving at a definitive estimate of Watauga County's seasonal population is difficult. Data is incomplete and conflicting. The data produced by the 2023 ACS is dated, but it is probably the most realistic indicator available. Based on the number of vacant homes categorized as "seasonal/recreational" (9,292) and the average household size in Watauga County (2.24 people) indicators, it can be estimated that the number of seasonal residents in Watauga County is around 20,000 or 37% of the County's permanent population.

In 2020, the U.S. Census reported 54,086 people living in Watauga County. If the above estimates of seasonal residents is reasonable, then the population of Watauga County may be as high as 74,000 on a seasonal basis. A figure that does not include tourists only here for a few days during the summer and winter months. This increase in population, even if temporary, is certain to place extra demand on essential services including water and sewer, fire and police protection, roads and streets, and emergency services.

Table 11
Housing Occupancy

TOTAL HOUSING UNITS	33,028	
OCCUPIED	21,187	64%
VACANT	11,841	36%
AVERAGE HOUSHOLD SIZE	2.24	
TOTAL OCCUPIED	21,187	
OWNER OCCUPIED	12,966	61%
RENTER OCCUPIED	8,221	39%
TOTAL VACANT UNITS	11,841	
FOR RENT	134	1%
RENTED, NOT OCCUPIED	538	5%
FOR SALE ONLY	286	2%
SOLD, NOT OCCUPIED	59	1%
FOR SEASONAL, RECREATIONAL, OR OCCASIONAL USE	9,292	80%
FOR MIGRANT WORKERS	0	
OTHER VACANT	1,532	13%





DEMOGRAPHIC CONCLUSIONS

Watauga County has transformed from a rural, agrarian county to a robust and growing transition community with a large tourism industry and growing population. Population growth more than doubled from 1970 to 2020. Predictions by the N.C. Office of State Budget and Management reflect continued steady growth through 2050.

Population projections for Watauga County place the population (excluding seasonal residents) in 2050 at approximately 71,000. To fully understand the potential for growth in Watauga County, one must consider two influencing factors, which are student enrollment at App State and seasonal population.

Analysis indicates that the seasonal population may increase the year-round permanent population by as much as 37%. Townships that currently have a very large percentage of seasonal population include Blowing Rock, Laurel Creek and Watauga. Therefore, the effective population could be as high as 97,200 by 2050.

Another noteworthy issue is that these numbers do not include tourists visiting Watauga County. Their numbers are substantial during three seasons of the year and add to the demand for services. The increasing number of seasonal residents and tourists are elements of growth that officials and planners must consider in weighing future growth issues.



ECONOMIC TRENDS

Income Characteristics

Three income characteristics are particularly important in analyzing the economic viability of the Watauga community: Income Per Capita, Median Household Income and Median Family Income. These three income characteristics, when viewed in comparison to one another, help to indicate the strength of the local economy. Table 12 compares these three income indicators for Watauga County, North Carolina and the United States.

NOTE: Income statistics are no longer provided within the decennial census. Since 2010 the information is only available through the American Community Survey (ACS). The ACS is an on-going survey that provides data every year – giving communities the most current information to use in their decision-making processes. Table 12 uses information from both sources, US Decennial Census and ACS.

- ▼ For each of these three income statistics, Watauga County is lower than the average for North Carolina and the United States in each census year from 1970 - 2000.
- ▼ From 2010 through 2023 similar averages show up with the exception of Family Median Income. In 2020 and 2023 the Watauga Family Median Income was more than the State.
- ▼ The 2010 ACS shows that Watauga County's per capita income is 84.7% of that for North Carolinians and 76.6% of the per capita income for the nation. In the 2023 ACS, these amounts have decreased slightly to 82% of North Carolina and 75% of the nation.
- ▼ For median family income in 2010, Watauga County families earn 99.9% of the income of other North Carolina families and 89.1% of families in the United States. By 2023 Watauga County families earned just over 100% of the North Carolina average but was still lower than the national average at 90%.
- ▼ Median household income in Watauga County lag significantly behind other North Carolina households in 2023 at 73% (down from 83% in 2000), and behind U.S. households at 65% (78% in 2000).
- ▼ Much of the difference in these income areas can be attributed to the high student population.

Table 12
Income Characteristics 1970-2023

		US Decennial Census				American Community Survey		
		1969	1979	1989	1999	2010	2020	2023
Watauga	<i>Per Capita Income</i>	\$1,969	\$5,097	\$10,628	\$17,258	\$20,961	\$27,962	\$32,631
	<i>Median Family Income</i>	\$6,149	\$14,532	\$27,752	\$45,508	\$56,112	\$75,042	\$87,273
	<i>Median Household Income</i>	\$5,323	\$11,039	\$20,252	\$32,611	\$31,967	\$46,453	\$51,367
North Carolina	<i>Per Capita Income</i>	\$2,474	\$6,133	\$12,885	\$20,307	\$24,745	\$31,993	\$39,616
	<i>Median Family Income</i>	\$7,770	\$16,792	\$31,548	\$46,335	\$56,153	\$70,978	\$86,947
	<i>Median Household Income</i>	\$7,025	\$14,481	\$26,647	\$39,184	\$45,570	\$56,642	\$69,904
US	<i>Per Capita Income</i>	\$3,119	\$7,298	\$14,420	\$21,587	\$27,334	\$35,384	\$43,289
	<i>Median Family Income</i>	\$9,586	\$19,917	\$35,225	\$50,046	\$62,982	\$80,069	\$96,922
	<i>Median Household Income</i>	\$8,486	\$16,841	\$30,056	\$41,994	\$51,914	\$64,994	\$78,538

US Decennial Census 1970, 1980, 1990, 2000; American Community Survey 5-Year Estimates 2010, 2020, 2023



Employment/Wages by Industry

In 2024, the number of employed persons in Watauga County was approximately 30,493, according to the U.S. Bureau of Labor Statistics (Table 13).

- ▼ Private industry employed 24,578 individuals.
- ▼ Federal, state and local governments employed 5,915 people.
- ▼ Specific areas that stand out as employers of a large percentage of workers include state government, educational services, the accommodations and food services sector, and retail trade.
- ▼ State government and educational services numbers are high, mainly due to the large number of employees in administration and teaching at Appalachian State University.
- ▼ Large numbers of workers in the accommodation and food services sector and retail trade are explained by the area's popularity as a tourist destination.
- ▼ The weekly wages for Watauga County workers are lower than the average wages in North Carolina in all categories of industry except one – education services.





Table 13
Employment/Wages by Industry - Watauga County with
State for Comparison (2024)

Governmental Industry	Watauga Average Employment	Watauga Average Weekly Wage	North Carolina Average Weekly Wage
Total Federal Government	106	\$1,314	\$1,724
Total State Government	4,082	\$1,243	\$1,304
Total Local Government	1,727	\$937	\$1,181
Private Industry			
Total Private Industry	24,578	\$999	\$1,732
Agriculture, Forestry, Fishing, & Hunting	0	\$0	\$931
Mining	0	\$0	\$2,078
Utilities	0	\$0	\$2,088
Construction	1,080	\$1,015	\$1,429
Manufacturing	482	\$680	\$1,436
Wholesale Trade	417	\$1,198	\$1,928
Retail Trade	3,527	\$597	\$752
Transportation and Warehousing	381	\$998	\$1,176
Information	0	\$0	\$2,490
Finance and Insurance	296	\$1,588	\$2,505
Real Estate and Rental and Leasing	765	\$894	\$1,335
Professional and Technical Services	908	\$1,598	\$2,132
Management of Companies and Enterprises	311	\$1,470	\$2,769
Administrative and Waste Services	907	\$815	\$1,075
Educational Services	4,828	\$1,186	\$1,170
Health Care and Social Assistance	3,889	\$1,267	\$1,296
Arts, Entertainment, and Recreation	937	\$557	\$802
Accommodation and Food Service	4,300	\$427	\$487
Other Services, (except Public Admin)	575	\$725	\$941
Public Administration	975	\$971	\$1,269
Unclassified	0	\$0	\$1,088
Total All Industries	30,493	\$1,123	\$1,485

NC Commerce - Quarterly Census of Employment and Wage (2024)




ECONOMIC TRENDS

Tourism Statistics 2023

- Domestic tourism in Watauga County generated an economic impact of \$517.51 million in 2023, a more than 172.6% increase since 2008 (\$189.8 million).
- In 2023, Watauga County ranked 15th in travel impact among North Carolina's 100 counties.
- More than 3,064 jobs in Watauga County were directly attributable to travel and tourism.
- Travel generated a \$127.7 million payroll in 2023.
- State and local tax revenues from travel to Watauga County amounted to \$35.60 million. This represents a \$652.00 tax saving for each County resident.
- Area attractions include the Blue Ridge Parkway, Horn in the West outdoor drama, Mast General Store, Beech Mountain Resort, Mystery Hill, museums devoted to Appalachian culture and heritage, Appalachian Theatre of the High Country, The Blowing Rock, Tweetsie Railroad, Hiking and Biking trails (Elk Knob, Rocky Knob), and Appalachian Ski Mountain.
- There are several attractions in adjoining counties that contribute to Watauga County for basic services, such as restaurants and lodging that also contribute to the county's tourism.
- Watauga County tourism saw a large (nearly 45%) increase in tourism revenue between 2020 and 2021. This growth in spending can be attributed to the COVID-19 pandemic. After months of quarantines, temporary business closures, social distancing, and travel restrictions, people wanted to travel again enjoying outdoor events and activities that Watauga County could offer while still observing mandated safety protocols.

Table 14
Watauga County Tourism Revenue 2000-2023



visitnc.com



PRINCIPAL EMPLOYERS

Table 15 25 Largest Employers - Watauga County (2024)

Rank	Company Name	Industry	Employment Range
1	Appalachian State University	Education	1,000+
2	ARHS Attn Human Resources	Health Services	1,000+
3	Samaritans Purse, Inc.	Health Services	1,000+
4	Watuaga County Board of Education	Education	500-999
5	Watauga County	Public Administration	250-499
6	Appalachian Ski Mountain	Arts, Entertainment & Recreation	250-499
7	Beech Mountain Resort, Inc	Arts, Entertainment & Recreation	250-499
8	Wal-Mart Associates, Inc.	Retail	250-499
9	Mast General Store, Ince	Retail	100-249
10	Glenbridge Health & Rehabilitation	Health Services	100-249
11	Advisor Irep, Inc	Administrative & Support	100-249
12	ECR Software Corp.	Professional, Scientific, & Technical Services	100-249
13	Town of Boone	Public Administration	100-249
14	Lowes Home Centers, Inc	Retail	100-249
15	Publix North Carolina	Retail	100-249
16	RHA Health Services	Health Services	100-249
17	Food Lion	Retail	100-249
18	Prospera-CMC	Accommodation & Food Service	100-249
19	Stick Boy Bread Company	Manufacturing	100-249
20	Lost Province Brewing Company	Accommodation & Food Service	100-249
21	High Country Community Health	Health Care & Social Assistance	100-249
22	Harris Teeter	Retail	100-249
23	About Health, LLC	Health Care & Social Assistance	100-249
24	Tweetsie Railroad, Inc	Arts, Entertainment & Recreation	100-249
25	Goodnight Bros. Produce Co., INC	Wholesale Trade	100-249

NC Commerce - Quarterly Census of Employment and Wage (2024)

Watauga County's largest employer is Appalachian State University (App State)

- ▼ In Fall 2024, App State had 3,228 full-time employees.
- ▼ The total employment is nearly 4,000 with part-time and temporary employees.
- ▼ Considering full-time employees, App State employees 11% of the County's entire workforce.
- ▼ The employment of Appalachian Regional Healthcare System was 1,600 in April 2025.
- ▼ The next largest employers are Samaritan's Purse with 1,000+employees and the Watauga County Board of Education, with more than 500 employees.
- ▼ Other major contributors to the labor force in Watauga County include Watauga County, Town of Boone, Wal-Mart, Mast General Store, Appalachian Ski Mountain, and Beech Mountain Resorts.



EMPLOYMENT TRENDS

The U.S. Census defines labor force as “all people classified in the civilian labor force (i.e., “employed” and “unemployed” people), plus members of the U.S. Armed Forces.” Tables 16 and 17 summarize key employment and economic sector statistics for Watauga County.

Table 16
Watauga County Employment Characteristics 2000-2024

	Labor Force	Employed	Unemployed	Unemployment Rate
2024	27,817	26,849	968	3.50%
2023	29,969	29,070	899	3.00%
2022	29,336	28,374	962	3.30%
2021	28,110	27,041	1,069	3.80%
2020	26,797	25,317	1,662	6.20%
2019	29,249	28,240	1,009	3.40%
2018	28,475	27,464	1,011	3.60%
2017	28,163	27,018	1,145	4.10%
2016	27,861	26,608	1,253	4.50%
2015	27,365	26,056	1,309	4.80%
2014	27,043	25,683	1,360	5.00%
2013	27,019	25,339	1,680	6.20%
2012	27,276	25,213	2,063	7.60%
2011	27,147	25,010	2,137	7.90%
2010	26,990	24,894	2,096	7.80%
2009	23,227	21,299	1,928	8.30%
2008	23,089	21,992	1,097	4.80%
2007	24,800	23,890	910	3.70%
2006	23,909	22,952	957	4.00%
2005	23,318	22,329	989	4.20%
2004	22,834	21,841	993	4.30%
2003	22,873	21,822	1,051	4.60%
2002	22,299	21,251	1,049	4.70%
2001	23,664	22,799	865	3.70%

Local Area Unemployment Statistics (LAUS)



Table 17
Current Industry Structure - Watauga County

	Number of Business Units	Average Employees	Percent of NC Average	Percent of Watauga Average
All Industries	1957	24,778	0.52%	
Construction	257	1,080	0.40%	4.36%
Manufacturing	51	482	0.10%	1.95%
Wholesale Trade	62	517	0.25%	2.09%
Retail Trade	294	3,527	0.66%	14.23%
Transportation and Warehousing	31	381	0.18%	1.54%
Finance and Insurance	58	296	0.13%	1.19%
Real Estate and Rental and Leasing	168	765	1.06%	3.09%
Professional and Technical Services	247	908	0.27%	3.66%
Management of Companies and Enterprises	8	311	0.37%	1.26%
Administrative and Waste Services	130	907	0.28%	3.66%
Educational Services	45	4,828	1.23%	19.49%
Health Care and Social Assistance	177	3,889	0.56%	15.70%
Arts, Entertainment, and Recreation	45	937	1.07%	3.78%
Accommodation and Food Service	205	4,300	0.94%	17.35%
Other Services, (except Public Admin)	156	675	0.51%	2.72%
Public Administration	23	975	0.00%	3.93%


NC Commerce - Quarterly Census of Employment and Wage (2024)



UNEMPLOYMENT RATE


Since 2000, the average annual unemployment rate in Watauga County has been lower than North Carolina's average annual rate and lower than the national average rate. The unemployment rate in Watauga County has also been very favorable compared to adjoining counties. Many individuals commute from other counties in North Carolina and Tennessee to work in Watauga County.

Table 18
Average Annual Unemployment Rate
Counties 2000-2023



Local Area Unemployment Statistics

Table 19
Average Annual Unemployment Rate - Comparison



Local Area Unemployment Statistics



WORKING COMMUTERS

- ▼ In 2022, 12,234 individuals, or 41.7% of the labor force in Watauga County, lived in counties other than Watauga County.
- ▼ Over one third of these people lived in the adjoining counties of Ashe (1,577) Caldwell (934), Avery (717), and Johnson County, TN (611).
- ▼ 3.1% of the workers commuting to Watauga County lived in Tennessee and 65.4% of these came from Johnson County.
- ▼ In 2022, 8,295 individuals living in Watauga County commuted outside of the county to work. Approximately 13.5% of these individuals work in states other than North Carolina.

Table 20

Workers Commuting TO Work in Watauga County, Living In


Counties	2012	2022
<i>Ashe, NC</i>	1,324	1,577
<i>Caldwell, NC</i>	857	934
<i>Avery, NC</i>	887	714
<i>Mecklenburg, NC</i>	498	658
<i>Wilkes, NC</i>	509	634
<i>Wake, NC</i>	417	484
<i>Johnson, TN</i>	661	611
<i>Gilford, NC</i>	301	404
<i>Other</i>	5,574	6,218
Total	11,028	12,234
States		
<i>Tennessee</i>	1,009	933
<i>Virginia</i>	345	395
<i>South Carolina</i>	128	212
<i>Other</i>	200	242
Total	1,682	1,782

Table 21

Workers Living IN Watauga County Commuting to Work In:

Counties	2012	2022
<i>Avery</i>	604	935
<i>Mecklenburg</i>	566	722
<i>Buncombe</i>	803	657
<i>Wake</i>	1,379	559
<i>Catawba</i>	537	416
<i>Caldwell</i>	443	394
<i>Wilkes</i>	361	332
<i>Other</i>	5,963	4,280
Total	10,656	8,295
States		
<i>Tennessee</i>	467	484
<i>Virginia</i>	193	191
<i>South Carolina</i>	173	83
<i>Other</i>	473	361
Total	1,306	1,119

US Census, Center for Economic Studies, LODES



Section 2

Physiographic Features

PHYSIOGRAPHIC FEATURES


The overall suitability of land to accommodate development is generally viewed as the cumulative constraint imposed by the natural features of slope, hydrology, soils, flooding and other sensitive environmental characteristics of the geographic area under consideration. For the purposes of this assessment, the additional factors of protected mountain ridges and certain publicly-owned lands have been added to this collective categorization. This assessment is made on the basis of natural constraints. Other limitations, such as the availability of water and sewer services and transportation capacities, are not considered.





Watauga County Hydrology and Flood Hazard


Illustration 1 Hydrology Map of Watauga County



Watauga County is fortunate to have abundant and relatively pure surface water in four major watersheds.

Topographic Characteristics

Illustration 2 Topographic Map of Watauga County




The lowest elevation is 1,350 feet above sea level in the Triplett Community in southeast Watauga County. The highest point is Calloway Peak at 5,964 feet above sea level. It is the highest peak of Grandfather Mountain and is shared with adjacent counties, Avery and Caldwell. The steeper the land, the more difficult it is to utilize and the more sensitive it is to change.



Slope Characteristics

Illustration 3 Slope Map of Watauga County



Watauga County has very diverse topographic features. Elevations range from as low as 1,350 feet above sea level to 5,964 feet above sea level.

The Slope Map (Illustration 3) shows topographic characteristics in three categories.

Light areas are slopes between 0% and 30% and are most amenable to change.

Medium blue areas have very steep slopes of 50% or greater and are most sensitive to change.


The slope of the land has a direct bearing on land stability and suitability for development. Areas of steep slope are often associated with earth slides, increased fire hazards, increased potential for damage to the natural environment, and greater economic issues.

The Watauga County subdivision ordinance notes that a slope of 50% or greater is generally “considered too steep for subdivision development.”

This does not prevent construction of improvements on steep slopes. It merely restricts subdivision development.

Elevation Diversity

Illustration 4 Elevation Map of Watauga County




The Elevation Map (Illustration 4) graphically displays the wide variation in elevation in Watauga County. The largest portion of the County falls in the 3,000 to 3,500 feet above sea level category. However, about 25% of the County has elevations above 3,500 feet.



Hill Shade View


Illustration 5 Hill Shade View Map of Watauga County



The Hill Shade View Map (Illustration 5) provides an alternate view of the topographic features of Watauga County. This map, along with the Topographic, Elevation and Slope Maps, provides a picture of the rugged and diverse landscape of the County. This graphic representation presents the relief of the landscape as viewed from the west quadrant of the map.

Protected Ridges

Illustration 6 Map of Protected Ridges




- ▼ In 1983, The General Assembly adopted North Carolina General Statute 113A - Article 14, known as the “Mountain Ridge Protection Act.” The regulations contained therein apply to mountain ridges with an elevation of 500 feet or more above the valley floor. The regulated portion of the ridge is the area within 100 feet below the elevation of the crest of the mountain.

 - ▼ The Act prohibits “tall buildings or structures” on protected mountain ridges.
- ▼ A “tall building or structure” has a vertical height of more than 40 feet measured from the top of the foundation to its highest point.
- ▼ Tall buildings or structures may not protrude above the crest of the ridge by more than 35 feet.
- ▼ Certain structures and building projections are not regulated under the Act, including towers for communications, electricity, telephone, television and radio, structures such as chimneys, spires, steeples, antennas, windmills, etc., and buildings and structures designated as National Historic Sites.



Soil Types

Illustration 7 Highly Erodible Land Based on Soil Characteristics




The Map shown in Illustration 7 shows the distribution of Highly Erodible Land Determinations (HEL) based on soil characteristics of Watauga County.

- ▼ Highly Erodible Land (HEL) provisions of The Food Security Act of 1985 are designed to protect the Nation’s long-term capability to produce food and fiber. HEL is land that can erode at an excessive rate because of soil properties leading to long-term decreased productivity. Highly erodible land is designed on a field basis and based on the proportion of the total field acreage that contains highly erodible soils.
 - ▼ The HEL Soils list identifies soils having an erodibility index (EI) of eight or more HEL. This index expresses the potential erodibility of a soil in relation to its tolerance for erosion without consideration of applied conservation practices or management. Soil can be classified as highly erodible for either wind or water erosion.
- ▼ Watauga County has approximately 171,152 acres (or 85.5% of the county) that is designated as highly erodible.

Significant Natural Areas

Illustration 8 Map of Natural Areas in Watauga County



Watauga County has several sites designated by the North Carolina Natural Heritage Program as natural heritage areas or significant natural areas. All have one of the following designations: national, state, regional or county significance. The following is a list of the sites in Watauga County, represented in Illustration 8 - Significant Natural Areas, along with acreages as recorded by the North Carolina Department of Environmental Quality, Division of Parks and Recreation, Natural Heritage Program. Some of the sites enjoy protection through ownership by federal or state entities. Others are in private ownership.




NATURAL AREA	LAND OWNER	ACREAGE
APPALACHIAN STATE UNIVERSITY FOREST	SITE IS OWNED BY APPALACHIAN STATE UNIVERSITY	67.35
BEECH CREEK NATURAL AREA	PORTION OWNED BY NORTH CAROLINA DEPARTMENT OF PARKS AND RECREATION AS A STATE NATURAL AREA AND THE REMAINDER IS PRIVATELY OWNED LOCATED NEAR BEECH MOUNTAIN	131.13
BEECH CREEK SLOPES	PORTION OWNED BY NORTH CAROLINA DEPARTMENT OF PARKS AND RECREATION AS A STATE NATURAL AREA AND THE REMAINDER IS PRIVATELY OWNED LOCATED NEAR BEECH MOUNTAIN	234.80
DEEP GAP NATURAL AREA	THE SITE IS PARTLY OWNED BY THE NATIONAL PARK SERVICE BLUE RIDGE PARKWAY AND IS A REGISTERED HERITAGE AREA AND THE REMAINDER IS PRIVATELY-OWNED LOCATED NEAR DEEP GAP.	11.08
DOE FORK SEEPS AND FORESTS	PRIVATELY-OWNED SITE LOCATED NORTH-NORTHWEST OF BOONE NEAR RICH MOUNTAIN.	252.04
DUN VEGAN MOUNTAIN	PRIVATELY-OWNED SITE NEAR THE TOWN OF SEVEN DEVILS.	144.34
DUTCH CREEK FALLS	PRIVATELY-OWNED SITE LOCATED NEAR THE VALLE CRUCIS COMMUNITY.	2.19
GILLEY FIELD STATION FORESTS	CURRENTLY BEING USED BY THE ANTHROPOLOGY AND BIOLOGY DEPARTMENTS AT APPALACHIAN STATE UNIVERSITY FOR FACULTY AND STUDENT RESEARCH PROJECTS AND OWNED BY THE ENDOWMENT FUND OF APPALACHIAN STATE UNIVERSITY LOCATED IN THE TODD COMMUNITY	201.68
GRANDFATHER MOUNTAIN	A HIGH, RUGGED MOUNTAIN LOCATED ON THE BLUE RIDGE ESCARPMENT. OWNERSHIP OF GRANDFATHER MOUNTAIN IS BY THE U.S. FOREST SERVICE, THE NATIONAL PARK SERVICE BLUE RIDGE PARKWAY, THE NATURE CONSERVANCY, AND PRIVATE OWNERSHIP. IN SEPTEMBER 2008, A LARGE PORTION OF GRANDFATHER MOUNTAIN WAS PURCHASED BY THE STATE OF NORTH CAROLINA TO BECOME THE STATE'S 34TH STATE PARK.	1,845.50
GRANDVIEW OVERLOOK SLOPES	LOCATED ON THE BLUE RIDGE ESCARPMENT BETWEEN BOONE AND DEEP GAP, NEAR THE BLUE RIDGE PARKWAY AND PRIVATELY OWNED.	224.06
HANGING ROCK MOUNTAIN	A RUGGED MOUNTAIN LOCATED NEAR THE TOWN OF SEVEN DEVILS UNDER PRIVATE OWNERSHIP.	635.52
HOWARDS CREEK FLOODPLAIN	THE PRIVATELY-OWNED SITE IS LOCATED NEAR THE HEADWATERS OF HOWARDS CREEK AND TATER HILL.	51.02
JULIAN PRICE PARK WETLANDS NATURAL AREA	LOCATED IN THE JULIAN PRICE MEMORIAL PARK ON THE BLUE RIDGE PARKWAY AND OWNED BY THE NATIONAL PARK SERVICE BLUE RIDGE PARKWAY.	300.46
LONG HOPE KNOB/ELK KNOB/THE PEAK	AN AMPHIBOLITE MOUNTAIN OWNED IN PART BY THE NORTH CAROLINA DEPARTMENT OF PARKS AND RECREATION AND THE NATURE CONSERVANCY WITH THE REMAINING PORTION UNDER PRIVATE OWNERSHIP.	4,403.77
MOSES CONE PARK/FLAT TOP MOUNTAIN	THIS SITE IS OWNED BY THE NATIONAL PARK SERVICE BLUE RIDGE PARKWAY.	298.17
MOSES CONE PARK/RICH MOUNTAIN	SITE OWNERSHIP IS BY THE NATIONAL PARK SERVICE.	290.78
ROCKY FACE	PRIVATELY-OWNED MOUNTAIN LOCATED IN THE VALLE CRUCIS COMMUNITY.	18.07
SIMS CREEK OLD GROWTH FOREST	THIS SITE IS OWNED BY THE NATIONAL PARK SERVICE BLUE RIDGE PARKWAY.	47.32
SNAKE MOUNTAIN	A HIGH MOUNTAIN TOP RIDGE LOCATED IN NORTHERN WATAUGA COUNTY AND UNDER PRIVATE OWNERSHIP.	1,043.65
SNAKEDEN MOUNTAIN	THIS SITE IS PART OF THE RICH MOUNTAIN RIDGE AND PRIVATELY-OWNED.	97.42
SOUTH FORK LAUREL CREEK/DUGGER MOUNTAIN	LOCATED ON THE EASTERN ESCARPMENT OF THE BLUE RIDGE AND PRIVATELY OWNED.	1,854.68
STONE MOUNTAIN (LOCUST GAP)	AN ELEVATED RIDGE ON THE NORTH CAROLINA-TENNESSEE STATE LINE UNDER PRIVATE OWNERSHIP.	1,100.88
TATER HILL NATURAL AREA	THIS SITE IS OWNED IN PART BY THE NORTH CAROLINA PLANT CONSERVATION PROGRAM, WITH THE REMAINDER UNDER PRIVATE OWNERSHIP.	3,229.58
THUNDER HILL	THIS SITE IS INCLUDED IN THE BLUE RIDGE PARKWAY BOUNDARY AND OWNED BY THE NATIONAL PARK SERVICE	270.25
TRIVETTE BRANCH FORESTS AND SEEPS	PRIVATELY-OWNED SITE.	282.96
VALLE MOUNTAIN	THE SITE IS A SMALL MOUNTAIN WITH STEEP SLOPES LOCATED IN THE VALLE CRUCIS COMMUNITY AND PRIVATELY-OWNED BY THE VALLE CRUCIS MISSION SCHOOL.	308.09
WHITE ROCK	THE SITE IS A SMALL PRIVATELY-OWNED MOUNTAIN NORTHWEST OF THE TOWN OF SEVEN DEVILS.	24.80
SOUTH FORK AND NEW RIVER AQUATIC HABITAT	AQUATIC HABITAT	257
WATAUGA RIVER AQUATIC HABITAT	AQUATIC HABITAT	229.38



Drinking Water - Watersheds

Illustration 9 Map of Watauga County Watersheds



Protected watersheds include:


The Legislature of the state of North Carolina delegates the responsibility to Watauga County to adopt regulations that provide protection for watersheds. New development is subject to the restrictions of the watershed ordinance.

- Buckeye Creek
- Pond Creek
- Flat Top Branch
- Winkler Creek
- Norris Branch
- Howards Creek
- South Fork New River
- South Fork New River (Boone)



Public Lands

Illustration 10 Map of Public Lands and Conservation Properties



Watauga County enjoys a large amount of public land owned by the federal government. It is mostly located in the southern portion of Watauga County and is part of the Blue Ridge Parkway and properties accessed from the Parkway.

Properties owned by the state of North Carolina include Elk Knob State Park in northern Watauga County, which has the second highest peak in Watauga County, and the property around Grandfather Mountain. The state of North Carolina also owns much property in and around Boone occupied by Appalachian State University.




Watauga County owns properties that include government buildings, schools, recreation fields, gyms, swimming pools and others. A partial list of the principal County operated and/or owned properties follows:

- Watauga County Government Buildings
- Watauga County Schools
- Brookshire Park
- Howards Knob County Park
- Watauga County Recreation Center
- Cove Creek Park
- Rocky Knob Bike Park
- Sterling Creek Park (Middle Fork Greenway)
- Payne Branch Park (Middle Fork Greenway)
- Goldmine Branch Park (Middle Fork Greenway)
- 312 Trailhead (Middle Fork Greenway)
- Complex Ball Fields
- Watauga County Tot Lot
- New River Access
- Watauga River Accesses



Land Use Classification

Illustration 11 Land Use Map of Watauga County





Section 3 Transportation



TRANSPORTATION PLANNING

Preface

Watauga County's goal is to achieve an efficient and balanced transportation system that combines motorized and non-motorized modes of transportation. Specific objectives include:

- ▼ An efficient and integrated multi-modal transportation system
- ▼ A transportation system that is affordable and accessible to all users.
- ▼ A multi-modal transportation system that supports future development and preserves community character.
- ▼ A regionally integrated transportation planning process.

The principal highways in Watauga County are U.S. 321, U.S. 221, U.S. 421, N.C. 105, N.C. 194, and N.C. 88. These roads form the backbone of the County's transportation network (Illustration 12). In Watauga County, current transportation modes are limited to surface transportation, including vehicles, bicycles, and pedestrians. The County does not have a public airport or any navigable waters


Public perceptions about transportation are summarized as follows:

- ▼ In a survey conducted in conjunction with the 2013 "Watauga County Comprehensive Transportation Plan", there was a desire for more non-traditional transportation options. More on-road bike lanes, greenways/off-road paths, and the expansion of sidewalks were high on the list of solutions to the County's traffic problems, with improvement of intersection design coming in a close second.
- ▼ A survey conducted for the update of this plan in 2024 found that a majority of the respondents (89%) were dissatisfied with traffic congestion in the County.
- ▼ Solutions to traffic congestion in both surveys tended to favor non-traditional transportation options (more bike lanes and pedestrian friendly paths). In addition, respondents in both surveys suggested Intersection design (more turn lanes) and widening existing roads would also improve traffic flow in problem areas.



Transportation Network


Illustration 12 Road and Highway Network





Widening Projects

Illustration 13 Proposed Widening Projects



TRANSPORTATION PLANNING

In March 2010, the Transportation Planning Branch of the North Carolina Department of Transportation (NCDOT) and Watauga County initiated a study to cooperatively develop the Watauga County Comprehensive Transportation Plan (CTP). This is a long range multi-modal transportation plan that covers transportation needs through 2040. Modes of transportation evaluated as part of this plan include highway, public transportation and rail, bicycle, and pedestrian. The current plan is scheduled to be reevaluated and updated in 2026.

Findings of the CTP study were based on an analysis of the transportation system, environmental screening, and public input. The report documents the following recommendations for improvement:

Highway

- ▼ US 221 – Widening US 221 from US 421 in Deep Gap to NC 88 in Ashe County to a four-lane boulevard. (COMPLETED)
- ▼ US 321/421 – Improving US 321/421 from the NC 105 Bypass to US 321 at Vilas to a four-lane divided, partially controlled access facility.
- ▼ US 421 Bypass (“The Boone Bypass”)– The CTP proposes a bypass south of Boone to relieve congestion on US 421, US 321, and NC 105 in Boone. This project would work in conjunction with other projects to reduce the mixed traffic on King Street, to improve linkage to major facilities, to improve traffic flow along major facilities, and to improve safety.
- ▼ NC 105 – Widening NC 105 from the NC 105 Bypass (SR1107) to Avery County to a four-lane facility with a median. (In Progress)

- ▼ NC 105 Bypass – Widening the NC 105 Bypass (SR 1107) from NC 105 to US 321/421 to a three-lane facility.
- ▼ NC 194 – Widening NC 194 from US 221/421 to Howards Creek Road (SR 13056) to a four-lane boulevard.

Public Transportation & Rail

- ▼ US 321 –A new bus route between Boone and Blowing Rock utilizing US 321.
- ▼ Park-and-Ride – The CTP proposes seven new park-and-ride locations along major routes.


Bicycle/Pedestrian

- ▼ Middle Fork Greenway – A new multi-use path between Boone and Blowing Rock parallel to US 321. (Construction on the first section of the trail began in 2012. To date, 1.75 miles of the 6.5 mile trail are complete, with another 2.3 miles currently under construction)





Illustration 14 Daniel Boone Parkway Preliminary Alignment




The Daniel Boone Parkway (AKA the Boone Bypass)

- ▼ Many of the issues related to transportation planning in Watauga County deal with traffic congestion, and particularly traffic congestion in Boone. Many believe a bypass around Boone is the answer to the problem. An alternate route around Boone will need to provide easy access points for those whose end destination is Boone.
- ▼ Boone also has a Thoroughfare Plan. The first plan was completed in 1964, the second in 1976, and the most recent in 1992. A major element in each of the plans was the construction of a route to bypass Boone. The NCDOT outlined possible routes in the 1992 plan.
- ▼ In 2008, a study, a “Pre-TIP Study Report US 421 Improvements TIP Project U-2703” was released. The study considered fifteen alternate routes for the Boone Bypass and narrowed it down to four low-build alternatives.
- ▼ The 2013 Watauga County Comprehensive Transportation Plan (CTP) evaluated the four Pre-Tip recommendations, and three additional alternatives were proposed.
- ▼ The CTP recommended a route that extends from US 421/321 west of the NC 105 Bypass to a new location on NC 105 further west of the existing interchange. It continues west (south of the existing US 105) intersecting with Hwy 321/221 near Fairway Drive and loops west of the headwaters of the Rocky Branch Stream.
- ▼ The CTP recommended route for the bypass was presented to the public in 2012 as part of the CTP draft. Numerous comments were made opposing the project and questioned its need according to the CTP.
- ▼ As of 2024 the project is still on the State Transportation Improvement Program (STIP), but only section B has been funded for preliminary engineering. **Illustration 14** shows the current proposed alignment of the roadway.

TRANSPORTATION PLANNING

- ▼ Watauga County's public transportation authority is the AppalCART. It serves all of Watauga County and operates as a coordinated effort between local, state, and federal governments, human service agencies and Appalachian State University. AppalCART provides numerous Boone routes free of charge and provides rural routes via van to destinations such as Zionville, Foscoe, Matney, Meat Camp, Blowing Rock, Deep Gap, and Cove Creek for a route fee. All routes are open to the public. Out-of-county routes to Winston-Salem, Hickory and Charlotte are available for residents to attend medical appointments.
- ▼ The County does not have a public airport, but there is a short, private airstrip in the Kellwood/ Bamboo area. The nearest airports providing commercial passenger service are in Charlotte, Greensboro, Asheville, North Carolina, and Blountville, Tennessee. General aviation airports with runways over 5,500 feet are located in North Wilkesboro, Morganton/Lenoir, and Hickory.
- ▼ Sunway charter provides two round trip routes from Boone daily, one to Greensboro and one to Charlotte with service to certain towns and hospitals in between.
- ▼ The Hickory "Hop" currently provides a shuttle service between Watauga County and the Charlotte airport at four scheduled times daily, seven days each week.





Recommendations

Highways

- Watauga County, Town of Boone, High Country Rural Planning Organization (RPO), NCDOT, App State and citizens groups should continue to work together to evaluate the Daniel Boone Parkway project. Further evaluation of the Daniel Boone Parkway will happen through a Comprehensive Transportation Plan (CTP) steering committee during its next update in 2026.
- Watauga County should continue to work with NCDOT officials through the High Country RPO to prioritize and advance projects identified in the Watauga County Comprehensive Transportation Plan.
- NCDOT, in conjunction with Watauga County and the High Country RPO, has prioritized the following transportation projects, scheduled for delivery in the Draft 2026-2035 State Transportation Improvement Plan (STIP):
 - ▼ Widen NC 105 to four lanes between NC 105 Bypass and Clarks Creek Road (SR 1136) (Right-of-way in progress) (R-2566B)
 - ▼ At NC 105 and Broadstone Road intersection, construct new bridge over the Watauga River and left-turn lane. (Construction in progress) (R-2566BA)
 - ▼ Realign intersection of NC 105 and Old Shulls Mill Road (SR 1658). (Construction in progress) (R-2566BB)
 - ▼ Upgrade Deerfield Road (SR 1522) from State Farm Road to Wilson Ridge Road (SR 1523). (Right-of-way to begin in 2025) (R-5830)
 - ▼ Modernize Bamboo Rd (SR 1514) and Wilson Ridge Road (SR 1523) from US 421/US 221 to Deerfield Road (SR 1522). (Right-of-way in progress) (U-5810)
 - ▼ Poplar Grove Connector Rd (SR1180) to Westwood Apartments. Sidewalk &

- ▼ Grove Street to Brookshire Rd. Construction of multi-use path. (EB-5983)


Multimodal

- Town, County, High Country Council of Governments, and NCDOT officials should place strong emphasis on creating roadways that are safe for all modes of transportation, including bicycles and pedestrians.
- Expand AppalCART rural routes and decrease the service intervals between existing stops so that more people have the opportunity to ride and waiting times are shorter.
- Expand AppalCART service to affordable housing projects as feasible.
- Create Park-n-Ride lots outside of Boone and provide AppalCART service to these lots in order to capitalize on the use of mass-transit and reduce downtown congestion.
- Boone and App State should work together to: Promote and provide more environmentally friendly, greener, safer, and sustainable transportation modes, especially for pedestrians and bicycles.
- Provide more parking areas for bicycles.

Transportation Planning

Watauga County should:

- Continue to work closely with NCDOT, The Towns of Boone, Blowing Rock, Beech Mountain, Seven Devils, App State, and the High Country RPO to identify needed transportation improvements in the County.
- Continue to develop minimum standards for new and redesigned roads that specify the creation of bicycle lanes and sidewalks that promote safe alternatives.



Section 4 Economic Development



ECONOMIC DEVELOPMENT

Preface

The economy of Watauga County is diverse. The principal economic segments that drive the County's economy include education, tourism, healthcare, finance, construction, services and agriculture. In 2024, Policom Corporation ranked Boone 47th among 543 micropolitan areas in the U.S. for economic strength.

Findings

- ▼ **Quality of Life** - The concern for preserving and improving "quality of life" is a theme that permeates all aspects of Watauga County's future. All efforts to promote economic development should focus on "better rather than bigger" and enhancing "quality of life."
- ▼ **Gateways** - Watauga County's principal transportation corridors are also its major economic corridors. They are "economic gateways" into the community. These corridors offer visitors their first perception of Watauga and they are therefore an essential element of planning for the future. The primary corridors include US 421, US 321 and NC Hwy 105. The Deep Gap area is of particular importance since it contains much of the most desirable land for development and has good transportation accessibility.

Economic Development Infrastructure

- ▼ The economic development related organizations are charged with various aspects of economic promotion and support in Watauga County. While each is important, there is a growing need to achieve a higher degree of cooperation and ensure that the array of activities collectively promote established core objectives.
- ▼ **Critical Economic Sectors** - Watauga County's key economic sectors are education and research, tourism and recreation, the medical services field, construction, retail, and tourism.

Education/Research

- ▼ Appalachian State University (App State) is the largest employer in Watauga County. In July 2024, it had just under 4,000 total full-time, part-time and temporary employees.

Medical/Research

- ▼ The second largest employer in the County is UNC Health - Appalachian (formerly known as Appalachian Regional Healthcare System). In 2025, it had 1,600 employees.
- ▼ UNC Health- Appalachian is the predominant regional medical center, comprised of three hospitals and thirteen medical practices.

Tourism and Recreation

- ▼ Tourism has a profound effect on the economy in Watauga County. According to “The Economic Impact of Travel on NC Counties,” a study prepared for Visit NC by Tourism Economics, Watauga tourism generated \$517.5 million in expenditures in 2023 and a tourism payroll of \$127.7 million for 3,064 jobholders.
- ▼ Ample recreational opportunities, including fishing, hiking, biking, skiing, rafting, canoeing, kayaking, rock climbing and App State athletic events, also add to the appeal of the County and contribute to the economy.
- ▼ Watauga County is a hub for many tourism activities that take place throughout the region. Visitors to adjoining counties make Boone the base of their activities for lodging, dining, medical services and other services.
- ▼ Watauga County’s recreational opportunities are enhanced by its unique and diverse environment, which includes assets such as the Blue Ridge Parkway, Mountain to Sea Trail, Elk Knob State Park, a portion of Grandfather Mountain State Park, New River, Watauga River and many pristine streams.
- ▼ App State athletics has had a significant impact on the Watauga County Economy. A 2024 study, “Annual Economic Impact of Appalachian Athletics” by the Center for Economic Research and Policy Analysis reports that App State athletics program provides an injection of money into the regional economy in the neighborhood of \$96 million annually. This increase in economic activity translates to 643 additional jobs and \$32.7 million in additional income as well as \$3.3 million in indirect tax revenue for local governments. In 2023, more than 208,000 spectators watched six home games and spent over \$34.9 million on hotels, restaurants, and grocery stores.
- ▼ Agritourism has become a thriving industry in recent years. Picking berries and fresh flowers in the summer; apple picking, pumpkin patch/corn mazes in the fall; and choose-and-cut Christmas tree farms in the winter, lure visitors to Watauga County all year long.





Industry and Business

- Retaining and enhancing existing industry and business are fundamental to the County's economic future. Local officials actively sought to promote economic development in the County with the creation of the Watauga County Industrial Park. The Park, now filled to capacity, provides many jobs to County residents.
- Over the years manufacturing and industry have had less of an impact on Watauga County's economy. Presently there are a handful of industrial firms conducting business in the County. Most are small "home grown" businesses. The two largest are ECR Software, developing software and point of sale equipment and Goodnight Brothers, specializing in the art of dry curing hams.
- A major factor in attracting industry and business is the provision of the services they need to thrive. Services such as the provision of water, sewer, electricity and communications are very important to almost any kind of business.



Agriculture

- Watauga County residents have considerable interest in local farming practices and the availability of local foods.
- Approximately 30 growers produce Fraser Firs in Watauga County.
- Local vegetables and other crops represent an important economic segment
- The County currently has three Farmer's Markets. Two operating in the summer months and one wintertime market, and one Food Hub; all featuring food from local growers.





Recommendations

Strengthening Organization


- Strengthen the focus of Economic Development continuing to make the Watauga Economic Commission the core agency for economic planning, policy interpretation and coordination. By continuing to support this ongoing program would enable the County to have a key role in economic development. This program fosters communication, “sustainability” and innovation among existing economic programs and facilitate new initiatives that either strengthen existing programs or create new initiatives designed to generate new economic investments and employment.
- Invest in the creation of a dynamic and comprehensive economic development strategy to better explore and capitalize on potential economic opportunities.
- Encourage and facilitate the provision of essential infrastructure, such as transportation, water, sewer and natural gas, to provide an attractive business climate for potential economic development.
- Work with and coordinate the wide range of economic development resources available to the County, including Appalachian Regional Commission, App State Center for Entrepreneurship, Boone Business Exchange, High Country Young Professionals, Startup High Country, Service Corps of Retired Executives, Tourism Development Authority, Watauga County Economic Development Commission, and others to explore innovative and fresh concepts. Organize annual or semi- annual workshops with these entities to create a spirit of cooperation and focus resources.
- Where appropriate, promote regional economic development strategies beyond Watauga County that provide employment opportunities for Watauga County residents.
- Promote the development of renewable energy concepts and participation in renewable energy initiatives.

Economic Gateways

- Watauga transportation corridors are also economic “Gateways” (Illustration 15) into the County and are critical to the County’s economic future. Watauga County should guide development and protect the integrity and potential of these key strategic economic corridors.
- “Gateways” are defined as the entrances or means of access to Watauga County and are identified as the primary arterial highways (US 321, US 421, and NC Hwy 105). Providing attractive as well as functional “Gateways” into Watauga County facilitates both the positive image and economy of the community.
- The economic growth of the community is linked to the vitality and appearance of these “Gateways.”



Illustration 15 Economic Gateways Map



- ▶ The quality of life enjoyed by Watauga County citizens and visitors is directly related to the natural environment. The “Gateways” are inextricably linked to the perception of this unique environment and the rich quality of life.
- ▶ The aesthetic quality of the “Gateways” concept is vitally important to the economic future of the community. Incentives for property owners and the community should be developed to maintain attractive and compatible development that will enhance the total economic value of the “Gateways” to the community.
- ▶ Formulate an individual “Gateway Corridor” strategy for each of the four (4) designated “Gateways.”



KEY ECONOMIC SECTORS

Education/Research

- ▼ Work with App State to capitalize on University research opportunities.
- ▼ Strengthen the alliance with Appalachian State University and Caldwell Community College & Technical Institute to understand and attain education and skill levels needed by Watauga residents.

Medical/Research

- ▼ Watauga County should collaborate with medical professionals and UNC Health - Appalachian to facilitate a “medical cluster” concept to further develop the groundwork that has been laid in making Watauga County a regional medical center.
- ▼ Encourage Appalachian State University and Caldwell Community College & Technical Institute to explore new healthcare ventures related to the nursing programs at each institution.
- ▼ Focus on and promote activities and businesses that are involved in technology, research, education and medicine.

Tourism and Recreation


- ▼ Capitalize on existing tourism by encouraging the Tourism Development Authorities to enhance and increase strategic marketing of Watauga County.
- ▼ Fully develop and promote the greenways concept such as the greenway connector near the high school, trails, parks and other eco-tourism assets. These assets are especially important in promoting a healthy lifestyle and quality of life themes.
- ▼ Promote eco-tourism, defined as “environmentally responsible travel and visitation to natural areas,” in order to
- ▼ Enjoy and appreciate nature (and any accompanying cultural features).

Industry and Business

- ▼ Expand and strengthen support between the community and existing businesses and industry to reassure businesses that their presence is appreciated and their needs are considered.

Agriculture

- ▼ Promote the production of agricultural products to capitalize on the growing demand for local food products. Conduct relevant market research to support a marketing strategy for such products.
- ▼ Find effective ways to facilitate the local farmers markets, and related efforts of the Watauga County Cooperative Extension. The Farmer’s Market has grown beyond the capacity of the initial site and a new location is warranted to enable the market to re-consolidate and continue to grow. A strategy is proposed that addresses a new location with expanded hours of operation and greater diversity of products.
- ▼ Promote and explore opportunities in niche markets of food production, such as herbs and spices, grapes (vineyards), strawberries, blueberries, raspberries, and local vegetables, and promote as local foods.
- ▼ Work with local agricultural interests to create an interest group committee to promote Agritourism and sponsor demonstration projects, such as organic gardening with a living historic farm.



Section 5

Water and Sewer



WATER AND SEWER

Preface

Water is a valuable and precious resource. Stress caused by increasing population and dwindling resources due to drought, pollution and misuse should cause us to look closer at how we use and protect our water resources.

- ▼ Within the County, four municipalities provide water services and three municipalities provide sewer services. Appalachian State University provides its own water supply.
- ▼ The adequacy of water and sewer is essential for commercial or residential growth. The provision of water and wastewater to areas outside of municipalities is of strategic interest to the County.

Findings – Water


- ▼ The National Integrated Drought Information System (NIDIS) has assigned Watauga County a drought rating of D-1 meaning the County is currently in a moderate drought . The County has been designated D1, D0 (Abnormally Dry), or “none” since 2016 when the county was briefly a D2 (Severe Drought).
- ▼ As part of a USDA Raw Water Project, the town of Boone constructed the Greg Young raw water intake facility on the New River. The project, completed in 2020, along with upgrades to the existing Ricky L. Miller Water Treatment Plant, expanded the Town’s water capacity from 3.0 million gallons per day (MGD) to 4.5 (MGD).
- ▼ The Greg Young New River Intake is now Boone’s primary water source providing 99.4% of their water in 2023 per the Division of Water Resources 2023 Local Water Supply Plan. The Town has two other intakes, Southfork Intake, providing 0.4% of the Town’s water supply in 2023 and Winkler Creek Intake, used only for emergencies.
- ▼ Water and sewer lines have been installed in recent years along the NC 105 corridor to the top of Rock Crusher Hill.
- ▼ Boone and Watauga County are presently considering the development of water supply lines along the U.S. 321 and 421 corridors.
- ▼ The water supply for Beech Mountain comes from Buckeye Lake which is located within the Town limits and some 2,000 feet below and five miles away from the Town Center.
- ▼ The water supply for Seven Devils is provided by wells with storage tanks owned by the Town.
- ▼ Several large developments provide water to their residents, including Hound Ears, Echota, Mill Ridge, Blue Ridge Mountain Club, and the Ponds.
- ▼ Watauga County is currently not a purveyor of water services.



Findings – Sewer


- ▼ The Town of Boone provides wastewater treatment to residents and businesses within the Town’s limits.
- ▼ Appalachian State University relies upon the Town of Boone for provision of sewer service.
- ▼ The Town of Blowing Rock provides sewer services to most residents within the Town’s limits, but none outside of the Town.
- ▼ Beech Mountain provides sewer services to most properties in the Town.
- ▼ Seven Devils does not provide sewer services. However, there are two private sewer systems serving certain parcels.
- ▼ Wastewater treatment systems and service are not available to most residents and businesses outside the municipalities. Private communities providing wastewater treatment include Hound Ears, Echota, Mill Ridge, Blue Ridge Mountain Club and the Ponds.

Illustration 16 Water and Sewer



Recommendations

- ➔ The County should continue in an undefined role regarding water and/or sewer projects.
- ➔ The County should promote sound water and sewer intergovernmental cooperation, facilitating needed and feasible development of infrastructure and services in areas not currently served.
- ➔ Watauga County should expect and plan for future strategic investments in the planning and the development of water and sewer infrastructure and services for areas of the County not presently served (where feasibility can be demonstrated).
- ➔ The ownership or resulting infrastructure should be assumed by existing service providers.
- ➔ Watauga County should work with municipalities to help guide water and sewer to areas targeted for economic development and affordable housing.
- ➔ Watauga County should make conservation and protection of water resources a principal goal.
- ➔ Watauga County should provide for the proper disposal of chemicals and substances likely to end up in the water supply by making disposal of such items easier and more convenient, and by increasing the frequency with which toxic substances can be disposed of at the landfill and convenience sites.
- ➔ Watauga County should encourage the use of indigenous vegetation for landscaping. Planting vegetation that is not indigenous to the area may require more water.
- ➔ Watauga County should seek grants and other funding to help with the expansion of municipal service to unserved areas.
- ➔ Watauga County should encourage an intergovernmental endeavor to develop a 10 year Capital Improvement Plan in the interest of economic development and public health.



Section 6

Key Community Services



KEY COMMUNITY SERVICES

Preface

Key community services provided by Watauga County include schools, law enforcement (Sheriff’s Office), emergency services and community centers.

KEY COMMUNITY SERVICES - SCHOOLS

- Watauga County elementary schools have 3,057 students in grades kindergarten through eight. The high school enrollment includes 1,245 students in grades 9 -12 (2024 - 2025 school year) with an additional 15 enrolled in Watauga Virtual Academy, and 272 in Watauga Innovation Academy, a partnership with CCC&TI. Pre-kindergarten students also attend the elementary schools.
- A new state-of-the art building is under construction to replace Valle Crucis Elementary School with occupancy planned during the 2025-26 school year.
- Enrollment in Watauga County schools is projected to be relatively stable over the next few years, indicating no need for additional schools in the short-term.
- The eight elementary schools are located throughout the County (Illustration 17) and conveniently serve most communities. In addition, Watauga County Virtual Academy is available for grades K-8 and is intended as an opportunity to serve families who need more flexibility in delivery.
- The Watauga County School system has a Facilities Improvement Plan outlining capital improvement needs for facilities.
- Based on 2024 “End-of-Course” test results for grades 3-8, Watauga County students had a higher percentage of students in

Level 4 (Through understanding of grade-level content) and Level 5 (Comprehensive understanding) than the state average in math, reading, and science. Watauga students in grades 8-12 scored higher in Biology, English, and Math than the average of students in all North Carolina schools.

- In 2024, High school students scored an average of 1,210 on SAT exams, which combine math and critical reading. This is compared to SAT scores averaging 1,166 for all North Carolina students.
- In 2024, Watauga County high school students scored an average of 19.8 on the ACT exam, compared to the state of North Carolina average of 18.1. The ACT assesses English, math, reading, and science proficiencies.
- The Watauga County graduation rate was 90.3% in 2024 compared to 87.0% for North Carolina.



Photo By: Element5 Digital

Recommendations - Schools

- ➔ Implement the following capital improvement projects listed in the Watauga County School Facilities Improvement Plan:
 - ➔ Construct an addition to Parkway Elementary School
 - ➔ Repair the roof at Green Valley Elementary School
 - ➔ Repairs to existing facilities for more utility efficiency
 - ➔ Install air conditioning at the following schools
 - ▾ Green Valley Elementary School (2025/2026)
 - ▾ Bethel Elementary School (2025/2026)
 - ▾ Blowing Rock Elementary School (2026/2027)
 - ▾ Cove Creek Elementary School (2026/2027)
 - ▾ Mabel Elementary School (2026/2027)

Illustration 17 Schools in Watauga County






Table 22
List of County Schools with Enrollment

ELEMENTARY SCHOOLS			ENROLLMENT SPRING 2025
BETHEL ELEMENTARY	SUGAR GROVE	K-8	127
BLOWING ROCK ELEMENTARY	BLOWING ROCK	K-8	402
COVE CREEK ELEMENTARY	VILAS	K-8	287
GREEN VALLEY ELEMENTARY	BOONE	K-8	294
HARDIN PARK ELEMENTARY	BOONE	K-8	861
MABEL ELEMENTARY	ZIONVILLE	K-8	137
PARKWAY ELEMENTARY	BOONE	K-8	618
VALLE CRUCIS ELEMENTARY	SUGAR GROVE	K-8	331
HIGH SCHOOL			
WATAUGA COUNTY HIGH SCHOOL	BOONE	9-12	1,245
OTHER			
WATAUGA VIRTUAL ACADEMY	ONLINE	K-8	15
WATAUGA INNOVATION ACADEMY	PARTNERSHIP BETWEEN WHS & CCC&TI	9-12+ ASSOCIATE DEGREE	272
TOTAL ENROLLMENT			4,589



KEY COMMUNITY SERVICES - LAW ENFORCEMENT


- ▼ In 2025, the Watauga County Sheriff's office had 55 sworn officers, including one sheriff, 3 captains, 15 detectives and civil officers, 22 shift deputies, and 9 school resource officers.
- ▼ In the Sheriffs' Offices 2020 report produced by the U.S. Department of Justice, the average number of sworn officers for counties with a population between 50,000 – 99,999 is 1.6 per 1,000 residents.
- ▼ Watauga County has a population of 54,784. With 55 sworn officers they are below the average of 86 expected for a county their size. The population figure does not include Watauga County's large number of seasonal residents and tourists, which should be considered in determining the adequacy of services.
- ▼ Additional Deputies have been requested in the 2025-2026 budget. The Department also applies for grants to help obtain equipment and tools used by law enforcement agencies.
- ▼ The Watauga County Detention Center has a maximum capacity of 106 and employs 28 jailers.
- ▼ A study is currently underway to plan for a medical/mental health wing at the Detention Center.
- ▼ Workspace for deputies and other staff is marginally adequate, indicating a probable need for expansion of the existing building/facility in the future. Watauga County deputies regularly respond to a wide range of calls. These include domestic disputes and family disturbances, theft, burglary, and other property crimes, as well as drug-related incidents. Deputies are often called for welfare checks and mental health crises, serving warrants, subpoenas, and other civil papers, and assisting other agencies like Boone Police or State Troopers. They also handle missing person reports in the county's rural and mountainous areas and respond to school-related incidents, whether through school resource officer duties or threats made toward educational facilities. Deputies are often assigned to special community events such as (Emergency Fest, Pill Turn In, and National Night Out) and engage in a lot of under reported community care-taking activities.
- ▼ There is now a dedicated transport officer that oversees most out of county transportation of mental commitments, prisoner transports, and pick-ups.
- ▼ The Narcotics division is dealing with narcotics entering Watauga County from a multitude of locations some from transnational organizations. Fentanyl is of great concern.
- ▼ All municipalities in Watauga County have police forces.



Recommendations - Law Enforcement

- Continue to advocate for additional deputies to meet the law enforcement needs and demands of Watauga County
- Continue to pursue the construction of a new medical/mental wing at Detention Center

Illustration 18 Watauga Fire Districts and Station Map



KEY COMMUNITY SERVICES - EMERGENCY SERVICES

Recommendations - Emergency Services

- ▼ Watauga County has a total of 15 fire districts, five of those, Beech Mountain, Creston, Fall Creek, Seven Devils, and Todd are shared with adjacent counties.
- ▼ There are a total of 23 fire stations, 17 of which are in the rural areas of Beaver Dam, Beech Mountain, Cove Creek, Deep Gap, Foscoe, Meat Camp, Seven Devils, Shawneehaw, Stewart Simmons, Todd and Zionville. (Illustration 18)
- ▼ The Beech Mountain, Blowing Rock, Boone, Depp Gap, Stewart Simmons, and Foscoe Fire Departments have at least one paid staff who work with volunteer firefighters. All of the other districts are strictly volunteer.
- ▼ All fire districts outside of municipalities in Watauga County are fire tax supported districts.
- ▼ The large amount of training required to become a volunteer firefighter, the time required away from primary jobs to fight fires, and the expense of travel to and from emergency calls often hurts retention of volunteer firefighters.
- ▼ For many years Watauga County's ambulance and rescue service has been a paid, contracted service with the Watauga County Emergency & Rescue squad acting as a backup.
- ▼ In June 2025, Watauga County Board of Commissioners voted to purchase the private service with their fleet of nine ambulances and station. The transition from private to public ambulance service will occur in late 2025 and early 2026.
- ▼ Meat Camp has a new station that just opened in early 2025.
- ▼ Deep Gap has a new station planned that should be operational by the end of 2025

- Continue to evaluate the ratio of population to emergency services
- Continue cooperation and coordination between the County and Emergency Services.
- Create an Emergency Services Master Plan for the County to address current and future needs including:
 - ▼ Evaluate the need for paid personnel in fire stations.
 - ▼ Evaluate methods to improve cooperation between the County and Emergency Services
 - ▼ Establish additional water points for retrieving water to fight rural fires.





KEY COMMUNITY SERVICES - COMMUNITY CENTERS

- ▼ Community centers help to promote community identity.
- ▼ Community centers may provide certain benefits such as, but not limited to, a library, meeting space, media center, childcare, senior programs, urgent care and recreation.
- ▼ The Western Watauga Center, operated by Watauga County, serves citizens in the Cove Creek Community.
- ▼ There are two other community centers in Watauga County. One, located at the old Seven Devils Town Hall, is only accessible to Seven Devils property owners. The other center, Foscoe-Grandfather Park and Community Center is a multi-use facility run by a non-profit and open to the public and located off NC Hwy 105 in Foscoe.
- ▼ Community centers play a vital role in the development of shared community identity, community pride, community preservation and community growth.
- ▼ In community surveys citizens expressed a desire to have a community center in eastern Watauga County.
- ▼ Schools are the main focal point and center for social activities in most Watauga communities.

Recommendations - Community Centers

- ➔ Assess the need and financial viability for a community center in eastern Watauga County similar to the Western Watauga Center.
- ➔ Establish a plan for greater cooperation between schools and communities for use of County school facilities.
- ➔ Facilitate community centers that are attractive, functional, visible, safe and accessible to their communities and reflective of each community's unique identity.

Other Human Services

- ▼ Although beyond the scope of the Plan, maintaining the “quality of life” in Watauga County must consider other human social needs, such as care for children and the elderly, health care and other fundamental human needs.
- ▼ An in-depth assessment of such needs and a plan for addressing the most pressing humanistic issues should be undertaken in the future.





**Section 7
Affordable Housing/
Workforce Housing**



AFFORDABLE HOUSING

Preface

The rich heritage of Watauga County coupled with its physical beauty, easy lifestyle and vast number of cultural and recreational opportunities make it an inviting place to live. As the popularity of mountain properties grow, and student and seasonal populations increase, so do the prices for purchasing or renting housing. A common complaint in the County is that affordable (or workforce) housing is difficult or impossible to find.

Findings

- ▼ Making affordable housing a priority in Watauga County is not an easy task. It involves many governmental entities, regulations, competing land uses, and the developers who seek the highest return for their investments.
- ▼ Planning for affordable housing for future residents will require a proactive approach.
- ▼ Recent survey responses for the Watauga County Comprehensive Plan confirm that Watauga County citizens agree that the County needs affordable-housing, and that it is one of the top concerns for the future.
- ▼ Housing is the greatest single expense for most residents in Watauga County and is often a major consideration among people who want to relocate to the area.
- ▼ In 2022 the volunteer led Watauga Housing Forum led to the establishment of a non-profit, the Watauga Housing Council. The Watauga Housing Council meets monthly with a mission to increase the housing supply for residents who are cost burdened, through partnerships and systematic change.

- ▼ Ideal sites for affordable housing would be near towns to eliminate travel time to and from employment, merchants and services.
- ▼ Rural areas may provide the most potential for affordable housing ventures.
- ▼ Emphasis should be given to both renters and owners of affordable housing.
- ▼ Comments from County stakeholders favor more single-family and multi-family developments with a focus on workforce housing and discouraged apartment complexes and short-term rentals.





Recommendations

- Ensure that subdivision regulations and other land use ordinances do not serve as barriers to the construction of affordable-housing. Rather, craft regulations and ordinances to favor affordable-housing.
- Promote mixed-land uses that incorporate housing with other uses that can be blended without sacrificing safety, health and welfare of citizens.
- Allow a broad range of housing choices in Watauga County ordinances. Encourage duplex, triplex and quadraplex development. Encourage higher density multi-family housing to reduce the cost of land per unit.
- Ensure that current and future regulations provide sufficient opportunities for nursing homes and other similar care facilities.
- Develop a county wide affordable housing plan in cooperation with municipalities.
- Investigate state and federally funded programs that assist in housing rehabilitation.
- Lead in establishing an affordable housing trust fund in cooperation with municipalities and the County and seek external funding from other sources.
- Preserve existing housing stock and address substandard housing wherever possible.



Section 8 Preservation of Community



PRESERVATION OF UNIQUE COMMUNITY IDENTITIES AND HERITAGE

Preface

Community identity is defined as the collection of attributes that makes a community unique and separates it from other places. In Phase 1 of the original “Citizens’ Plan for Watauga,” citizens expressed their interest in preserving the unique community identities and heritage of the County. Phase 1 community meetings revealed that citizens take great pride in their communities and believe, regardless of which neighborhood they live in, that theirs is the best part of Watauga County.

Citizen participants in a recent survey continued to express a desire to preserve rural areas, to be a destination remembered for its culture and history, to retain its natural beauty, and to preserve its Appalachian roots. It is important that communities preserve their culture and history for future generations.

Findings - Community Identities

- ▼ According to the North Carolina State Historic Preservation Office, the National Register is an official listing of “buildings, structures, objects, sites and districts worthy of preservation for their significance in American history, architecture, archaeology, and culture.
- ▼ The Valle Crucis community took steps toward preservation by creating the Valle Crucis Historic District – the first rural historic district in North Carolina. The entire community is listed on the National Register of Historic Places.

- ▼ Valle Crucis adopted a “Historic District Ordinance” on September 1, 1990, which provides for preservation and protection of the heritage of the community, protection of properties, conservation of the district for education, pleasure and enrichment, fostering civic beauty, and improvement of the general health and welfare of the residents.
- ▼ The Todd community is on the National Register of Historic Places and has been also been designated a Historic District.
- ▼ Watauga County has “Community Planning Guidelines” for developing a system of community planning. These guidelines were adopted in 1986.
- ▼ Several unincorporated communities in Watauga County have cultural, historical or architectural significance and contribute to the quality of life for residents and tourists. Such communities include Beaver Dam-Bethel, Cove Creek, Deep Gap, Elk, Foscoe-Grandfather, Mabel, Matney, Rutherwood, Stony Fork, Sugar Grove, Todd, Triplett, Valle Crucis, Vilas, Zionville and others.
- ▼ In many communities, schools are the main focal point and center for social activities.
- ▼ Residents feel strongly that newcomers to the area would benefit from education about mountain traditions and attitudes.
- ▼ Community planning districts (Illustration 19) have been established in Foscoe, Cove Creek and Valle Crucis.
- ▼ The Watauga County Tourism Development Authority (TDA) installed a series of “wayfinding” signage along the corridors into Watauga County identifying cultural and recreational opportunities in the area.




Recommendations

- Create a strategy for preservation of unique communities that identifies and promotes preservation of significant historic, scenic and cultural features. Encourage restoration and use of historic sites and community landmarks to foster community identity.
- Review the Community Planning Guidelines to determine if the guidelines are still appropriate for current needs in the County.
- Develop Small Area Planning guidelines and initiatives to guide land use, open space, transportation improvements, capital improvements and identify opportunities for preservation and revitalization.
- Enhance community-gathering points at convenient locations.
- Explore whether some school sites could be utilized to accommodate facilities necessary for other community programs, such as community center facilities, park/ school combinations, libraries and daycare.
- Design and locate public spaces and buildings to reinforce and express Appalachian Heritage/Culture.
- Implement programs for removing unattractive elements, such as illegal signs, graffiti, litter, utility poles and billboards, as feasible.
- Promote art and cultural opportunities at appropriate public and private locations in unique communities.





Illustration 19 Historical Sites and Districts



BETHEL

Wilson - Vines House (Roby Vines House)

SUGAR GROVE

Cove Creek High School
Ben Farthing Farm
Ward Family House

BOONE

The John Smith Miller House
U.S. Post Office
Jones House
Blue Ridge Tourist Court

TODD

Todd Historic District
A.S. Cooper Farm (partial)

VALLE CRUCIS

Valle Crucis Historic District
Mast Farm
Mast General Store
Valle Crucis Episcopal Mission
Blair Farm

BLOWING ROCK

Randall Memorial Building (Village Cafe)
Bollinger-Hartley House
Green Park Historic District
Green Park Inn
Gragg House
Vardell Family Cottages District
East Tennessee and Western North Carolina
Railroad Locomotive #12
Westglow
Flat Top Estate (Moses H. Cone Memorial Park)



PRESERVATION OF FARMLAND

Preface

Preserving community identity and the County’s unique heritage is a worthy endeavor.

Findings


- ▼ The Voluntary Farmland Preservation Program is an instrument designed “to encourage the voluntary preservation and protection of farmland from non-farm development.”
- ▼ The Watauga County Board of Commissioners adopted the Farmland Preservation Program in October 2000.
- ▼ Participants in the Voluntary Farmland Preservation Program must also be participants in the Present Use-Value taxation program.
- ▼ An Agricultural Advisory Board reviews and approves applications for qualifying farmland and the establishment of voluntary agricultural districts, which consist of at least 25 acres of qualifying farmland located within one mile of each other.
- ▼ Participating landowners sign agreements to sustain, encourage and promote agriculture.
- ▼ The land must be certified by the Natural Resources Conservation Service as appropriate for the Voluntary Farmland Preservation Program.
- ▼ The Voluntary Farmland Preservation Program members are subject to a conservation agreement between the County and the landowner that prohibits non-farm use or development of that land for a period of at least 10 years.
- ▼ As of July 2025, 131 farms with a total of 8,057 acres are enrolled in the Voluntary Farmland Preservation Program.

Recommendations

- ➔ Promote the Watauga County Voluntary Farmland Preservation Program and work to ensure the Soil and Water Conservation office continues to provide education and opportunities for individuals interested in the program.
- ➔ Support the Soil and Water Conservation office in its efforts to provide information about the Agriculture Cost Share Program (ACSP). This program is voluntary and is designed to protect water quality by installing best management practices on agricultural lands.
- ➔ Promote and educate citizens on the benefits of establishing conservation easements by involving local land conservancies and Soil and Water Conservation personnel.
- ➔ Promote the use of the Present-Use-Value taxation program.



Photo By: Ellia Oakes



Section 9 Parks and Recreation



PARKS AND RECREATION

Preface

Watauga County is a wonderful place for those seeking outdoor recreational activities. Preservation and promotion of recreational endeavors is of great importance to sustaining the quality of life theme. Recreational activities are also vital to the economic well-being of Watauga County. Most of these activities relate to the natural environment. They include opportunities such as hiking, biking, fishing, rock climbing, canoeing, rafting, kayaking, hunting, skiing, sledding, snowboarding and others.

Findings

- ▼ The Parks and Recreation Department, which was formed in 1973, is advised by an 18-member Recreation Commission, and appointed by the Watauga County Board of Commissioners.
- ▼ The commission's role is to guide and advise the Parks and Recreation Department in its mission to provide for adequate recreational opportunities for all citizens of the County.
- ▼ Table 24 provides a summary of the recreation facilities that are presently operated by the County and other public organizations.
- ▼ Several of the facilities in Watauga County offer specific recreational opportunities:
 - ➔ Rocky Knob Park is a 100+ acre mountain bike park with more than 10 miles of single-track mountain bike trails.
 - ➔ The Ted Mackorell Soccer Complex offers three soccer fields and is not only used for tournament play, but also by Appalachian State University and Lees-McRae College. (*HC Soccer Association*)

- ➔ The Middle Fork Greenway – a multi-use trail under development. It will eventually connect Boone and Blowing Rock.
- ➔ Tot Lot – Playground for 2-12 year olds.
- ➔ New River & Watauga River Accesses – Four public access points to the rivers for tubing and kayakers.

Watauga County Parks and Recreation Department

- ▼ The Parks and Recreation staff offers both adult and youth team sports and programs and special events.
- ▼ The athletic opportunities for adults include softball, basketball, soccer, co-ed volleyball, pickleball, and dodgeball.
- ▼ Youth athletics include tball, softball, baseball, coed, girls, & boys basketball, flag football, and co-ed, girls, & boys soccer.
- ▼ In 2021 Watauga County opened the new, state-of-the-art Watauga County Recreation Center. The Center features four indoor basketball courts, two swimming pools, weight room, and workout facilities. Outside there is outdoor basketball, tennis, pickleball, playgrounds, five baseball/softball fields, picnic shelters, and access to the Boone Greenway.
- ▼ The Parks and Recreation Department offers a variety of summer camps each year such as Adventure Camp, Fun in the Sun Camp, Teen Extreme Camp, and Extreme Dance Camp.
- ▼ In the Watauga County Comprehensive Plan survey popular changes/upgrades to current recreational opportunities/facilities include:
 - More Greenways
 - Repair and/or upgrade to existing facilities



- More hiking trails
- More safe bike lanes on the roads
- More public river access points (New River & Watauga River)

The mission statement of Watauga County Parks and Recreation is:

“The Watauga County Parks and Recreation Department strives to provide a wide variety of quality recreational programming opportunities in the areas of arts, youth and adult athletics, special programs, special events, special populations including Special Olympics, aquatics, and summer youth camps. The department’s mission is for these programs to be enjoyable, fun, fulfilling, safe and rewarding for all Watauga County citizens.”



In 2023, with assistance from High Country Watauga County

Council of Governments, Watauga County adopted a Comprehensive Systemwide Parks and Recreation Plan. Based on the citizens’ survey, community meetings, staff observations, recreation commission comments, facilities inventory, demographic trends, and stakeholder comments, the following recommendations were suggested:

Recommendations

- Construct outdoor restrooms at Complex 2 & 3 fields
- Update/revamp Old Cove Creek School outdoor amenities
- Construct an indoor practice/playing field for baseball, softball, football, soccer, etc.
- Add/replace fitness equipment in the recreation center
- Restore/preserve streambanks near the armory, Brookshire Park, and Old Cove Creek School fields.
- Upgrade Tot Lot playground with inclusive features
- Hire additional full-time staff for the recreation center
- Hire additional full-time staff for the parks and recreation department, specifically a camps/special events coordinator.
- Establish a disc golf course
- Construct outdoor bocce courts
- Integrate Middle Fork Greenway, Howards Knob Park, and outdoor recreation areas into Watauga Parks and Recreation programming.
- Construct a stand-alone building for camps, meetings, and special events.
- Construct an outdoor sand volleyball court
- Enhance the landscaping at the Watauga County Community Recreation Center
- Construct an additional multipurpose room onto the Recreation Center
- Continue to support the construction of the Middle Fork Greenway
- Continue to implement recommendations in the Howard's Knob Park Master Plan
- Support efforts to establish the Deep Gap Community Recreation Area



Table 23

Recreational Facilities Owned and/or Operated by Watauga County

Facility	Restrooms	Playground	Hiking/Walking Trails	Mountain Bike Trails	Picnic Shelters	Picnic Tables (no shelter)	Baseball/Softball Fields	Athletic/Soccer Fields	Multipurpose Field	Tennis Court	Basketball Court	Pickleball Court	Fishing	River Access	Walking Track	Gym	Swimming Pool
Watauga Community Recreation Center												4					2
Recreation Complex					3					4		2					
Industrial Fields							2										
Anne-Marie Fields						4	2										
Brookshire Park																	
Ted Mackorell Soccer Complex																	
Rocky Knob Mountain Bike Park																	
Middle Fork Greenway																	
Watauga River Access at Guy Ford Rd																	
Watauga River Access at Watauga River Rd.																	
New River Access at Pine Run Rd																	
Watauga River Access at Valle Crucis																	
Howards Knob Park																	
Old Cove Creek School Park						4				2							
Health Department Field																	
Green Valley Elementary School Park																	
Hardin Park Elementary School Park																	
Parkway Elementary School Park		2															
Cove Creek Elementary School Park																	
Watauga High School						13	2			6							
Bethel Elementary School Park		2															
Mabel Elementary School Park									3								
Blowing Rock Elementary School Park																	
Valle Crucis Elementary School Park																	




Table 24 Other Recreational Facilities Located in Watauga County

Facility	Restrooms	Playground	Hiking/ Walking Trails	Mountain Bike Trails	Picnic Shelters	Picnic Tables (no shelter)	Baseball /Softball Fields	Athletic/ Soccer Fields	Multipurpose Field	Tennis Court	Basketball Court	Pickleball Court	Fishing	River Access	Walking Track	Gym	Swimming Pool
Boone Greenway Trail																	
Jaycess Park																	
Strawberry Hill Arboretum																	
Junaluska Park																	
Clawson Burnley Park					2	24											
North Street Park																	
Jones House & Grounds																	
Rivers House Park																	
Memorial Park										2	2						
Broyhill Park																	
Davant Field																	
Robbin's Pool																	
Annie L. Cannon Memorial Garden																	
Glen Burney Trail																	
Koerschner Memorial Garden																	
American Legion Building																	
Blowing Rock Clubhouse																	
Blowing Rock Recreation Center																	
Buckeye Recreation Center																	
Lake Coffey																	
Hayden's Park																	
Beech Mountain Hiking Trails																	
Beech Mountain Sledding Hill																	
Otter Falls Trail																	
Seven Devils Old Town Hall																	
Black Bear Family Park										2		2					
Alpine Meadows Mini Park																	
Valle Crucis Community Park		2			2	9											
Mountaineer Ruritan Club Field																	
Green Valley Community Park																	
Foscoe/Grandfather Community Center & Park																	
Elk Knob State Park																	
Grandfather Mountain State Park																	
Blue Ridge Parkway (within Watauga County)																	
Cone Park Carriage Trails																	
Price Park Picnic Area						100											
Price Park Trails																	
Tanawha Trail																	
NC Mountain-to-Sea Trail																	



Parks and Recreation

Illustration 20 Parks and Recreation



The map shows the distribution of parks and recreation sites in Watauga County that are owned and managed by federal, state and conservation organizations.

A scenic landscape photograph featuring a wooden fence in the foreground, a tree trunk on the right, and a mountain range in the background under a clear sky. The text is overlaid in the bottom left corner.

**Section 10
Managing Change in
Watauga County**



PREPARING FOR CHANGE

Natural Limitations

Understanding the interrelationship among the various natural or physiographic and other factors that influence future growth and change is an essential step in the process of preparing for managing change. The initial step in this process is to view these physiographic influences in terms of their collective capability to withstand change created by various levels of land use or future development:

- ▼ Using Geographic Information System (GIS) technology, one is able to layer the various maps showing the components.
- ▼ The series of natural limitations are interrelated.
- ▼ They build on one another to present a composite view of the overall capacity of land within Watauga County to withstand or support changes.
- ▼ Understanding these relationships is fundamental to managing such change in the future

MANAGING CHANGE IN WATAUGA COUNTY

Preface


Change is inevitable in Watauga County; however, future change can be influenced by many factors, which may be altered or utilized to direct or mitigate such change. This fundamental assumption is the basis for managing change. The principal factors that influence change include:

- ▼ Transportation Routes
- ▼ Physiographic Constraints
- ▼ Public Policy
- ▼ Water and Wastewater Infrastructure
- ▼ Centers of Employment
- ▼ Proximity to Urban Centers
- ▼ Community Facilities (including schools)
- ▼ Land Use Regulations
- ▼ Public Health Regulations



The planning, placement, modification or enforcement of such influences become primary tools that are available to the community in managing change. It is therefore incumbent upon Watauga County to recognize the importance of acknowledging and managing these factors of change and deliberately planning for their impacts.

Illustration 21 Areas for Development and Unsited Areas



The categories of suitability of land for development for Watauga County may be explained as follows:

Areas Best Suited for Development

Land areas that have few constraints for development activity. With appropriate services, such land could best accommodate future change (Illustration 21).

Areas Least Suited for Development

Land that has limited or no development potential because of severe physiographic challenges or other impeding limitations, such as land under public ownership. These areas also encompass protected ridge tops and flood zones.



Growth Objectives for the Community

Achieving balance between fostering change and protecting community values and important economic, environmental and cultural resources is the foundation of change management. The following objectives are intended to guide the County:

- ▼ Population growth should be concentrated in areas of Watauga County where essential services and infrastructure are adequate to meet the needs of future populations. Population and development densities should vary in accordance with the availability of such services and infrastructure, with more dense concentrations of development being directed to locations where essential services and infrastructure may be provided most efficiently.
- ▼ Extension of essential services and infrastructure should be planned to support future growth within these designated concentrations of development, with such extensions being guided by deliberate policies that acknowledge efficiency and change management strategies.
- ▼ Growth in rural areas of the community, outside of planned concentrations of development, should be managed to occur at densities that do not require inefficient investments in essential services and infrastructure.
- ▼ Growth outside of planned concentrations of development should not infringe on prevailing agricultural or rural land use patterns in such rural areas.
- ▼ Growth management in both urban and rural areas of the community should be sensitive to valuable environmental, cultural, or historic resources and assets.





Acknowledging Municipal Planning Jurisdictions

Managing change should reflect a regional strategy. Therefore, planning for Watauga County's growth should consider similar endeavors across governmental jurisdictions. It is incumbent upon County government to consult with its political neighbors as it plans for its future growth. Its plans and policies should efficiently and effectively mesh with those of the municipalities within Watauga County.

At present, the four municipalities of Boone, Blowing Rock, Beech Mountain and Seven Devils each have land use plans, land use regulations and various other ongoing planning activities that are in place and reflect their individual objectives and policies regarding managing growth and influencing change (Illustration 22). Further, Blowing Rock and Seven Devils have extraterritorial jurisdictions within which they plan and administer land use regulations.



Illustration 22 Municipal Planning Jurisdictions





The County's Growth Management Policy should:

- ▼ Acknowledge these individual municipal planning jurisdictions.
- ▼ Reflect the current plans that have been adopted for each municipal jurisdiction.
- ▼ Strive to ensure that County plans and recommendations for those areas of Watauga County that are adjacent to municipal jurisdictions are consistent with municipal planning.
- ▼ Coordinate plans and recommendations for essential services and infrastructure with corresponding plans for the municipal jurisdictions.
- ▼ Strive for regional or countywide solutions to planning and urban services.
- ▼ In the absence of municipal plans for essential services and infrastructure, the County should coordinate its planning with the affected municipality.

MANAGING FUTURE CHANGE IN WATAUGA COUNTY

The County's strategy for managing change is developed to reflect the diversity of the community and to provide for a logical approach to addressing this diversity of needs and the wide range of factors that influence and direct growth under these unique conditions.

Watauga County is a community in transition. It has evolved from a principally rural environment into a community that is typically urban along its principal highway corridors and progressively more rural and agricultural as distances increase away from those transportation corridors. This urban / rural setting, coupled with its complex physiographic limitations, provides a great challenge.

Growth management issues in the community are complex. A single planning model for the County is probably not adequate to comprehensively address the requirements of this transitional planning environment. Therefore, multiple planning paths may better provide for the flexibility to address the range of factors and issues that are presented to the community.

Emphasis should be directed toward achieving change that reflects sustainability in future development and ensures a minimal disruption to the natural environment and maximize use of energy, land resources and other natural and community assets.

The Change Management Strategy for Watauga County divides the County into three Growth Paths, acknowledging the range of planning objectives and developmental environments throughout the community:

- ▼ The Watauga "Gateway Corridors"
- ▼ Unique Community Areas
- ▼ Rural / Agriculture Regions

Illustration 23 Community Planning Districts




Illustration 23 presents the locations and extent of two of the three community planning districts in Watauga:

- ▼ No regulations have been adopted for the Cove Creek Community Council District.
- ▼ The Valle Crucis Community Council District is primarily dedicated to historic preservation. It contains a designated historic district zone.
- ▼ The Foscoe-Grandfather Community Council District is divided into four zones, as shown on Illustration 23.



WATAUGA GATEWAY CORRIDORS

Watauga County is characterized by distinct and constantly changing primary transportation corridors, which include key segments of highways 421, 321 and 105. These corridors are considered the strategic or key Gateways to the community and managing change within these so called “Gateway Corridors” should be guided by the following principles:

Population

- ▼ The average population densities achieved in these “Gateway Corridors” are, or will in the future, be substantially higher than other regions of the County and generally fall into a range of 500 to 900 persons per square mile.

Land Use Patterns

- ▼ Land use patterns will be generally more complex with wide ranges of residential densities, substantial commercial concentrations, as well as industrial and institutional complexes.
- ▼ Within these “Gateway Corridors,” the County and its municipalities should aggressively avoid conflicting land uses and maintain minimum standards of quality for development.

Economic Development

- ▼ The County’s economic development activities should be aggressively pursued within the Watauga “Gateway Corridors.”
- ▼ Care should be taken to protect areas identified as prime industrial land or key economic assets.
- ▼ Appropriate infrastructure should be developed to sustain this ongoing and planned economic development program. However, investments in public infrastructure should be cost-effective,

with economic benefits to the Community outweighing the costs of new investments in infrastructure.

- ▼ A formula should be developed to assess this cost/benefit ratio, and the County should utilize a concise policy to guide in its future capital investments in economic development related services and infrastructure.

Essential Services

- ▼ Development within these “Gateway Corridors” would be accessible by highways and streets, which are developed to urban standards, having capacities to accommodate increasingly complex volumes of traffic.
- ▼ Development within this growth path should be served by water and sewer infrastructure, except for areas that are deemed infeasible to receive such services due to excessive cost, incompatible slopes, or factors, which serve to isolate certain areas from essential services.
- ▼ Transportation, water and sewer planning should be conducted within a regional framework, with active participation by all units of local government. The County should assume a leadership role in such planning activities.

Environmental Considerations

- ▼ Managing change initiatives should acknowledge the presence of sensitive natural areas, such as floodplains, wetlands, unique natural assets and areas exhibiting excessively steep topography, and strive to protect these areas from development, which would damage such resources or diminish their integrity.
- ▼ Planning initiatives should attempt to

incorporate natural assets into future preservation projects, such as greenways, parks, conservation easements and other ventures, which would serve to protect such areas from serious damage or destruction.

- ▼ The County's growth management policies and regulations should be reviewed and revised as required to ensure that new growth is both sustainable and minimizes the consumption of valuable resources and energy.
- ▼ The "quality of life" theme should be reflected in all aspects of planning.

Planning and Organizational Structure

- ▼ Much of this "Gateway Corridors" growth path would fall within municipal planning jurisdictions and be managed within the provisions of urban scale guidelines and regulations, including zoning, subdivision regulations, stormwater ordinances, floodplain regulations, local erosion control ordinances, and other such municipal land use standards and guidelines.
- ▼ Planning for areas that fall outside of such municipal planning jurisdictions should be coordinated with municipal programs.
- ▼ Tools used for managing change for areas falling within the County's jurisdiction should be comparable and compatible in approach and intensity to planning conducted within the various municipal jurisdictions, except where the County determines that its requirements should vary from those of adjacent municipalities.
- ▼ A permanent mechanism for ensuring coordination and consistency in planning in this "Gateway Corridor" setting should be implemented to ensure that planning, growth management activities, transportation, water, sewer, schools, housing and other

essential services are conducted within a regional framework. Such a vehicle might be viewed as a Cooperative Planning Council. It would be assigned a formal agenda, by way of an interlocal agreement, for intergovernmental coordination among the local governments that have a direct interest in the "Gateway Corridors".





UNIQUE COMMUNITY AREAS

Beyond the designated “Gateway Corridors” there are other significant areas of Watauga County that are recognized as established rural communities which exhibit unique characteristics worthy of preservation. Although these areas may be isolated from the more developed “Gateway Corridors,” their service needs are not typical of the most rural regions of the County, primarily due to the density of development or other unique circumstances. At present, these unique Rural Communities include Deep Gap, Todd, Valle Crucis, Cove Creek, Foscoe, Matney, Bethel, Zionville and Mabel.

Some of these unique places are located within the designated “Gateway Corridors,” including Deep Gap, Foscoe-Grandfather, and portions of Cove Creek and Zionville. Change in these unique communities would be managed within the parameters established for the “Gateway Corridors.”

Managing change within these Unique Community Areas shall be guided by the following principles:

Population

- ▼ The average development density may be higher than other typically rural regions of the County but would be substantially lower than urban concentrations of population within “Gateway Corridors.”

Land Use Patterns

- ▼ Land use patterns should be managed with conscious efforts to prevent incompatible land uses, maintain low population densities, and preserve the integrity of the Unique Community Areas.
- ▼ The nature of such communities tends to encourage the mixing of land uses, with

limited commercial and service activities inter-dispersed among residential land uses. Unique Community Areas should be more tolerant of mixed land uses, as might be seen in more densely developed areas of the County.

- ▼ As growth continues in these unique communities, commercial development should be encouraged to concentrate in nodes, becoming more isolated from residential concentrations.
- ▼ However, incompatible industrial or other land uses should be avoided in favor of the predominant residential character of these communities.

Economic Development

- ▼ New economic development activities should not be encouraged within the boundaries of Unique Community Areas, which would demand levels of urban services that are not currently present in the community.
- ▼ The natural evolution of commercial activities in Unique Community Areas should not be prohibited, except where such development is incompatible with the character of the community and would tend to damage property values and disrupt the community.

Essential Services and Infrastructure

- ▼ The extent of development in these existing unique communities may dictate certain essential services, including water and sewer, where such services are economically feasible.
- ▼ Such infrastructure should be developed as self-sustaining enterprise funds, which can be supported without subsidy by the larger community.

Environmental Considerations

- ▼ County regulations should acknowledge the presence of sensitive natural areas, such as floodplains, wetlands, unique natural assets and areas exhibiting excessively steep topography, and strive to protect these areas from development.
- ▼ Planning initiatives should attempt to incorporate such natural assets into future preservation projects, such as greenways, parks, conservation easements and other ventures, that would serve to protect such areas from serious damage or destruction.

Planning and Organizational Structure

- ▼ The County should endeavor to establish some level of ongoing community planning within these individual areas, which would reflect a degree of self-determination in decisions relating to planning and services. Such planning structure should be incorporated into the structure of the County's planning program. This level of autonomy might help to avoid future unnecessary incorporation of new municipal governments.
- ▼ The development of new Unique Community Areas should be discouraged by the utilization of planning services and regulations. New Unique Community Areas should be developed only with the provision of essential services and infrastructure by the forces which are responsible for their planning and development.
- ▼ The County should review its present community planning guidelines to ensure that the present ordinance is adequate to meet future needs related to establishing valuable and unique rural communities.





RURAL/AGRICULTURAL REGIONS

All areas that fall outside of the Watauga Gateway Corridors and designated Unique Community Areas would be contained within the designated Rural / Agriculture Regions (Illustration 24).

These areas are predominantly rural and are characterized by low-density residential development with substantial land areas devoted to agriculture and undeveloped forest lands. Growth management within Rural/Agriculture regions is characterized by the following principles:

Population

- ▼ The average population densities within these areas would be less than the Gateway Corridors and Rural Communities growth paths.

Land Use Patterns

- ▼ Development densities should be substantially lower than those for the Watauga Gateways Corridors, so as to avoid future pressures for extending urban services and infrastructure.
- ▼ Development that tends to increase pressure on County government for the provision of essential urban services should be discouraged by policy and by the absence of such urban services and infrastructure.
- ▼ Some mixing of residential and non-residential land uses should be encouraged and provided for in future planning and management of growth. Rural service centers providing limited shopping and services should be encouraged within prescribed guidelines.

Economic Development

- ▼ Except for agricultural business activity, no new large-scale economic development activities, such as industrial parks or shopping centers, should be encouraged within the boundaries of such regions of the County.
- ▼ The natural evolution of economic activity in Rural/Agriculture Regions should not be prohibited, except where such development is incompatible with the character of the area and would tend to damage property values or be incompatible with the predominant agricultural or residential land uses.

Essential Services and Infrastructure

- ▼ No water and sewer services would be promoted or provided by local government within these areas, due to the inefficiencies of providing such services and their ultimate impacts on rural areas. However, this does not preclude the provision of water and sewer services by private providers for specific areas of development that are self-sustaining.
- ▼ Highway transportation would be accomplished principally by two-lane roads that are typically not consistent with urban design standards, except for state highways, which traverse certain areas of the community.


Environmental Considerations


- ▶ Extraordinary care should be taken in these areas to preserve their rural character and to protect valuable farmlands, as well as environmental and cultural resources.
- ▶ The suitability of land within these regions of the County should be a principal consideration in determining appropriate developmental densities and segregation of incompatible land uses.

Planning and Organizational Structure

- ▶ Planning for these regions of the community should be managed within the structure of the Watauga County Planning Board and the County Board of Commissioners.

Illustration 24 Change in Watauga County





Section 11 Implementation



IMPLEMENTATION OF THE WATAUGA COUNTY COMPREHENSIVE PLAN

The “Watauga County Comprehensive Plan” should be the beginning point in a process that carries the community forward into a continuum of deliberate strategies and actions designed to understand, anticipate and manage changes that will occur in the future and to ensure that such change is consistent with the will of the Watauga citizenry and compatible with the fragile natural environment that is the essence of Watauga County.

Public Involvement

The public must be involved in this essential process. This element of awareness and participation is fundamental to the successful implementation of this strategy for managing change.

This Comprehensive plan must be followed by many subsequent initiatives that are necessary to deal with the multitude of details and actions that are intended to carry out the vision. The public must understand that this process is continual and that its role in this process is the most essential ingredient for its success.

Intergovernmental Coordination

▼ A key consideration in achieving a successful process for plan implementation is meaningful and deliberate cooperation among the local governments, and their management and planning staffs, within Watauga County. Mistrust and competition must not be permitted to delay the creation of a productive and innovative solution to achieving a desirable level of information sharing and collaboration among the County, the four municipalities and

Appalachian State University. Suggestions for continuing this important involvement process include:

- ▼ Establish a “Comprehensive Plan” newsletter that would be published quarterly on the County’s website and further distributed in the community. The newsletter would post news related to important planning and change management initiatives and summarize information and events that relate to this theme.
- ▼ Create a “Watauga County Comprehensive Plan” Forum composed of a cross-section of community leaders and citizens in Watauga County, including elected officials, businesspeople, institutional representatives, retirees, youth and others who have stake in managing change in Watauga County. Cultivate an environment in which participation in this forum is both prestigious and meaningful. Meet periodically with this group and present the progress of the preceding year and formulate at least five (5) concrete objectives for the subsequent year.
- ▼ Take planning and information about managing change in Watauga County into the schools. The future of Watauga County rests with our children. They must understand and accept this immense responsibility.




ORGANIZATIONAL CONSIDERATIONS

- ▼ Formalize and enhance the planning consortium among the local governments and App State to foster intergovernmental collaboration on key planning issues that are both current and prominent to the community.
- ▼ Establish quarterly status retreats of the consortium that are managed by a facilitator that rotates annually among the five governments.
- ▼ Formulate specific annual objectives related to plan implementation and sponsor joint participation in work tasks that are of mutual interest to the participants.
- ▼ Assign responsibilities among the participants for staffing and participation in the annual “Watauga County Comprehensive Plan” Forum.
- ▼ Facilitate coordinated involvement in strategic public participation events and processes.

An impression derived during the course of preparing the “Watauga County Comprehensive Plan” is that the County’s planning program has accomplished many objectives and achieved a great deal of success despite limited funding and little notoriety during its brief history. However, there are many recommendations and issues raised within this plan that will bring new pressures and demands to bear on this very streamlined program, which presently assumes responsibility for many aspects of Watauga County government.

This raises the question of how this efficient program will evolve and expand to meet these new stresses and demands. Attention should be given to:

- ➔ Assessing the overall programmatic needs associated with the ongoing planning program and the new initiatives that are associated with this plan.
- ➔ Evaluating alternative organizational options that could address the increased workload demands, to ensure that the program continues to be a viable and creative mechanism for managing change in Watauga County.
- ➔ Establishing an organizational model that would be implemented in phases in the coming years, as the need for growth and change is evident.



In conclusion, Watauga County is a unique and vital place, long appreciated for its natural beauty, vast open spaces, unique climate and wonderful sense of place. Its people and communities are special combinations of independent thinking and an expression of history and values.

It is our good fortune to be part of this diverse community and our responsibility to prepare a prudent and responsible path for change in these times of economic and cultural transition. The approach should be a logical process of understanding, participation, soul-searching and decision-making, which would lead us to the means and will to manage the inevitable changes that will confront this generation and future generations.

It is a challenge that is worthy of our complete attention until we are certain that we can appreciate, protect, and enhance our community and its precious environment and culture.

Photo by William Reinos



WATAUGA COUNTY

*Department of
Planning & Inspections*

126 Poplar Grove Connector Suite 201 • Boone, North Carolina 28607 (828) 265-8043

TTY 1-800-735-2962

Voice 1-800-735-8262

or 711

FAX (828) 265-8080

Memorandum

Date: December 8, 2025
To: Watauga County Board of Commissioners
Deron Geouque, County Manager
From: Jason Walker, Director of Planning & Inspections
Re: Planning and Development Ordinance Changes

A number of Watauga County's development regulations—specifically the Soil Erosion and Sedimentation Control, Flood Damage Prevention, and Watershed Protection ordinances—are based on model ordinances issued by state agencies. The NC Department of Environmental Quality recently revised the model Watershed Protection ordinance, requiring the County to update its own regulations to remain compliant.

In addition, the previous County Attorney advised that the Planning & Development Ordinance should be updated to clearly outline the procedures for obtaining development permits. In response, a new Chapter 24 – Administration is being proposed to address this recommendation. Given these required updates, the Planning Board and Planning Staff also undertook a comprehensive review of the entire Development Ordinance to identify any other needed corrections or improvements.

Over the last two years, the Planning Board and Planning Staff have collaboratively developed the proposed amendments. County Attorney Nathan Miller has reviewed the draft changes. The Planning Board approved the amendments, along with a Statement of Plan Consistency, at its November 17, 2025 meeting; these materials are now being forwarded to the Board of Commissioners for consideration.

Attached are the following items:

- The Planning & Development Ordinance with proposed amendments
- A summary and explanation of the proposed changes
- The adopted Statement of Plan Consistency

The Planning Board is available to participate in a work session should the Board of Commissioners desire one. Planning Staff is also available to answer any questions.

If the Board chooses to move forward with potential adoption of the amendments, a formal public hearing is required. State law mandates that notice of the hearing be published twice, once a week for two successive calendar weeks, with the first notice appearing no fewer than ten days and no more than twenty-five days before the hearing date.

Following the public hearing, if the Board votes to approve or deny the amendments, it must also adopt a plan-consistency statement. This statement must explain how the Board's action is reasonable and in the public interest. A draft plan-consistency statement is included for your review and consideration.



**PLANNING BOARD STATEMENT OF PLAN CONSISTENCY
WATAUGA COUNTY PLANNING & INSPECTIONS DEVELOPMENT
ORDINANCE TEXT AMENDMENTS**

Application #: 27389

Chapter 10 Foscoe Grandfather Zoning:

Article V Section 3(C)

Article VI

Article VI Section 3

Article VI Section 5

Article VI Section 6

Article VI Section 7

Chapter 20 Valle Crucis Historic District:

Article II Section 5(B)

Article II Section 8(B)

Chapter 21 Watershed Protection

Change to comply with State Model

In accordance with NCGS§160D-604, the Planning Board is required to advise and comment on whether a proposed ordinance amendment is consistent with the comprehensive plan and any other applicable long-range county plans. The following statement was adopted by the Planning Board.

The Planning Board finds the proposed zoning amendments to be consistent with the following findings and recommendations from the Citizen's Plan for Watauga:

- The Plan's purpose is to provide a balance between managing change, preserving community traditions, protecting the natural environment and enhancing "quality of life".*
- Retaining and enhancing existing industry and business is fundamental to the County's economic development.*
- Watauga County should make conservation and protection of water resources a principal goal.*

Date

4/19/2025
Richard E. Mattar, Chairman Planning Board



STATEMENT OF PLAN CONSISTENCY
WATAUGA COUNTY BOARD OF COMMISSIONERS
PLANNING & DEVELOPMENT ORDINANCE TEXT AMENDMENTS

Chapter 10 Foscoe Grandfather Zoning:

Article V Section 3(C)

Article VI

Article VI Section 3

Article VI Section 5

Article VI Section 6

Article VI Section 7

Chapter 20 Valle Crucis Historic District:

Article II Section 5(B)

Article II Section 8(B)

Chapter 21 Watershed Protection

Change to comply with State Model

In accordance with NCGS§160D-605, the Board of Commissioners is required to advise and comment on whether a proposed ordinance amendment is consistent with the comprehensive plan and any other applicable long-range county plans. The following statement was adopted by the Board of Commissioners:

The Board of Commissioners find the proposed zoning amendments to be consistent with the following findings and recommendations from the Citizen's Plan for Watauga:

- *The Plan's purpose is to provide a balance between managing change, preserving community traditions, protecting the natural environment and enhancing "quality of life".*
- *Retaining and enhancing existing industry and business is fundamental to the County's economic development.*
- *Watauga County should make conservation and protection of water resources a principal goal.*

Date

Braxton Eggers, Chairman

Explanation of Proposed Changes to Planning & Development Ordinance

Required changes due to state changing Model Watershed Ordinance. Needed to keep us in compliance with requirements.

Minor Errors: incorrect reference, wrong word.

Deleted due to information being moved to Chapter 24 - Administration

Proposed changes to existing regulations. More detail below:

Chapter 2 – Planning Board; Planning and Inspections Department

Move Valle Crucis Historic Preservation Commission guidelines from Chapter 20 Valle Crucis Historic District. This brings all Boards together in one place.

Chapter 5 – Miscellaneous Provisions

Article XIII: Add Section 2 allowing for administrative modification of setbacks. This would allow for minor variances without having to go through quasi-judicial hearing before Planning Board or Board of Adjustment.

Chapter 7 – Definitions: some were left out from previous compiling of all ordinances into one, some are needed due to NCGS language.

Add the following:

- Farm Sign
- Multi-Phased Development
- Outdoor Storage
- Recreation Park Trailer
- Recreation Vehicle (RV)
- Self-Storage Facility
- Site Specific Vesting Plan
- Substantially Commenced
- Vegetative Buffer

Chapter 10 Foscoe Grandfather Zoning:

Article V Section 3(C): Post Construction Stormwater Permits and rules are set by NCDEMLR.

Reword to reflect they are the permitting agency and what they will approve is what is allowed.

Article VI: Correct as multi-family residential requires compliance.

Article VI Section 3: reword and make parking requirements to be the same for all regulations and also match occupancy types from the building code.

Article VI Section 5: Ensure DOT has issued a driveway connection permit before any grading is started.

Article VI Section 6: Match Erosion Control Regulations

Article VI Section 7: Insert missing diagram

Chapter 13 High Impact Land Uses:

Article II Section 2(A): reword and make parking requirements to be the same for all regulations and also match occupancy types from the building code.

Article II Section 2(F): add wording to ensure that screening is maintained. (same wording used in other chapters)

Chapter 14 Manufactured Home Parks:

- Add Recreation Park Trailers to requirements. We are having a large number of “park models” placed throughout the county and as these are not actually as mobile as a Recreational Vehicle recommend better regulating them.

Article IV (B)(4): correct as buffer is required to be 25’ so 20’ is incorrect.

Article IV (G): add wording to ensure that screening is maintained. (same wording used in other chapters)

Chapter 16 Signs:

Article III Section 1(G): Add Farm signs as now added to NCGS 136-32.

Article IV Section 6(F): delete due to Farm signs now being allowed under an exemption.

Chapter 18 Subdivision and Multi-Unit Structures:

Change title to include Planned Unit Developments -clarify these types of development fall under Chapter 18 regulations.

Article V Section 2 (E): Ensure DOT has issued a driveway connection permit before any grading is started.

Article V Section 3(P) & (R): remove duplication

Article V Section 6(D): delete as proposing preliminary plats expire

Article V Section 7: Add expiration of 7 years to Multi-Phase Development

Article V Section 7(A): delete as mylar is no longer required to record

Article V Section 7(A)(13): Add proposed use note to final plat

Article V Section 8: Require filing of final plat within 90 days after approval.

Article VI Section 1(C): Make Board responsible for deciding if traffic study is necessary instead of staff

Article VI Section 1(M): add statement that development names be approved by Emergency Mngt.

Article VI Section 1(R): require right-of-way access to cemeteries when property is subdivided or developed.

Article VI Section 3 Table 1 Notes: delete duplicate information and incorrect septic information

Article VII Section 2(A)(3): add requirement same as subdivision.

Article VII Section 2(A)(5): reword and make parking requirements to be the same for all regulations and also match occupancy types from the building code.

Article VIII Section 3: increase amount of bond and set a time frame as prices for road development can change drastically quickly.

Appendix B: update to match current Erosion Control requirements

Chapter 20 Valle Crucis Historic District:

Article II Section 5(B): reword and make parking requirements to be the same for all regulations and also match occupancy types from the building code.

Article II Section 6 & 7: move to Chapter 3 dealing with Boards so all Boards are together.

Article II Section 8(B)2-7: moved to Chapter 24 Administration

Article II Section 8(B): Add list of minor works that Staff can approve to regulations as only found in Rules of Procedure currently.

Chapter 23 Wireless Communication Towers:

Article V Section 7(C): add wording to ensure that screening is maintained. (same wording used in other chapters)

Chapter 24 Administration:

Chapter added to outline procedures for applying for all permits/approvals covered by the Planning & Development Ordinance. Outlines who approves, different types of hearings, adds some recommended wording and procedures for dealing with site-specific vesting plans. This was done by request of previous County Attorney Chelsea Garrett to have a written policy on what constitutes a complete application and timeframes for approval.



PLANNING AND
DEVELOPMENT
ORDINANCE

Title I Planning and Development Ordinance

CHAPTER 1 AUTHORITY AND JURISDICTION	1
Article I Title of Ordinance.....	1
Article II Authority and Purposes.....	1
Article III Jurisdiction.....	1
Article IV Effective Date	1
Article V Relationship to Existing Ordinances.....	1
Article VI Fees	1
CHAPTER 2 PLANNING BOARD; PLANNING AND INSPECTIONS DEPARTMENT	2
Article I Planning Board Established; Duties.....	2
Article II Planning Board Membership and Vacancies.....	2
Article III Department of Planning and Inspections	5
Article IV Ordinance Administrator.....	6
CHAPTER 3 BOARD OF ADJUSTMENT	7
Article I Establishment of Board	7
Article II Duties of the Board	7
Article III Administration	8
Section 1. Administrative Materials.....	8
Section 2. Presentation of Evidence.....	8
Section 3. Appearance of Official New Issues.....	9
Section 4. Decisions.....	9
Section 5. Appeals in Nature of Certiorari.....	9
Section 6. Standing.....	9
Section 7. Judicial Review.....	10
Article IV Notice of Hearing	10
Article V Voting.....	11
Article VI Variances	11
Article VII Appeals.....	12
Section 1. Designated Board.....	12
Section 2. Standing.....	12
Section 3. Time to Appeal.....	13
Section 4. Record of Decision.....	13

Section 5. Stays.....	13
Section 6. Alternative Dispute Resolution.	14
Section 7. No Estoppel.	14
Article VIII Special Use Permits	14
Article IX Appeals of Board Actions	16
CHAPTER 4 PROCEDURE FOR ADOPTING, AMENDING, OR REPEALING DEVELOPMENT REGULATIONS.	17
Article I Hearing with Published Notice	17
Article II Notice of Hearing on Proposed Zoning Map Amendments	17
Article III Citizen Comments	18
Article IV Amendments	18
Article V Down-Zoning	18
Article VI Plan Consistency	19
Article VII Statement of Board of Commissioners	19
CHAPTER 5 MISCELLANEOUS PROVISIONS	21
Article I Conflict with Other Laws	21
Article II Notices of Violation.....	21
Article III Stop Work Orders	21
Article IV Remedies	22
Article V Penalties	22
Article VI Additional Remedies and Penalties for Soil Erosion and Sedimentation	22
Article VII Severability Clause.....	23
Article VIII Development Approvals	23
Article IX Duration of Development Approval	23
Article X Inspections	23
Article XI Revocation of Development Approvals.....	24
Article XII Development Approvals Run With the Land	24
Article XIII Minor Modifications	24
Article XIV Conditional Districts.....	26
Article XV Determinations.....	26
Article XVI Optional Posting of Signs By Owner	27
Article XVII Word Interpretation.....	27
CHAPTER 6 STATUTORY PROVISIONS.....	28
CHAPTER 7 DEFINITIONS	39

CHAPTER 8 CONTROL OF SOIL EROSION AND SEDIMENTATION....	88
Article I Title	88
Article II Purpose	88
Article III Scope and Exclusions	88
Section 1. Geographical Scope of Regulated Land-Disturbing Activity	88
Section 2. Exclusions from Regulated Land-Disturbing Activity	88
Section 3. Plan Approval Requirement for Land-Disturbing Activity	89
Section 4. Protection of Property	90
Section 5. Plan Approval Exceptions	90
Article IV Mandatory Standards for Land-Disturbing Activity	90
Section 1. Buffer Zone	90
Section 2. Graded Slopes and Fills	91
Section 3. Fill Material	91
Section 4. Ground Cover	92
Section 5. Prior Plan Approval	92
Article V Erosion and Sedimentation Control Plans	92
Section 1. Plan Submission	92
Section 2. Financial Responsibility and Ownership	93
Section 3. Environmental Policy Act Document	93
Section 4. Content	93
Section 5. Soil and Water Conservation District Comments	94
Section 6. Timeline for Decisions on Plans	94
Section 7. Approval	94
Section 8. Disapproval for Content	94
Section 9. Other Disapprovals	94
Section 10. Transfer of Plans	95
Section 11. Notice of Activity Initiation	96
Section 12. Preconstruction Conference	96
Section 13. Display of Plan Approval	97
Section 14. Required Revisions	97
Section 15. Amendment to a Plan	97
Section 16. Failure to File a Plan	97
Section 17. Self-Inspections	97
Article VI Basic Control Objectives	99
Section 1. Identify Critical Areas	99
Section 2. Limit Time of Exposure	99
Section 3. Limit Exposed Areas	99

Section 4. Control Surface Water.....	99
Section 5. Control Sedimentation.....	99
Section 6. Manage Storm Water Runoff.....	100
Article VII Design and Performance Standards	100
Section 1. Non-High Quality Water Zones.....	100
Section 2. HQW Zones.....	100
Article VIII Storm Water Outlet Protection	101
Section 1. Intent.....	101
Section 2. Performance standard.....	101
Section 3. Acceptable Management Measures.....	102
Section 4. Exceptions.....	103
Article IX Borrow and Waste Areas	103
Article X Access and Haul Roads	103
Article XI Operations in Lakes or Natural Watercourses.....	103
Article XII Responsibility for Maintenance	104
Article XIII Additional Measures	104
Article XIV Fees.....	104
Article XV Plan Appeals	104
Section 1. Disapprovals	104
Section 2. Other Disapprovals	105
Article XVI Inspections and Investigations	105
Section 1. Inspection.....	105
Section 2. Willful Resistance, Delay or Obstruction.....	105
Section 3. Notice of Violation.....	105
Section 4. Investigation.....	106
Section 5. Statements and Reports.....	106
Article XVII Stop Orders.....	106
Article XVIII Revocation of Grading Permits	107
Article XIX Building Permits.....	107
Article XX Security Required	107
Article XXI Penalties	108
Section 1. Civil Penalties.....	108
Article XXII Injunctive Relief	110
Section 1. Violation of Local Program.....	110
Section 2. Abatement of Violation.....	110
Article XXIII Restoration After Non-Compliance	110

Article XXIV Effective Date.....	111
CHAPTER 9 FLOOD DAMAGE PREVENTION	112
Article I Statutory Authorizations, Findings of Fact, Purpose, & Objectives	112
Section 1. Statutory Authorization.	112
Section 2. Findings of Fact.	112
Section 3. Statement of Purpose.	112
Section 4. Objectives.....	113
Article II General Provisions	113
Section 1. Lands To Which This Ordinance Applies.	113
Section 2. Basis For Establishing The Special Flood Hazard Areas.	113
Section 3. Establishment Of Floodplain Development Permit.	114
Section 4. Compliance.	114
Section 5. Abrogation and Greater Restrictions.....	114
Section 6. Interpretation.....	114
Section 7. Warning and Disclaimer of Liability.	114
Section 8. Penalties for Violation.	115
Article III Administration.....	115
Section 1. Designation of Floodplain Administrator.....	115
Section 2. Floodplain Development Application, Permit and Certification Requirements.....	115
Section 3. Duties and Responsibilities of the Floodplain Administrator.	121
Section 4. Corrective Procedures.....	123
Section 5. Variance Procedures.	124
Article IV Provisions For Flood Hazard Reduction	127
Section 1. General Standards.	127
Section 2. Specific Standards.	129
Section 3. Reserved.....	135
Section 4. Standards For Floodplains Without Established Base Flood Elevations.	135
Section 5. Standards For Riverine Floodplains With Base Flood Elevations But Without Established Floodways or Non-Encroachment Areas.	136
Section 6. Floodways and Non-Encroachment Areas.	136
Article V Legal Status Provisions.....	137
Section 1. Effect on Rights and Liabilities Under the Existing Flood Damage Prevention Ordinance.....	137
Section 2. Effect Upon Outstanding Floodplain Development Permits. ...	137
Section 3. Severability.....	138
Section 4. Adoption Certification.	138

CHAPTER 10 FOSCOE GRANDFATHER ZONING	139
Article I Purpose, Authority and Jurisdiction	139
Section 1. Purpose.	139
Section 2. Authority.....	139
Section 3. Jurisdiction.	139
Article II General Provisions	139
Section 1. Application.	139
Section 2. New Uses or Construction.	140
Section 3. Conforming Uses.....	140
Section 4. Nonconforming Uses.....	140
Section 5. Open Space Requirements.	141
Section 6. Reduction of Lot and Yard Areas Prohibited.	141
Section 7. Projections into Public Rights-of-way.	141
Section 8. Interpretation of District Boundaries.	142
Article III Official Zoning Map	142
Section 1. Zoning Map.	142
Article IV Administration and Enforcement.....	142
Section 1. Administration and Enforcement.	142
Section 2. Permit Process.	143
Section 3. Right of Appeal.	144
Article V District Regulations.....	144
Section 1. Rural District.	144
Section 2. Rural/Residential District.....	146
Section 3. Highway District.....	148
Section 4. Light Industrial Conditional Zoning District.	150
Section 5. Accessory Uses.	151
Article VI Site Plan Review	152
Section 1. Sign Regulations	152
Section 2. Buffer Areas	152
Section 3. Parking Standards.....	154
Section 4. Yard Requirements – Highway and Industrial Districts	156
Section 5. Driveway Connections.....	156
Section 6. Drainage, Erosion Control, Storm Water Management.....	156
Section 7. Stream Protection, Flood Plain Protection	157
CHAPTER 11 INSTALLATION AND MAINTENANCE OF ELECTRONIC ACCESS GATES FOR GATED COMMUNITIES	159
Article I Authority and Purpose	159

Article II Requirements	159
Article III Gate Development Specifics	159
Article IV Application and Approval Process	160
Article V Maintenance	161
Article VI Modifications.....	161
CHAPTER 12 HEIGHT OF STRUCTURES.....	162
Article I Regulation of Height of Structures	162
Article II Permits.....	163
CHAPTER 13 HIGH IMPACT LAND USES	164
Article I Introduction	164
Section 1. General Purpose.....	164
Section 2. Legal Authority.	164
Section 3. Territorial Coverage.....	164
Article II Regulated Land Uses	164
Section 1. Regulated Uses.	164
Section 2. Regulations and Standards Imposed.....	165
Article III Pre-Existing High Impact Land Uses	171
Section 1. Grandfathering of Pre-existing High Impact Land Uses.....	171
Section 2. New High Impact Land Uses Regulated.	172
Section 3. Pre-existing Regulated Land Uses.....	172
Article IV Permit Required	172
Section 1. Permitting Process.....	172
Section 2. Permit Expiration.	173
Section 3. High Impact Land Use Occupancy Permit.	173
CHAPTER 14 MANUFACTURED HOME PARKS	174
Article I Authority and Purpose	174
Article II Health Department Review.....	174
Article III Preliminary Site Plan Submission	174
Section 1. Preliminary Site Plan Specifications.	174
Article IV Park Development Standards	175
Article V Individual Manufactured Homes Within a Park.....	176
Article VI Applicability to Existing Manufactured Home Parks	177
Article VII Registration.....	177
CHAPTER 15 SEXUALLY ORIENTED BUSINESSES	178
Article I Purpose and Findings.....	180

Section 1. Purpose.	180
Section 2. Findings.	180
Article II Classification	182
Article III License Required.....	183
Section 1. Unlawful Operation and Employment Without License	183
Section 2. Application.	183
Section 3. Qualified Applicant.	183
Section 4. Signatures.....	183
Section 5. Application Contents.	184
Section 6. Employee Application.....	185
Section 7. Additional Requirements.	186
Article IV Issuance of License	186
Section 1. Investigation.	186
Section 2. Annual Renewal.	187
Section 3. Approval/Denial.	187
Section 4. Posted License.	188
Section 5. Timeline for Review.	188
Section 6. License Classification.	188
Article V Fees	189
Article VI Inspection	189
Article VII Expiration of License.....	189
Article VIII Suspension	190
Article IX Revocation	190
Section 1. Previous Suspension.....	190
Section 2. Evidence.	190
Section 3. Length of Revocation.....	191
Section 4. Judicial Review.	191
Article X Transfer of License	191
Article XI Location of Sexually Oriented Businesses	191
Section 1. Residential Structures.....	191
Section 2. Non-Residential Structures.....	191
Section 3. Proximity to Existing Sexually Oriented Business.....	192
Section 4. Highway.....	192
Section 5. Existing Sexually Oriented Business.....	192
Section 6. Measurement to Property Line.	192
Section 7. Measurement to Structure.....	192
Section 8. Applicably to Other Ordinances.	193

Article XII Additional Regulations For Adult Motels.....	193
Section 1. Adult Motel.....	193
Section 2. Penalties.....	193
Section 3. Word Interpretation.....	193
Article XIII Regulation Pertaining To Exhibition of Sexually Explicit Films, Videos or Live Entertainment.....	193
Section 1. Requirements.....	193
Section 2. Maintenance.....	195
Section 3. Penalties.....	195
Article XIV Additional Regulations.....	195
Section 1. For Escort Agencies.....	195
Section 2. For Nude Model Studios.....	195
Section 3. Concerning Public Nudity.....	196
Article XVII Prohibition Against Youth in a Sexually Oriented Business.....	196
Article XVIII Prohibition Of Sale or Consumption of Alcohol.....	196
Article XIX Exterior Portions of Sexually Oriented Businesses.....	197
Section 1. Visibility.....	197
Section 2. Exterior Appearance.....	197
Section 3. Parking.....	197
Section 4. Lighting.....	197
Section 5. Buffering.....	197
Section 6. Maintenance.....	198
Section 7. Penalties.....	198
Article XX Signage.....	199
Article XXI Hours of Operation.....	199
Article XXII Exemptions.....	199
Article XXIII Injunction.....	199
CHAPTER 16 SIGNS.....	201
Article I Purpose and Legislative Intent.....	201
Article II Sign Review Procedures.....	202
Article III Sign Regulations.....	202
Section 1. Exempt from these Regulations.....	202
Section 2. Prohibited Signs.....	202
Article IV Development Standards.....	203
Section 1. Wall Signs.....	203
Section 2. Freestanding signs.....	204

Section 3. On-Premise Electronic Message Center/Changeable Copy Signs.	204
Section 4. Instructional signs.	204
Section 5. Window Signs.	205
Section 6. Temporary Signs.	205
Section 7. Highway Signs.	206
Article V Measurement Standards.....	207
Section 1. Determining Sign Area and Dimensions.....	207
Section 2. Determining Sign Height.	208
Section 3. Determining Building Frontages and Frontage Lengths.	208
Section 4 . Length of Building Frontage.	208
Article VI Non-Conforming Signs	209
Section 1. General Provisions.....	209
Article VII Supplemental Considerations.....	209
Section 1. Construction Standards.....	209
Section 2. Maintenance.	210
Article VIII Jurisdiction.....	211
CHAPTER 17 STRUCTURES LOCATED ON LAND ADJACENT TO NATIONAL PARK SERVICE LAND.....	212
Article I Regulation of Location of Structures	212
Article II Permit	212
Article III Jurisdiction and Effective Date	212
CHAPTER 18 SUBDIVISION, PLANNED UNIT DEVELOPMENT AND MULTI-UNIT STRUCTURES	213
Article I Title.....	213
Article II Authority and Enactment Clause	213
Article III Jurisdiction and Purpose	213
Section 1. Jurisdiction.....	213
Section 2. Purpose	213
Article IV Planning Board Review and Legal Status Provisions	214
Section 1. Planning Board Review and Approval.	214
Section 2. Exemptions.	214
Section 3. Building Permits.....	214
Section 4. Recording of Plats.	215
Section 5. Duty of Register of Deeds.....	215
Section 6. Relationship to Effective Changes in the Chapter.....	215
Article V Procedures For Review and Approval of Subdivisions.....	216

Section 1. Plat Required on Any Subdivision of Land.	216
Section 2. Submission of Preliminary Plat.	216
Section 3. Specifications for Preliminary Plat.	217
Section 4. Minor Subdivisions.	218
Section 5. Phased Developments.	220
Section 6. Submission of Final Plat.	220
Section 7. Approval of Final Plat.	225
Section 8. Advisory Opinion.	225
Article VI General Requirements and Minimum Standards of Design	226
Section 1. General Requirements.	226
Section 2. Design Standards for Streets.	230
Section 3. Design Standards for Lots.	235
Section 4. Design Standards for Easements.	239
Article VII Planned Unit Development	239
Section 1. Definition.	239
Section 2. Purpose.	239
Section 3. Affordable Housing PUD.	245
Article VIII Installation of Permanent Reference Points and Improvements	247
Section 1. Permanent Reference Points.	247
Section 2. Installation of Improvements.	248
Section 3. Deferment of Improvements.	248
ARTICLE IX - Regulation Of Multi-Unit Structures	249
Section 1. Definition.	249
Section 2. Purpose.	249
Section 3. Application of Article.	249
Section 4. Standards of Design.	249
Section 5. Submission of Site Plans.	251
Section 6. Inspections.	252
Section 7. Building Permits.	252
Appendix A Guide For Sub-Division Development In Watauga County	253
Appendix B Guidelines For Developing Erosion and Sediment Control Plans	254
Appendix C Erosion and Sedimentation Plan Checklist	259
Appendix D Ownership/Financial Responsibility Form	260
Appendix E Preliminary Plat Checklist	262
Appendix F Final Plat Checklist	264
Appendix G Subdivision Specifications Checklist	266

Appendix H Method of Defining Slope	267
Appendix I Minor Bridge Maintenance Checklist.....	269
Appendix J Buffering and Screening.....	272
Appendix K Fire Apparatus Access Roads.....	274
Appendix L Affordable Workforce Housing Policy	275
Appendix M Developer Authorization Form	277
CHAPTER 19 REGULATION OF RECREATIONAL VEHICLE	
SUBDIVISIONS.....	278
Article I Authority and Enactment Clause	278
Article II Jurisdiction and Purpose	278
Section 1. Jurisdiction.....	278
Section 2. Purpose.....	278
Section 3. Permits.....	278
Article III Planning Board Review	279
Article IV Procedures For Review And Approval Of Subdivisions.....	279
Section 1. Submission of Preliminary Plan to Planning Board.....	279
Section 2. What the Preliminary Plat Shall Show.....	280
Section 3. Submission of Final Plat to Planning Board.....	281
Section 4. What the Final Plat Shall Show.....	281
Section 5. Approval of Final Plat by Planning Board and Recording Thereof.....	282
Section 6. The Following Certificates Shall Be Shown On The Final Plat.....	282
Section 7. Appeal by Developer.....	283
Section 8. Feasibility Plan.....	283
Section 9. Minor Subdivisions.....	283
Article V Environmental, Open Space and Access Requirements	284
Section 1. Environmental, Open Space and Access Requirements.....	284
Section 2. Miscellaneous Requirements.....	286
Article VI Effective Date.....	286
CHAPTER 20 VALLE CRUCIS HISTORIC DISTRICT	287
Article I General Provisions.....	287
Section 1. Purposes.....	287
Section 2. Legislative Authority.....	287
Article II Historic District and Historic Preservation Commission	288
Section 1. Historic District Established.....	288
Section 2. Application of Regulations.....	288
Section 3. Exemption of Bonafide Farms and Public Schools.....	288

Section 4. Area, Height and Placement Standards.	288
Section 5. Performance Standards.	289
Section 6. Historic Preservation Commission.	293
Section 7. Commission Powers.	294
Section 8. Certificate of Appropriateness.	295
Article III Nonconformities.	302
Section 1. Classification.	302
Section 2. Repair, Reconstruction, Expansion, Reinstatement.	302
Section 3. Nonconforming Lots.	303
Article IV Public Buildings.	303
CHAPTER 21 WATERSHED PROTECTION (WINKLERS CREEK, HOWARDS CREEK, NORRIS BRANCH, FLAT TOP BRANCH, SOUTH FORK NEW RIVER, AND POND CREEK)	304
Article I Authority and General Regulations	304
Section 1. Authority and Enactment.	304
Section 2. Jurisdiction.	304
Section 3. Exceptions to Applicability.	304
Section 4. Applicability to Agricultural Uses.	306
Article II Subdivision Regulations	306
Section 1. General Provisions.	306
Article III Development Regulations	308
Section 1. Establishment of Watershed Areas.	308
Section 2. Watershed Areas – Allowed and Not Allowed Uses	308
Section 3. Cluster Development	310
Section 4. Density Averaging.	313
Section 5. Cluster Development	314
Section 6. Vegetated Setbacks Required.	315
Section 7. Application of Regulations.	315
Section 8. Rules Governing the Interpretation of Watershed Area Boundaries.	316
Section 9. Existing Development.	316
Section 10. Watershed Protection Permit.	317
Section 11. Building Permit Required.	318
Section 12. Watershed Protection Occupancy Permit.	318
Article IV Public Health Regulations	318
Section 1. Public Health, in general.	318
Section 2. Abatement.	319

Article V Administration, Enforcement and Appeals	319
Section 1. Watershed Administrator and Duties thereof.	319
Article VI Appearance Standards	320
Section 1. Buffer Areas.	320
Section 2. Location and Buffering of Parking.	322
Article VII Changes and Amendments to the Watershed Protection Regulations	322
Article VIII Variances	322
CHAPTER 22 WIND ENERGY SYSTEMS	327
Article I Authority and Purpose.	327
Article II Findings.	327
Article III Small Wind Energy Systems.	327
Section 1. Wind Turbine Height.	327
Section 2. Setback.	327
Section 3. Building Permit Requirements.	328
Section 4. Compliance with FAA Regulations.	328
Section 5. Utility Notification.....	328
Section 6. Appearance.	328
Section 7. Removal of Defective or Abandoned Wind Energy Systems.	328
Article IV Large Wind Energy Systems	329
Section 1. Permit Application.	329
Section 2. Special Use Permit Required.	332
CHAPTER 23 WIRELESS TELECOMMUNICATIONS	333
Article I Purpose and Legislative Intent	333
Article II Approvals Required for Wireless Facilities and Wireless Support Structures ..	333
Section 1. Administrative Review and Approval.	333
Section 2. Board Review and Approval.	334
Section 3. Exempt from Review and Approval.	334
Article III Administrative Review and Approval Process	335
Section 1. Content of Application Package for New Sites.....	335
Section 2. Content of Application Package for Other Sites/Facilities.	335
Section 3. Fees.	336
Section 4. Procedure and Timing.	336
Article IV Special Use Permit Process.	337
Section 1. Special Use Permit.	337
Section 2. Content of Special Use Permit Application Package.	338

Section 3. Fees.	338
Section 4. Procedure and Timing.	338
Article V General Standards and Design Requirements.	339
Section 1. Design.	339
Section 2. Setbacks.	340
Section 3. Height.	340
Section 4. Aesthetics.	340
Section 5. Accessory Equipment.	341
Section 6. Fencing.	341
Section 7. Landscaping.	341
Article VI Miscellaneous Provisions.	341
Section 1. Abandonment and Removal.	341
Section 2. Multiple Uses on a Single Parcel or Lot.	342
Article VII Wireless Facilities and Wireless Support Structures in Existence on the Date of Adoption of this Ordinance.	342
Section 1. Existing Wireless Facilities.	342
Section 2. Activities at Non-Conforming Wireless Support Structures.	342
Article VIII Jurisdiction.	343
Article IX National Park Service Review.	343
Article X Valle Crucis Historic District.	343

CHAPTER 1 AUTHORITY AND JURISDICTION

Article I Title of Ordinance

This ordinance shall be known and may be cited as the Watauga County Planning and Development Ordinance.

Article II Authority and Purposes

This ordinance is enacted pursuant to the authority contained in the North Carolina Constitution and General Statutes, and is in fact a compilation of existing individual ordinances, amended as required by SL 2019-111, SL 2020-25, and NCGS 160D. Specific authorities and purposes for each chapter are stated therein.

Article III Jurisdiction

This ordinance shall be effective throughout unincorporated Watauga outside of the jurisdictions of the municipalities; for regulations adopted under the authority of N.C.G.S. 160D, said municipal jurisdictions shall include extraterritorial jurisdictions, if any.

Article IV Effective Date

This ordinance shall take effect April 21, 2021. Amended November 16, 2021.

Article V Relationship to Existing Ordinances

To the extent that the provisions of this ordinance are the same in substance as the provisions they replace in previously adopted County ordinances, they shall be considered as continuations thereof and not new enactments unless otherwise specifically provided, as stated above in Article II.

Article VI Fees

Pursuant to N.C.G.S. 160D-402(d), reasonable fees for support, administration, and implementation of programs authorized by the General Statutes are established and amended from time-to-time by the Board of County Commissioners of Watauga County.

**CHAPTER 2 PLANNING BOARD; HISTORIC PRESERVATION
COMMISSION; PLANNING AND INSPECTIONS
DEPARTMENT**

Article I Planning Board Established; Duties

The Watauga County Planning Board is established pursuant to North Carolina General Statute 160D-301. The Board shall have the following powers and duties:

- (A) To prepare, review, maintain, monitor, and periodically update and recommend to Board of Commissioners a comprehensive plan, and such other plans as deemed appropriate, and conduct ongoing related research, data collection, mapping, and analysis.
- (B) To facilitate and coordinate citizen engagement and participation in the planning process.
- (C) To develop and recommend policies, ordinances, development regulations, administrative procedures, and other means for carrying out plans in a coordinated and efficient manner.
- (D) To advise the Board of Commissioners concerning the implementation of plans, including, but not limited to, review and comment on all zoning text and map amendments as required by G.S. 160D-604.
- (E) To exercise any functions in the administration and enforcement of various means for carrying out plans that the Board of Commissioners may direct.
- (F) To provide a preliminary forum for review of quasi-judicial decisions, provided that no part of the forum or recommendation may be used as a basis for the deciding board.
- (G) To perform any other related duties that the Board of Commissioners may direct.

Article II Planning Board Membership and Vacancies

The Planning Board shall consist of seven (7) members; five (5) appointed by the Board of County Commissioners on a district basis and two (2) appointed at-large with no residency requirements. Upon taking office after a general election, each County Commissioner shall nominate, subject to the approval of a majority of the Board of County Commissioners, one (1) person from his/her district. Two (2) at-large members shall be nominated and approved

by the entire Board of County Commissioners. No more than three (3) members at one time shall be from the same profession or occupation.

The terms of the appointees representing districts shall be concurrent with the terms of the County Commissioners elected to represent the districts. At-large appointees' terms shall be four (4) years, staggered. Planning Board members may be reappointed upon expiration of terms, and shall serve at the pleasure of the Board of Commissioners.

Vacancies occurring for reasons other than expiration of terms shall be filled as they occur for the period of the unexpired term. Faithful attendance at the meetings of the Planning Board is considered a prerequisite for the maintenance of membership on the Planning Board. Failure to attend three (3) consecutive regular meetings of the Planning Board without good cause shall terminate the membership of any appointee to the Planning Board.

Article III Historic Preservation Commission

There is hereby established the Valle Crucis Historic Preservation Commission (hereafter referred to as the Commission) to consist of five members appointed by the Watauga County Board of Commissioners. Members of the Commission shall serve without compensation.

(A) Tenure

Initially members shall be appointed for staggered terms with one member being appointed for one year, two members for two years and two members for three years. Thereafter, all appointments shall be for a term of three years.

(B) Qualifications

Three (3) members of the Commission shall be resident property owners of the Historic District, two (2) shall be members of the Valle Crucis Community Council and residents of Watauga County, and the majority of the members shall have special interest, experience or education in history or architecture.

(C) Meetings

The Commission shall establish a meeting time and shall meet monthly and more or less often as it shall determine and require. All meetings of the Commission shall be open to the public and reasonable notice of the time and place thereof shall be given to the public. All meetings shall conform to the North Carolina Open Meeting Law. (See North Carolina General Statutes 143, Article 33C).

(D) Attendance at Meetings

Any member of the Commission who misses more than three consecutive regular meetings or more than half of the regular meetings in a calendar year shall lose status with the Commission and shall be replaced or reappointed by the Watauga County Board of County Commissioners.

Absence due to sickness, death or emergencies of like nature shall be recognized as approved absences and shall not affect a member's status on the Commission, except in the event of long illness or other such cause for prolonged absence a member shall be replaced.

(E) Rules of Procedure

The Commission shall adopt and publish Rules of Procedure for the conduct of its business.

(F) Annual Report

An annual report shall be prepared and submitted by February 1st of each year to the Board of County Commissioners. Such report shall include a comprehensive review of the activities, problems, and actions of the Commission as well as any budget requests or recommendations.

(G) Meeting Minutes

The Commission shall keep permanent minutes of all its meetings. The minutes shall record attendance of its members, its resolution, findings, recommendations and actions.

The minutes of the Commission shall be a public record.

Article IV Historic Preservation Commission Powers

The Commission shall seek to promote, enhance and preserve the character of the Valle Crucis Historic District, provided however that the Commission shall not require the reconstruction of individual or original buildings or structures or portion thereof.

The Commission is authorized and empowered to undertake such action as is reasonably necessary to the discharge and conduct of its duties and responsibilities as outlined in this Ordinance Chapter and Chapter 160D of the General Statutes of the State of North Carolina including but not limited to the following:

- (A)** Undertake an inventory of properties of historical, prehistorical, architectural, and/or cultural significance.
- (B)** Recommend to the governing board areas to be designated by ordinance as "Historic Districts" and individual structures, buildings,

sites, areas, or objects to be designated by ordinance as "Landmarks."

- (C) Acquire by any lawful means the fee or any lesser included interest, including options to purchase, to properties within established districts or to any such properties designated as landmarks to hold, manage, preserve, restore, and improve such properties, and to exchange or dispose of the property by public or private sale, lease or otherwise, subject to covenants or other legally binding restrictions that will secure appropriate rights of public access and promote the preservation of the property.
- (D) Restore, preserve, and operate historic properties.
- (E) Recommend to the governing board that designation of any area as a historic district or part thereof, or designation of any building, structure, site, area, or object as a landmark, be revoked or removed for cause.
- (F) Conduct an educational program regarding historic properties and districts within its jurisdiction.
- (G) Cooperate with the State, federal, and local governments in pursuance of the purposes of this Part. The governing board or the commission, when authorized by the governing board, may contract with the State, or the United States of America, or any agency of either, or with any other organization provided the terms are not inconsistent with State or federal law.
- (H) Enter, solely in performance of its official duties and only at reasonable times, upon private lands for examination or survey thereof. However, no member, employee, or agent of the commission may enter any private building or structure without the express consent of the owner or occupant thereof.
- (I) Prepare and recommend the official adoption of a preservation element as part of the local government's comprehensive plan.
- (J) Review and act upon proposals for alterations, demolitions, or new construction within historic districts, or for the alteration or demolition of designated landmarks, pursuant to this Part.
- (K) Negotiate at any time with the owner of a building, structure, site, area, or object for its acquisition or its preservation, when such action is reasonably necessary or appropriate.

Article III V Department of Planning and Inspections

The Department of Planning and Inspections is established pursuant to North Carolina General Statute 160D-401. The staff may consist of a director, administrators, inspectors, enforcement officers, planners, technicians, and other staff necessary to fulfill the duties of the Department.

Duties assigned to staff include, but are not limited to, drafting and implementing plans and development regulations to be adopted pursuant to NCGS 160D and 153A; determining whether applications for development approvals are complete; receiving and processing applications for development approvals; providing notices of applications and hearings; making decisions and determinations regarding development regulation implementation; determining whether applications for development approvals meet applicable standards as established by law and local ordinance; enforcing the North Carolina Building and Residential Codes (pursuant to NCGS 160D-1102); conducting inspections; issuing or denying certificates of compliance or occupancy; enforcing development regulations, including issuing notices of violation, orders to correct violations, and recommending bringing judicial actions against actual or threatened violations; keeping adequate records; and any other actions that may be required in order adequately to enforce the laws and development regulations under their jurisdiction.

Article ~~IV~~ VI Ordinance Administrator

The "Ordinance Administrator" is the Planning & Inspections Director or his/her subordinate officials designated by him/her. The title may be used interchangeably with: watershed administrator, floodplain administrator, county official, administrator, zoning official, planning staff, Department of Planning & Inspections, Office of Planning & Inspections, the County.

CHAPTER 3 BOARD OF ADJUSTMENT

Article I Establishment of Board

Board of Adjustment members shall be appointed by the Board of Commissioners and shall consist of five (5) regular members and any alternate members (if any) that the Board of Commissioners shall designate. Appointments shall be for three (3) years. If practicable, the Board of Commissioners shall appoint at least one member from each zoned and watershed area in the County.

Article II Duties of the Board

The board shall hear and decide all matters upon which it is required to pass under any statute or development regulation adopted pursuant to NCGS 153A-121 or NCGS 160D, with the exception that the Watauga County Planning Board shall perform the duties of the Board of Adjustment pertaining to Chapter 18 Subdivisions and Multi-Unit Structures, and shall comply with all of the procedures and process applicable to the Board of Adjustment in making quasi-judicial decisions.

- (A) Hear and decide appeals from and review any order, requirement, decision, or determination made by the Department of Planning & Inspections in the performance of official duties.
- (B) Hear and decide appeals for variances. Nothing in this Section shall be construed to authorize the Board to permit a use in a district where that use is not a permitted use.
- (C) Hear and decide upon applications for special use permits.
- (D) Subpoenas. – The board making a quasi-judicial decision under this Chapter through the chair or, in the chair's absence, anyone acting as chair may subpoena witnesses and compel the production of evidence. To request issuance of a subpoena, the applicant, the County, and any person with standing under G.S. 160D-1402(c) may make a written request G.S. 160D-406 Page 2 to the chair explaining why it is necessary for certain witnesses or evidence to be compelled. The chair shall issue requested subpoenas he or she determines to be relevant, reasonable in nature and scope, and not oppressive. The chair shall rule on any motion to quash or modify a subpoena. Decisions regarding subpoenas made by the chair may be immediately appealed to the full board. If a person fails or refuses to obey a subpoena issued pursuant to this subsection, the board or the party seeking the subpoena may apply to the General Court of Justice for an order requiring that its subpoena be obeyed, and the court shall have jurisdiction to issue these orders after notice to all proper parties.

Article III Administration

The Board shall adopt rules of procedures and regulations for the conduct of its affairs.

All meetings of the Board shall be open to the public. The Board shall keep a record of its meetings, including the vote of each member on every question, a complete summary of the evidence submitted to it, documents submitted to it and all official actions.

The Board Chair or any member acting as Chair and Board Clerk are authorized to administer oaths to any witnesses in any matter coming before the Board. Any person who, while under oath during a proceeding before the Board of Adjustment willfully swears falsely is guilty of a Class 1 misdemeanor.

Applications for special use permits, variances, and appeal of decisions of the Department of Planning & Inspections shall be filed with the Clerk to the Board of Adjustment, as agent for the Board, on forms provided by the Clerk.

Section 1. Administrative Materials.

The administrator or staff to the board shall transmit to the board all applications, reports, and written materials relevant to the matter being considered. The administrative materials may be distributed to the members of the board prior to the hearing if at the same time they are distributed to the board a copy is also provided to the appellant or applicant and to the landowner if that person is not the appellant or applicant. The administrative materials shall become a part of the hearing record. The administrative materials may be provided in written or electronic form. Objections to inclusion or exclusion of administrative materials may be made before or during the hearing. Rulings on unresolved objections shall be made by the board chair at the hearing; such ruling may be appealed to the full board.

Section 2. Presentation of Evidence.

The applicant, the local government, and any person who would have standing to appeal the decision under G.S. 160D-1402(c) shall have the right to participate as a party at the evidentiary hearing. Other witnesses may present competent, material, and substantial evidence that is not repetitive as allowed by the board. Objections regarding jurisdictional and evidentiary issues, including, but not limited to, the timeliness of an appeal or the standing of a party, may be made to the board. The board chair shall rule on any objections, and the chair's rulings may be appealed to the full board. These rulings are also subject to judicial review pursuant to G.S. 160D-1402. Objections based on jurisdictional issues may be raised for the first time on judicial review.

Section 3. Appearance of Official New Issues.

The official who made the decision or the person currently occupying that position, if the decision maker is no longer employed by the local government, shall be present at the evidentiary hearing as a witness. The appellant shall not be limited at the hearing to matters stated in a notice of appeal. If any party or the local government would be unduly prejudiced by the presentation of matters not presented in the notice of appeal, the board shall continue the hearing.

Section 4. Decisions.

The board shall determine contested facts and make its decision within a reasonable time. When hearing an appeal, the board may reverse or affirm, wholly or partly, or may modify the decision appealed from and shall make any order, requirement, decision, or determination that ought to be made. The board shall have all the powers of the official who made the decision. Every quasi-judicial decision shall be based upon competent, material, and substantial evidence in the record. Each quasi-judicial decision shall be reduced to writing, reflect the board's determination of contested facts and their application to the applicable standards, and be approved by the board and signed by the chair or other duly authorized member of the board. A quasi-judicial decision is effective upon filing the written decision with the clerk to the board or such other office or official as the development regulation specifies. The decision of the board shall be delivered within a reasonable time by personal delivery, electronic mail, or first-class mail to the applicant, landowner, and any person who has submitted a written request for a copy prior to the date the decision becomes effective. The person required to provide notice shall certify to the local government that proper notice has been made, and the certificate shall be deemed conclusive in the absence of fraud.

Section 5. Appeals in Nature of Certiorari.

When hearing an appeal pursuant to G.S. 160D-947(e) or any other appeal in the nature of certiorari, the hearing shall be based on the record below, and the scope of review shall be as provided in G.S. 160D-1402(j).

Section 6. Standing.

A petition may be filed under this Chapter only by a petitioner who has standing to challenge the decision being appealed. The following persons shall have standing to file a petition under this Chapter:

- (A) Any person possessing any of the following criteria:
 - (1) An ownership interest in the property that is the subject of the decision being appealed, a leasehold interest in the property

that is the subject of the decision being appealed, or an interest created by easement, restriction, or covenant in the property that is the subject of the decision being appealed.

- (2) An option or contract to purchase the property that is the subject of the decision being appealed.
- (3) An applicant before the decision-making board whose decision is being appealed.
- (B) Any other person who will suffer special damages as the result of the decision being appealed.
- (C) An incorporated or unincorporated association to which owners or lessees of property in a designated area belong by virtue of their owning or leasing property in that area, or an association otherwise organized to protect and foster the interest of the particular neighborhood or local area, so long as at least one of the members of the association would have standing as an individual to challenge the decision being appealed, and the association was not created in response to the particular development or issue that is the subject of the appeal.

Section 7. Judicial Review.

Every quasi-judicial decision shall be subject to review by the superior court by proceedings in the nature of certiorari pursuant to G.S. 160D-1402. Appeals shall be filed within the times specified in G.S. 160D-1405(d). (2019-111, s. 2.4.)

Article IV Notice of Hearing

- (A) Notice of evidentiary hearings conducted pursuant to this Chapter shall be mailed to the person or entity whose appeal, application, or request is the subject of the hearing; to the owner of the property that is the subject of the hearing if the owner did not initiate the hearing; to the owners of all parcels of land abutting the parcel of land that is the subject of the hearing; and to any other persons entitled to receive notice as provided by the local development regulation. In the absence of evidence to the contrary, the local government may rely on the county tax listing to determine owners of property entitled to mailed notice. The notice must be deposited in the mail at least 10 days, but not more than 25 days, prior to the date of the hearing. Within that same time period, the local government shall also prominently post a notice of the hearing on the site that is the subject of the hearing or on an adjacent street or highway right-of-way. The board may continue an evidentiary hearing that has been convened without further advertisement. If an

evidentiary hearing is set for a given date and a quorum of the board is not then present, the hearing shall be continued until the next regular board meeting without further advertisement.

- (B) Additional notice for evidentiary hearings conducted under Chapter 13, High Impact Land Uses is required as follows. Notice shall be posted on the subject parcel and mailed to all owners of property abutting and within 500 feet of the subject parcel twenty five (25) days in advance of the hearing. In addition, notice shall be published in a newspaper of general circulation in the area sixty (60) days and again two (2) weeks in advance of the hearing, and an announcement of the hearing shall be placed on the County's web site sixty (60) days in advance of the hearing, and remain there continuously until the hearing.

Article V Voting

- (A) The concurring vote of four-fifths of the board shall be necessary to grant a variance. A majority of the members shall be required to decide any other quasi-judicial matter or to determine an appeal made in the nature of certiorari. For the purposes of this subsection, vacant positions on the board and members who are disqualified from voting on a quasi-judicial matter shall not be considered members of the board for calculation of the requisite majority if there are no qualified alternates available to take the place of such members.
- (B) A member of any board exercising quasi-judicial functions pursuant to this Chapter shall not participate in or vote on any quasi-judicial matter in a manner that would violate affected persons' constitutional rights to an impartial decision maker. Impermissible violations of due process include, but are not limited to, a member having a fixed opinion prior to hearing the matter that is not susceptible to change, undisclosed ex parte communications, a close familial, business, or other associational relationship with an affected person, or a financial interest in the outcome of the matter. If an objection is raised to a member's participation and that member does not recuse himself or herself, the remaining members shall by majority vote rule on the objection.

Article VI Variances

A variance may only be allowed by the Board in cases involving unnecessary hardships when competent, material, and substantial evidence in the record supports all of the following findings:

- (A) Unnecessary hardship would result from the strict application of the ordinance. It shall not be necessary to demonstrate that, in the absence of the variance, no reasonable use can be made of the property.
- (B) The hardship results from conditions that are peculiar to the property, such as location, size, or topography. Hardships resulting from personal circumstances, as well as hardships resulting from conditions that are common to the neighborhood or the general public, may not be the basis for granting a variance. A variance may be granted when necessary and appropriate to make a reasonable accommodation under the Federal Fair Housing Act for a person with a disability.
- (C) The hardship did not result from actions taken by the applicant or the property owner. The act of purchasing property with knowledge that circumstances exist that may justify the granting of a variance shall not be regarded as a self-created hardship.
- (D) The requested variance is consistent with the spirit, purpose, and intent of the ordinance, such that public safety is secured and substantial justice is achieved.

No change in permitted uses may be authorized by variance.

The Board may impose appropriate conditions upon the granting of any variance, provided that the conditions are reasonably related to the variance.

Article VII Appeals

Section 1. Designated Board.

Except as provided in N.C.G.S 160D-1403.1, appeals of administrative decisions made by the staff under this Chapter shall be made to the board of adjustment unless a different board is provided or authorized otherwise by statute or an ordinance adopted pursuant to this Chapter. If this function of the board of adjustment is assigned to any other board pursuant to G.S. 160D-302(b), that board shall comply with all of the procedures and processes applicable to a board of adjustment hearing appeals. Appeal of a decision made pursuant to an erosion and sedimentation control regulation, a storm water control regulation, or a provision of the housing code shall not be made to the board of adjustment unless required by a County ordinance or code provision.

Section 2. Standing.

Any person who has standing under G.S. 160D-1402(c) or the County may appeal an administrative decision to the board. An appeal is taken by filing a

notice of appeal with the clerk or such other local government official as designated by regulation. The notice of appeal shall state the grounds for the appeal.

Section 3. Time to Appeal.

The owner or other party shall have 30 days from receipt of the written notice of the determination within which to file an appeal. Any other person with standing to appeal has 30 days from receipt from any source of actual or constructive notice of the determination within which to file an appeal. In the absence of evidence to the contrary, notice given pursuant to G.S. 160D-403(b) by first-class mail is deemed received on the third business day following deposit of the notice for mailing with the United States Postal Service.

Section 4. Record of Decision.

The official who made the decision shall transmit to the board all documents and exhibits constituting the record upon which the decision appealed from is taken. The official shall also provide a copy of the record to the appellant and to the owner of the property that is the subject of the appeal if the appellant is not the owner.

Section 5. Stays.

An appeal of a notice of violation or other enforcement order stays enforcement of the action appealed from including any accumulation of fines, during the pendency of the appeal to the board of adjustment and any subsequent appeal in accordance with G.S. 160D-1402 or during the pendency of any civil proceeding authorized by law, or appeals therefrom, unless the official who made the decision certifies to the board after notice of appeal has been filed that, because of the facts stated in an affidavit, a stay would cause imminent peril to life or property or, because the violation is transitory in nature, a stay would seriously interfere with enforcement of the development regulation. In that case, enforcement proceedings shall not be stayed except by a restraining order, which may be granted by a court. If enforcement proceedings are not stayed, the appellant may file with the official a request for an expedited hearing of the appeal, and the board shall meet to hear the appeal within 15 days after such a request is filed. Notwithstanding any other provision of this Section, appeals of decisions granting a development approval or otherwise affirming that a proposed use of property is consistent with the development regulation does not stay the further review of an application for development approvals to use such property; in these situations, the appellant or local government may request and the board may

grant a stay of a final decision of development approval applications, including building permits affected by the issue being appealed.

Section 6. Alternative Dispute Resolution.

The parties to an appeal that has been made under this section may agree to mediation or other forms of alternative dispute resolution. The development regulation may set standards and procedures to facilitate and manage such voluntary alternative dispute resolution. (2019-111, s. 2.4.)

Section 7. No Estoppel.

N.C.G.S. 160D-1403.2, limiting a local government's use of the defense of estoppel, applies to proceedings under this Section.

Article VIII Special Use Permits

- (A) An application for a special use permit shall be submitted to the Board of Adjustment by filing a copy of the application with the Clerk to the Board.
- (B) Subject to [subsection \(C\)](#), the Board of Adjustment shall issue the requested permit unless it concludes, based upon the information submitted at the hearing, that:
 - (1) The requested permit is not within its jurisdiction according to the district regulations pertaining to uses, or
 - (2) The application is incomplete, or
 - (3) If completed as proposed in the application, the development will not comply with one or more requirements of the subject regulation.
- (C) Even if the Board finds that the application complies with all other provisions of this chapter, it may still deny the permit if it concludes, based upon the information submitted at the hearing, that if completed as proposed, the development, more probably than not:
 - (1) Will materially endanger the public health or safety, or
 - (2) Will substantially injure the value of adjoining or abutting property, or
 - (3) Will not be in harmony with the area in which it is to be located, or
 - (4) Will not be in general conformity with the land-use plan, thoroughfare plan, or other plan officially adopted by the Board of Commissioners.
- (D) The Board shall consider whether the application is complete. If the Board concludes that the application is incomplete and the applicant refuses to provide the necessary information, the application shall be denied. A motion to this effect shall specify either the particular type

of information lacking or the particular requirement with respect to which the application is incomplete. A motion to this effect, concurred in by a majority of the Board, shall constitute the Board's finding on this issue. If a motion to this effect is not made and concurred in by a majority of members, this shall be taken as an affirmative finding by the Board that the application is complete.

- (E) The Board shall consider whether the application complies with all of the applicable requirements of the subject regulation. If a motion to this effect passes by a majority of members, the Board need not make further findings concerning such requirements. If such a motion fails to receive the majority vote or is not made, then a motion shall be made that the application be found not in compliance with one or more requirements of the ordinance. Such a motion shall specify the particular requirements the application fails to meet. A separate vote may be taken with respect to each requirement not met by the application. It shall be conclusively presumed that the application complies with all requirements not found by the Board to be unsatisfied through this process. As provided in [subsection \(C\)](#) if the Board concludes that the application fails to meet one or more of the requirements of this section, the application shall be denied.
- (F) If the Board concludes that all such requirements are met, it shall issue the permit unless it adopts a motion to deny the application for one or more of the reasons set forth in [subsection \(C\)](#). Such motion shall propose specific findings, based upon the evidence submitted, justifying such a conclusion and is carried by a simple majority vote.
- (G) Subject to [subsection \(H\)](#), in granting a special use permit, the Board of Adjustment may attach to the permit such reasonable requirements in addition to those specified in this chapter as will ensure that the development in its proposed location:
 - (1) Will not endanger the public health or safety,
 - (2) Will not injure the value of adjoining or abutting property,
 - (3) Will be in harmony with the area in which it is located, and
 - (4) Will be in conformity with the land-use plan, thoroughfare plan, or other plan officially adopted by the Board of Commissioners.
- (H) The board may not attach additional conditions that modify or alter the specific requirements set forth in this ordinance unless the development in question presents extraordinary circumstances that justify the variation from the specified requirements.
The board may not impose conditions that the County does not otherwise have statutory authority to impose unless agreed to in writing by the applicant.
- (I) Without limiting the foregoing, the board may attach to a permit a condition limiting the permit to a specified duration.

- (J) All additional conditions or requirements shall be entered on the permit, and consented to in writing by the applicant.
- (K) All additional conditions or requirements authorized by this Section are enforceable in the same manner and to the same extent as any other applicable requirements of the subject Ordinance.
- (L) A vote may be taken on application conditions or requirements before consideration of whether the permit should be denied for any of the reasons set forth in [Subsections \(B\)](#) or [\(C\)](#).

Article IX Appeals of Board Actions

Every decision of the Board shall be subject to review at the instance of any aggrieved party by the Superior Court by proceedings in the nature of certiorari. The appeal to Superior Court must be filed within 30 days of the filing by the Board Clerk of the decision in the office of the Department of Planning & Inspections or the delivery of the notice required in [Article III, Section 4](#), whichever is later.

CHAPTER 4 PROCEDURE FOR ADOPTING, AMENDING, OR REPEALING DEVELOPMENT REGULATIONS.

Article I Hearing with Published Notice

Before adopting, amending, or repealing any development regulation authorized by NCGS 160D, the Board of Commissioners shall hold a legislative hearing. A notice of the hearing shall be given once a week for two successive calendar weeks in a newspaper having general circulation in the area. The notice shall be published the first time not less than 10 days nor more than 25 days before the date scheduled for the hearing. In computing such period, the day of publication is not to be included but the day of the hearing shall be included.

Article II Notice of Hearing on Proposed Zoning Map Amendments

- (A) Mailed Notice. –The owners of affected parcels of land and the owners of all parcels of land abutting that parcel of land shall be mailed a notice of the hearing on a proposed zoning map amendment by first-class mail at the last addresses listed for such owners on the county tax abstracts. For the purpose of this section, properties are "abutting" even if separated by a street, railroad, or other transportation corridor. This notice must be deposited in the mail at least 10 but not more than 25 days prior to the date of the hearing.
- (B) Optional Notice for Large-Scale Zoning Map Amendments. – The first-class mail notice required under [subsection \(A\)](#) of this section is not required if the zoning map amendment proposes to change the zoning designation of more than 50 properties, owned by at least 50 different property owners, and the ordinance administrator elects to use the expanded published notice provided for in this subsection. In this instance, a local government may elect to make the mailed notice provided for in [subsection \(A\)](#) of this section or, as an alternative, elect to publish notice of the hearing as required by G.S. 160D-601, provided that each advertisement shall not be less than one-half of a newspaper page in size. The advertisement is only effective only for property owners who reside in the area of general circulation of the newspaper that publishes the notice. Property owners who reside outside of the newspaper circulation area, according to the address listed on the most recent property tax listing

for the affected property, shall be notified according to the provisions of [subsection \(A\)](#) of this section.

- (C) Posted Notice. – When a zoning map amendment is proposed, the County shall prominently post a notice of the hearing on the site proposed for the amendment or on an adjacent public street or highway right-of-way. The notice shall be posted within the same time period specified for mailed notices of the hearing. When multiple parcels are included within a proposed zoning map amendment, a posting on each individual parcel is not required but the County shall post sufficient notices to provide reasonable notice to interested persons.

Article III Citizen Comments

If any resident or property owner submits a written statement regarding a proposed amendment, modification, or repeal to a development regulation, including a text or map amendment, that has been properly initiated as provided in N.C.G.S. 160D-601, to the Clerk to the Board of Commissioners at least two business days prior to the proposed vote on such change, the Clerk to the Board shall deliver such written statement to the Board.

Article IV Amendments

Subsequent to initial adoption of a development regulation, all proposed amendments to the regulation or map shall be submitted to the Planning Board for review and comment. If no written report is received from the Planning Board within 30 days of referral of the amendment to that board, the Board of Commissioners may act on the amendment without the Planning Board report. The Board of Commissioners is not bound by the recommendations, if any, of the Planning Board. Proposed amendments to the zoning regulations or maps for the Foscoe Grandfather Community and Valle Crucis Historic District shall be submitted to the Community Councils, if active, for those communities respectively, under the same conditions as referral to the Planning Board.

Article V Down-Zoning

No amendment to zoning regulations or a zoning map that down-zones property shall be initiated nor shall it be enforceable without the written consent of all property owners whose property is the subject of the down-zoning amendment, unless the down-zoning amendment is initiated by the

county. For purposes of this section, "down-zoning" means a zoning ordinance that affects an area of land in one of the following ways:

- (A) By decreasing the development density of the land to be less dense than was allowed under its previous usage.
- (B) By reducing the permitted uses of the land that are specified in a zoning ordinance or land development regulation to fewer uses than were allowed under its previous usage.

Article VI Plan Consistency

When conducting a review of proposed zoning text or map amendments pursuant to this section, the Planning Board shall advise and comment on whether the proposed action is consistent with any comprehensive plan that has been adopted and any other officially adopted plan that is applicable. The Planning Board shall provide a written recommendation to the Board of Commissioners that addresses plan consistency and other matters as deemed appropriate by the Planning Board, but a comment by the Planning Board that a proposed amendment is inconsistent with the comprehensive plan shall not preclude consideration or approval of the proposed amendment by the Board of Commissioners. If a zoning map amendment qualifies as a "large-scale rezoning" under G.S. 160D-602(b), the Planning Board statement describing plan consistency may address the overall rezoning and describe how the analysis and policies in the relevant adopted plans were considered in the recommendation made.

Article VII Statement of Board of Commissioners

- (A) Plan Consistency. – When adopting or rejecting any zoning text or map amendment, the Board of Commissioners shall approve a brief statement describing whether its action is consistent or inconsistent with an adopted comprehensive plan. The requirement for a plan consistency statement may also be met by a clear indication in the minutes of the Board that at the time of action on the amendment the Board was aware of and considered the Planning Board's (and Community Council's if applicable) recommendations and any relevant portions of an adopted comprehensive plan. If a zoning map amendment is adopted and the action was deemed inconsistent with the adopted plan, the zoning amendment shall have the effect of also amending any future land-use map in the approved plan, and no

additional request or application for a plan amendment shall be required. A plan amendment and a zoning amendment may be considered concurrently. The plan consistency statement is not subject to judicial review. If a zoning map amendment qualifies as a "large-scale rezoning" under G.S. 160D-602(b), the Board of Commissioners' statement describing plan consistency may address the overall rezoning and describe how the analysis and policies in the relevant adopted plans were considered in the action taken.

- (B)** Additional Reasonableness Statement for Rezoning. – When adopting or rejecting any petition for a zoning map amendment, a statement analyzing the reasonableness of the proposed rezoning shall be approved by the Board of Commissioners. This statement of reasonableness may consider, among other factors, (i) the size, physical conditions, and other attributes of the area proposed to be rezoned, (ii) the benefits and detriments to the landowners, the neighbors, and the surrounding community, (iii) the relationship between the current actual and permissible development on the tract and adjoining areas and the development that would be permissible under the proposed amendment; (iv) why the action taken is in the public interest; and (v) any changed conditions warranting the amendment. If a zoning map amendment qualifies as a "large-scale rezoning" under G.S. 160D-602(b), the Board's statement on reasonableness may address the overall rezoning.
- (C)** Single Statement Permissible. – The statement of reasonableness and the plan consistency statement required by this section may be approved as a single statement.

CHAPTER 5 MISCELLANEOUS PROVISIONS

Article I Conflict with Other Laws

Wherever the regulations made under authority of any chapter of this ordinance require a greater width or size or yards, or courts, or require a lower height of building or less number of stories, or require a greater percentage of lots to be left unoccupied or impose other higher standards than that required in any other chapter, the more restrictive provisions shall govern.

Article II Notices of Violation

When the Ordinance Administrator determines work or activity has been undertaken in violation of a development regulation adopted pursuant to this ordinance or other local development regulation or any State law delegated to Watauga County for enforcement purposes in lieu of the State including but not limited to the NC Building and Residential Codes (NCGS 160D, Article 11), or in violation of the terms of a development approval, a written notice of violation may be issued. The notice of violation shall be delivered to the holder of the development approval and to the landowner of the property involved, if the landowner is not the holder of the development approval, by personal delivery, electronic delivery, or first-class mail and may be provided by similar means to the occupant of the property or the person undertaking the work or activity. The notice of violation may be posted on the property. The person providing the notice of violation shall certify to the local government that the notice was provided, and the certificate shall be deemed conclusive in the absence of fraud. Except as provided by G.S. 160D-1123 or G.S. 160D-1206 or otherwise provided by law, a notice of violation may be appealed to the board of adjustment pursuant to G.S. 160D-405.

Article III Stop Work Orders

Whenever any work or activity subject to regulation pursuant to this ordinance or other applicable local development regulation or any State law delegated to the County for enforcement purposes in lieu of the State is undertaken in substantial violation of any State or local law, or in a manner that endangers life or property, staff may order the specific part of the work or activity that is in violation or presents such a hazard to be immediately stopped. The order shall be in writing, directed to the person doing the work or activity, and shall state the specific work or activity to be stopped, the reasons therefor, and the conditions under which the work or activity may be resumed. A copy of the order shall be delivered to the holder of the development approval and to the owner of the property involved (if that person is not the holder of the development approval) by personal delivery, electronic delivery, or first-class mail. The person or persons delivering the stop work order shall certify to the local government that the order was delivered and that certificate shall be

deemed conclusive in the absence of fraud. Except as provided by G.S. 160D-1112 and G.S. 160D-1208, a stop work order may be appealed pursuant to G.S. 160D-405. No further work or activity shall take place in violation of a stop work order pending a ruling on the appeal.

Article IV Remedies

Subject to the provisions of the development regulation, any development regulation adopted pursuant to authority conferred by N.C.G.S. 153A-121 or N.C.G.S. 160D, or any State law delegated to the County for enforcement purposes in lieu of the State may be enforced by any remedy provided by N.C.G.S. 160A-175 or N.C.G.S. 153A-123. If a building or structure is erected, constructed, reconstructed, altered, repaired, converted, or maintained, or any building, structure, or land is used or developed in violation of any development regulation or other regulation made under authority of the cited statutes, the County, in addition to other remedies, may institute any appropriate action or proceedings to prevent the unlawful erection, construction, reconstruction, alteration, repair, conversion, maintenance, use, or development; to restrain, correct or abate the violation; to prevent occupancy of the building, structure, or land; or to prevent any illegal act, conduct, business, or use in or about the premises.

Article V Penalties

Any person, firm or corporation who violates any provision of any article of this ordinance, or NCGS 160D, Article 11; or who shall violate or fail to comply with any order made there under; or who shall continue to work upon any structure after having received written notice from the Ordinance Administrator or Building Inspector to cease work, a person violating this ordinance may be subject to a civil penalty, under N.C.G.S. 153A-123(c), in the discretion of the Board of County Commissioners, not to exceed \$100.00. No penalty shall be assessed prior to notice to the violator. For every day a violator is in violation of this ordinance, it may be considered a separate offense. If the violator does not pay such penalty within 30 days of notification of its assessment by written citation it may be recovered by the County in a civil action in the nature of a debt. The violator may contest said penalty in the court of appropriate jurisdiction.

Article VI Additional Remedies and Penalties for Soil Erosion and Sedimentation

Additional remedies and penalties are set forth in [Chapter 8, Soil Erosion and Sedimentation Control](#) for violations of that chapter.

Article VII Severability Clause

Should any section or provisions of this code be declared by the courts to be unconstitutional or invalid, such decision shall not affect the validity of this code as a whole, or any part thereof other than the part so declared to be unconstitutional or invalid

Article VIII Development Approvals

To the extent consistent with the scope of regulatory authority granted by this ordinance, no person shall commence or proceed with development without first securing any required development approval from the County. A development approval shall be in writing and may contain a provision that the development shall comply with all applicable State and local laws. The County may issue development approvals in print or electronic form. Any development approval issued exclusively in electronic form shall be protected from further editing once issued. Applications for development approvals may be made by the landowner, a lessee or person holding an option or contract to purchase or lease land, or an authorized agent of the landowner. An easement holder may also apply for development approval for such development as is authorized by the easement.

Article IX Duration of Development Approval

Unless a different period is specified by this ordinance or other specific applicable law, including for a development agreement, or a local ordinance, a development approval issued pursuant to this ordinance expires one year after the date of issuance if the work authorized by the development approval has not been substantially commenced. Local development regulations may provide for development approvals of shorter duration for temporary land uses, special events, temporary signs, and similar development. Nothing in this subsection limits any vested rights secured under N.C.G.S. 160D-108 or 108.1. To secure such vested rights, an applicant may request approval of a site-specific development plan for any project that is to be reviewed and approved by the Planning Board or Board of Adjustment.

Article X Inspections

Pursuant to N.C.G.S. 160D-403(e) the Ordinance Administrator may inspect work undertaken pursuant to a development approval to assure that the work is being done in accordance with applicable State and local laws and of the terms of the approval. In exercising this power, staff are authorized to enter any premises within the jurisdiction of the County at all reasonable hours for the purposes of inspection or other enforcement action, upon presentation of proper credentials; provided, however, that the appropriate consent has been given for inspection of areas not open to the public or that an appropriate

inspection warrant has been secured. Pursuant to N.C.G.S 160D-402(b), the Ordinance Administrator may inspect premises at all reasonable hours for which ordinance violations are suspected, upon presentation of proper credentials.

Article XI Revocation of Development Approvals

In addition to initiation of enforcement actions under N.C.G.S. 160D-404, development approvals may be revoked by the County by notifying the holder in writing stating the reason for the revocation. The County shall follow the same development review and approval process required for issuance of the development approval, including any required notice or hearing, in the review and approval of any revocation of that approval. Development approvals shall be revoked for any substantial departure from the approved application, plans, or specifications; for refusal or failure to comply with the requirements of any applicable local development regulation or any State law delegated to the County for enforcement purposes in lieu of the State; or for false statements or misrepresentations made in securing the approval. Any development approval mistakenly issued in violation of an applicable State or local law may also be revoked. The revocation of a development approval by a staff member may be appealed pursuant to G.S. 160D-405. If an appeal is filed regarding a development regulation adopted by the County pursuant to N.C.G.S 153A-121 or N.C.G.S 160D, the provisions of G.S. 160D-405(e) regarding stays apply.

Article XII Development Approvals Run With the Land

Unless provided otherwise by law, all rights, privileges, benefits, burdens, and obligations created by development approvals made pursuant to this ordinance attach to and run with the land.

Article XIII Minor Modifications

Section 1. Special Use Permits & Conditional Zoning

Modifications of special use permits and conditional zoning that may be reviewed and approved by the Ordinance Administrator. Such modifications include changes to: building locations, landscaping, parking locations, grading, storm water, lighting, road/street names, development names, provided no violation or waiver of ordinance provisions is approved. Minor modifications shall not include change of use (except in mix of residential types), increase in development density, ~~set-back encroachments~~, or reduction of road/street right-of-way.


Section 2. Administrative Modification of Setbacks

In keeping with the purpose of these regulations to accomplish coordinated, balanced, and harmonious development in a manner which will best promote the health, safety, and general welfare while avoiding undue and unnecessary hardships, the Administrator is authorized to approve certain requests for deviation from dimensional standards.

(A) Conditions for Modification of Setbacks -Requests for deviation from required setbacks set forth in this ordinance by up to ten percent of the required setbacks or 24 inches, whichever is greater, may be considered upon determination that one or more of the following conditions exists:

(1) There are site or structural conditions that preclude strict adherence to the setback requirements, such as, but not limited to: the lot does not meet the dimensional standards established for the zoning district in which it is located; the lot has topographic limitations that require placement of the structure into the required setback area; or the structure is physically in line with an existing, legally established wall or walls of a principal structure already within the minimum setback area.

(2) The part of the proposed structure that would encroach into the minimum setback area is less than fifty percent of the width of the affected building facade(s), provided the part of the structure that would encroach into a front setback shall either be open (such as a porch or screen room) or not subject to occupancy (such as chimney).



(3) The part of the proposed structure that encroaches into the minimum setback area is necessitated by a life safety code, flood hazard reduction, Americans with Disabilities Act standard, or other public safety code requirements.

(4) A good faith error was made in the location of a building foundation not exceeding two (2) foot due to either field construction error or survey oversight.

(B) Administrative Authority is Permissive Only - The authority given to the Administrator to grant such modification shall be construed to be permissive and not mandatory and the Administrator may decline to make such modification. In the event this occurs, the applicant shall

have the right to submit a variance request to the appropriate Board. Nothing in this section shall be construed as limiting the Administrator's duties and rights under this chapter, or an applicant's right to appeal the decision of the Administrator to the appropriate Board.

Article XIV Conditional Districts

Property may be placed in a conditional district only in response to a petition by all owners of the property to be included. Specific conditions may be proposed by the petitioner or the local government or its agencies, but only those conditions mutually approved by the local government and the petitioner may be incorporated into the zoning regulations. Conditions and site-specific standards imposed in a conditional district shall be limited to those that address the conformance of the development and use of the site to local government ordinances, plans adopted pursuant to G.S. 160D-501, or the impacts reasonably expected to be generated by the development or use of the site. The zoning regulation may provide that defined minor modifications in conditional district standards that do not involve a change in uses permitted or the density of overall development permitted may be reviewed and approved administratively. Any other modification of the conditions and standards in a conditional district shall follow the same process for approval as are applicable to zoning map amendments. If multiple parcels of land are subject to a conditional zoning, the owners of individual parcels may apply for modification of the conditions so long as the modification would not result in other properties failing to meet the terms of the conditions. Any modifications approved shall only be applicable to those properties whose owners petition for the modification. The applicant's written consent is required for conditions not authorized by otherwise applicable law, including, without limitation, taxes, impact fees, building design elements within the scope of N.C.G.S 160D-702, driveway-related improvements in excess of those allowed in N.C.G.S. 136-18(29), or other unauthorized limitations on the development or use of land.

Article XV Determinations

The officer making the determination shall give written notice to the owner of the property that is the subject of the determination and to the party who sought the determination, if different from the owner. The written notice shall be delivered by personal delivery, electronic mail, or by first-class mail. The notice shall be delivered to the last address listed for the owner of the affected property on the county tax abstract and to the address provided in the application or request for a determination if the party seeking the determination is different from the owner.

Article XVI Optional Posting of Signs By Owner

It is conclusively presumed that all persons with standing to appeal have constructive notice of the determination from the date a sign providing notice that a determination has been made is prominently posted on the property that is the subject of the determination, provided the sign remains on the property for at least 10 days. The sign shall contain the words "Zoning Decision" or "Subdivision Decision" or similar language for other determinations in letters at least 6 inches high and shall identify the means to contact a local government staff member for information about the determination. Posting of signs is not the only form of constructive notice. Any such posting is the responsibility of the landowner, applicant, or person who sought the determination. Verification of the posting shall be provided to the staff member responsible for the determination. Posting of signs shall not be required by the Ordinance Administrator.

Article XVII Word Interpretation

For the purpose of this ordinance, certain words shall be interpreted as follows:

Words in the present tense include the future tense.

Words used in the singular number include the plural, and words used in the plural number include the singular, unless the natural construction of the wording indicates otherwise.

The word "person" includes a firm, association, corporation, trust, and company as well as an individual.

The word "structure" shall include the word "building."

The word "lot" shall include the words, "plot," "parcel," or "tract."

The word "shall" is always mandatory and not merely directory.

The word "will" is always mandatory and not merely directory.

CHAPTER 6 STATUTORY PROVISIONS

The following provisions are found in the North Carolina General Statutes and are adopted by reference and incorporated in this code as currently set forth and as amended in the future. Copies of the current versions are included here for ease of review.

Permit Choice and Vested Rights: [NCGS 160D-108](#) & [108.1](#)

[Conflicts of Interest: NCGS 160D-109](#)

[Split Jurisdiction: NCGS 160D-203](#)

[Agricultural Uses: NCGS 160D-903](#)

§ 160D-108. Permit choice and vested rights.

(a) Findings. - The General Assembly recognizes that local government approval of development typically follows significant investment in site evaluation, planning, development costs, consultant fees, and related expenses. The General Assembly finds that it is necessary and desirable to provide for the establishment of certain vested rights in order to ensure reasonable certainty, stability, and fairness in the development regulation process, to secure the reasonable expectations of landowners, and to foster cooperation between the public and private sectors in land-use planning and development regulation. The provisions of this section and G.S. 160D-108.1 strike an appropriate balance between private expectations and the public interest.

(b) Permit Choice. - If a land development regulation is amended between the time a development permit application was submitted and a development permit decision is made or if a land development regulation is amended after a development permit decision has been challenged and found to be wrongfully denied or illegal, G.S. 143-755 applies.

(c) Vested Rights. - Amendments in land development regulations are not applicable or enforceable without the written consent of the owner with regard to any of the following:

- (1) Buildings or uses of buildings or land for which a development permit application has been submitted and subsequently issued in accordance with G.S. 143-755.
- (2) Subdivisions of land for which a development permit application authorizing the subdivision has been submitted and subsequently issued in accordance with G.S. 143-755.
- (3) A site-specific vesting plan pursuant to G.S. 160D-108.1.

- (4) A multi-phased development pursuant to subsection (f) of this section.
- (5) A vested right established by the terms of a development agreement authorized by Article 10 of this Chapter.

The establishment of a vested right under any subdivision of this subsection does not preclude vesting under one or more other subdivisions of this subsection or vesting by application of common law principles. A vested right, once established as provided for in this section or by common law, precludes any action by a local government that would change, alter, impair, prevent, diminish, or otherwise delay the development or use of the property allowed by the applicable land development regulation or regulations, except where a change in State or federal law mandating local government enforcement occurs after the development application is submitted that has a fundamental and retroactive effect on the development or use.

(d) Duration of Vesting. - Upon issuance of a development permit, the statutory vesting granted by subsection (c) of this section for a development project is effective upon filing of the application in accordance with G.S. 143-755, for so long as the permit remains valid pursuant to law. Unless otherwise specified by this section or other statute, local development permits expire one year after issuance unless work authorized by the permit has substantially commenced. A local land development regulation may provide for a longer permit expiration period. For the purposes of this section, a permit is issued either in the ordinary course of business of the applicable governmental agency or by the applicable governmental agency as a court directive.

Except where a longer vesting period is provided by statute or land development regulation, the statutory vesting granted by this section, once established, expires for an uncompleted development project if development work is intentionally and voluntarily discontinued for a period of not less than 24 consecutive months, and the statutory vesting period granted by this section for a nonconforming use of property expires if the use is intentionally and voluntarily discontinued for a period of not less than 24 consecutive months. The 24-month discontinuance period is automatically tolled during the pendency of any board of adjustment proceeding or civil action in a State or federal trial or appellate court regarding the validity of a development permit, the use of the property, or the existence of the statutory vesting period granted by this section. The 24-month discontinuance period is also tolled during the pendency of any litigation involving the development project or property that is the subject of the vesting.

(e) Multiple Permits for Development Project. - Subject to subsection (d) of this section, where multiple local development permits are required to complete a development project, the development permit applicant may choose the version of each of the local land development regulations applicable to the project upon submittal of the application for the initial development permit. This provision is applicable only for those subsequent

development permit applications filed within 18 months of the date following the approval of an initial permit. For purposes of the vesting protections of this subsection, an erosion and sedimentation control permit or a sign permit is not an initial development permit.

(f) Multi-Phased Development. - A multi-phased development is vested for the entire development with the land development regulations then in place at the time a site plan approval is granted for the initial phase of the multi-phased development. A right which has been vested as provided for in this subsection remains vested for a period of seven years from the time a site plan approval is granted for the initial phase of the multi-phased development.

(g) Continuing Review. - Following issuance of a development permit, a local government may make subsequent inspections and reviews to ensure compliance with the applicable land development regulations in effect at the time of the original application.

(h) Process to Claim Vested Right. - A person claiming a statutory or common law vested right may submit information to substantiate that claim to the zoning administrator or other officer designated by a land development regulation, who shall make an initial determination as to the existence of the vested right. The decision of the zoning administrator or officer may be appealed under G.S. 160D-405. On appeal, the existence of a vested right shall be reviewed de novo. In lieu of seeking such a determination or pursuing an appeal under G.S. 160D-405, a person claiming a vested right may bring an original civil action as provided by G.S. 160D-1403.1.

(i) Miscellaneous Provisions. - The vested rights granted by this section run with the land except for the use of land for outdoor advertising governed by G.S. 136-131.1 and G.S. 136-131.2 in which case the rights granted by this section run with the owner of a permit issued by the North Carolina Department of Transportation. Nothing in this section precludes judicial determination, based on common law principles or other statutory provisions, that a vested right exists in a particular case or that a compensable taking has occurred. Except as expressly provided in this section, nothing in this section shall be construed to alter the existing common law.

(j) [Definitions. -] As used in this section, the following definitions apply:

- (1) Development. - As defined in G.S. 143-755(e)(1).
- (2) Development permit. - As defined in G.S. 143-755(e)(2).
- (3) Land development regulation. - As defined in G.S. 143-755(e)(3).
- (4) Multi-phased development. - A development containing 25 acres or more that is both of the following:
 - a. Submitted for development permit approval to occur in more than one phase.
 - b. Subject to a master development plan with committed elements showing the type and intensity of use of each

phase. (2019-111, s. 2.4; 2020-3, s. 4.33(a); 2020-25, ss. 5(a), 50(b), 51(a), (b), (d).)

§ 160D-108.1. Vested rights - site-specific vesting plans.

(a) Site-Specific Vesting Plan. - A site-specific vesting plan consists of a plan submitted to a local government in which the applicant requests vesting pursuant to this section, describing with reasonable certainty on the plan the type and intensity of use for a specific parcel or parcels of property. The plan may be in the form of, but not be limited to, any of the following plans or approvals: a planned unit development plan, a subdivision plat, a preliminary or general development plan, a special use permit, a conditional district zoning plan, or any other land-use approval designation as may be utilized by a local government. Unless otherwise expressly provided by the local government, the plan shall include the approximate boundaries of the site; significant topographical and other natural features affecting development of the site; the approximate location on the site of the proposed buildings, structures, and other improvements; the approximate dimensions, including height, of the proposed buildings and other structures; and the approximate location of all existing and proposed infrastructure on the site, including water, sewer, roads, and pedestrian walkways. What constitutes a site-specific vesting plan under this section that would trigger a vested right shall be finally determined by the local government pursuant to a development regulation, and the document that triggers the vesting shall be so identified at the time of its approval. A variance does not constitute a site-specific vesting plan, and approval of a site-specific vesting plan with the condition that a variance be obtained does not confer a vested right unless and until the necessary variance is obtained. If a sketch plan or other document fails to describe with reasonable certainty the type and intensity of use for a specified parcel or parcels of property, it may not constitute a site-specific vesting plan.

(b) Establishment of Vested Right. - A vested right is established with respect to any property upon the valid approval, or conditional approval, of a site-specific vesting plan as provided in this section. Such a vested right confers upon the landowner the right to undertake and complete the development and use of the property under the terms and conditions of the site-specific vesting plan, including any amendments thereto.

(c) Approval and Amendment of Plans. - If a site-specific vesting plan is based on an approval required by a local development regulation, the local government shall provide whatever notice and hearing is required for that underlying approval. A duration of the underlying approval that is less than two years does not affect the duration of the site-specific vesting plan established under this section. If the site-specific vesting plan is not based on such an approval, a legislative hearing with notice as required by G.S. 160D-602 shall be held.

A local government may approve a site-specific vesting plan upon any terms and conditions that may reasonably be necessary to protect the public health, safety, and welfare. Conditional approval results in a vested right, although failure to abide by the terms and conditions of the approval will result in a forfeiture of vested rights. A local government shall not require a landowner to waive the landowner's vested rights as a condition of developmental approval. A site-specific vesting plan is deemed approved upon the effective date of the local government's decision approving the plan or another date determined by the governing board upon approval. An approved site-specific vesting plan and its conditions may be amended with the approval of the owner and the local government as follows: any substantial modification must be reviewed and approved in the same manner as the original approval; minor modifications may be approved by staff, if such are defined and authorized by local regulation.

(d) Continuing Review. - Following approval or conditional approval of a site-specific vesting plan, a local government may make subsequent reviews and require subsequent approvals by the local government to ensure compliance with the terms and conditions of the original approval, provided that these reviews and approvals are not inconsistent with the original approval. The local government may, pursuant to G.S. 160D-403(f), revoke the original approval for failure to comply with applicable terms and conditions of the original approval or the applicable local development regulations.

(e) Duration and Termination of Vested Right. -

- (1) A vested right for a site-specific vesting plan remains vested for a period of two years. This vesting shall not be extended by any amendments or modifications to a site-specific vesting plan unless expressly provided by the local government.
- (2) Notwithstanding the provisions of subdivision (1) of this subsection, a local government may provide for rights to be vested for a period exceeding two years but not exceeding five years where warranted in light of all relevant circumstances, including, but not limited to, the size and phasing of development, the level of investment, the need for the development, economic cycles, and market conditions or other considerations. These determinations are in the sound discretion of the local government and shall be made following the process specified for the particular form of a site-specific vesting plan involved in accordance with subsection (a) of this section.
- (3) Upon issuance of a building permit, the provisions of G.S. 160D-1111 and G.S. 160D-1115 apply, except that a permit does not expire and shall not be revoked because of the running of time while a vested right under this section is outstanding.

- (4) A right vested as provided in this section terminates at the end of the applicable vesting period with respect to buildings and uses for which no valid building permit applications have been filed.
- (f) Subsequent Changes Prohibited; Exceptions. -
- (1) A vested right, once established as provided for in this section, precludes any zoning action by a local government which would change, alter, impair, prevent, diminish, or otherwise delay the development or use of the property as set forth in an approved site-specific vesting plan, except under one or more of the following conditions:
 - a. With the written consent of the affected landowner.
 - b. Upon findings, by ordinance after notice and an evidentiary hearing, that natural or man-made hazards on or in the immediate vicinity of the property, if uncorrected, would pose a serious threat to the public health, safety, and welfare if the project were to proceed as contemplated in the site-specific vesting plan.
 - c. To the extent that the affected landowner receives compensation for all costs, expenses, and other losses incurred by the landowner, including, but not limited to, all fees paid in consideration of financing, and all architectural, planning, marketing, legal, and other consulting fees incurred after approval by the local government, together with interest as provided under G.S. 160D-106. Compensation shall not include any diminution in the value of the property which is caused by the action.
 - d. Upon findings, by ordinance after notice and an evidentiary hearing, that the landowner or the landowner's representative intentionally supplied inaccurate information or made material misrepresentations that made a difference in the approval by the local government of the site-specific vesting plan or the phased development plan.
 - e. Upon the enactment or promulgation of a State or federal law or regulation that precludes development as contemplated in the site-specific vesting plan or the phased development plan, in which case the local government may modify the affected provisions, upon a finding that the change in State or federal law has a fundamental effect on the plan, by ordinance after notice and an evidentiary hearing.

- (2) The establishment of a vested right under this section does not preclude the application of overlay zoning or other development regulations which impose additional requirements but do not affect the allowable type or intensity of use, or ordinances or regulations which are general in nature and are applicable to all property subject to development regulation by a local government, including, but not limited to, building, fire, plumbing, electrical, and mechanical codes. Otherwise applicable new regulations become effective with respect to property which is subject to a site-specific vesting plan upon the expiration or termination of the vesting rights period provided for in this section.
 - (3) Notwithstanding any provision of this section, the establishment of a vested right does not preclude, change, or impair the authority of a local government to adopt and enforce development regulations governing nonconforming situations or uses.
- (g) Miscellaneous Provisions. -
- (1) A vested right obtained under this section is not a personal right, but attaches to and runs with the applicable property. After approval of a site-specific vesting plan, all successors to the original landowner are entitled to exercise these rights.
 - (2) Nothing in this section precludes judicial determination, based on common law principles or other statutory provisions, that a vested right exists in a particular case or that a compensable taking has occurred. Except as expressly provided in this section, nothing in this section shall be construed to alter the existing common law.
 - (3) In the event a local government fails to adopt a development regulation setting forth what constitutes a site-specific vesting plan triggering a vested right, a landowner may establish a vested right with respect to property upon the approval of a zoning permit, or otherwise may seek appropriate relief from the Superior Court Division of the General Court of Justice. (2020-25, ss. 5(b), 50(b).)

§ 160D-109. Conflicts of interest.

(a) Governing Board. - A governing board member shall not vote on any legislative decision regarding a development regulation adopted pursuant to this Chapter where the outcome of the matter being considered is reasonably likely to have a direct, substantial, and readily identifiable financial impact on the member. A governing board member shall not vote on any zoning amendment if the landowner of the property subject to a rezoning

petition or the applicant for a text amendment is a person with whom the member has a close familial, business, or other associational relationship.

(b) Appointed Boards. - Members of appointed boards shall not vote on any advisory or legislative decision regarding a development regulation adopted pursuant to this Chapter where the outcome of the matter being considered is reasonably likely to have a direct, substantial, and readily identifiable financial impact on the member. An appointed board member shall not vote on any zoning amendment if the landowner of the property subject to a rezoning petition or the applicant for a text amendment is a person with whom the member has a close familial, business, or other associational relationship.

(c) Administrative Staff. - No staff member shall make a final decision on an administrative decision required by this Chapter if the outcome of that decision would have a direct, substantial, and readily identifiable financial impact on the staff member or if the applicant or other person subject to that decision is a person with whom the staff member has a close familial, business, or other associational relationship. If a staff member has a conflict of interest under this section, the decision shall be assigned to the supervisor of the staff person or such other staff person as may be designated by the development regulation or other ordinance.

No staff member shall be financially interested or employed by a business that is financially interested in a development subject to regulation under this Chapter unless the staff member is the owner of the land or building involved. No staff member or other individual or an employee of a company contracting with a local government to provide staff support shall engage in any work that is inconsistent with his or her duties or with the interest of the local government, as determined by the local government.

(d) Quasi-Judicial Decisions. - A member of any board exercising quasi-judicial functions pursuant to this Chapter shall not participate in or vote on any quasi-judicial matter in a manner that would violate affected persons' constitutional rights to an impartial decision maker. Impermissible violations of due process include, but are not limited to, a member having a fixed opinion prior to hearing the matter that is not susceptible to change, undisclosed ex parte communications, a close familial, business, or other associational relationship with an affected person, or a financial interest in the outcome of the matter.

(e) Resolution of Objection. - If an objection is raised to a board member's participation at or prior to the hearing or vote on a particular matter and that member does not recuse himself or herself, the remaining members of the board shall by majority vote rule on the objection.

(f) Familial Relationship. - For purposes of this section, a "close familial relationship" means a spouse, parent, child, brother, sister, grandparent, or grandchild. The term includes the step, half, and in-law relationships. (2019-111, s. 2.4; 2020-3, s. 4.33(a); 2020-25, s. 51(a), (b), (d).)

§ 160D-203. Split jurisdiction.

If a parcel of land lies within the planning and development regulation jurisdiction of more than one local government, for the purposes of this Chapter, the local governments may, by mutual agreement pursuant to Article 20 of Chapter 160A of the General Statutes and with the written consent of the landowner, assign exclusive planning and development regulation jurisdiction under this Chapter for the entire parcel to any one of those local governments. Such a mutual agreement shall only be applicable to development regulations and shall not affect taxation or other nonregulatory matters. The mutual agreement shall be evidenced by a resolution formally adopted by each governing board and recorded with the register of deeds in the county where the property is located within 14 days of the adoption of the last required resolution. (2019-111, s. 2.4; 2020-3, s. 4.33(a); 2020-25, s. 51(a), (b), (d).)

§ 160D-903. Agricultural uses.

(a) Bona Fide Farming Exempt From County Zoning. - County zoning regulations may not affect property used for bona fide farm purposes; provided, however, that this section does not limit zoning regulation with respect to the use of farm property for nonfarm purposes. Except as provided in G.S. 106-743.4 for farms that are subject to a conservation agreement under G.S. 106-743.2, bona fide farm purposes include the production and activities relating or incidental to the production of crops, grains, fruits, vegetables, ornamental and flowering plants, dairy, livestock, poultry, and all other forms of agriculture, as defined in G.S. 106-581.1. Activities incident to the farm include existing or new residences constructed to the applicable residential building code situated on the farm occupied by the owner, lessee, or operator of the farm and other buildings or structures sheltering or supporting the farm use and operation. For purposes of this section, "when performed on the farm" in G.S. 106-581.1(6) includes the farm within the jurisdiction of the county and any other farm owned or leased to or from others by the bona fide farm operator, no matter where located. For purposes of this section, the production of a nonfarm product that the Department of Agriculture and Consumer Services recognizes as a "Goodness Grows in North Carolina" product that is produced on a farm subject to a conservation agreement under G.S. 106-743.2 is a bona fide farm purpose. For purposes of determining whether a property is being used for bona fide farm purposes, any of the following is sufficient evidence that the property is being used for bona fide farm purposes:

- (1) A farm sales tax exemption certificate issued by the Department of Revenue.

- (2) A copy of the property tax listing showing that the property is eligible for participation in the present-use value program pursuant to G.S. 105-277.3.
- (3) A copy of the farm owner's or operator's Schedule F from the owner's or operator's most recent federal income tax return.
- (4) A forest management plan.

A building or structure that is used for agritourism is a bona fide farm purpose if the building or structure is located on a property that (i) is owned by a person who holds a qualifying farm sales tax exemption certificate from the Department of Revenue pursuant to G.S. 105-164.13E(a) or (ii) is enrolled in the present-use value program pursuant to G.S. 105-277.3. Failure to maintain the requirements of this subsection for a period of three years after the date the building or structure was originally classified as a bona fide farm purpose pursuant to this subsection subjects the building or structure to applicable zoning and development regulation ordinances adopted by a county pursuant to G.S. 160D-702 in effect on the date the property no longer meets the requirements of this subsection. For purposes of this section, "agritourism" means any activity carried out on a farm or ranch that allows members of the general public, for recreational, entertainment, or educational purposes, to view or enjoy rural activities, including farming, ranching, historic, cultural, harvest-your-own activities, hunting, fishing, equestrian activities, or natural activities and attractions. A building or structure used for agritourism includes any building or structure used for public or private events, including, but not limited to, weddings, receptions, meetings, demonstrations of farm activities, meals, and other events that are taking place on the farm because of its farm or rural setting.

(b) County Zoning of Residential Uses on Large Lots in Agricultural Districts. - A county zoning regulation shall not prohibit single-family detached residential uses constructed in accordance with the North Carolina State Building Code on lots greater than 10 acres in size and in zoning districts where more than fifty percent (50%) of the land is in use for agricultural or silvicultural purposes, except that this restriction does not apply to commercial or industrial districts where a broad variety of commercial or industrial uses are permissible. A zoning regulation shall not require that a lot greater than 10 acres in size have frontage on a public road or county-approved private road or be served by public water or sewer lines in order to be developed for single-family residential purposes.

(c) Agricultural Areas in Municipal Extraterritorial Jurisdiction. - Property that is located in a city's extraterritorial planning and development regulation jurisdiction and that is used for bona fide farm purposes is exempt from the city's zoning regulation to the same extent bona fide farming activities are exempt from county zoning pursuant to this section. As used in this subsection, "property" means a single tract of property or an identifiable portion of a single tract. Property that ceases to be used for bona fide farm

purposes becomes subject to exercise of the city's extraterritorial planning and development regulation jurisdiction under this Chapter. For purposes of complying with State or federal law, property that is exempt from municipal zoning pursuant to this subsection is subject to the county's floodplain regulation or all floodplain regulation provisions of the county's unified development ordinance.

(d) Accessory Farm Buildings. - A city may provide in its zoning regulation that an accessory building of a "bona fide farm" has the same exemption from the building code as it would have under county zoning.

(e) City Regulations in Voluntary Agricultural Districts. - A city may amend the development regulations applicable within its planning and development regulation jurisdiction to provide flexibility to farming operations that are located within a city or county, voluntary agricultural district, or enhanced voluntary agricultural district adopted under Article 61 of Chapter 106 of the General Statutes. Amendments to applicable development regulations may include provisions regarding on-farm sales, pick-your-own operations, road signs, agritourism, and other activities incident to farming. (2019-111, s. 2.4; 2020-3, s. 4.33(a); 2020-25, ss. 22, 51(a), (b), (d); 2020-74, s. 20.)

CHAPTER 7 DEFINITIONS

- (1) Abandoned Sign - A sign which for a period of at least 180 consecutive days or longer no longer advertises or identifies a legal business establishment, product or activity.
- (2) Abandonment – Cessation of use of a wireless support structure for wireless telecommunications activity for at least the minimum period of time specified under this ordinance.
- (3) Accelerated Erosion - means any increase over the rate of natural erosion as a result of land-disturbing activity.
- (4) Accessory Equipment - Any equipment serving or being used in conjunction with a wireless facility or wireless support structure. The term includes utility or transmission equipment, power supplies, generators, batteries, cables, equipment buildings, cabinets and storage sheds, shelters or similar structures.
- (5) Accessory Structure (Appurtenant Structure, Accessory Building) - means a structure located on the same parcel of property as the principal structure and the use of which is incidental to the use of the principal structures. Garages, carports and storage sheds are common urban accessory structures. Pole barns hay sheds and the like qualify as accessory structures on farms and may or may not be located on the same parcel as the farm dwelling or shop building.
- (6) Accessory Use - See [Chapter 10, Article V, Section 5](#).
- (7) Act - means the North Carolina Sedimentation Pollution Control Act of 1973 and all rules and orders adopted pursuant to it.
- (8) Addition (to an existing building) - means an extension or increase in the floor area or height of a building or structure.
- (9) Adequate Erosion Control Measure, Structure, or Device - means one which controls the soil material within the land area under responsible control of the Person conducting the land-disturbing activity.
- (10) Administrative Approval – Approval that the Administrator or designee is authorized to grant after administrative review.
- (11) Administrative Decision – Decisions made in the implementation, administration, or enforcement of development regulations that involve the determination of facts and the application of objective standards set forth in this Chapter or local government development regulations. These are sometimes referred to as ministerial decisions or administrative determinations.
- (12) Administrative Hearing – A proceeding to gather facts needed to make an administrative decision.

- (13) Administrative Review – Non-discretionary evaluation of an application by the Administrator or designee. The process is not subject to a public hearing.
- (14) Administrator - The person or persons assigned by the Board of Commissioners to enforce this ordinance. Aka, Ordinance Administrator, County Official, Zoning Administrator, Watershed Administrator, Planning Staff, etc.
- (15) Adult Arcade - means any place to which the public is permitted or invited wherein coin-operated, slug-operated, or for any form of consideration, or electronically, electrically, or mechanically controlled still or motion picture machines, projectors, video or laser disc players, or other image-producing devices are maintained to show images to five or fewer persons per machine at any one time, and where the images so displayed are distinguished or characterized by the depicting or describing of "specified sexual activities" or "specified anatomical areas."
- (16) Adult Bookstore - means a bookstore:
- (a) which receives a majority of its gross income during any calendar month from the sale or rental of publications (including books, magazines, other periodicals, videotapes, compact discs, other photographic, electronic, magnetic, digital, or other imaging medium) which are distinguished or characterized by their emphasis on matter depicting, describing, or relating to specified sexual activities or specified anatomical areas, as defined in this section; or
 - (b) having as a preponderance (either in terms of the weight and importance of the material or in terms of greater volume of materials) of its publications (including books, magazines, other periodicals, videotapes, compact discs, other photographic, electronic, magnetic, digital, or other imaging medium) which are distinguished or characterized by their emphasis on matter depicting, describing, or relating to specified sexual activities or specified anatomical areas, as defined in this section. A commercial establishment may have other principal business purposes that do not involve the offering for sale or rental of material depicting or describing "specified sexual activities" or "specified anatomical areas" and still be categorized as ADULT BOOKSTORE, ADULT NOVELTY STORE, or ADULT VIDEO STORE. Such other business purposes will not serve to exempt such commercial establishments from being categorized as an ADULT BOOKSTORE, ADULT NOVELTY STORE, or ADULT VIDEO STORE so long as one of its principal business purposes is the offering for sale or rental for consideration the specified materials which are characterized by the depiction or description of "specified

sexual activities" or "specified anatomical areas."

- (17) Adult Cabaret - means a nightclub, bar, restaurant, or similar commercial establishment which regularly features:
- (a) persons who appear in a state of nudity or semi-nude; or
 - (b) live performances which are characterized by the exposure of "specified anatomical areas" or by "specified sexual activities"; or
 - (c) films, motion pictures, video cassettes, slides or other photographic reproductions which are characterized by the depiction or description of "specified sexual activities" or "specified anatomical areas."
- (18) Adult Establishment - means an adult bookstore, adult motion, picture theatre, adult mini motion picture theatre, adult live entertainment business, or massage business as defined in this section.
- (19) Adult Live Entertainment - means any performance of or involving the actual presence of real people which exhibits specified sexual activities or specified anatomical areas, as defined in this section.
- (20) Adult Live Entertainment Business – means any establishment or business wherein adult live entertainment is shown for observation by patrons.
- (21) Adult Mini Motion Picture Theatre - means an enclosed building with viewing booths designed to hold patrons which is used for presenting motion pictures, a preponderance of which are distinguished or characterized by an emphasis on matter depicting, describing, or relating to specified sexual activities or specified anatomical areas as defined in this section, for observation by patrons therein.
- (22) Adult Motel - means a hotel, motel or similar commercial establishment which:
- (a) offers accommodations to the public for any form of consideration; provides patrons with closed-circuit television transmissions, films, motion pictures, video cassettes, slides, or other photographic reproductions which are characterized by the depiction or description of "specified sexual activities" or "specified anatomical areas"; and has a sign visible from the public right of way which advertises the availability of this adult type of photographic reproductions; or
 - (b) offers a sleeping room for rent for a period of time that is less than ten (10) hours; or
 - (c) allows a tenant or occupant of a sleeping room to sub-rent the room for a period of time that is less than ten (10) hours.
- (23) Adult Motion Picture Theatre - Means enclosed adult building or premises used for presenting motion pictures, a preponderance of which are distinguished or characterized by an emphasis on matter depicting, describing, or relating to specified sexual activities or

- specified anatomical areas, as defined in this section, for observation by patrons therein. "Adult motion picture theatre" does not include any adult mini motion picture theatre as defined in this section.
- (24) Adult Theatre - means a theatre, concert hall, auditorium, or similar commercial establishment which regularly features persons who appear in a state of nudity or semi-nude, or live performances which are characterized by the exposure of "specified anatomical areas" or by "specified sexual activities."
- (25) Affiliate – means a person that directly, or indirectly through one or more intermediaries, controls, is controlled by, or is under common control of another person.
- (26) Agricultural Farm – A bona fide farm whose primary purpose is the production of agricultural products including but not limited to crops, fruits, Christmas trees, vegetables, ornamental or flowering plants, dairy, livestock, poultry, and all other forms of agricultural products having a domestic or foreign market.
- (27) Agricultural Use - The use of waters for stock watering, irrigation, and other farm purposes.
- (28) Alteration - Any change in copy, color, size or shape, which changes appearance of a sign, or a change in position, location, construction or supporting structure of a sign, except that a copy change on a sign is not an alteration.
- (29) Alteration of a watercourse - means a dam, impoundment, channel relocation, change in channel alignment, channelization, or change in cross-sectional area of the channel or the channel capacity, or any other form of modification which may alter, impede, retard or change the direction and/or velocity of the riverine flow of water during conditions of the base flood.
- (30) Animated Sign - A sign which has any visible moving part, flashing or osculating lights, visible mechanical movement of any description, or other apparent visible movement achieved by any means that move, change, flash, osculate or visibly alters in appearance in a manner that is not permitted by these regulations.
- (31) Antenna - Communications equipment that transmits, receives or transmits and receives electromagnetic radio signals used in the provision of all types of wireless communications services.
- (32) Appeal - means a request for a review of the Ordinance Administrator's interpretation of any provision of this ordinance.
- (33) Approving Authority – means the Division or other State or a local government agency that has been delegated erosion and sedimentation plan review responsibilities in accordance with the provisions of the Act.

- (34) Area of Sign - Refer to measurement standards in [Chapter 16 Article II Section 1](#).
- (35) Area of Special Flood Hazard" see "Special Flood Hazard Area (SFHA)".
- (36) Art - An aesthetic physical item or artistic creation.
- (37) Asphalt Plant – A facility utilizing equipment that blends, dries, heats and mixes aggregates with asphalt cement to produce hot mix asphalt (HMA), including *batch* and *drum* plants.
- (38) Assisted Living Facility – Any group housing and services program for two or more unrelated adults, however named, that makes available, at a minimum, one meal a day and housekeeping services and provides personal care services directly or through a formal written agreement with one or more NC licensed home care or hospice agencies.
- (39) Attraction or Reader Board - Any sign having changeable copy for the purpose of advertising events, sales, services or products provided on the site.
- (40) Automatic Changeable Facing Billboard. - A sign, display, or device which changes the message or copy on the sign facing electronically by movement or rotation of panels or slats.
- (41) Automobile Graveyard – An outdoor establishment which is used for storing, keeping, processing, buying or selling more than five (5) wrecked, abandoned, scrapped, ruined or dismantled motor vehicles or motor vehicle parts.
- (42) Awning Sign - Any permanent sign painted on or attached to or supported by an awning.
- (43) Awning - A shelter extending from the exterior wall of a building and composed of non-rigid materials except for the supporting framework.
- (44) Balance of Watershed (BW). The area adjoining and upstream of the critical area in a WS-II and WS-III water supply watershed. The "balance of watershed" is comprised of the entire land area contributing surface drainage to the stream, river, or reservoir where a water supply intake is located.
- (45) Balloon Sign - A temporary lighter-than-air gas-filled balloon, tethered in a fixed location that has a sign with a message on its surface or attached in any manner to the balloon.
- (46) Banner Sign - A temporary, lightweight sign that contains a message which is attached or imprinted on a flexible surface that deforms under light pressure and that is typically constricted of non-durable materials, including, but not limited to, cardboard, cloth and/or plastic.

- (47) Base Flood Elevation (BFE) - means a determination of the water surface elevations of the base flood as published in the Flood Insurance Study. When the BFE has not been provided in a "Special Flood Hazard Area", it may be obtained from engineering studies available from a Federal, State, or other source using FEMA approved engineering methodologies. This elevation, when combined with the "Freeboard", establishes the "Regulatory Flood Protection Elevation".
- (48) Base Flood - means the flood having a one (1) percent chance of being equaled or exceeded in any given year.
- (49) Base Station - A station at a specific site authorized to communicate with mobile stations, generally consisting of radio transceivers, antennas, coaxial cables, power supplies and other associated electronics.
- (50) Basement - means any area of the building having its floor subgrade (below ground level) on all sides.
- (51) Being Conducted - means a land-disturbing activity has been initiated and not deemed complete by the Approving Authority.
- (52) Best Management Practices (BMP) - A structural or nonstructural management-based practice used singularly or in combination to reduce nonpoint source inputs to receiving waters in order to achieve water quality protection goals.
- (53) Billboard. - A sign structure and/or sign utilized to display a commercial message or provide commercial advertising for an establishment, an activity, a product, service or entertainment, which is sold, produced, manufactured, available or furnished at a place other than on the property on which said sign and/or sign structure is located.
- (54) Bona Fide Farm Purposes – Agricultural activities as set forth in G.S. 160D-903.
- (55) Boarding House - A residential use consisting of at least one dwelling unit together with more than two rooms that are rented or are designed or intended to be rented but which rooms, individually or collectively, do not constitute separate dwelling units. A rooming house or boarding house is distinguished from a tourist home in that the former is designed to be occupied by longer-term residents (at least month-to-month tenants) as opposed to overnight or weekly guests.
- (56) Borrow - means fill material that is required for on-site construction that is obtained from other locations.
- (57) Buffer Zone - means the strip of land adjacent to a lake or natural watercourse.
- (58) Buffer - An area of natural or planted vegetation through which stormwater runoff flows in a diffuse manner so that the runoff does

not become channelized and which provides for infiltration of the runoff and filtering of pollutants. The buffer is measured landward from the normal pool elevation of impounded structures and from the bank of each side of streams or rivers.

- (59) Building - Any structure having a roof supported by columns or by walls, and intended for shelter, housing or enclosure of persons, animals or property. The connection of two buildings by means of an open porch, breezeway, passageway, carport or other structure, with or without a roof, shall not be deemed to make them one building.
- (60) Building Identification Sign - A permanent sign containing the name or address of a building and may include hours of operation and emergency information, such sign being located on the same site as the structure.
- (61) Building Lines - Lines tangent to the exterior surface of a building and parallel to front, side and rear property lines.
- (62) Building Setback Line (Minimum) - A line parallel with the property line designating an area bordering the property lines on which no building shall be placed.
- (63) Building, Accessory - A minor building that is located on the same lot as a principal building and that is used incidentally to a principal building or that houses an accessory use.
- (64) Building, Principal - The primary building on a lot or a building that house a principal use.
- (65) Built-upon area - ~~Built-upon areas shall include that portion of a development project that is covered by impervious or partially impervious cover including buildings, pavement, gravel roads, recreation facilities (e.g. tennis courts), etc. (Note: Wooden slatted decks and the water area of a swimming pool are considered pervious).~~ Built-upon area means impervious surface and partially impervious surface to the extent that the partially impervious surface does not allow water to infiltrate through the surface and into the subsoil. "Built-upon area" does not include a slatted deck; the water area of a swimming pool; a surface of number 57 stone, as designated by the American Society for Testing and Materials, laid at least four inches thick over a geotextile fabric; a trail as defined in G.S. 113A-85 that is either unpaved or paved as long as the pavement is porous with a hydraulic conductivity greater than 0.001 centimeters per second (1.41 inches per hour); or landscaping material, including, but not limited to, gravel, mulch, sand, and vegetation, placed on areas that receive pedestrian or bicycle traffic or on portions of driveways and parking areas that will not be compacted by the weight of a vehicle, such as the area between sections of pavement that support the weight of a vehicle (except as exempted by State law); and artificial turf, manufactured to allow

water to drain through the backing of the turf and installed according to the manufacturer's specifications over a pervious surface.

- (66) Canopy - A freestanding permanent roof-like shelter not attached to or requiring support from an adjacent structure.
- (67) Canopy Sign - Any permanent sign attached to or constructed underneath a canopy. These signs are below a projecting structure which extends over the pedestrian walkway which effectively prevents the wall signs for being visible to the pedestrian walking under the canopy. See Also Projecting Sign.
- (68) Carrier on Wheels or Cell on Wheels (COW) - A portable self-contained wireless facility that can be moved to a location and set up to provide wireless services on a temporary or emergency basis. A COW is normally vehicle-mounted and contains a telescoping boom as the antenna support structure.
- (69) Cement Mixing Facility – A facility utilizing equipment that combines materials including but not limited to sand, water, aggregate, ash, and cement to form concrete, including *ready mix* and *central mix* plants.
- (70) Certified Local Government (CLG) Program - Certified Local Government (CLG) Programs are approved by the US Department of the Interior in cooperation with the North Carolina Department of Cultural Resources through the State Historic Preservation Officer as having met the requirements of the National Historic Preservation Act of 1966 as amended in 1980.
- (71) Certify - Whenever this chapter requires that some agency certify the existence of some fact or circumstance to the county, the county may require that such certification be made in any manner that provides reasonable assurance of the accuracy of the certification. By way of illustration, and without limiting the foregoing, the county may accept certification by telephone from some agency when the circumstances warrant it, or the county may require that the certification be in the form of a letter or other document.
- (72) Chemical – An element, chemical compound, a mixture of elements or compounds or both.
- (73) Chemical Manufacturing – A facility involved in the production, synthesis, formation, processing, refining, manufacturing, and/or distribution of chemical products in bulk.
- (74) Chemical Storage Facilities – A facility used for the storage of chemical compounds in bulk.
- (75) Child Care Facility – Includes child care centers, family child care homes, and any other child care arrangement not excluded by NCGS

- §110-86(2), that provides child care, regardless of the time of day, wherever operated, and whether or not operated for profit.
- (a) A child care center is an arrangement where, at any one time, there are three or more preschool-age children or nine or more school-age children receiving child care.
 - (b) A family child care home is a child care arrangement located in a residence where, at any one time, more than two children, but less than nine children, receive child care.
- (76) Chip Mill – A mechanized facility that grinds whole logs into wood chips for paper, particle board and other products and is capable of producing at least 250,000 tons annually.
- (77) Cluster Development - The grouping of buildings in order to conserve land resources and provide for innovation in the design of the project including minimizing stormwater runoff impacts. This term includes non-residential development as well as single-family residential subdivisions and multi-family developments that do not involve the subdivision of land. ~~that do not involve the subdivision of land.~~ For the purpose of Chapter 21, planned unit developments and mixed-use development are considered cluster development.
- (78) Coastal Counties - means the following counties: Beaufort, Bertie, Brunswick, Camden, Carteret, Chowan, Craven, Currituck, Dare, Gates, Hertford, Hyde, New Hanover, Onslow, Pamlico, Pasquotank, Pender, Perquimans, Tyrrell and Washington.
- (79) Collocation - The placement or installation of wireless facilities on existing structures, including electrical transmission towers, water towers, buildings and other structures capable of structurally supporting the attachment of wireless facilities in compliance with applicable codes.
- (80) Combination Use - A use consisting of a combination on one lot of two or more principal uses. When two or more separately owned or separately operated enterprises occupy the same lot, and all such enterprises fall within the same principal use classification, this shall not constitute a combination use.
- (81) Commercial – Used for an occupation, employment, or enterprise that is carried on for profit by the owner, lessee, or licensee.
- (82) Commercial or Industrial Area (re: wireless telecommunications regulations) – A parcel of land on which commercial or industry activity is actually conducted and the area along the highway extending outward 800 feet from and beyond such activity.
- (83) Commission - means the North Carolina Sedimentation Control

Commission.

- (84) Common Plan of Development – site where multiple separate and distinct development activities may be taking place at different times or different schedules but governed by a single development plan regardless of ownership of parcels.
- (85) Completion of Construction or Development - means that no further land-disturbing activity is required on a phase of a project except that which is necessary for establishing a permanent ground cover.
- (86) Composting Facility – A facility in which only stumps, limbs, leaves, grass and untreated wood collected from land clearing or landscaping operations is deposited.
- (87) Concealed Wireless Facility - Any wireless facility that is integrated as an architectural feature of an existing structure or any new wireless support structure designed to camouflage or conceal the presence of antennas or towers so that the purpose of the facility or wireless support structure is not readily apparent to a casual observer.
- (88) Conditional Zoning – A legislative zoning map amendment with site-specific conditions incorporated into the zoning map amendment.
- (89) Construction Sign - A temporary sign identifying the persons, firms or business directly connected with a construction project.
- (90) Convenience Store - A one-story, retail store containing less than 2,000 square feet of gross floor area that is designed and stocked to sell primarily food, beverages, and other household supplies to customers who purchase only a relatively few items (in contrast to a “supermarket”). It is designed to attract and depends upon a large volume of stop-and-go traffic. Illustrative examples of convenience stores are those operated by the “Fast Fare”, “7-11” and “Pantry” chains.
- (91) Critical Area - The area adjacent to a water supply intake or reservoir where risk associated with pollution is greater than from the remaining portions of the watershed. The critical area is defined as extending either one-half mile from the normal pool elevation of the reservoir in which the intake is located or to the ridge line of the watershed (whichever comes first); or one-half mile upstream from the intake located directly in the stream or river (run-of-the-river), or the ridge line of the watershed (whichever comes first). ~~Since WS-1 watersheds are essentially undeveloped, establishment of a critical area is not required.~~ Local governments may extend the critical area as needed. Major landmarks such as highways or property lines may be used to delineate the outer boundary of the critical area if these landmarks are immediately adjacent to the appropriate outer boundary of one-half mile.

- (92) Cul-de-sac - A short subdivision street having but one end open to traffic and the other end being permanently terminated and a vehicular turn-around provided.
- (93) Customary Home Occupations - Any use conducted entirely within a dwelling and carried on by the occupants thereof, which use is clearly incidental and secondary to the use of the dwelling for residential purposes and does not change the character thereof. Provided further that no mechanical equipment is installed or used except as is normally used for domestic or professional purposes, and that not over twenty-five percent (25%) of the total floor space of any structure is used for the occupation. No home occupation shall be conducted in any accessory building except for the storage and service of a vehicle that is driven off site, such as a service repair truck, delivery truck, etc.
- (94) Department – when used alone means the North Carolina Department of Environmental Quality.
- (95) Determination – A written, final, and binding order, requirement, or determination regarding an administrative decision.
- (96) Developer - A person, including a governmental agency or redevelopment authority, who undertakes any development and who is the landowner of the property to be developed or who has been authorized by the landowner to undertake development on that property.
- (97) Development – Unless the context clearly indicated otherwise, the term means any man-made change to improved or unimproved real estate, including, but not limited to the following:
- (a) The construction, erection, alteration, enlargement, renovation, substantial repair, movement to another site, or demolition of any building or structure.
 - (b) The excavation, grading, filling, clearing, paving, mining, dredging, drilling operation, storage of equipment or materials, or alteration of land.
 - (c) The subdivision of land as defined in G.S. 160D-802.
 - (d) The initiation or substantial change in the use of land or the intensity of use of land.
 - (e) Any land disturbing activity which adds to or changes the amount or nature of impervious or partially impervious cover on a land area or which otherwise decreases the infiltration of precipitation into the soil.

The definition does not alter the scope of regulatory authority granted by this Chapter.

- (98) Development Activity - means any activity defined as Development which will necessitate a Floodplain Development Permit. This includes buildings, structures, and non-structural items, including

(but not limited to) fill, bulkheads, piers, pools, docks, landings, ramps, and erosion control/stabilization measures.

- (99)** Development Approval – An administrative or quasi-judicial approval made pursuant to this Chapter that is written and that is required prior to commencing development or undertaking a specific activity, project, or development proposal. Development approvals include, but are not limited to, zoning permits, site plan approvals, special use permits, variances, and certificates of appropriateness. The term also includes all other regulatory approvals required by regulations adopted pursuant to this Chapter, including plat approvals, permits issued, development agreements entered into, and building permits issued.
- (100)** Development regulation – A unified development ordinance, zoning regulation, subdivision regulation, erosion and sedimentation control regulation, floodplain or flood damage prevention regulation, mountain ridge protection regulation, stormwater control regulation, wireless telecommunication facility regulation, historic preservation or landmark regulation, housing code, State Building Code enforcement, or any other regulation adopted pursuant to NCGS160D, or a local act or charter that regulates land use or development.
- (101)** Digital Flood Insurance Rate Map (DFIRM) - means the digital official map of a community, issued by the Federal Emergency Management Agency (FEMA), on which both the Special Flood Hazard Areas and the risk premium zones applicable to the community are delineated.
- (102)** Dimensional Nonconformity - A nonconforming situation that occurs when the height, size, or minimum floor space of a structure or the relationship between an existing building or buildings and other buildings or lot lines does not conform to the regulations applicable to the district in which the property is located.
- (103)** Director - means the Director of the Division of Energy Mineral and Land Resources of the Department of Environment and Natural Resources.
- (104)** Discharge Point or Point of Discharge - means that point where runoff leaves a tract of land where a land-disturbing activity has occurred or enters a lake or natural watercourse.
- (105)** Discharging Landfill - A facility with liners, monitoring equipment and other measures to detect and/or prevent leachate from entering the environment and in which the leachate is treated on site and discharged to a receiving stream.
- (106)** Disposal - means, as defined in NCGS 130A-290(a)(6), the discharge, deposit, injection, dumping, spilling, leaking, or placing of any solid waste into or on any land or water so that the solid

waste or any constituent part of the solid waste may enter the environment or be emitted into the air or discharged into any waters, including groundwater.

- (107) District - means the Watauga County Soil and Water Conservation District created pursuant to Chapter 139, North Carolina General Statutes.
- (108) Double Frontage Lot - A continuous (through) lot which borders two or more streets.
- (109) Dwelling - Any building, structure, manufactured home, or mobile home, or part thereof, used and occupied for human habitation or intended to be so used and includes any outhouses and appurtenances belonging thereto or usually enjoyed therewith. For the purposes of Article 12 of NCGS 106D, the term does not include any manufactured home, mobile home, or recreational vehicle, if used solely for a seasonal vacation purpose.
- (110) Dwelling Unit - A building, or portion thereof, providing complete and permanent living facilities for one family.
- (111) Easement - A strip of land designated by the property owner for a specified purpose and use by the public, a corporation, or persons.
- (112) Educational Facility - Elementary schools, secondary schools, community colleges, colleges, and universities, including support facilities such as administration for all of the preceding. Also includes any property owned or operated by those facilities used for educational, vocational or athletic purposes.
- (113) Electrical Transmission Tower - An electrical transmission structure used to support high voltage overhead power lines. The term shall not include any utility pole.
- (114) Electricity Generating Facility - A stand-alone plant, not ancillary to another land use which generates electricity to be distributed to consumers including but not limited to fossil fuel burning facilities and solar power farms. This definition shall not include electricity produced on an agricultural farm or residence whose use is limited to on-site consumption which only sells electricity to a public utility incidental to the on-site use.
- (115) Electronic Message Center/Changeable Copy Sign - A permanent sign or portion thereof on which the copy or symbols change either automatically through electrical or electronic means (for example, time and temperature units), or manually through placement of letters or symbols on a panel mounted in or on a track system.

- (116) Elevated Building - means a non-basement building which has its lowest elevated floor raised above ground level by foundation walls, shear walls, posts, piers, pilings, or columns.
- (117) Eligible Facilities Request – A request for modification of an existing wireless tower or base station that involves collocation of new transmission equipment or replacement of transmission equipment but does not include a substantial modification.
- (118) Employee (re: Sexually Oriented Business regulations) - means a person who performs any service on the premises of a sexually oriented business on a full-time, part-time or contract basis, whether or not the person is denominated an employee, independent contractor, agent or otherwise and whether or not said person is paid a salary, wage or other compensation by the operator of said business. Also included are all persons who participate for consideration or possibility of a prize in any contests, performances, or exhibitions sponsored by or allowed at a sexually oriented business or occurring upon the premises of the sexual oriented business. Employee does not include a person exclusively on the premises for repair or maintenance of the premises or equipment on the premises, or for the delivery of goods to the premises.
- (119) Encroachment - means the advance or infringement of uses, fill, excavation, buildings, structures or development into a floodplain, which may impede or alter the flow capacity of a floodplain.
- (120) Energy Dissipator - means a structure or a shaped channel section with mechanical armoring placed at the outlet of pipes or conduits to receive and break down the energy from high velocity flow.
- (121) Equipment Compound - An area surrounding or near the base of a wireless support structure within which are located wireless facilities.
- (122) Erosion - means the wearing away of land surfaces by the action of wind, water, gravity, or any combination thereof.
- (123) Escort (re: Sexually Oriented Business regulations) - means a person who, for consideration, agrees or offers to act as a companion, guide, or date for another person, or who agrees or offers to privately model lingerie or to privately perform a striptease for another person.
- (124) Escort Agency (re: Sexually Oriented Business regulations) - means a person or business association who furnishes, offers to furnish, or advertises to furnish escorts as one of its primary business purposes for a fee, tip, or other consideration.
- (125) Establishment (re: Sexually Oriented Business regulations) - means and includes any of the following:
- (a) the opening or commencement of any sexually oriented business as a new business;

- (b) the conversion of an existing business, whether or not a sexually oriented business, to any sexually oriented business;
 - (c) the additions of any sexually oriented business to any other existing sexually oriented business; or
 - (d) the relocation of any sexually oriented business.
- (126) Evidentiary Hearing – A hearing to gather competent, material, and substantial evidence in order to make findings for a quasi-judicial decision required by a development regulation adopted under this Chapter.
- (127) Existing Development - Those projects that are built or those projects that ~~at a minimum~~ have established a vested right under North Carolina zoning law as of the effective date of this ordinance. ~~based on at least one of the following criteria: substantial expenditures of resources (time, labor, money) based on a good faith reliance upon having received a valid local government approval to proceed with the project, or having an outstanding valid building permit as authorized by the General Statutes (G.S. 160D-108, 108.1), or (3) having an approved site specific or phased development plan as authorized by the General Statutes (G.S. 160D-108, 108.1).~~
- (128) Existing Lot (Lot of Record) - A lot which is part of a subdivision, a plat of which has been recorded in the Office of the Register of Deeds prior to the adoption of this ordinance, or a lot described by metes and bounds, the description of which has been so recorded prior to the adoption of this ordinance.
- (129) Existing Manufactured Home Park or Manufactured Home Subdivision -means a manufactured home park or subdivision for which the construction of facilities for servicing the lots on which the manufactured homes are to be affixed (including, at a minimum, the installation of utilities, the construction of streets, and either final site grading or the pouring of concrete pads) was completed before the initial effective date of the floodplain management regulations adopted by the community.
- (130) Existing Structure (re: Wireless Telecommunications regulations) - A wireless support structure, erected prior to the application for an eligible facilities request, collocation or substantial modification under this ordinance that is capable of supporting the attachment of wireless facilities. The term includes but is not limited to, electrical transmission towers, buildings and water towers. The term shall not include any utility pole.
- (131) Explosives Manufacturing – Manufacturing of a chemical compound, mixture, or device the primary or common purpose of which is to function by explosion. This term includes but is not limited

- to dynamite, black powder, pellet powder, initiating explosives, detonators, safety fuses, squibs, detonating cord, igniting cord, igniters, and display fireworks, but does not include hand-loaded small arms ammunition.
- (132) Fall Zone - The area in which a wireless support structure may be expected to fall in the event of a structural failure as measured by engineering standards.
- (133) Family - One or more persons occupying a single dwelling unit, provided that unless all members are related by blood or marriage or adoption, no such family shall contain over five persons, but further provided that domestic servants employed or living on the premises may be housed on the premises without being counted as a family or families.
- (134) Farm Sign - A sign that advertises a farm, products grown, raised, or produced on a bona fide farm, or services provided on a bona fide farm; or that provides customers with direction to a bona fide farm.
- (135) Farmer's Market - A retail establishment primarily engaged in the sale of fresh fruits, vegetables and similar perishable goods.
- (136) Feather Flag - A piece of cloth or similar material, typically elongated, oblong, and/or with a curved top or bottom edge, which is attached by two edges or one long, curving edge to a pole, and resembles a feather in shape. Generally, the sign is self-supporting (not attached to a building) and/or stuck into the ground in a temporary fashion, the flag is attached by a sleeve (and not by grommets or rope), and the entire sign is temporary in nature
- (137) Flea Market - Buildings or open areas in which booths or sales areas are provided for rent by various unrelated individuals to sell a variety of merchandise. This does not include yards sales, rummage sales, or farmer's markets.
- (138) Flood Boundary and Floodway Map (FBFM) - means an official map of a community, issued by the FEMA, on which the Special Flood Hazard Areas and the floodways are delineated. This official map is a supplement to and shall be used in conjunction with the Flood Insurance Rate Map (FIRM).
- (139) Flood Hazard Boundary Map (FHBM) - means an official map of a community, issued by the FEMA, where the boundaries of the Special Flood Hazard Areas have been defined as Zone A.
- (140) Flood Insurance - means the insurance coverage provided under the National Flood Insurance Program.
- (141) Flood Insurance Rate Map (FIRM) - means an official map of a community, issued by the Federal Emergency Management

- Agency, on which both the Special Flood Hazard Areas and the risk premium zones applicable to the community are delineated.
- (142) Flood Insurance Study (FIS) - means an examination, evaluation, and determination of flood hazards, corresponding water surface elevations (if appropriate), flood hazard risk zones, and other flood data in a community issued by the Federal Emergency Management Agency. The Flood Insurance Study report includes Flood Insurance Rate Maps (FIRMs) and Flood Boundary and Floodway Maps (FBFMs), if published.
- (143) Flood Prone Area - see "Floodplain"
- (144) Flood Zone - means a geographical area shown on a Flood Hazard Boundary Map or Flood Insurance Rate Map that reflects the severity or type of flooding in the area.
- (145) Flood or Flooding - means a general and temporary condition of partial or complete inundation of normally dry land areas from: (1) the overflow of inland or tidal waters; and/or (2) the unusual and rapid accumulation or runoff of surface waters from any source.
- (146) Floodplain - Any land area susceptible to be inundated by water from any source.
- (147) Floodplain Administrator - is the individual appointed to administer and enforce the floodplain management regulations.
- (148) Floodplain Development Permit - means any type of permit that is required in conformance with the provisions of this ordinance, prior to the commencement of any development activity.
- (149) Floodplain Management - means the operation of an overall program of corrective and preventive measures for reducing flood damage and preserving and enhancing, where possible, natural resources in the floodplain, including, but not limited to, emergency preparedness plans, flood control works, floodplain management regulations, and open space plans.
- (150) Floodplain Management Regulations - means this ordinance and other zoning ordinances, subdivision regulations, building codes, health regulations, special purpose ordinances, and other applications of police power. This term describes Federal, State or local regulations, in any combination thereof, which provide standards for preventing and reducing flood loss and damage.
- (151) Floodproofing - means any combination of structural and nonstructural additions, changes, or adjustments to structures which reduce or eliminate flood damage to real estate or improved real property, water and sanitation facilities, structures, and their contents.

- (152)** Flood-resistant material - means any building product [material, component or system] capable of withstanding direct and prolonged contact (minimum 72 hours) with floodwaters without sustaining damage that requires more than low-cost cosmetic repair. Any material that is water-soluble or is not resistant to alkali or acid in water, including normal adhesives for above-grade use, is not flood-resistant. Pressure-treated lumber or naturally decay-resistant lumbers are acceptable flooring materials. Sheet-type flooring coverings that restrict evaporation from below and materials that are impervious, but dimensionally unstable are not acceptable. Materials that absorb or retain water excessively after submergence are not flood-resistant. Please refer to Technical Bulletin 2, Flood Damage-Resistant Materials Requirements, and available from the FEMA. Class 4 and 5 materials, referenced therein, are acceptable flood-resistant materials.
- (153)** Floodway - The channel of a river or other watercourse and the adjacent land areas that must be reserved in order to discharge the base flood without cumulatively increasing the water surface elevation more than one foot. As used in this chapter, the term refers to that area designated as a floodway on the "Flood Boundary and Floodway Map" prepared by the U.S. Department of Housing and Urban Development, a copy of which is on file in the planning department.
- (154)** Floodway encroachment analysis - means an engineering analysis of the impact that a proposed encroachment into a floodway or non-encroachment area is expected to have on the floodway boundaries and flood levels during the occurrence of the base flood discharge. The evaluation shall be prepared by a qualified North Carolina licensed engineer using standard engineering methods and hydraulic models meeting the minimum requirements of the National Flood Insurance Program.
- (155)** Footcandle - A measure of illumination on a surface that is one foot from a uniform source of light of one candle and equal to one lumen per square foot.
- (156)** Freeboard - means the height added to the Base Flood Elevation (BFE) to account for the many unknown factors that could contribute to flood heights greater than the height calculated for a selected size flood and floodway conditions, such as wave action, blockage of bridge openings, and the hydrological effect of urbanization of the watershed. The Base Flood Elevation (BFE) plus the freeboard establishes the "Regulatory Flood Protection Elevation".

- (157) Freestanding Sign - Any permanent sign which is affixed in or upon the ground, supported by one or more structural members, with air space between the ground and the sign face.
- (158) Functionality Dependent Facility - means a facility which cannot be used for its intended purpose unless it is located in close proximity to water, limited to a docking or port facility necessary for the loading and unloading of cargo or passengers, shipbuilding, or ship repair. The term does not include long-term storage, manufacture, sales, or service facilities.
- (159) Gated Community - A development that is enclosed within a geographical area by restrictive gates.
- (160) Gate - A crossbar, door, or other obstructive device which is utilized for the purpose of restricting, controlling, or obstructing entry or exit by motor vehicles or pedestrians to or from a private roadway.
- (161) Governmental Sign - A sign erected and maintained pursuant to and in discharge of any governmental functions, or required by law, ordinance or other governmental regulation.
- (162) Grade (re: Sign regulations) - The level of the site at the property line located at the closest distance to the sign.
- (163) Ground Cover - means any natural vegetative growth or other material which renders the soil surface stable against accelerated erosion.
- (164) Halfway House - A home for not more than nine person who have demonstrated a tendency toward alcoholism, drug abuse, mental illness, or antisocial or criminal conduct, together with not more than two person providing supervision and other services to such persons, the eleven of whom live together as a single housekeeping unit.
- (165) Handicapped or Inform Home - A residence within a single dwelling unit for at least six but not more than nine persons who are physically or mentally handicapped or inform, together with not more than two persons providing care or assistance to such person, all living together as a single housekeeping unit. Person residing in such homes, including the aged and disabled, principally need residential care rather than medical treatment.
- (166) Hazardous Material - Any substance listed as such in: SARA Section 302, Extremely Hazardous Substances, CERCLA Hazardous Substances, or Section 311 of CWA (oil and hazardous substances).
- (167) Hazardous Waste Management Facility - means, as defined in NCGS 130A, Article 9, a facility for the collection, storage, processing, treatment, recycling, recovery, or disposal of hazardous waste.
- (168) Height of Sign - Refer to measurement standards in [Chapter 16 Article II Section 2](#).

- (169) High Impact Land Use – For the purposes of this ordinance, means any and all of the Category 1, Category 2, and Category 3 uses listed in [Chapter 13](#).
- (170) High Quality Water (HQW) Zones –means, for the Coastal Counties, areas within 575 feet of High Quality Waters; and for the remainder of the state, areas within one mile and draining to HQW's.
- (171) High Quality Waters - means those classified as such in 15A NCAC 02B .0224, which is herein incorporated by reference including subsequent amendments and additions.
- (172) Highest Adjacent Grade (HAG) - means the highest natural elevation of the ground surface, prior to construction, immediately next to the proposed walls of the structure.
- (173) Highway Sign - A sign directing attention to a business, commodity, service or entertainment which is conducted, sold or offered on premises other than the premises upon which the sign is located.
- (174) Historic Structure - means any structure that is:
- (a) listed individually in the National Register of Historic Places (a listing maintained by the US Department of Interior) or preliminarily determined by the Secretary of Interior as meeting the requirements for individual listing on the National Register;
 - (b) certified or preliminarily determined by the Secretary of Interior as contributing to the historical significance of a registered historic district or a district preliminarily determined by the Secretary to qualify as a registered historic district;
 - (c) individually listed on a local inventory of historic landmarks in communities with a "Certified Local Government (CLG) Program"; or
 - (d) certified as contributing to the historical significance of a historic district designated by the County.
- (175) Holiday Decorations - Signs or displays including lighting which are a nonpermanent installation celebrating national, state, and local holidays or holiday seasons.
- (176) Home Occupation - An accessory use of a dwelling unit for gainful employment which: is clearly incidental and subordinate to the use of the dwelling unit; is carried on within or from accessory buildings from the main dwelling unit and does not alter or change the exterior character or appearances of the dwelling; is located in a residential district; is created and operated as a sole proprietorship.
- (177) Illegal Sign - Any sign placed without proper approval or permits as required by this Ordinance at the time of sign placement. Illegal

sign shall also mean any sign placed contrary to the terms or time limits of any permit and any nonconforming sign which has not been brought into compliance with any applicable provisions of this Ordinance.

- (178) Illuminated Sign - A permanent sign for which an artificial source of light is used in order to make readable the sign's message, including internally and externally lighted signs and reflectorized, glowing or radiating signs.
- (179) Immediate Family – A person's parents, spouse, children, and siblings, including the parent's spouse. Includes step children and adopted children and their spouses.
- (180) Impervious Surface - Any material that substantially reduces or prevents the infiltration of stormwater into previously undeveloped land.
- (181) Industrial – Use engaged in the manufacturing, and basic processing of materials or products predominantly from extracted or raw materials, or previously prepared materials, including processing, fabrication, assembly, treatment, packaging, storage, sales, and distribution of such products.
- (182) Industrial Development (Re: watershed regulations only) - Any non-residential development that requires an NPDES permit for an industrial discharge and/or requires the use or storage of any hazardous material for the purpose of manufacturing, assembling, finishing, cleaning or developing any product or commodity.
- (183) Ingress/Egress - The point where vehicles or pedestrians enter and exit a development.
- (184) Instructional Signs - A permanent sign clearly intended for instructional purposes, as determined by the Ordinance Administrator, shall not be included in the permitted sum of the sign area of identification wall signs, provided such sign(s) shall contain the minimum information and the minimum area necessary to convey the message and instruct the viewer in the safe and efficient use of the facility.
- (185) Junk/Scrap Yards – An outdoor establishment primarily engaged in the collection, sorting, outdoor storage and/or distribution of recyclable scrap and waste materials including automobiles, cans, steel containers, cast iron, appliances, construction materials, and other ferrous metals.
- (186) Kennel - A commercial operation that: (i) provides food and shelter and care of animals for purposes not primarily related to medical care (a kennel may or may not be run by or associated with a veterinarian), or (ii) engages in the breeding of animals for sale.

- (187) Key Box - A secure, tamperproof device with a lock operable only by a fire department, police department, or emergency services department master key, and containing building entry keys and other such devices that may be required for access in an emergency.
- (188) Lake or Natural Watercourse – means any stream, river, brook, swamp, sound, bay, creek, run, branch, canal, waterway, estuary, and any reservoir, lake or pond.
- (189) Land-disturbing Activity - means any use of the land by any Person in residential, industrial, educational, institutional, or commercial development, highway and road construction and maintenance that results in a change in the natural cover or topography and that may cause or contribute to sedimentation.
- (190) Landfill - A facility for the disposal of solid waste on land in a sanitary manner in accordance with Chapter 130A Article 9 of the N.C. General Statutes. For the purpose of this ordinance this term does not include composting facilities.
- (191) Landowner or Owner – The holder of the title in fee simple. Absent evidence to the contrary, the County may rely on the county tax records to determine who is a landowner. The landowner may authorize a person holding a valid option, lease, or contract to purchase to act as his or her agent or representative for the purpose of making applications for development approvals.
- (192) Large Wind Energy System - A wind energy conversion system consisting of one or more wind turbine(s), a tower(s), and associated control or conversion electronics, which has a rated capacity of more than 20 kW.
- (193) Legislative Decision – The adoption, amendment, or repeal of a regulation under this Title or applicable local act. The term also includes the decision to approve, amend, or rescind a development agreement consistent with the provisions of Article 1- of NCGS 160D.
- (194) Legislative Hearing – A Hearing to solicit public comment on a proposed legislative decision.
- (195) Length of Building Frontage - The measurement purposes, the length of any primary or secondary frontage as defined in [Chapter 16 Article II Section 3](#), shall be the sum of all wall lengths parallel, or nearly parallel, to such frontage, excluding any such wall length determined by the Administrator or Planning Commission as clearly unrelated to the frontage criteria. For buildings with two or more frontages, the length and allowable sign area shall be calculated separately for each such frontage. The building frontage for a building unit shall be measured from the centerline of the party walls defining the building unit.

- (196)** Letter of Map Change (LOMC) - means an official determination issued by FEMA that amends or revises an effective Flood Insurance Rate Map or Flood Insurance Study. Letters of Map Change include:
- a. Letter of Map Amendment (LOMA): An official amendment, by letter, to an effective National Flood Insurance Program map. A LOMA is based on technical data showing that a property had been inadvertently mapped as being in the floodplain, but is actually on natural high ground above the base flood elevation. A LOMA amends the current effective Flood Insurance Rate Map and establishes that a specific property, portion of a property, or structure is not located in a special flood hazard area.
 - b. Letter of Map Revision (LOMR): A revision based on technical data that may show changes to flood zones, flood elevations, special flood hazard area boundaries and floodway delineations, and other planimetric features.
 - c. Letter of Map Revision Based on Fill (LOMR-F): A determination that a structure or parcel of land has been elevated by fill above the BFE and is, therefore, no longer located within the special flood hazard area. In order to qualify for this determination, the fill must have been permitted and placed in accordance with the community's floodplain management regulations.
 - d. Conditional Letter of Map Revision (CLOMR): A formal review and comment as to whether a proposed project complies with the minimum NFIP requirements for such projects with respect to delineation of special flood hazard areas. A CLOMR does not revise the effective Flood Insurance Rate Map or Flood Insurance Study; upon submission and approval of certified as-built documentation, a Letter of Map Revision may be issued by FEMA to revise the effective FIRM.
- (197)** Licensee (re: Sexually Oriented Business regulations)- means a person in whose name a license to operate a sexually oriented business has been issued, as well as the individual listed as an applicant on the application for a license; and in the case of an employee, a person in whose name a license has been issued authorizing employment in a sexually oriented business.
- (198)** Light Duty Truck - means any motor vehicle rated at 8,500 pounds Gross Vehicular Weight Rating or less which has a vehicular curb weight of 6,000 pounds or less and which has a basic vehicle frontal area of 45 square feet or less as defined in 40 CFR 86.082-2 and is:
- a. Designed primarily for purposes of transportation of property or is a derivation of such a vehicle, or
 - b. Designed primarily for transportation of persons and has a capacity of less than 12 persons; or
 - c. Available with special features enabling off-street or off-highway

operation and use.

- (199) Local Government - means any county, incorporated village, town or city, or any combination of counties, incorporated villages, towns, and cities, acting through a joint program pursuant to the provisions of the Act.
- (200) Logo, Logogram, or Logotype - An emblem, letter, character, pictograph, trademark, or symbol used to represent any firm, organization, entity, or product.
- (201) Lot - A parcel of land occupied or capable of being occupied by a building or group of buildings devoted to a common use, together with the customary accessories and open spaces belonging to the same.
- (202) Lot Area - The total area circumscribed by the boundaries of a lot, except that: (i) when the legal instrument creating a lot shows the boundary of the lot extending into public street right-of-way, then the lot boundary for purposes of computing the lot area shall be street right-of-way line, or if the right-of-way line cannot be determined, a line running parallel to and 30 feet from the center of the traveled portion of the street, and (ii) in a residential district, when a private road that served more than three dwelling units is located along any lot boundary, then the lot boundary for purposes of computing the lot area shall be inside boundary of the traveled portion of that road.
- (203) Lowest Adjacent Grade (LAG) - means the elevation of the ground, sidewalk or patio slab immediately next to the building, or deck support, after completion of the building.
- (204) Lowest Floor (re: Flood Damage Prevention regulations) - means the lowest floor of the lowest enclosed area (including basement). An unfinished or flood resistant enclosure, usable solely for parking of vehicles, building access, or limited storage in an area other than a basement area is not considered a building's lowest floor, provided that such an enclosure is not built so as to render the structure in violation of the applicable non-elevation design requirements of this ordinance.
- (205) Major Mountain Ridge - A ridge with an elevation higher than 3000 feet above mean sea level and an elevation 500 feet or more above the elevation of an adjacent valley floor including all land within 100 feet below the elevation of any portion of such line or surface along the crest.
- (206) Major Variance (re: watershed regulations) - A variance that results in any one or more of the following:
~~(a) the complete waiver of a management requirement; or~~

~~(b) the relaxation, by a factor of more than ten (10) percent, of any management requirement that takes the form of a numerical standard.~~

is not a Minor Variance as defined in this chapter.

(207) Manufactured Home or Mobile Home –A structure, transportable in one or more sections, which in the traveling mode is eight body feet or more in width, or 40 body feet or more in length, or, when erected on site, is 320 or more square feet; and which is built on a permanent chassis and designed to be used as a dwelling, with or without permanent foundation when connected to the required utilities, including the plumbing, heating, air conditioning and electrical systems contained therein. "Manufactured home" includes any structure that meets all of the requirements of this subsection except the size requirements and with respect to which the manufacturer voluntarily files a certification required by the Secretary of HUD and complies with the standards established under the Act. For manufactured homes built before June 15, 1976, "manufactured home" means a portable manufactured housing unit designed for transportation on its own chassis and placement on a temporary or semi-permanent foundation having a measurement of over 32 feet in length and over eight feet in width. "Manufactured home" also means a double-wide manufactured home, which is two or more portable manufactured housing units designed for transportation on their own chassis that connect on site for placement on a temporary or semi-permanent foundation having a measurement of over 32 feet in length and over eight feet in width. The term "manufactured home" does not include a "recreational vehicle".

(208) Manufactured Home Park or Subdivision – means a parcel or contiguous parcels of land divided into two or more manufactured home lots for rent or sale (applicable to Chapter 9 only); for land outside of flood hazard areas (all other chapters) - the rental of any site or tract of land upon which three (3) or more manufactured homes occupied for dwelling or sleeping purposes are located. Leases of a term longer than ten (10) years shall be constructed as a sale of property. In determining the term of proposed lease, periods that may add to the original term by options to renew or extend shall be included. Any sale of land within the manufactured home park shall comply with the Watauga County Ordinance to Govern Subdivision and Multi-unit Structures. For purposes of this ordinance, the term "mobile home" may be substituted for "manufactured home."

(209) Map Repository - means the location of the official flood hazard data to be applied for floodplain management. It is a central

location in which flood data is stored and managed; in North Carolina, FEMA has recognized that the application of digital flood hazard data products have the same authority as hard copy products. Therefore, the NCEM's Floodplain Mapping Program websites house current and historical flood hazard data. For effective flood hazard data the NC FRIS website (<http://FRIS.NC.GOV/FRIS>) is the map repository, and for historical flood hazard data the FloodNC website (<http://FLOODNC.GOV/NCFLOOD>) is the map repository.

- (210) Market Value" means the building value, not including the land value and that of any accessory structures or other improvements on the lot. Market value may be established by independent certified appraisal; replacement cost depreciated for age of building and quality of construction (Actual Cash Value); or adjusted tax assessed values.
- (211) Marquee - A permanent roof-like shelter extending from part or all of a building face and constructed of some durable material which may or may not project over a public right-of-way.
- (212) Marquee Sign - A permanent sign painted on or attached to or supported by a marquee.
- (213) Massage - means the manipulation of body muscular tissue by rubbing, stroking, kneading, or tapping, by hand or mechanical device.
- (214) Massage Business - means any establishment or business wherein massage is practiced, including establishments commonly known as health clubs, physical culture studios, massage studios, or massage parlors.
- (215) Mean Sea Level - means, for purposes of this ordinance, the National Geodetic Vertical Datum (NGVD) as corrected in 1929, the North American Vertical Datum (NAVD) as corrected in 1988, or other vertical control datum used as a reference for establishing varying elevations within the floodplain, to which Base Flood Elevations (BFEs) shown on a FIRM are referenced. Refer to each FIRM panel to determine datum used.
- (216) Minor Variance (re: watershed regulations) - A variance ~~that does not qualify as a major variance.~~ from the minimum statewide watershed protection rules that results in a relaxation, by a factor of up to five (5) percent of any buffer, density or built-upon area requirement under the high-density option; or that results in a relaxation, by a factor of up to ten (10) percent, of any management requirement under the low-density option. For variances to a vegetated setback requirement, the percent variation shall be calculated using the footprint of built-upon area proposed to encroach with the vegetated setback divided by the total area of vegetated setback within the project.

- (217) Modifications (re. Electronic Access Gate regulations) - Any structural changes from the original configuration (new or existing), change from manual to electric, change of electronic control operation or alterations requiring a permit.
- (218) Modular Home - A dwelling unit constructed to accordance with the standards as set forth in the state building code applicable to site-built homes and composed of components substantially assembled in a manufacturing plant and transported to the building site for final assembly on permanent foundation. Among other possibilities, a modular home may consist of two sections transported to the site in a manner similar to a mobile home (except that the modular home meets the county building code applicable to site-built homes), or a series of panels or room sections transported on a truck or erected or joined together on the site.
- (219) Monopole – A single, freestanding pole-type structure supporting one or more antennas. For the purposes of this Ordinance, a monopole is not a tower or a utility pole.
- (220) Motor Sports Facility – A facility, track or course open to the general public or accessed by more than five (5) simultaneous riders outside of the owner’s immediate family upon which motor sports racing, racing practice or motor sports related activity is conducted and may include paved or dirt tracks, spectator seating/standing areas, concession areas, restrooms, parking facilities, and broadcast platforms or booths.
- (221) Multi-Family Development - Three or more dwelling units intended for residential occupancy contained within one building or a Planned Unit Development.
- (222) Multi-Phased Development - A development containing 25 acres or more that is both of the following: (1) submitted for development permit approval to occur in more than one phase and (2) subject to a master development plan with committed elements showing the type and intensity of use of each phase.
- (223) Mural - A picture on an exterior surface of a structure. A mural is a sign only if it is related by language, logo, or pictorial depiction to the advertisement of any product or service or the identification of any business.
- (224) Natural Erosion - means the wearing away of the earth’s surface by water, wind, or other natural agents under natural environmental conditions undisturbed by man.
- (225) Neon Sign - A sign with tubing that is internally illuminated by neon or other electrically charged gas.
- (226) New Construction - means structures for which the “start of construction” commenced on or after the effective date of the

initial floodplain management regulations and includes any subsequent improvements to such structures.

- (227) Nonconforming existing lot of record (re: Watershed Protection regulations) - A lot described by a plat or a deed that was recorded prior to the effective date of local regulations (or their amendments) that does not meet the minimum lot-size or other development requirements of these rules.
- (228) Nonconforming Sign - A sign which was validly installed under laws or ordinances in effect at the time of its installation, but which is in conflict with the current provisions of this Ordinance.
- (229) Nonconforming Situation - A situation that occurs when, on the effective date of this chapter, any existing lot or structure or use of an existing lot or structure does not conform to one or more of the regulations applicable to the district in which the lot or structure is located. Among other possibilities, a non-conforming situation may arise because a lot does not meet minimum acreage requirements, because structures exceed maximum height limitations, because the relationship between existing buildings and the land (in such matters as density and setback requirements) is not in conformity with this chapter, or because land or buildings are used for purposes made unlawful by this chapter.
- (230) Nonconforming Use - A nonconforming situation that occurs when property is used for a purpose or in a manner unlawful by the use regulations applicable to the district in which the property is located. (For example, a commercial office building in a residential district may be a nonconforming use). The term also refers to the activity that constitutes the use made of the property. (For example, all activity associated with operating a retail clothing store in a residentially zoned area constitutes a nonconforming use).
- (231) Non-Encroachment Area - means the channel of a river or other watercourse and the adjacent land areas that must be reserved in order to discharge the base flood without cumulatively increasing the water surface elevation more than one (1) foot as designated in the Flood Insurance Study report.
- (232) Non-residential Development - All development other than residential development, agriculture and silviculture.
- (233) Nude Model Studio - means any place where a person who appears semi-nude, in a state of nudity, or who displays "specified anatomical areas" and is provided to be observed, sketched, drawn, painted, sculptured, photographed, or similarly depicted by other persons who pay money or any form of consideration. Nude Model Studio shall not include a proprietary school licensed by the State of North Carolina or a college, junior college or university supported entirely or in part by public taxation; a private college or university which maintains and

- operates educational programs in which credits are transferable to a college, junior college, or university supported entirely or partly by taxation; or in a structure: (a) that has no sign visible from the exterior of the structure and no other advertising that indicates a nude or semi-nude person is available for viewing; and (b) where in order to participate in a class a student must enroll at least three days in advance of the class; and (c) where no more than one nude or semi-nude model is on the premises at any one time.
- (234) Nudity or a State of Nudity - means the showing of the human male or female genitals, pubic area, vulva, anus, anal cleft or cleavage with less than a fully opaque covering, the showing of the female breast with less than a fully opaque covering of any part of the nipple, or the showing of the covered male genitals in a discernibly turgid state.
- (235) Nursing Home – A facility, however named, which is advertised, announced, or maintained for the express or implied purpose of providing nursing or convalescent care for three or more persons unrelated to the operator.
- (236) Official Maps or Plans - Any maps or plans officially adopted by the County Commissioners as a guide to the development of the County.
- (237) Off-Premises Sign - Any sign normally used for promoting an interest other than that of a business, individual, products, or service available on the premises where the sign is located.
- (238) On-Premises Sign - Any sign used for promoting a business, individual, product or service available on the premises where the sign is located.
- (239) Ordinance Administrator – The Watauga County Department of Planning and Inspections.
- (240) Ordinary Maintenance - Ensuring that wireless facilities and wireless support structures are kept in good operating condition. Ordinary maintenance includes inspections, testing and modifications that maintain functional capacity and structural integrity; for example, the strengthening of a wireless support structure's foundation or of the wireless support structure itself. Ordinary maintenance includes replacing antennas of a similar size, weight, shape and color and accessory equipment within an existing equipment compound and relocating the antennas to different height levels on an existing monopole or tower upon which they are currently located. Ordinary maintenance does not include substantial modifications.
- (241) Outdoor storage - shall include any site or use of land that includes the outdoor storage of machinery, equipment, towed

vehicles or other bulk material or item. Finished products as included on a business site and placed out of doors for the purposes of sale or display of product shall not be considered as outdoor storage.

- (242) Parent – means an affiliate that directly, or indirectly through one or more intermediaries, controls another person.
- (243) Parking Space - A portion of the vehicle accommodation area set aside for the parking of one vehicle.
- (244) Person - means any individual, partnership, firm, association, joint venture, public or private corporation, trust, estate, commission, board, public or private institution, utility, cooperative, interstate body, or other legal entity.
- (245) Person Conducting Land-Disturbing Activity - means any Person who may be held responsible for violation unless expressly provided otherwise by this Ordinance, the Act, or any order adopted pursuant to this Ordinance or the Act.
- (246) Person who Violates or Violator - Person Who Violates or Violator, as used in G.S. 113A-64, means: any landowner or other Person who has financial or operational control over the land-disturbing activity; or who has directly or indirectly allowed the activity, and who has failed to comply with any provision of the Act, the rules of this Chapter or any order or local ordinance adopted pursuant to the Act as it imposes a duty upon that Person.
- (247) Planned Unit Development (PUD) - The planned unit development is a permitted use designed to provide for developments incorporating a single type or a variety of related uses which are planned and developed as a unit. Such development may consist of individual lots or common building sites. Common land must be an element of the plan related to affecting the long-term value of the entire development.
- (248) Planning Board – Any board or commission established pursuant to NCGS 160D-301.
- (249) Plat - A map or plan of a parcel of land which is to be, or has been, subdivided.
- (250) Post-FIRM - means construction or other development for which the “start of construction” occurred on or after the effective date of the initial Flood Insurance Rate Map.
- (251) Pre-FIRM - means construction or other development for which the “start of construction” occurred before the effective date of the initial Flood Insurance Rate Map.
- (252) Primary and Secondary Frontage - The frontage of any building or site shall include the elevation(s) facing a public street, facing a primary parking area for the building or tenants, or containing the

public entrance(s) to the building or building units. For multi-tenant buildings, the portion of such building that is owned, or leased by a single tenant, shall be considered a building unit. The primary frontage shall be considered the portion of any frontage containing the primary public entrance(s) to the building or building units. The secondary frontage shall include frontages containing secondary public entrances to the building or building units, and all walls facing a public street or primary parking area not designated as the primary frontage.

- (253) Principally Above Ground - means that at least 51% of the actual cash value of the structure is above ground.
- (254) Private Driveway - A roadway serving three (3) or fewer lots, building sites or other divisions of land and not intended to be public ingress or egress.
- (255) Private Streets - Internal streets that are not owned or maintained by North Carolina Department of Transportation and that are owned and maintained by an entity responsible for upkeep and maintenance, such as a homeowner's association, community group, property management company, or similar organization.
- (256) Processing – Any technique designed to change the physical, chemical, or biological character or composition of any material so as to render it safe for transport; amenable to recovery, storage or recycling; safe for disposal; or reduced in volume or concentration.
- (257) Projecting Sign - A permanent sign which projects from and is supported by a wall or parapet of a building with the display surface of the sign in a plane perpendicular to or approximately perpendicular to the wall. See also [Canopy sign](#).
- (258) Propane – A heavy flammable gaseous alkane C₃H₈, found in crude petroleum and natural gas, also known as LP Gas.
- (259) Propane, Gasoline or Fuel Oil Bulk Storage Facilities – A facility whose primary purpose is the storage, distribution, mixing or transfer of flammable or combustible liquids or gases received by or transferred by tank vessel, pipelines, tank car, piping, or portable tank or container. This definition shall not include filling stations used solely for distribution to individual consumers.
- (260) Protected Area - The area adjoining and upstream of the critical area of WS-IV watersheds. The boundaries of the protected area are defined as within five miles of and draining to the normal pool elevation of the reservoir or to the ridgeline of the watershed; or within 10 miles upstream and draining to the intake located directly in the stream or river or to the ridgeline of the watershed.

- (261) Public Outdoor Recreation Area – A tract of land owned by a government agency or a non-profit community group intended for use for active or passive recreation. This does not include similarly owned land intended for conservation.
- (262) Public Safety and/or Nuisance - means anything which is injurious to the safety or health of an entire community or neighborhood, or any considerable number of persons, or unlawfully obstructs the free passage or use, in the customary manner, of any navigable lake, or river, bay, stream, canal, or basin.
- (263) Qualified Individual. A person certified to perform stream determinations by completing and passing the Surface Water Identification Training and Certification (SWITC) course offered by the N.C. Div. of Water Resources at N.C. State University.
- (264) Quarry/Stone Crusher – A place from which dimension stone, rock, construction aggregate, riprap, sand, gravel, or slate is excavated from the ground and/or processed for use.
- (265) Quasi-judicial Decision – A decision involving the finding of facts regarding a specific application of a development regulation and that requires the exercise of discretion when applying the standards of the regulation. The term includes, but is not limited to, decisions involving variances, special use permits, certificate of appropriateness, and appeals of administrative determinations. Decisions on the approval of subdivision plats and site plans are quasi-judicial in nature if the regulation authorizes a decision-making board to approve or deny the application based not only upon whether the application complies with the specific requirements set forth in the regulation, but also on whether the application complies with one or more generally stated standards requiring a discretionary decision on the findings to be made by the decision-making board.
- (266) Recovered Material – A material that has known recycling potential, can be feasibly recycled, and has been diverted or removed from the solid waste stream for sale, use, or reuse.
- (267) Recreational Park Trailer – a trailer type unit that primarily designed to provide temporary living quarters for recreational, camping, or seasonal use that meets following criteria:
- (a) Built on a single chassis mounted on wheels;

(b) Having a gross trailer area not exceeding 400 square feet in the setup mode, and if less than 320 square feet in the setup mode would require a special movement permit for highway transit; and

(c) Certified by the manufacturer as complying with ANSI A119.5, Recreational Park Trailer Standard.

(268) Recreational Vehicle (RV) – A vehicular-type unit that is primarily designed as temporary living quarters for recreational, camping, or seasonal use; has its own motive power or is mounted on or towed by another vehicle; is regulated by the National Highway Traffic Safety Administration as a vehicle or vehicle equipment; does not require a special highway use permit for operation on the highways; and can be easily transported or set up on a daily basis by an individual.

(269) Recreational Vehicle (RV) (re: Flood Damage Prevention regulations) - means a vehicle, which is:

(a) built on a single chassis;

(b) 400 square feet or less when measured at the largest horizontal projection;

(c) designed to be self-propelled or permanently towable by a light duty truck; and

(d) designed primarily not for use as a permanent dwelling, but as temporary living quarters for recreational, camping, travel, or seasonal use.

(e) Is fully licensed and ready for highway use.

For the purpose of this chapter, "Tiny Homes/Houses" and Park Models that do not meet the items listed above are not considered Recreational Vehicles and should meet the standards of and be permitted as Residential Structures.

(270) Recycling Facility – A building or structure used for the indoor collection, separation, storage and/or processing of recovered materials including non-ferrous metals and may include a time-limited outdoor material collection area. It does not include a thrift store, antique or secondhand store.

(271) Reference Level - is the top of the lowest floor for structures within Special Flood Hazard Areas designated as Zone AI-A30, AE, A, A99 or AO.

(272) Regulatory Flood Protection Elevation - means the "Base Flood Elevation" plus the "Freeboard". In "Special Flood Hazard Areas"

where Base Flood Elevations (BFEs) have been determined, this elevation shall be the BFE plus two (2) feet of freeboard. In "Special Flood Hazard Areas" where no BFE has been established, this elevation shall be at least two (2) feet above the highest adjacent grade.

- (273)** Religious Facility – A facility operated by religious organizations for worship, religious activity or instruction, and related accessory uses on the same site including living quarters and/or child care operations. Solo cemeteries are excluded.
- (274)** Remedy a Violation - means to bring the structure or other development into compliance with State and community floodplain management regulations, or, if this is not possible, to reduce the impacts of its noncompliance. Ways that impacts may be reduced include protecting the structure or other affected development from flood damages, implementing the enforcement provisions of the ordinance or otherwise deterring future similar violations, or reducing Federal financial exposure with regard to the structure or other development.
- (275)** Replacement Pole – Pole of equal proportions and of equal height or such other height that would not constitute a substantial modification to an existing structure in order to support wireless facilities or to accommodate collocation. Requires removal of the wireless support structure it replaces.
- (276)** Replacement Value – The cost to restore a structure to its previously existing condition as computed by an appraisal which has been conducted by an appraiser holding a North Carolina State Certified General Real Estate Appraisal License and conducted in compliance with generally accepted practices within the appraisal community.
- (277)** Residence, Duplex - A two-family residential use in which the dwelling units share a common wall (including without limitation the wall of an attached garage or porch) and in which each dwelling unit has living space on the ground floor and a separate, ground floor entrance.
- (278)** Residence, Multi-Family - A residential use consisting of a building containing three or more dwelling units. For purposes of this definition, a building includes all dwelling units that are enclosed within that building or attached to it by a common floor or wall (even the wall of an attached garage or porch).

- (279) Residence, Single-Family Detached - A residential use consisting of a single detached building containing one dwelling unit and located on a lot or tract.
- (280) Residence, Two-Family - A residential use consisting of a building containing two dwelling units. If two dwellings units share a common wall, even the wall of an attached garage or porch, the dwelling units shall be considered to be located in one building.
- (281) Residential Development - Buildings ~~for residence~~ **constructed for human habitation** such as attached and detached single-family dwellings, apartment complexes, condominiums, townhouses, cottages, etc., and their associated outbuildings such as garages, storage buildings, gazebos, etc., and customary home occupations.
- (282) Residential Subdivisions - A collection of land parcels designated and platted (mapped) exclusively for residential development.
- (283) Residuals. Any solid or semi-solid waste generated from a wastewater treatment plant, water treatment plant or air pollution control facility permitted under the authority of the Environmental Management Commission.
- (284) Revolving or Rotating Sign - An Animated Sign.
- (285) Right of Way - A strip of land designated by the owner or other authority or acquired by other over which other person may legally pass, and on which may be constructed a road or utilities.
- (286) Riverine - means relating to, formed by, or resembling a river (including tributaries), stream, brook, etc.
- (287) Road, County Standard, Private - A road constructed and dedicated in accordance with provisions as set forth in Chapter 18 Article VI, Section 2, with provisions for private maintenance.
- (288) Road, State Standard, Public - A dedicated and accepted public right-of-way for vehicular traffic on which is constructed a road which meets the specifications of North Carolina Department of Transportation, (See [Chapter 18 Article VI, Section 2](#)).
- (289) Road - All private ways used to provide motor vehicle access to (i) two or more lots or (ii) two or more distinct areas or buildings in unsubdivided developments.
- (290) Roof Sign - Any sign erected upon a roof, parapet, or roof-mounted equipment structure and extending above a roof, parapet, or roof-mounted equipment structure of a building or structure.
- (291) Rummage Sales - A sale by a non-profit organization where individual members bring personal property to be sold in order to raise funds for the organization.
- (292) Salvage Yard - means any non-residential property used for the storage, collection, and/or recycling of any type of equipment, and including but not limited to vehicles, appliances and related machinery.

- (293) Sediment - means solid particulate matter, both mineral and organic, that has been or is being transported by water, air, gravity, or ice from its site of origin.
- (294) Sedimentation - means the process by which sediment resulting from accelerated erosion has been or is being transported off the site of the land-disturbing activity or into a lake or natural watercourse.
- (295) Self-Service Storage Facility – Real property designed and used for the purpose of renting or leasing individual storage spaces to customers for the purpose of storing and removing personal property on a self-service basis.
- (296) Semi-Nude or in a Semi-Nude Condition - means the showing of the female breast below a horizontal line across the top of the areola at its highest point or the showing of the male or female buttocks. This definition shall include the entire lower portion of the human female breast, but shall not include any portion of the cleavage of the human female breast, exhibited by a dress, blouse, skirt, leotard, bathing suit, or other wearing apparel provided the areola is not exposed in whole or in part.
- (297) Sewage Treatment Systems –
- (a) Individual Systems. Sewage treatment and disposal systems designed to serve a single connection utilizing the soil for the subsurface disposal of partially treated or treated sewage effluent. Individual systems with a design capacity of less than 3,000 gallons per day will be designed and approved by the Appalachian District Health Department. Individual systems with a design capacity of 3,000 gallons per day or more will be designed by a professional engineer and approved by the designated state agency or the Appalachian District Health Department, whichever is applicable. Individual systems may be shared upon approval of the appropriate agency.
 - (b) Non-Discharge Systems. Sewage treatment and disposal systems designed to serve multiple connections utilizing the soil for the subsurface disposal of partially treated or treated sewage effluent. Non-Discharge systems will be approved by the designated state agency.
 - (c) NPDES Systems. Sewage treatment and disposal systems designed to serve multiple connections discharging into surface waters of the state and subject to the National Pollutant Discharge Elimination System (NPDES) permit program. NPDES systems include those that are owned and operated by the County, a municipality, a sanitary district, a property owners association, utility company and any connections thereto. NPDES Systems will be approved by the designated state agency.

- (298) Sexual Encounter Center - means a business or commercial enterprise that, as one of its principal business purposes, offers for any form of consideration:
- (a) physical contact in the form of wrestling or tumbling between persons of the opposite sex; or
 - (b) activities between male and female persons and/or persons of the same sex when one or more of the persons is in a state of nudity or semi-nude.
- (299) Sexually Oriented Business - means an adult arcade, adult bookstore, adult novelty store, adult video store, adult cabaret, adult motel, adult motion picture theater, adult theater, escort agency, nude model studio, or sexual encounter center.
- (300) Sexually Oriented Devices - means without limitation any artificial or simulated specified anatomical area or other device or paraphernalia that is designed principally for specified sexual activities but shall not mean any contraceptive device.
- (301) Sign - Any name, figure, character, outline, display, announcement, or device, or structure supporting the same, or any other device of similar nature designed to attract attention outdoors, and shall include all parts, portions, units, and materials composing the same, together with the frame, background, and supports or anchoring thereof. A sign shall not include any architectural or landscape features that may also attract attention.
- (302) Sign Face - An exterior display surface of a sign including nonstructural trim exclusive of the supporting structure.
- (303) Sign Permit - A permit issued by the Ordinance Administrator that authorizes the recipient to erect, move, enlarge, or substantially alter a sign.
- (304) Sign, Political -A sign promoting or publicizing a candidate/candidates for election or signs related to issues on a ballot.
- (305) Siltation - means sediment resulting from accelerated erosion which is settleable or removable by properly designed, constructed, and maintained control measures; and which has been transported from its point of origin within the site of a land-disturbing activity; and which has been deposited, or is in suspension in water.
- (306) Site - All the contiguous ground area legally assembled into one development location or individual lot defined as a permanent parcel (lot of record), multiple lots of record, or a portion of a lot of record.
- (307) Site Plan - A scaled drawing and supporting text showing the relationship between lot lines and the existing or proposed uses, buildings, or structures on the lot. The site plan may include site-specific details such as building areas, building height and floor area, setbacks from lot lines and street rights-of-way, intensities,

densities, utility lines and locations, parking, access points, roads, and stormwater control facilities that are depicted to show compliance with all legally required development regulations that are applicable to the project and the site plan review. A site plan approval based solely upon application of objective standards is an administrative decision and a site plan approval based in whole or in part upon the application of standards involving judgment and discretion is a quasi-judicial decision. A site plan may also be approved as part of a conditional zoning decision.

- (308)** Site Specific Vesting Plan - A plan of land development submitted to the County for purpose of obtaining one of the following zoning or land use permits or approvals in which the applicant requests vesting pursuant to Chapter 24 Article XIV of this Ordinance: any project that is to be reviewed by the Planning Board or Board of Adjustment. The plan shall describe with reasonable certainty the type and intensity of use for a specific parcel or parcels of property and include the approximate boundaries of the site; significant topographical and other natural features affecting development of the site; the approximate location of all existing and proposed infrastructure on the site, including water, sewer, roads, pedestrian walkways, driveways and parking areas; and required landscaping areas and buffers.
- (309)** Small Wind Energy System - A wind energy conversion system consisting of a single wind turbine, a tower, and associated control or conversion electronics, which has a rated capacity of not more than 20 kW. Multiple systems located on agricultural farms as defined in the Watauga County High Impact Land Use Ordinance are also considered small wind energy systems even if the aggregate kW exceeds 20, provided the primary intent is to generate power to reduce on-site consumption.
- (310)** Solid Waste Disposal Facility - means any facility involved in the disposal of solid waste, as defined in NCGS 130A-290(a)(35).
- (311)** Solid Waste Disposal Site - means, as defined in NCGS 130A-290(a)(36), any place at which solid wastes are disposed of by incineration, sanitary landfill, or any other method.
- (312)** Special Event Sign - A temporary sign advertising or pertaining to any annual or seasonal event of interest to, open to, or available to, the general public.
- (313)** Special Events - Circuses, fairs, carnivals, festivals, or other types of special events that (i) run for longer than one day but not longer than two weeks, (ii) are intended to or likely to attract substantial

crowds, and (iii) are unlike the customary or usual activities generally associated with the property where the special event is to be located.

- (314)** Special Flood Hazard Area (SFHA) - means the land in the floodplain subject to a one percent (1%) or greater chance of being flooded in any given year. as determined in Article 3, Section B of this ordinance.
- (315)** Special Use Permit - A permit issued to authorize development or land uses in a particular zoning district upon presentation of competent, material, and substantial evidence establishing compliance with one or more general standards requiring that judgment and discretion be exercised as well as compliance with specific standards. The term includes permits previously referred to as conditional use permits or special exceptions.
- (316)** Specified Anatomical Areas - means less than completely and opaquely covered: human genitals, pubic region, buttock, or female breast below a point immediately above the top of the areola; or human male genitals in a discernibly turgid state, even if completely and opaquely covered.
- (317)** Specified Criminal Activity - means any of the following offenses:
- (a)** prostitution or promotion of prostitution; dissemination of obscenity; sale, distribution or display of harmful material to a minor; sexual performance by a child; possession or distribution of child pornography; public lewdness; indecent exposure; indecency with a child; engaging in organized criminal activity; sexual assault; molestation of a child; gambling; or distribution of a controlled substance; or any similar offenses to those described above under the criminal or penal code of other states or countries;
 - (b)** for which:
 - (1)** less than two years have elapsed since the date of conviction or the date of release from confinement imposed for the conviction, whichever is the later date, if the conviction is of a misdemeanor offense;
 - (2)** less than five years have elapsed since the date of conviction or the date of release from confinement for the conviction, whichever is the later date, if the conviction is of a felony offense; or
 - (3)** less than five years have elapsed since the date of the last conviction or the date of release from confinement for the last conviction, whichever is the later date, if the convictions are of two or more misdemeanor offenses or combination of misdemeanor offenses occurring within any 24-month period.
 - (c)** The fact that a conviction is being appealed shall have no effect

on the disqualification of the applicant or a person residing with the applicant.

- (318)** Specified Sexual Activities - means human genitals in a state of sexual stimulation or arousal; acts of human masturbation, sexual intercourse or sodomy; or fondling or other erotic touching of human genitals, pubic regions, buttocks, or female breasts.
- (319)** Stable - A building in which horses or other livestock are kept for commercial use including boarding, hire, and sell.
- (320)** Start of Construction - includes substantial improvement, and means the date the building permit was issued provided the actual start of construction, repair, reconstruction, rehabilitation, addition placement, or other improvement was within 180 days of the permit date. The actual start means either the first placement of permanent construction of a structure on a site, such as the pouring of slab or footings, the installation of piles, the construction of columns, or any work beyond the stage of excavation; or the placement of a manufactured home on a foundation. Permanent construction does not include land preparation, such as clearing, grading, and filling; nor does it include the installation of streets and/or walkways; nor does it include excavation for a basement, footings, piers, or foundations or the erection of temporary forms; nor does it include the installation on the property of accessory buildings, such as garages or sheds not occupied as dwelling units or not part of the main structure. For a substantial improvement, the actual start of construction means the first alteration of any wall, ceiling, floor, or other structural part of the building, whether or not that alteration affects the external dimensions of the building.
- (321)** Stormwater Control Measure (SCM). means a permanent structural device that is designed, constructed, and maintained to remove pollutants from stormwater runoff by promoting settling or filtration; or to mimic the natural hydrologic cycle by promoting infiltration, evapo-transpiration, post-filtration discharge, reuse of stormwater or a combination thereof.
- (322)** Stormwater Runoff - means the runoff of water resulting from precipitation in any form and occurring immediately after rainfall or melting.
- (323)** Storm Drainage Facilities - means the system of inlets, conduits, channels, ditches and appurtenances which serve to collect and convey storm water through and from a given drainage area.
- (324)** Storm water collection system - Any conduit, pipe, channel, curb or gutter for the primary purpose of transporting (not treating) runoff. A storm water collection system does not include vegetated swales, swales stabilized with armoring and/or alternative methods where natural topography prevents the use of vegetated swales

(subject to case-by-case review, curb outlet systems or pipes used to carry drainage underneath built-upon surfaces that are associated with development controlled by the provisions of 15A NCAC 2H. 1003 (c)(1).

(325) Street (Road)(re: Watershed Protection regulations) - A right-of-way for vehicular traffic which affords the principal means of access to abutting properties.

(326) Structure - Anything constructed or erected, including but not limited to buildings, which requires location on the land or attachment to something having permanent location on the land.

(327) Structure (Flood Damage Prevention) - means a walled and roofed building, a manufactured home, or a gas, liquid or liquefied gas storage tank that is principally above ground.

(328) Subdivider - Any person, firm, or corporation who subdivides or develops any land deemed to be a subdivision.

(329) Subdivision - A "subdivision" shall include all divisions of a tract of land into two or more lots, building sites, (including buildings constructed for rental purposes) or other divisions when any one or more of those divisions are created for the purpose whether immediate or future, of sale or building development, and shall include all divisions of land involving the dedication of a new street or a change in existing streets; provided, however, that the following shall not be included within this definition nor be subject to the regulations prescribed by this ordinance:

(a) The combination or recombination of portions of previously platted lots where the total number of lots is not increased and the resultant lots are equal to or exceed the standards of the county as shown in this ordinance, and documented with a recorded plat or a map attached to recorded deed(s).

(b) The division of land into parcels greater than (10) acres where no street right-of-way dedication is involved.

(c) The public acquisition by purchase of strips of land for the widening or opening of streets.

(d) The division of a tract in single ownership whose entire area is no greater than two (2) acres into not more than three (3) lots, where no street right-of-way dedication is involved, and where the resultant lots are equal to or exceed the standards of the county as shown in this ordinance.

(e) The division of land solely among members of the same family, which shall include all lineal descendants or ancestors plus brothers, sisters, aunts, uncles, fathers-in-law, mothers-in-law, brothers-in-law, sisters-in-law, nieces, nephews and stepchildren by any method of transfer except where the parties contemplate development for resale, and where the

resultant lots are equal to or exceed the standards of the county as shown in this ordinance.

(f) The division of land by court ordered/approved division except where the parties contemplate development for resale.

(330) Subsidiary – means an affiliate that is directly, or indirectly through one or more intermediaries, controlled by another person.

(331) Substantially Commenced - For the purposes of this ordinance a development is determined by the Ordinance Administrator to have substantially commenced if evidence is provided that one or more of the following applies:

a. The development has received and maintained a valid erosion and sedimentation control permit and conducted grading activity on a continuous basis and not discontinued it for more than thirty (30) days; or

b. The development has installed substantial on-site infrastructure; or

c. The development has received and maintained a valid building permit for the construction and approval of a building foundation; or

d. Ten percent (10%) or more of the total cost of design- and construction-related activities authorized by such approvals or permits has been completed on the site.

(332) Substantial Damage (Flood Damage Prevention) - means damage of any origin sustained by a structure during any five-year period whereby the cost of restoring the structure to its before damaged condition would equal or exceed 50 percent of the market value of the structure before the damage occurred, See definition of “substantial improvement”.

(333) Substantial Enlargement of a Sexually Oriented Business - means the increase in floor areas occupied by the business by more than twenty-five percent (25%), as the floor areas exist on the date this ordinance takes effect.

(334) Substantial Improvement (Flood Damage Prevention) - means any combination of repairs, reconstruction, rehabilitation, addition, or other improvement of a structure, taking place during any five-year period for which the cost equals or exceeds 50 percent of the market value of the structure before the “start of construction” of the improvement. This term includes structures which have incurred “substantial damage”, regardless of the actual repair work performed. The term does not, however, include either:

(a) any correction of existing violations of State or community health, sanitary, or safety code specifications which have been identified by the community code enforcement official

and which are the minimum necessary to assure safe living conditions; or

- (b) any alteration of a historic structure, provided that the alteration will not preclude the structure's continued designation as a historic structure.

(335) Substantial Modification - The mounting of a proposed wireless facility or wireless facilities on a wireless support structure that substantially changes the physical dimensions of the support structure. A mounting is presumed to be a substantial modification if it meets any one or more of the following criteria:

- (a) increases the existing vertical height of the wireless support structure by
 - (1) more than ten percent (10%), or
 - (2) the height of one additional antenna array with separation from the nearest existing antenna not to exceed twenty (20) feet, whichever is greater;
- (b) adds an appurtenance to the body of a wireless support structure that protrudes horizontally from the edge of the wireless support structure more than twenty (20) feet, or more than the width of the wireless support structure at the level of the appurtenance, whichever is greater (except where necessary to shelter the antenna from inclement weather or to connect the antenna to the tower via cable);
- (c) increases the square footage of the existing equipment compound by more than 2,500 square feet.

(336) Surface Waters - All waters of the State as defined in NCGS 143-212 except underground waters.

(337) Technical Bulletin and Technical Fact Sheet - means a FEMA publication that provides guidance concerning the building performance standards of the NFIP, which are contained in Title 44 of the U.S. Code of Federal Regulations at Section 60.3. The bulletins and fact sheets are intended for use primarily by State and local officials responsible for interpreting and enforcing NFIP regulations and by members of the development community, such as design professionals and builders. New bulletins, as well as updates of existing bulletins, are issued periodically as needed. The bulletins do not create regulations; rather they provide specific guidance for complying with the minimum requirements of existing NFIP regulations.

It should be noted that Technical Bulletins and Technical Fact Sheets provide guidance on the minimum requirements of the NFIP regulations. State or community requirements that exceed those of the NFIP take precedence. Design professionals should contact the community officials to determine whether more restrictive State or

local regulations apply to the building or site in question. All applicable standards of the State or local building code must also be met for any building in a flood hazard area.

- (338)** Temperature Controlled - means having the temperature regulated by a heating and/or cooling system, built-in or appliance.
- (339)** Temporary Directional Sign - A temporary sign, not exceeding 4 square feet, used as a navigational aid to direct motorists to specific destination(s) for a single purpose or event open to the public.
- (340)** Temporary Emergency, Construction, or Repair Residence - A residence (which may be a mobile home) that is:
 - (a)** located on the same lot as a residence made uninhabitable by fire, flood, or other natural disaster and occupied by the person displaced by such disaster, or
 - (b)** located on the same lot as a residence that is under construction or undergoing substantial repairs or reconstruction and occupied by the person intending to live in such permanent residence when the work is completed, or
 - (c)** located on a nonresidential construction site and occupied by persons having construction or security responsibilities over such construction site.
- (341)** Temporary Sign - A sign utilized for a limited time which is not permanently anchored or secured to a building or the ground and may be easily moved from one location to another. Examples include air-activated motion signs, balloon signs, banner signs, yard signs, feather flag signs, portable message center signs, snipe signs, and sidewalk signs.
- (342)** Ten-Year Storm - a rainfall of an intensity that, based on historical data, is predicted by a method acceptable to the Approving Authority to be equaled or exceeded, on the average, once in ten years, and of a duration that will produce the maximum peak rate of runoff for the watershed of interest under average antecedent wetness conditions.
- (343)** Tower - A lattice-type structure, guyed or freestanding, that supports one or more antennas.
- (344)** Toxic Substance - Any substance or combination of substances (including disease causing agents), which after discharge and upon exposure, ingestion, inhalation, or assimilation into any organism, either directly from the environment or indirectly by ingestion through food chains, has the potential to cause death, disease, behavioral abnormalities, cancer, genetic mutations, physiological malfunctions (including malfunctions or suppression in reproduction or growth) or physical deformities in such organisms or their offspring or other adverse health effects.
- (345)** Tract (re: erosion control regulations) - means all contiguous land and bodies of water being disturbed or to be disturbed as a unit,

regardless of ownership.

- (346) Tract - A lot. The term tract is used interchangeably with the term lot, particularly in the context of subdivisions, where one "tract" is subdivided into several "lots."
- (347) Transfer of Ownership or Control of a Sexually Oriented Business - means and includes any of the following:
- (a) the sale, lease, or sublease of the business;
 - (b) the transfer of securities which constitute a controlling interest in the business, whether by sale, exchange, or similar means; or
 - (c) the establishment of a trust, gift, or other similar legal device which transfers the ownership or control of the business, except for transfer by bequest or other operation of law upon the death of the person possessing the ownership or control.
- (348) ~~Travel Trailer - A structure that (i) is intended to be transported over the streets and highways (either as a motor vehicle or attached to or hauled by a motor vehicle) and (ii) is designed for temporary use as sleeping quarters but that does not satisfy one or more of the definitional criteria of a mobile home.~~
- (349) Twenty-five Year Storm - means a rainfall of an intensity that, based on historical data, is predicted by a method acceptable to the Approving Authority to be equaled or exceeded, on the average, once in 25 years, and of a duration that will produce the maximum peak rate of runoff for the watershed of interest under average antecedent wetness conditions.
- (350) Uncovered - means the removal of ground cover from, on, or above the soil surface.
- (351) Undertaken - means the initiating of any activity, or phase of activity, which results or will result in a change in the ground cover or topography of a tract of land.
- (352) Unit - A structure or portion of a structure which is a single, habitable dwelling or single place of business.
- (353) Unzoned Commercial Area - A site outside of municipal and county zoning jurisdiction which is within 660 feet of the nearest edge of the primary highway right of way and is actually used for commercial or industrial purposes that meets all requirements of NCDOT Administrative Code 2E.0203(5).
- (354) Use - The activity or function that actually takes place or is intended to take place on a lot.
- (355) Utility Facilities - Any above-ground structures or facilities (other than buildings, unless such buildings are used as storage incidental to operation of such structures or facilities) owned by a governmental entity, a nonprofit organization, a corporation, or any entity defined as a public utility for any purpose by the appropriate provision of state law and used in connection with the production, generation,

transmission, delivery, collection, or storage of water, sewage, solid waste, electricity, gas, oil or electronic signals. Excepted from this definition are utility lines and supporting structures.

- (356) Utility Pole - A structure owned and/or operated by a public utility, municipality, electric membership corporation or rural electric cooperative that is designed specifically for and used to carry lines, cables, or wires for telephone, cable television, or electricity, or to provide lighting.
- (357) Variance - is a grant of relief from the requirements of this ordinance.
- (358) Vegetative Buffer - shall generally mean an undisturbed area of native plant vegetation, or a restored area of vegetation, adjacent to a lake, perennial stream, or intermittent stream. Clearing, grading, filling, building of structures, and other activities are limited or prohibited.
- (359) Vehicle Sign - A sign attached to, painted on or mounted on a parked vehicle or trailer in a location not normally used in the daily activity of the business, with the sign visible from a public location so as to act as a sign for the advertisement of products or direction to a business or activity.
- (360) Velocity - means the speed of flow through the cross section perpendicular to the direction of the main channel at the peak flow of the storm of interest but not exceeding bank full flows.
- (361) Vested Right - The right to undertake and complete the development and use of property under the terms and conditions of an approval secured as specified in G.S. 160D-108 or under common law.
- (362) Visible - Capable of being seen without visual aid by a person of normal acuity.
- (363) Violation (re: Flood Damage Prevention regulations) - means the failure of a structure or other development to be fully compliant with the community's floodplain management regulations. A structure or other development without the elevation certificate, other certifications, or other evidence of compliance required in Chapter 9 Article III and IV is presumed to be in violation until such time as that documentation is provided.
- (364) Wall Sign - A sign permanently attached to or painted on the wall of a building or structure in a plane parallel or approximately parallel to the plane of said wall.
- (365) Waste - means surplus materials resulting from on-site land-disturbing activities and being disposed of at other locations.
- (366) Water Dependent Structure - Any structure for which the use requires access to or proximity to or citing within surface waters to

fulfill its basic purpose, such as boat ramps, boat houses, docks and bulkheads. Ancillary facilities such as restaurants, outlets for boat supplies, parking lots and commercial boat storage areas are not water dependent structures.

- (367)** Water Supply Systems –
- (a)** Individual Systems. A well, spring, stream or other source used to supply a single connection.
 - (b)** Community Systems. A water system serving two (2) or more connections and not qualifying as a public water supply (PWS) under North Carolina regulations.
 - (c)** Public Systems. A water system owned and/or operated by the county, any municipality, water district, property owner's association, or utility company that qualifies as a public water supply (PWS) under North Carolina regulations.
- (368)** Water Surface Elevation (WSE) - means the height, in relation to NAVD 1988, of floods of various magnitudes and frequencies in the floodplains of riverine areas.
- (369)** Water Tower - A water storage tank, or a standpipe or an elevated tank situated on a support structure, originally constructed for use as a reservoir or facility to store or deliver water.
- (370)** Watercourse - means a lake, river, creek, stream, wash, channel or other topographic feature on or over which waters flow at least periodically. Watercourse includes specifically designated areas in which substantial flood damage may occur.
- (371)** Watershed - The entire land area contributing surface drainage to a specific point (e.g. the water supply intake.) or alternatively, the geographic region within which water drains to a particular river, stream or body of water.
- (372)** Watershed Administrator - An official or designated person of the county responsible for administration and enforcement of this ordinance.
- (373)** Wholesale Sales - On-premises sales of goods primarily to customers engaged in the business of reselling the goods.
- (374)** Wind Turbine Height - The height above grade to the tip of the turbine blade when it reaches its highest elevation.
- (375)** Window Sign - A sign viewable through and/or affixed in any manner to a window or exterior glass door such that it is intended to be viewable from the exterior (beyond the sidewalk immediately adjacent to the window), including signs located inside a building but visible primarily from the outside of the building.
- (376)** Window, Area of - The area of a single window includes all of the window panes in an area that is separated by mullions, muntins, or other dividers which are less than 3 inches wide.

- (377)** Wireless Facility or Wireless Facilities - The set of equipment and network components, exclusive of the underlying wireless support structure, including, but not limited to, antennas, accessory equipment, transmitters, receivers, base stations, power supplies, cabling and associated equipment necessary to provide wireless telecommunications services.
- (378)** Wireless Support Structure - A freestanding structure, such as a monopole or tower, designed to support wireless facilities. This definition does not include utility poles.
- (379)** Wooded Area - An area of contiguous wooded vegetation where trees are at a density of at least one six-inch or greater caliper tree per 325 square feet of land and where the branches and leaves form a contiguous canopy.
- (380)** Yard Sales - An occasional sale (no more than two (2) in a twelve (12) month period) held for the purpose of disposing of personal property. The term yard sale shall include attic sales, garage sales and patio sales.
- (381)** Yard Setback - A required open space on a lot adjoining a lot line, containing only landscaping or other uses. (front) A yard extending along the full width of a front line between side lot lines and from the front line to the front building line in depth, and the face of the building which is paralleled to a public road. (rear) A yard extending across the full width of the lot and lying between the rear lot line and the nearest line of the building. (side) A yard lying between the side line of the lot and nearest line of the building and extending from the front yard to the rear yard, or in the absence of either of such front or rear yards, to the front or rear lot lines.
- (382)** Zoning Map Amendment or Rezoning - An amendment to a zoning regulation for the purpose of changing the zoning district that is applied to a specified property or properties. The term also includes (i) the initial application of zoning when land is added to the territorial jurisdiction of a local government that has previously adopted zoning regulations and (ii) the application of an overlay zoning district or a conditional zoning district. The term does not include (i) the initial adoption of a zoning map by a local government, (ii) the repeal of a zoning map and readoption of a new zoning map for the entire planning and development regulation jurisdiction, or (iii) updating the zoning map to incorporate amendments to the names of zoning districts made by zoning text amendments where there are no changes in the boundaries of the zoning district or land uses permitted in the district.
- (383)** Zoning Permit - A permit issued by the zoning officer that authorizes the recipient to make use of property in accordance with the requirements of this ordinance.

CHAPTER 8 CONTROL OF SOIL EROSION AND SEDIMENTATION

These regulations are enacted under the delegation of authority by the NC Sedimentation Control Commission, and pursuant to [N.C.G.S. 113A, Article 4](#), and consist of the model ordinance developed by the Commission, including local additions.

Article I Title

This chapter may be cited as the Watauga County Soil Erosion and Sedimentation Control Ordinance.

Article II Purpose

This chapter is adopted for the purposes of:

- (A) regulating certain land-disturbing activity to control accelerated erosion and sedimentation in order to prevent the pollution of water and other damage to lakes, watercourses, and other public and private property by sedimentation; and
- (B) establishing procedures through which these purposes can be fulfilled.

Article III Scope and Exclusions

Section 1. Geographical Scope of Regulated Land-Disturbing Activity.

This chapter shall apply to land-disturbing activity within the territorial jurisdiction of the County and as allowed by agreement between local governments, the extent of annexation or other appropriate legal instrument or law.

Section 2. Exclusions from Regulated Land-Disturbing Activity.

Notwithstanding the general applicability of this chapter to all land-disturbing activity, this chapter shall not apply to the following types of land-disturbing activity:

- (A) Activities, including the production and activities relating or incidental to the production of crops, grains, fruits, vegetables, ornamental and flowering plants, dairy, livestock, poultry, and all other forms of agriculture undertaken on agricultural land for the production of plants and animals useful to man, including, but not limited to:

- (1) forage and sod crops, grain and feed crops, tobacco, cotton, and peanuts.
 - (2) dairy animals and dairy products.
 - (3) poultry and poultry products.
 - (4) livestock, including beef cattle, llamas, sheep, swine, horses, ponies, mules, and goats.
 - (5) bees and apiary products.
 - (6) fur producing animals.
 - (7) mulch, ornamental plants, and other horticultural products. For purposes of this section, "mulch" means substances composed primarily of plant remains or mixtures of such substances.
- (B) An Activity undertaken on forestland for the production and harvesting of timber and timber products and conducted in accordance with standards defined by the Forest Practice Guidelines Related to Water Quality (Best Management Practices), as adopted by the North Carolina Department of Agriculture and Consumer Services. If land-disturbing activity undertaken on forestland for the production and harvesting of timber and timber products is not conducted in accordance with standards defined by the Forest Practice Guidelines Related to Water Quality, the provisions of this ordinance shall apply to such activity and any related land-disturbing activity on the tract.
- (C) An activity for which a permit is required under the Mining Act of 1971, Article 7 of Chapter 74 of the N.C. General Statutes.
- (D) A land-disturbing activity over which the State has exclusive regulatory jurisdiction as provided in N.C.G.S. 113A-56(a).
- (E) An activity which is essential to protect human life during an emergency.
- (F) Activities undertaken to restore the wetland functions of converted wetlands to provide compensatory mitigation to offset impacts permitted under Section 404 of the Clean Water Act.
- (G) Activities undertaken pursuant to Natural Resources Conservation Service standards to restore the wetlands functions of converted wetlands as defined in Title 7 Code of Federal Regulations § 12.2.

Section 3. Plan Approval Requirement for Land-Disturbing Activity.

No Person shall undertake any land-disturbing activity subject to this ordinance without first obtaining an erosion and sedimentation control plan (hereinafter "Plan") approval therefor from the County.

Section 4. Protection of Property.

Persons conducting land-disturbing activity shall take all reasonable measures to protect all public and private property from damage caused by such activity.

Section 5. Plan Approval Exceptions.

Notwithstanding the general requirement to obtain a Plan approval prior to undertaking land-disturbing activity, a Plan approval shall not be required for land-disturbing activity that does not exceed 21,780 square feet in surface area. In determining the area, lands under one or diverse ownership being developed as a unit will be aggregated.

Article IV Mandatory Standards for Land-Disturbing Activity

No land-disturbing activity subject to the control of this chapter shall be undertaken except in accordance with the following mandatory standards:

Section 1. Buffer Zone

- (A) Standard Buffer. No land-disturbing activity during periods of construction or improvement to land shall be permitted in proximity to a lake or natural watercourse unless a buffer zone is provided along the margin of the watercourse of sufficient width to confine visible siltation within the twenty-five percent (25%) of the buffer zone nearest the land-disturbing activity.
 - (1) Projects On, Over or Under Water. This subdivision shall not apply to a land-disturbing activity in connection with the construction of facilities to be located on, over, or under a lake or natural watercourse.
 - (2) Buffer Measurement. Unless otherwise provided, the width of a buffer zone is measured horizontally from the edge of the water to the nearest edge of the disturbed area, with the 25 percent of the strip nearer the land-disturbing activity containing natural or artificial means of confining visible siltation.
- (B) Trout Buffer. Waters that have been classified as trout waters by the Environmental Management Commission shall have an undisturbed buffer zone 25 feet wide or of sufficient width to confine visible siltation within the twenty-five percent (25%) of the buffer zone nearest the land-disturbing activity, whichever is greater. Provided, however, that the Commission may approve plans which include land-disturbing activity along trout waters when the duration of said disturbance would be temporary and the extent of said disturbance

would be minimal.

- (1) Projects On, Over or Under Water. This subdivision shall not apply to a land-disturbing activity in connection with the construction of facilities to be located on, over, or under a lake or natural watercourse.
- (2) Trout Buffer Measurement. The 25-foot minimum width for an undisturbed buffer zone adjacent to designated trout waters shall be measured horizontally from the top of the bank to the nearest edge of the disturbed area.
- (3) Limit on Land Disturbance. Where a temporary and minimal disturbance has been permitted as an exception to the trout buffer, land-disturbing activities in the buffer zone adjacent to designated trout waters shall be limited to a maximum of ten percent (10%) of the total length of the buffer zone within the tract to be disturbed such that there is not more than 100 linear feet of disturbance in each 1000 linear feet of buffer zone. Larger areas may be disturbed with the written approval of the Director.
- (4) Limit on Temperature Fluctuations. No land-disturbing activity shall be undertaken within a buffer zone adjacent to designated trout waters that will cause adverse temperature fluctuations in the trout waters, as set forth in 15 NCAC 2B.0211 "Fresh surface Water Classification and Standards."

Section 2. Graded Slopes and Fills.

The angle for graded slopes and fills shall be no greater than the angle that can be retained by vegetative cover or other adequate erosion control devices or structures. In any event, slopes left exposed will, within 21 calendar days of completion of any phase of grading, be planted or otherwise provided with temporary or permanent ground cover, devices, or structures sufficient to restrain erosion. The angle for graded slopes and fills must be demonstrated to be stable. Stable is the condition where the soil remains in its original configuration, with or without mechanical constraints.

Section 3. Fill Material.

Materials being used as fill shall be consistent with those described in 15A NCAC 13B .0562 unless the site is permitted by the Department's Division of Waste Management to operate as a landfill. Not all materials described in Section .0562 may be suitable to meet geotechnical considerations of the fill activity and should be evaluated accordingly.

Section 4. Ground Cover.

Whenever land-disturbing activity that will disturb more than one acre is undertaken on a tract, the Person conducting the land-disturbing activity shall install erosion and sedimentation control devices and practices that are sufficient to retain the sediment generated by the land disturbing activity within the boundaries of the tract during construction upon and development of said tract, and shall plant or otherwise provide a permanent ground cover sufficient to restrain erosion after completion of construction or development. Provisions for a permanent ground cover sufficient to restrain erosion must be accomplished within 90 calendar days following completion of construction or development.

Section 5. Prior Plan Approval.

No Person shall initiate any land-disturbing activity that will disturb more than one acre on a tract unless, thirty (30) or more days prior to initiating the activity, a Plan for the activity is filed with and approved by the County or unless for land-disturbing activity of more than a half-acre but less than an acre the requirement for such plan had been waived as specified in [Article V](#). The County will attempt to review plans as quickly as possible. The initiation of land-disturbing activities shall not be restricted when the plan is approved and permit issued in less than 30 days.

The County shall forward to the Director of the Division of Water Resources a copy of each Plan for a land-disturbing activity that involves the utilization of ditches for the purpose of de-watering or lowering the water table of the tract.

The land-disturbing activity shall be conducted in accordance with the approved erosion and sedimentation control plan.

Article V Erosion and Sedimentation Control Plans

Section 1. Plan Submission.

A Plan shall be prepared for all land-disturbing activities subject to this chapter whenever the proposed activity will disturb more than one-half acre on a tract. For land-disturbing activity of a half-acre or more but less than one acre, the Watauga County Department of Planning and Inspection may waive the submission of an erosion control plan if, upon site inspection a determination is made that the site does not have the potential to cause erosion or off-site damage. A plan is required for all land-disturbing activity of one acre or more. Three (3) copies of the Plan shall be filed with the County; a copy shall be simultaneously submitted to the Watauga County Soil and Water Conservation District at least 30 days prior to the commencement of the proposed activity.

Section 2. Financial Responsibility and Ownership.

Plans may be disapproved unless accompanied by an authorized statement of financial responsibility and documentation of property ownership. This statement shall be signed by the Person financially responsible for the land-disturbing activity or his attorney in fact. The statement shall include the mailing and street addresses of the principal place of business of (1) the person financially responsible, (2) the owner of the land, and (3) any registered agents. If the Person financially responsible is not a resident of North Carolina, a North Carolina agent must be designated in the statement for the purpose of receiving notice of compliance or non-compliance with the Plan, the Act, this ordinance, or rules or orders adopted or issued pursuant to this ordinance. Except as provided in [sections \(2\)](#) or [\(10\)](#) of this article, if the applicant is not the owner of the land to be disturbed, the draft erosion and sedimentation control plan must include the owner's written consent for the applicant to submit a draft erosion and sedimentation control plan and to conduct the anticipated land-disturbing activity.

If the applicant is not the owner of the land to be disturbed and the anticipated land-disturbing activity involves the construction of utility lines for the provision of water, sewer, gas, telecommunications, or electrical service, the draft erosion and sedimentation control plan may be submitted without the written consent of the owner of the land, so long as the owner of the land has been provided prior notice of the project.

Section 3. Environmental Policy Act Document.

Any Plan submitted for a land-disturbing activity for which an environmental document is required by the North Carolina Environment Policy Act (G.S. 113A-1, et seq.) shall be deemed incomplete until a complete environmental document is available for review. The County shall promptly notify the Person submitting the Plan that the 30-day time limit for review of the Plan pursuant to this ordinance shall not begin until a complete environmental document is available for review.

Section 4. Content.

The Plan required by this section shall contain architectural or engineering drawings, maps, assumptions, calculations, and narrative statements as needed to adequately describe the proposed development of the tract and the measures planned to comply with the requirements of this ordinance. Plan content may vary to meet the needs of specific site requirements. Detailed guidelines for Plan preparation may be obtained from the County on request.

Section 5. Soil and Water Conservation District Comments.

The District shall review the Plan and submit any comments and recommendations to the County within 20 days after the District received the Plan, or within any shorter period of time as may be agreed upon by the District and the County. Failure of the District to submit its comments and recommendations within 20 days or within any agreed-upon shorter period of time shall not delay final action on the Plan.

Section 6. Timeline for Decisions on Plans.

The County will review each complete Plan submitted to them and within 30 days of receipt thereof will notify the Person submitting the Plan that it has been approved, approved with modifications, or disapproved. Failure to approve, approve with modifications, or disapprove a complete Plan within 30 days of receipt shall be deemed approval. The County will review each revised Plan submitted to them and within 15 days of receipt thereof will notify the Person submitting the Plan that it has been approved, approved with modifications, or disapproved. Failure to approve, approve with modifications, or disapprove a revised Plan within 15 days of receipt shall be deemed approval.

Section 7. Approval.

The County shall only approve a Plan upon determining that it complies with all applicable State and local regulations for erosion and sedimentation control. Approval assumes the applicant's compliance with the federal and state water quality laws, regulations and rules. The County shall condition approval of Plans upon the applicant's compliance with federal and state water quality laws, regulations and rules. The County may establish an expiration date, not to exceed three (3) years, for Plans approved under this chapter whereby no land-disturbing activity has been undertaken.

Section 8. Disapproval for Content.

The County may disapprove a Plan or draft Plan based on its content. A disapproval based upon a Plan's content must specifically state in writing the reasons for disapproval.

Section 9. Other Disapprovals.

The County shall disapprove an erosion and sedimentation control plan if implementation of the plan would result in a violation of rules adopted by the Environmental Management Commission to protect riparian buffers

along surface waters. The County may disapprove an erosion and sedimentation control plan or disapprove a transfer of a plan under section (10) of this article upon finding that an applicant or a parent, subsidiary, or other affiliate of the applicant:

- (A) Is conducting or has conducted land-disturbing activity without an approved plan, or has received notice of violation of a plan previously approved by the Commission or a local government pursuant to N.C.G.S. 113A, Article 4 and has not complied with the notice within the time specified in the notice.
- (B) Has failed to pay a civil penalty assessed pursuant to said Article 4 or a local ordinance adopted pursuant to said Article by the time the payment is due.
- (C) Has been convicted of a misdemeanor pursuant to N.C.G.S. 113A-64(b) or any criminal provision of a local ordinance adopted pursuant to N.C.G.S. 113A, Article 4.
- (D) Has failed to substantially comply with State rules or local ordinances and regulations adopted pursuant to said [Article V](#).

In the event that an erosion and sedimentation control plan or a transfer of a plan is disapproved by the County pursuant to section (9) of this article, the local government shall so notify the Director of the Division of Energy, Mineral, and Land Resources within 10 days of the disapproval. The County shall advise the applicant or the proposed transferee and the Director in writing as to the specific reasons that the plan was disapproved. Notwithstanding the provisions of [Article XVI](#), the applicant may appeal the local government's disapproval of the plan directly to the Commission.

For purposes of this subsection, an applicant's record or the proposed transferee's record may be considered for only the two years prior to the application date.

Section 10. Transfer of Plans.

The County administering an erosion and sedimentation control program may transfer an erosion and sedimentation control plan approved pursuant to this section without the consent of the plan holder to a successor-owner of the property on which the permitted activity is occurring or will occur as provided in this subsection.

- (A) The County may transfer a plan if all of the following conditions are met:

- (1) The successor-owner of the property submits to the local government a written request for the transfer of the plan and an authorized statement of financial responsibility and documentation of property ownership.
- (2) The County finds all of the following:
 - (a) The plan holder is one of the following:
 - (i.) A natural person who is deceased.
 - (ii.) A partnership, limited liability corporation, corporation, or any other business association that has been dissolved.
 - (iii.) A Person who has been lawfully and finally divested of title to the property on which the permitted activity is occurring or will occur.
 - (iv.) A Person who has sold the property on which the permitted activity is occurring or will occur.
 - (b) The successor-owner holds title to the property on which the permitted activity is occurring or will occur.
 - (c) The successor-owner is the sole claimant of the right to engage in the permitted activity.
 - (d) There will be no substantial change in the permitted activity.
- (B) The plan holder shall comply with all terms and conditions of the plan until such time as the plan is transferred.
- (C) The successor-owner shall comply with all terms and conditions of the plan once the plan has been transferred.
- (D) Notwithstanding changes to law made after the original issuance of the plan, the County may not impose new or different terms and conditions in the plan without the prior express consent of the successor-owner. Nothing in this subsection shall prevent the County from requiring a revised plan pursuant to G.S. 113A-54.1(b).

Section 11. Notice of Activity Initiation.

No Person may initiate a land-disturbing activity before notifying the agency that issued the Plan approval of the date that land-disturbing activity will begin.

Section 12. Preconstruction Conference.

When deemed necessary by the approving authority a preconstruction conference may be required and noted on the approved plan.

Section 13. Display of Plan Approval.

A Plan approval issued under this article shall be prominently displayed until all construction is complete, all temporary measures have been removed, all permanent sedimentation and erosion control measures are installed, and the site has been stabilized. A copy of the approved plan shall be kept on file at the job site.

Section 14. Required Revisions.

After approving a Plan, if the County either upon review of such Plan or on inspection of the job site, determines that a significant risk of accelerated erosion or off-site sedimentation exists, the County shall require a revised Plan. Pending the preparation of the revised Plan, work shall cease or shall continue under conditions outlined by the appropriate authority. If following commencement of a land-disturbing activity pursuant to an approved Plan, the County determines that the Plan is inadequate to meet the requirements of this ordinance, the County may require any revision of the Plan that is necessary to comply with this ordinance.

Section 15. Amendment to a Plan.

Applications for amendment of a Plan in written and/or graphic form may be made at any time under the same conditions as the original application. Until such time as said amendment is approved by the County, the land-disturbing activity shall not proceed except in accordance with the Plan as originally approved.

Section 16. Failure to File a Plan.

Any Person engaged in land-disturbing activity who fails to file a Plan in accordance with this chapter, or who conducts a land-disturbing activity except in accordance with provisions of an approved Plan shall be deemed in violation of this chapter.

Section 17. Self-Inspections.

The landowner, the financially responsible party, or the landowner's or the financially responsible party's agent shall perform an inspection of the area covered by the plan after each phase of the plan has been completed and after establishment of temporary ground cover in accordance with G.S. 113A-57(2). In addition, weekly and rain-event self-inspections are required by federal regulations, that are implemented through the NPDES Construction General Permit No. NCG010000. The Person who performs the inspection shall

maintain and make available a record of the inspection at the site of the land-disturbing activity. The record shall set out any significant deviation from the approved erosion control plan, identify any measures that may be required to correct the deviation, and document the completion of those measures. The record shall be maintained until permanent ground cover has been established as required by the approved erosion and sedimentation control plan. The inspections required by this subsection shall be in addition to inspections required by G.S. 113A-61.1.

Where inspections are required by this section or G.S. 113A-54.1(e), the following apply:

- (A)** The inspection shall be performed during or after each of the following phases of the plan;
 - (1)** initial installation of erosion and sediment control measures;
 - (2)** clearing and grubbing of existing ground cover;
 - (3)** completion of any grading that requires ground cover;
 - (4)** completion of all land-disturbing activity, construction, or development, including permanent ground cover establishment and removal of all temporary measures; and
 - (5)** transfer of ownership or control of the tract of land where the erosion and sedimentation control plan has been approved and work has begun. The new owner or Person in control shall conduct and document inspections until the project is permanently stabilized as set forth in Sub-Item (iii) of this Item.
- (B)** Documentation of self-inspections performed under Item (1) of this Rule shall include:
 - (1)** Visual verification of ground stabilization and other erosion control measures and practices as called for in the approved plan;
 - (2)** Verification by measurement of settling basins, temporary construction entrances, energy dissipators, and traps.
 - (3)** The name, address, organization affiliation, telephone number, and signature of the person conducting the inspection and the date of the inspection shall be included, whether on a copy of the approved erosion and sedimentation control plan or an inspection report. A template for an example of an inspection and monitoring report is provided on the DEMLR website at: <https://deq.nc.gov/about/divisions/energy-mineral-land-resources/erosion-sediment-control/forms>. Any relevant licenses and certifications may also be included. Any

documentation of inspections that occur on a copy of the approved erosion and sedimentation control plan shall occur on a single copy of the plan and that plan shall be made available on the site.

- (4) A record of any significant deviation from any erosion or sedimentation control measure from that on the approved plan. For the purpose of this Rule, a "significant deviation" means an omission, alternation, or relocation of an erosion or sedimentation control measure that prevents it from performing as intended. The record shall include measures required to correct the significant deviation, along with documentation of when those measures were taken. Deviations from the approved plan may also be recommended to enhance the intended performance of the sedimentation and erosion control measures.

Article VI Basic Control Objectives

An erosion and sedimentation control Plan may be disapproved if the Plan fails to address the following control objectives:

Section 1. Identify Critical Areas.

On-site areas which are subject to severe erosion, and off-site areas which are especially vulnerable to damage from erosion and/or sedimentation, are to be identified and receive special attention.

Section 2. Limit Time of Exposure.

All land-disturbing activities are to be planned and conducted to limit exposure to the shortest time specified in G.S. 113A-57, the rules of this Chapter, or as directed by the Approving Authority.

Section 3. Limit Exposed Areas.

All land-disturbing activity is to be planned and conducted to minimize the size of the area to be exposed at any one time.

Section 4. Control Surface Water.

Surface water runoff originating upgrade of exposed areas should be controlled to reduce erosion and sediment loss during the period of exposure.

Section 5. Control Sedimentation.

All land-disturbing activity is to be planned and conducted so as to prevent off-site sedimentation damage.

Section 6. Manage Storm Water Runoff.

Plans shall be designed so that any increase in velocity of stormwater runoff resulting from a land-disturbing activity will not result in accelerated erosion of the receiving stormwater conveyance or at the point of discharge. Plans shall include measures to prevent accelerated erosion within the project boundary and at the point of discharge.

Article VII Design and Performance Standards

Section 1. Non-High Quality Water Zones.

Except as provided in [Section 2\(B\)](#) of this Article, erosion and sedimentation control measures, structures, and devices shall be planned, designed, and constructed to provide protection from the calculated maximum peak rate of runoff from the ten-year storm. Runoff rates shall be calculated using the procedures in the latest edition of the United States Department of Agriculture (USDA), Natural Resources Conservation Service's "National Engineering Field Handbook", or other acceptable calculation procedures.

Section 2. HQW Zones.

In High Quality Water (HQW) zones the following design standards shall apply:

- (A) Limit on Uncovered Area. Uncovered areas in HQW zones shall be limited at any time to a maximum total area of twenty acres within the boundaries of the tract. Only the portion of the land-disturbing activity within a HQW zone shall be governed by this section. Larger areas may be uncovered within the boundaries of the tract with the written approval of the Director upon providing engineering justification with a construction sequence that considers phasing, limiting exposure, weekly submitted self-inspection reports, and a more conservative design than the Twenty-five Year Storm.
- (B) Maximum Peak Rate of Runoff Protection. Erosion and sedimentation control measures, structures, and devices within HQW zones shall be planned, designed and constructed to provide protection from the runoff of the twenty-five year storm which produces the maximum peak rate of runoff as calculated according to procedures in the latest edition of the United States Department of Natural Resources Conservation Service's "National Engineering Field Handbook" or according to procedures adopted by any other agency of this state or the United States or any generally recognized organization or association.
- (C) Sediment Basin Design. Sediment basins within HQW zones shall be

designed and constructed according to the following criteria:

- (1) use a surface withdrawal mechanism, except when the basin drainage area is less than 1.0 acre;
- (2) have a minimum of 1800 cubic feet of storage area per acre of disturbed area;
- (3) have a minimum surface area of 325 square feet per cfs of the Twenty-five Year Storm (Q25) peak flow;
- (4) have a minimum dewatering time of 48 hours;
- (5) incorporate 3 baffles, unless the basin is less than 20 feet in length, in which case 2 baffles shall be sufficient.

Upon a written request of the applicant, the Director may allow alternative design and control measures in lieu of meeting the conditions required in Section 2(C)(1) through Section 2(C)(5) if the applicant demonstrates that meeting all of those conditions will result in design or operational hardships and that the alternative measures will provide an equal or more effective level of erosion and sediment control on the site. Alternative measures may include quicker application of ground cover, use of sediment flocculants, and use of enhanced ground cover practices.

- (D) Grade. Newly constructed open channels in HQW zones shall be designed and constructed with side slopes no steeper than two horizontal to one vertical if a vegetative cover is used for stabilization unless soil conditions permit a steeper slope or where the slopes are stabilized by using mechanical devices, structural devices or other forms of ditch liners proven as being effective in restraining accelerated erosion. In any event, the angle for side slopes shall be sufficient to restrain accelerated erosion.

Article VIII Storm Water Outlet Protection

Section 1. Intent.

Stream banks and channels downstream from any land disturbing activity shall be protected from increased degradation by accelerated erosion caused by increased velocity of runoff from the land disturbing activity.

Section 2. Performance standard.

Persons shall conduct land-disturbing activity so that the post construction velocity of the 10-year storm runoff in the receiving watercourse to the discharge point does not exceed the greater of:

- (A) the velocity established by the Maximum Permissible Velocities Table set out within this subsection; or

(B) the velocity of the ten-year storm runoff in the receiving watercourse prior to development.

If condition (A) or (B) of this Paragraph cannot be met, then the receiving watercourse to and including the discharge point shall be designed and constructed to withstand the expected velocity anywhere the velocity exceeds the "prior to development" velocity by 10%.

Maximum Permissible Velocities Table

The following is a table for maximum permissible velocity for storm water discharges in feet per second (F.P.S.) and meters per second (M.P.S.):

<u>Material</u>	F.P.S.	M.P.S.
Fine sand (noncolloidal)	2.5	.8
Sandy loam (noncolloidal)	2.5	.8
Silt loam (noncolloidal)	3.0	.9
Ordinary firm loam	3.5	1.1
Fine gravel	5.0	1.5
Stiff clay (very colloidal)	5.0	1.5
Graded, loam to cobbles (noncolloidal)	5.0	1.5
Graded, silt to cobbles (Colloidal)	5.5	1.7
Alluvial silts (noncolloidal)	3.5	1.1
Alluvial silts (colloidal)	5.0	1.5
Coarse gravel (noncolloidal)	6.0	1.8
Cobbles and shingles	5.5	1.7
Shales and hard pans	6.0	1.8

Source - Adapted from recommendations by Special Committee on Irrigation Research, American Society of Civil Engineers, 1926, for channels with straight alignment. For sinuous channels, multiply allowable velocity by 0.95 for slightly sinuous, by 0.9 for moderately sinuous channels, and by 0.8 for highly sinuous channels.

Section 3. Acceptable Management Measures.

Measures applied alone or in combination to satisfy the intent of this section are acceptable if there are no objectionable secondary consequences. The County recognizes that the management of storm water runoff to minimize or control downstream channel and bank erosion is a developing technology. Innovative techniques and ideas will be considered and may be used when shown to have the potential to produce successful results. Some alternatives,

while not exhaustive, are to:

- (A) Avoid increases in surface runoff volume and velocity by including measures to promote infiltration to compensate for increased runoff from areas rendered impervious;
- (B) Avoid increases in storm water discharge velocities by using vegetated or roughened swales and waterways in place of closed drains and high velocity paved sections;
- (C) Provide energy dissipators at outlets of storm drainage facilities to reduce flow velocities to the point of discharge;
- (D) Protect watercourses subject to accelerated erosion by improving cross sections and/or providing erosion-resistant lining; and
- (E) Upgrade or replace the receiving device structure, or watercourse such that it will receive and conduct the flow to a point where it is no longer subject to degradation from the increased rate of flow or increased velocity.

Section 4. Exceptions.

This rule shall not apply where it can be demonstrated to the County that storm water discharge velocities will not create an erosion problem in the receiving watercourse.

Article IX Borrow and Waste Areas

If the same Person conducts the land-disturbing activity and any related borrow or waste activity, the related borrow or waste activity shall constitute part of the land-disturbing activity, unless the borrow or waste activity is regulated under the Mining Act of 1971, G.S. 74, Article 7, or is a landfill regulated by the Division of Waste Management. If the land-disturbing activity and any related borrow or waste activity are not conducted by the same Person, they shall be considered by the Approving Authority as separate land-disturbing activities.

Article X Access and Haul Roads

Temporary access and haul roads, other than public roads, constructed or used in connection with any land-disturbing activity shall be considered a part of such activity.

Article XI Operations in Lakes or Natural Watercourses

Land disturbing activity in connection with construction in, on, over, or under a lake or natural watercourse shall minimize the extent and duration of

disruption of the stream channel. Where relocation of a stream forms an essential part of the proposed activity, the relocation shall minimize changes in the stream flow characteristics.

Article XII Responsibility for Maintenance

During the development of a site, the Person conducting the land-disturbing activity shall install and maintain all temporary and permanent erosion and sedimentation control measures as required by the approved plan or any provision of this Chapter, the Act, or any order adopted pursuant to this Chapter or the Act. After site development, the landowner or Person in possession or control of the land shall install and/or maintain all necessary permanent erosion and sediment control measures, except those measures installed within a road or street right-of-way or easement accepted for maintenance by a governmental agency.

Article XIII Additional Measures

Whenever the County determines that accelerated erosion and sedimentation continues despite the installation of protective practices, they shall direct the person conducting the land-disturbing activity to take additional protective action necessary to achieve compliance with the conditions specified in the Act or its rules.

Article XIV Fees

The County may establish a fee schedule for the review and approval of plans.

Article XV Plan Appeals

Section 1. Disapprovals

Except as provided in [Section 2](#) of this Article, the appeal of a disapproval or approval with modifications of a plan shall be governed by the following provisions:

- (1) The disapproval or modification of any proposed plan by the County shall entitle the Person submitting the plan to a public hearing if such Person submits written demand for a hearing within 15 days after receipt of written notice of disapproval or modifications.

- (2) A hearing held pursuant to this section shall be conducted by the Watauga County Planning Board within thirty (30) days after the date of the written appeal or request for a hearing.
- (3) The Planning Board shall make recommendations to the Board of Commissioners within seven (7) days after the date of the hearing on any plan.
- (4) The Board of Commissioners will render its final decision on any plan within five (5) days of receipt of the recommendations from the agency conducting the hearing.
- (5) If the Board of Commissioners upholds the disapproval or modification of a proposed plan following the hearing, the Person submitting the plan shall then be entitled to appeal the County's decision to the Commission as provided in G.S. 113A-61(c) and 15A NCAC 4B .0118(d)

Section 2. Other Disapprovals

In the event that a plan is disapproved pursuant to [Article V Section 9](#) of this Chapter, the applicant may appeal the County's disapproval of the plan directly to the Commission.

Article XVI Inspections and Investigations

Section 1. Inspection.

Agents, officials, or other qualified persons authorized by the County will periodically inspect land-disturbing activities to ensure compliance with the Act, this chapter, or rules or orders adopted or issued pursuant to this chapter, and to determine whether the measures required in the Plan are effective in controlling erosion and sedimentation resulting from land-disturbing activity. Notice of the right to inspect shall be included in the certificate of approval of each Plan.

Section 2. Willful Resistance, Delay or Obstruction.

No person shall willfully resist, delay, or obstruct an authorized representative, employee, or agent of the County while that person is inspecting or attempting to inspect a land-disturbing activity under this section.

Section 3. Notice of Violation.

If the County determines that a Person engaged in land-disturbing activity has failed to comply with the Act, this chapter, or rules, or orders adopted or issued pursuant to this chapter, a notice of violation shall be served upon that

Person. The notice may be served by any means authorized under GS 1A-1, Rule 4. The notice shall specify a date by which the Person must comply with the Act, or this ordinance, or rules, or orders adopted pursuant to this chapter, and inform the person of the actions that need to be taken to comply with the Act, this chapter, or rules or orders adopted pursuant to this chapter. Any Person who fails to comply within the time specified is subject to additional civil penalties for a continuing violation as provided in G.S. 113A-64 and this chapter. If the Person engaged in the land-disturbing activity has not received a previous notice of violation under this section, the county shall offer assistance in developing corrective measures. Assistance may be provided by referral to a technical assistance program on behalf of the Approving Authority, referral to a cooperative extension program, or by the provision of written materials such as Department guidance documents. The notice of violation may be served in the manner prescribed for service of process by G.S. 1A-1, Rule 4, and shall include information on how to obtain assistance in developing corrective measures.

Section 4. Investigation.

The County shall have the power to conduct such investigation as it may reasonably deem necessary to carry out its duties as prescribed in this chapter, and who presents appropriate credentials for this purpose to enter at reasonable times upon any property, public or private, for the purpose of investigating and inspecting the sites of any land-disturbing activity.

Section 5. Statements and Reports.

The County shall also have the power to require written statements, or filing of reports under oath, with respect to pertinent questions relating to land-disturbing activity.

Article XVII Stop Orders

Wherever land-disturbing activity is being undertaken in a manner which is in violation of this chapter, the Watauga County Department of Planning and Inspection may order the work that is in violation to be immediately stopped. The stop order shall be in writing and directed to the person responsible for the violation, and shall state the specific work to be stopped, the specific reasons for the stoppage, and the conditions under which the work may be resumed. Appeals from a stop order shall be made as prescribed in [Article XVI](#) of this chapter. Pending the ruling on the appeal, no further work may take place in violation of a stop order.

In addition, in accordance with N.C.G.S. 160D-404(b), the Watauga County Building Inspectors are authorized to issue stop orders for building permits where violations of this ordinance are taking place in connection with construction authorized by the building permit.

Article XVIII Revocation of Grading Permits

The Watauga County Department of Planning and Inspections may revoke and require the return of any permit by giving written notice to the permit holder, stating the reason for the revocation. Permits shall be revoked for any substantial departure from the approved application or plans and specifications, for refusal or failure to comply with the requirements of any applicable State or local laws or local ordinances or regulations, or for false statements or misrepresentations made in securing the permit. A permit mistakenly issued in violation of an applicable State or local law or local ordinance or regulation also may be revoked.

Article XIX Building Permits

No permits for any building or structure shall be issued upon any land requiring submission of a soil erosion control plan and issuance of a grading permit until such plan is submitted and permit issued.

Article XX Security Required

The applicant for a permit may, prior to commencing any land-disturbing activity, be required to file with Watauga County an improvement security in the form of an escrow account, surety bond, irrevocable letter of credit, or other undertaking satisfactory to the County Attorney, in an amount deemed sufficient by the Watauga County Department of Planning and Inspections, to cover all costs of protection or other improvements required to establish protective cover on the site in conformity with this chapter. Such security shall remain in force until the improvements are completed in accordance with the approved plan and said improvements are finally inspected and approved as set out in paragraph below.

Upon completion of the improvements as required by this chapter, written notice thereof shall be given by the applicant to the Department of Planning and Inspections and the Department shall cause an inspection of the improvements to be made and, if approved, shall within 30 days of the date of notice authorize in writing the release of the security given provided that the improvements have been made in accordance with the approved plan and this chapter.

The security shall be forfeited upon violation of this chapter and shall be used to establish protective cover on the site. Any monies in excess of the cost of establishing protective cover shall be refunded.

Article XXI Penalties

Section 1. Civil Penalties.

- (A) Civil Penalty for a Violation. Any Person who violates any of the provisions of this chapter, or rule or order adopted or issued pursuant to this chapter, or who initiates or continues a land-disturbing activity for which a Plan is required except in accordance with the terms, conditions, and provisions of an approved Plan, is subject to a civil penalty. The maximum civil penalty amount that the County may assess per violation is five thousand dollars (\$5,000.00). A civil penalty may be assessed from the date of the violation. Each day of a continuing violation shall constitute a separate violation. When the Person has not been assessed any civil penalty under this subsection for any previous violation, and that Person abated continuing environmental damage resulting from the violation within 180 days from the date of the notice of violation, the maximum cumulative total civil penalty assessed under this subsection for all violations associated with the land-disturbing activity for which the erosion and sedimentation control plan is required is twenty-five thousand dollars (\$25,000).]
- (B) Civil Penalty Assessment Factors. The governing body of the County shall determine the amount of the civil penalty based upon the following factors:
- (1) the degree and extent of harm caused by the violation,
 - (2) the cost of rectifying the damage,
 - (3) the amount of money the violator saved by noncompliance,
 - (4) whether the violation was committed willfully, and
 - (5) the prior record of the violator in complying or failing to comply with this chapter.
- (C) Notice of Civil Penalty Assessment. The governing body of the County shall provide notice of the civil penalty amount and basis for assessment to the Person assessed. The notice of assessment shall be served by any means authorized under G.S. 1A-1, Rule 4. A notice of assessment by the County shall direct the violator to either pay the assessment, contest the assessment within 30 days by filing a petition for hearing with the County (as directed by procedures within the local ordinances or regulations adopted to establish and enforce the erosion and sedimentation control program), or file a request with the County for remission of the assessment within 30

days of receipt of the notice of assessment. A remission request must be accompanied by a waiver of the right to a contested case hearing pursuant to Chapter 150B of the North Carolina General Statutes and a stipulation of the facts on which the assessment was based.

- (D) Final Decision: The final decision on contested assessments shall be made by the Board of Commissioners in accordance with this ordinance.
- (E) Appeal of Final Decision. Appeal of the final decision of the Board of Commissioners shall be to the Superior Court of the county where the violation occurred. Such appeals must be made within 30 days of the final decision of the Board of Commissioners.
- (F) Remission of Civil Penalties. A request for remission of a civil penalty imposed under G.S. 113A-64 may be filed with the Board of Commissioners within 30 days of receipt of the notice of assessment. A remission request must be accompanied by a waiver of the right to a contested case hearing pursuant to Chapter 150B of the General Statutes and a stipulation of the facts on which the assessment was based. The following factors shall be considered in determining whether a civil penalty remission request will be approved:
 - (1) Whether one or more of the civil penalty assessment factors in G.S. 113A-64(a)(3) were wrongly applied to the detriment of the petitioner.
 - (2) Whether the petitioner promptly abated continuing environmental damage resulting from the violation.
 - (3) Whether the violation was inadvertent or a result of an accident.
 - (4) Whether the petitioner had been assessed civil penalties for any previous violations.
 - (5) Whether payment of the civil penalty will prevent payment for necessary remedial actions or would otherwise create a significant financial hardship.
 - (6) The assessed property tax valuation of the petitioner's property upon which the violation occurred, excluding the value of any structures located on the property.
- (G) Collection. If payment is not received within 30 days after it is due, the County may institute a civil action to recover the amount of the assessment. The civil action may be brought in the Superior Court of the county where the violation occurred, or the violator's residence or principal place of business is located. Such civil actions must be filed within three (3) years of the date the assessment was due. An assessment that is not contested and a remission that is not required is due when the violator is served with a notice of assessment. An assessment that is contested or a remission that is not requested is due at the conclusion of the administrative and judicial review of the

assessment.

- (H) Credit of Civil Penalties. The clear proceeds of civil penalties collected by the County under this subsection shall be remitted to the Civil Penalty and Forfeiture Fund in accordance with G.S. 115C-457.2. Penalties collected by the County may be diminished only by the actual costs of collection. The collection cost percentage to be used shall be established and approved by the North Carolina Office of State Budget and Management on an annual basis, based upon the computation of actual collection costs by the County for the prior fiscal year.

[In any event, the cost percentage shall not exceed twenty percent (20%) of penalties collected.]

Article XXII Injunctive Relief

Section 1. Violation of Local Program.

Whenever the Board of Commissioners has reasonable cause to believe that any person is violating or threatening to violate any ordinance, rule, regulation or order adopted or issued by the County or any term, condition, or provision of an approved Plan, it may, either before or after the institution of any other action or proceeding authorized by this chapter, institute a civil action in the name of the County for injunctive relief to restrain the violation or threatened violation. The action shall be brought in the superior court of the county in which the violation is occurring or is threatened.

Section 2. Abatement of Violation.

Upon determination by a court that an alleged violation is occurring or is threatened, the court shall enter any order or judgment that is necessary to abate the violation, to ensure that restoration is performed, or to prevent the threatened violation. The institution of an action for injunctive relief under this section shall not relieve any party to the proceedings from any civil or criminal penalty prescribed for violations of this chapter.

Article XXIII Restoration After Non-Compliance

The County may require a Person who engaged in a land-disturbing activity and failed to retain sediment generated by the activity, as required by G.S. 113A-57 (3), to restore the waters and land affected by the failure so as to minimize the detrimental effects of the resulting pollution by sedimentation. This authority is in addition to any other civil or criminal penalty or injunctive relief authorized under this chapter.

Article XXIV Effective Date

February 20, 2019, Amended November 16, 2021

CHAPTER 9 FLOOD DAMAGE PREVENTION

Article I Statutory Authorizations, Findings of Fact, Purpose, & Objectives

Section 1. Statutory Authorization.

The Legislature of the State of North Carolina has in Part 6, Article 21 of Chapter 143; Part 2, Articles 1,7,9, and 11 of Chapter 160D; and Part 121, Article 6 of Chapter 153A of the North Carolina General Statutes, delegated to local governmental units the responsibility to adopt regulations designed to promote the public health, safety, and general welfare. Therefore, the Board of Commissioners of Watauga County, North Carolina, enacts the following:

Section 2. Findings of Fact.

- (A) The flood prone areas within the jurisdiction of Watauga County are subject to periodic inundation which results in loss of life, property, health and safety hazards, disruption of commerce and governmental services, extraordinary public expenditures of flood protection and relief, and impairment of the tax base, all of which adversely affect the public health, safety, and general welfare.
- (B) These flood losses are caused by the cumulative effect of obstructions in floodplains causing increases in flood heights and velocities and by the occupancy in flood prone areas of uses vulnerable to floods or other hazards.

Section 3. Statement of Purpose.

- (A) It is the purpose of this chapter to promote public health, safety, and general welfare and to minimize public and private losses due to flood conditions within flood prone areas by provisions designed to:
- (B) restrict or prohibit uses that are dangerous to health, safety, and property due to water or erosion hazards or that result in damaging increases in erosion, flood heights or velocities;
- (C) require that uses vulnerable to floods, including facilities that serve such uses, be protected against flood damage at the time of initial construction;
- (D) control the alteration of natural floodplains, stream channels, and natural protective barriers, which are involved in the accommodation of floodwaters;

- (E) control filling, grading, dredging, and all other development that may increase erosion or flood damage; and
- (F) prevent or regulate the construction of flood barriers that will unnaturally divert flood waters or which may increase flood hazards to other lands.

Section 4. Objectives.

- (A) The objectives of this chapter are to:
- (B) protect human life, safety, and health;
- (C) minimize expenditure of public money for costly flood control project;
- (D) minimize the need for rescue and relief efforts associated with flooding and generally undertaken at the expense of the general public;
- (E) minimize prolonged business losses and interruptions;
- (F) minimize damage to public facilities and utilities (i.e. water and gas mains, electric, telephone, cable and sewer lines, streets, and bridges) that are located in flood prone areas;
- (G) help maintain a stable tax base by providing for the sound use and development of flood prone areas; and
- (H) ensure that potential buyers are aware that property is in a Special Flood Hazard Area;
- (I) Minimize damage to private and public property due to flooding;
- (J) Make flood insurance available to the community through the National Flood Insurance Program;
- (K) Maintain the natural and beneficial functions of floodplains.

Article II General Provisions

Section 1. Lands To Which This Ordinance Applies.

This chapter shall apply to all Special Flood Hazard Areas within the jurisdiction of Watauga County and within the jurisdiction of any other community whose governing body agrees, by resolution, to such applicability.

Section 2. Basis For Establishing The Special Flood Hazard Areas.

The Special Flood Hazard Areas are those identified under the Cooperating Technical State (CTS) agreement between the State of North Carolina and FEMA in its FIS dated December 3, 2009 for Watauga County and associated DFIRM panels, including any digital data developed as part of the FIS, which

are adopted by reference and declared a part of this ordinance, and all revisions thereto.

Section 3. Establishment of Floodplain Development Permit.

A Floodplain Development Permit shall be required in conformance with the provisions of this chapter prior to the commencement of any development activities within Special Flood Hazard Areas determined in accordance with the provisions of Section 2 of this Article.

Section 4. Compliance.

No structure or land shall hereafter be located, extended, converted, altered, or developed in any way without full compliance with the terms of this chapter and other applicable regulations.

Section 5. Abrogation and Greater Restrictions.

This ordinance is not intended to repeal, abrogate, or impair any existing easements, covenants, or deed restrictions. However, where this chapter and another conflict or overlap, whichever imposes the more stringent restrictions shall prevail.

Section 6. Interpretation.

In the interpretation and application of this ordinance, all provisions shall be:

- (A) considered as minimum requirements;
- (B) liberally construed in favor of the governing body; and
- (C) deemed neither to limit nor repeal any other powers granted under State statutes.

Section 7. Warning and Disclaimer of Liability.

The degree of flood protection required by this ordinance is considered reasonable for regulatory purposes and is based on scientific and engineering consideration. Larger floods can and will occur. Actual flood heights may be increased by man-made or natural causes. This ordinance does not imply that land outside the Special Flood Hazard Areas or uses permitted within such areas will be free from flooding or flood damages. This ordinance shall not create liability on the part of Watauga County or by any officer or employee thereof for any flood damages that result from reliance on this ordinance or any administrative decision lawfully made hereunder.

Section 8. Penalties for Violation.

[See Chapter 5, Article IV and V.](#)

Article III Administration

Section 1. Designation of Floodplain Administrator.

The Director or other authorized staff of the Watauga County Department of Planning and Inspections, hereinafter referred to as the "Floodplain Administrator", is hereby appointed to administer and implement the provisions of this chapter. In instances where the Floodplain Administrator receives assistance from others to complete tasks to administer and implement this ordinance, the Floodplain Administrator shall be responsible for the coordination and community's overall compliance with the National Flood Insurance Program and the provisions of this ordinance.

Section 2. Floodplain Development Application, Permit and Certification Requirements.

- (A) Application Requirements. Application for a Floodplain Development Permit shall be made to the Floodplain Administrator prior to any development activities located within Special Flood Hazard Areas. The following items shall be presented to the Floodplain Administrator to apply for a floodplain development permit:
- (1) A plot plan drawn to scale which shall include, but shall not be limited to, the following specific details of the proposed floodplain development:
 - (a) the nature, location, dimensions, and elevations of the area of development/disturbance; existing and proposed structures, utility systems, grading/pavement areas, fill materials, storage areas, drainage facilities, and other development;
 - (b) the boundary of the Special Flood Hazard Area as delineated on the FIRM or other flood map as determined in [Article II, Section 2](#), or a statement that the entire lot is within the Special Flood Hazard Area;
 - (c) flood zone(s) designation of the proposed development area as determined on the FIRM or other flood map as determined in [Article II, Section 2](#);
 - (d) the boundary of the floodway(s) or non-encroachment area(s) as determined in [Article II, Section 2](#);

- (e) the Base Flood Elevation (BFE) where provided as set forth in [Article II, Section 2](#); [Article III, Section 3](#); or [Article IV, Section 4](#);
 - (f) the old and new location of any watercourse that will be altered or relocated as a result of proposed development; and
 - (g) the certification of the plot plan by a registered land surveyor or professional engineer as determined to be necessary by the Floodplain Administrator.
- (2) Proposed elevation, and method thereof, of all development within a Special Flood Hazard Area including but not limited to:
- (a) Elevation in relation to NAVD 1988 of the proposed reference level (including basement) of all structures;
 - (b) Elevation in relation to NAVD 1988 to which any non-residential structure in Zone AE or A will be floodproofed; and
 - (c) Elevation in relation to NAVD 1988 to which any proposed utility systems will be elevated or floodproofed.
- (3) If floodproofing, a Floodproofing Certificate (FEMA Form 086-0-34) with supporting data, an operational plan, and an inspection and maintenance plan that include, but are not limited to, installation, exercise, and maintenance of floodproofing measures,
- (4) A Foundation Plan, drawn to scale, which shall include details of the proposed foundation system to ensure all provisions of this ordinance are met. These details include but are not limited to:
- a) The proposed method of elevation, if applicable (i.e., fill, solid foundation perimeter wall, solid backfilled foundation, open foundation on columns/posts/piers/piles/shear walls); and
 - b) Openings to facilitate automatic equalization of hydrostatic flood forces on walls in accordance with [Article IV, Section 2\(D\)\(4\)](#) when solid foundation perimeter walls are used in Zones A, AE, and A I-30.
- (5) Usage details of any enclosed areas below the lowest floor.
- (6) Plans and/or details for the protection of public utilities and facilities such as sewer, gas, electrical, and water systems to be located and constructed to minimize flood damage.
- (7) Certification that all other Local, State and Federal permits required prior to floodplain development permit issuance have been received.

- (8) Documentation for placement of Recreational Vehicles and/or Temporary Structures, when applicable, to ensure that the provisions of [Article IV, Section 2, \(F\)](#) and [\(G\)](#) of this chapter are met.
 - (9) A description of proposed watercourse alteration or relocation, when applicable, including an engineering report on the effects of the proposed project on the flood-carrying capacity of the watercourse and the effects to properties located both upstream and downstream; and a map (if not shown on plot plan) showing the location of the proposed watercourse alteration or relocation.
- (B) Permit Requirements. The Floodplain Development Permit shall include, but not be limited to:
- (1) A complete description of all the development to be permitted under the floodplain development permit (e.g. house, garage, pool, septic, bulkhead, cabana, pier, bridge, mining, dredging, filling, grading, paving, excavation or drilling operations, or storage of equipment or materials, etc.).
 - (2) The Special Flood Hazard Area determination for the proposed development in accordance with available data specified in [Article II, Section 2](#).
 - (3) The Regulatory Flood Protection Elevation required for the reference level and all attendant utilities.
 - (4) The Regulatory Flood Protection Elevation required for the protection of all public utilities.
 - (5) All certification submittal requirements with timelines.
 - (6) A statement that no fill material or other development shall encroach into the floodway or non-encroachment area of any watercourse, as applicable.
 - (7) The flood openings requirements.
 - (8) Limitations of below BFE enclosure uses (if applicable). (i.e., parking, building access and limited storage only).
 - (9) A statement, that all materials below BFE/RFPE must be flood resistant materials.
- (C) Certification Requirements.
- (1) Elevation Certificates
 - (a) An Elevation Certificate (FEMA Form 086-0-33) is required prior to the actual start of any new construction. It shall be the duty of the permit holder to submit to the Floodplain Administrator a certification of the elevation of the reference level, in relation to NAVD 1988, The Floodplain Administrator shall review the certificate data submitted.

Deficiencies detected by such review shall be corrected by the permit holder prior to the beginning of construction. Failure to submit the certification or failure to make required corrections shall be cause to deny a floodplain development permit.

- (b)** An Elevation Certificate (FEMA Form 086-0-33) is required after the reference level is established. Within seven (7) calendar days of establishment of the reference level elevation, it shall be the duty of the permit holder to submit to the Floodplain Administrator a certification of the elevation of the reference level, in relation to mean sea level. Any work done within the seven (7) day calendar period and prior to submission of the certification shall be at the permit holder's risk. The Floodplain Administrator shall review the certificate data submitted. Deficiencies detected by such review shall be corrected by the permit holder immediately and prior to further work being permitted to proceed. Failure to submit the certification or failure to make required corrections shall be cause to issue a stop-work order for the project.
 - (c)** A final as-built Elevation Certificate (FEMA Form 086-0-33) is required after construction is completed and prior to Certificate of Compliance/Occupancy issuance. It shall be the duty of the permit holder to submit to the Floodplain Administrator a certification of final as-built construction of the elevation of the reference level and all attendant utilities. The Floodplain Administrator shall review the certificate data submitted. Deficiencies detected by such review shall be corrected by the permit holder immediately and prior to Certificate of compliance/Occupancy issuance. In some instances, another certification may be required to certify corrected as-built construction. Failure to submit the certification or failure to make required corrections shall be cause to withhold the issuance of a Certificate of Compliance/Occupancy.
- (2)** Floodproofing Certificates. If non-residential floodproofing is used to meet the Regulatory Flood Protection Elevation requirements, a Floodproofing Certificate (FEMA Form 086-0-34), with supporting data, an operational plan, and an inspection and maintenance plan are required prior to the

actual start of any new construction. It shall be the duty of the permit holder to submit to the Floodplain Administrator a certification of the floodproofed design elevation of the reference level and all attendant utilities, in relation to NAVD 1988. Floodproofing certification shall be prepared by or under the direct supervision of a professional engineer or architect and certified by same. The Floodplain Administrator shall review the certificate data, the operational plan, and the inspection and maintenance plan. Deficiencies detected by such review shall be corrected by the applicant prior to permit approval. Failure to submit the certification or failure to make required corrections shall be cause to deny a Floodplain Development Permit. Failure to construct in accordance with the certified design shall be cause to withhold the issuance of a Certificate of Compliance/Occupancy.

A final Finished Construction Floodproofing Certificate (FEMA Form 086-0-34), with supporting data, an operational plan, and an inspection and maintenance plan are required prior to the issuance of a Certificate of Compliance/Occupancy. It shall be the duty of the permit holder to submit to the Floodplain Administrator a certification of the floodproofed design elevation of the reference level and all attendant utilities, in relation to NAVD 1988. Floodproofing certificate shall be prepared by or under the direct supervision of a professional engineer or architect and certified by same. The Floodplain Administrator shall review the certificate data, the operational plan, and the inspection and maintenance plan. Deficiencies detected by such review shall be corrected by the applicant prior to Certificate of Occupancy. Failure to submit the certification or failure to make required corrections shall be cause to deny a Floodplain Development Permit. Failure to construct in accordance with the certified design shall be cause to deny a Certificate of Compliance/Occupancy.

- (3) If a manufactured home is placed within Zone A, AE, or AI-3D and the elevation of the chassis is more than 36 inches in height above grade, an engineered foundation certification is required in accordance with the provisions of [Article IV, Section 2\(C\)\(2\)](#).
- (4) If a watercourse is to be altered or relocated, a description of the extent of watercourse alteration or relocation; a professional engineer's certified report on the effects of the proposed project on the flood-carrying capacity of the

watercourse and the effects to properties located both upstream and downstream; and a map showing the location of the proposed watercourse alteration or relocation shall all be submitted by the permit applicant prior to issuance of a floodplain development permit.

(5) Certification Exemptions. The following structures, if located within Zone A, AE or AI -30, are exempt from the elevation/floodproofing certification requirements specified in items (a) and (b) of this subsection:

- a)** Recreational Vehicles meeting requirements of [Article IV, Section 2\(F\)\(1\)](#);
- b)** Temporary Structures meeting requirements of [Article IV, Section 2\(G\)](#); and
- c)** Accessory Structures 150 square feet or less and meeting requirements of [Article IV, Section 2\(H\)](#).

(D) Determinations for existing buildings and structures.

For applications for building permits to improve buildings and structures, including alterations, movement, enlargement, replacement, repair, change of occupancy, additions, rehabilitations, renovations, substantial improvements, repairs of substantial damage, and any other improvement of or work on such buildings and structures, the Floodplain Administrator, in coordination with the Building Official, shall:

- (1)** Estimate the market value, or require the applicant to obtain an appraisal of the market value prepared by a qualified independent appraiser, of the building or structure before the start of construction of the proposed work; in the case of repair, the market value of the building or structure shall be the market value before the damage occurred and before any repairs are made;
- (2)** Compare the cost to perform the improvement, the cost to repair a damaged building to its pre-damaged condition, or the combined costs of improvements and repairs, if applicable, to the market value of the building or structure;
- (3)** Determine and document whether the proposed work constitutes substantial improvement or repair of substantial damage; and
- (4)** Notify the applicant if it is determined that the work constitutes substantial improvement or repair of substantial damage and that compliance with the flood resistant construction requirements of the NC Building Code and this ordinance is required.

Section 3. Duties and Responsibilities of the Floodplain Administrator.

The Floodplain Administrator shall perform, but not be limited to, the following duties:

- (A) Review all floodplain development applications and issue permits for all proposed development within Special Flood Hazard Areas to assure that the requirements of this ordinance have been satisfied.
- (B) Review all proposed development within Special Flood Hazard Areas to assure that the requirements of this ordinance have been satisfied including Section 404 of the Federal Water Pollution Control Act Amendments of 1972, 33 U.S.C. 1334.
- (C) Notify adjacent communities and the North Carolina Department of Crime Control and Public Safety, Division of Emergency Management, State Coordinator for the National Flood Insurance Program prior to any alteration or relocation of a watercourse, and submit evidence of such notification to the Federal Emergency Management Agency (FEMA).
- (D) Assure that maintenance is provided within the altered or relocated portion of said watercourse so that the flood-carrying capacity is maintained.
- (E) Prevent encroachments into floodways and non-encroachment areas unless the certification and flood hazard reduction provisions of [Article IV, Section 6](#) are met.
- (F) Obtain actual elevation (in relation to NAVD 1988) of the reference level (including basement) and all attendant utilities of all new and substantially improved structures, in accordance with the provisions of [Article III, Section 2\(C\)](#).
- (G) Obtain actual elevation (in relation to NAVD 1988) to which all new and substantially improved structures and utilities have been floodproofed, in accordance with the provisions of [Article III, Section 2\(C\)](#).
- (H) Obtain actual elevation (in relation to NAVD 1988) of all public utilities in accordance with the provisions of [Article III, Section 2\(C\)](#).
- (I) When floodproofing is utilized for a particular structure, obtain certifications from a registered professional engineer or architect in accordance with the provisions of [Article III, Section 2\(C\)](#) and [Article IV, Section 2\(B\)](#).
- (J) Where interpretation is needed as to the exact location of boundaries of the Special Flood Hazard Areas, floodways, or non-encroachment areas (for example, where there appears to be a conflict between a mapped boundary and actual field conditions), make the necessary interpretation. The person contesting the

location of the boundary shall be given a reasonable opportunity to appeal the interpretation as provided in this article.

- (K)** When Base Flood Elevation (BFE) data has not been provided in accordance with the provisions of [Article II, Section 2](#), obtain, review, and reasonably utilize any BFE data, along with floodway data or non-encroachment area data available from a Federal, State, or other source, including data developed pursuant to [Article IV, Section 4\(B\)\(2\)](#), in order to administer the provisions of this ordinance.
- (L)** When Base Flood Elevation (BFE) data is provided but no floodway or non-encroachment area data has been provided in accordance with the provisions of [Article IV, Section 2](#), obtain, review, and reasonably utilize any floodway data or non-encroachment area data available from a Federal, State, or other source in order to administer the provisions of this ordinance.
- (M)** When the lowest floor and the lowest adjacent grade of a structure or the lowest ground elevation of a parcel in a Special Flood Hazard Area is above the Base Flood Elevation (BFE), advise the property owner of the option to apply for a Letter of Map Amendment (LOMA) from FEMA. Maintain a copy of the LOMA issued by FEMA in the floodplain development permit file,
- (N)** Permanently maintain all records that pertain to the administration of this ordinance and make these records available for public inspection, recognizing that such information may be subject to the Privacy Act of 1974, as amended.
- (O)** Make on-site inspections of work in progress. As the work pursuant to a floodplain development permit progresses, the Floodplain Administrator shall make as many inspections of the work as may be necessary to ensure that the work is being done according to the provisions of the local ordinance and the terms of the permit. In exercising this power, the Floodplain Administrator has a right, upon presentation of proper credentials, to enter on any premises within the jurisdiction of the community at any reasonable hour for the purposes of inspection or other enforcement action.
- (P)** Issue stop-work orders as required. Whenever a building or part thereof is being constructed, reconstructed, altered, or repaired in violation of this ordinance, the Floodplain Administrator may order the work to be immediately stopped. The stop-work order shall be in writing and directed to the person doing or in charge of the work. The stop-work order shall state the specific work to be stopped, the specific reason(s) for the stoppage, and the condition(s) under which the work may be resumed.

- (Q) Revoke floodplain development permits as required. The Floodplain Administrator may revoke and require the return of the floodplain development permit by notifying the permit holder in writing stating the reason(s) for the revocation. Permits shall be revoked for any substantial departure from the approved application, plans, and specifications; for refusal or failure to comply with the requirements of State or local laws; or for false statements or misrepresentations made in securing the permit. Any floodplain development permit mistakenly issued in violation of an applicable State or local law may also be revoked.
- (R) Make periodic inspections throughout the Special Flood Hazard Areas within the jurisdiction of the community. The Floodplain Administrator and each member of his or her inspections department shall have a right, upon presentation of proper credentials, to enter on any premises within the territorial jurisdiction of the department at any reasonable hour for the purposes of inspection or other enforcement action.
- (S) Follow through with corrective procedures of [Article III, Section 4.](#)
- (T) Review, provide input, and make recommendations for variance requests.
- (U) Maintain a current map repository to include, but not limited to, the FIS Report, FIRM and other official flood maps and studies adopted in accordance with the provisions of Article II, Section 2 of this ordinance, including any revisions thereto including Letters of Map Change, issued by FEMA. Notify State and FEMA of mapping needs.
- (V) Coordinate revisions to FIS reports and FIRMs, including Letters of Map Revision Based on Fill (LOMR-Fs) and Letters of Map Revision (LOMRs).

Section 4. Corrective Procedures.

- (A) Violations to be Corrected: When the Floodplain Administrator finds violations of applicable State and local laws, it shall be his or her duty to notify the owner or occupant of the building of the violation. The owner or occupant shall immediately remedy each of the violations of law cited in such notification.
- (B) Actions in Event of Failure to Take Corrective Action: If the owner of a building or property shall fail to take prompt corrective action, the Floodplain Administrator shall give the owner written notice, by certified or registered mail to the owner's last known address or by personal service, stating:
 - (1) that the building or property is in violation of the floodplain management regulations;

- (2) that a hearing will be held before the Floodplain Administrator at a designated place and time, not later than ten (10) days after the date of the notice, at which time the owner shall be entitled to be heard in person or by counsel and to present arguments and evidence pertaining to the matter; and
 - (3) that following the hearing, the Floodplain Administrator may issue an order to alter, vacate, or demolish the building; or to remove fill as applicable.
- (C) Order to Take Corrective Action: If, upon a hearing held pursuant to the notice prescribed above, the Floodplain Administrator shall find that the building or development is in violation of this chapter, he or she shall issue an order in writing to the owner, requiring the owner to remedy the violation within a specified time period, not less than sixty (60) calendar days, nor more than one hundred-eighty (180) calendar days. Where the Floodplain Administrator finds that there is imminent danger to life or other property, he or she may order that corrective action be taken in such lesser period as may be feasible.
- (D) Appeal: Any owner who has received an order to take corrective action may appeal the order to the Board of Adjustment by giving notice of appeal in writing to the Floodplain Administrator and the Clerk to the Board of Adjustment within thirty (30) days following issuance of the final binding order. In the absence of an appeal, the order of the Floodplain Administrator shall be final. The Board of Adjustment shall hear an appeal within a reasonable time and may affirm, modify and affirm, or revoke the order.
- (E) Failure to Comply with Order: If the owner of a building or property fails to comply with an order to take corrective action for which no appeal has been made or fails to comply with an order of the Board of Adjustment following an appeal, the owner shall be subject to civil penalties as set forth in Chapter 5 of this ordinance.

Section 5. Variance Procedures.

- (A) The Board of Adjustment as established by Watauga County, hereinafter referred to as the "appeal board", shall hear and decide requests for variances from the requirements of this chapter.
- (B) Any person aggrieved by the decision of the appeal board may appeal such decision to the Court, as provided in Chapter 7A of the North Carolina General Statutes.
- (C) Variances may be issued for:

- 1) the repair or rehabilitation of historic structures upon the determination that the proposed repair or rehabilitation will not preclude the structure's continued designation as a historic structure and that the variance is the minimum necessary to preserve the historic character and design of the structure;
 - 2) functionally dependent facilities if determined to meet the definition as stated in [Chapter 7](#), provided provisions of [Article III, Section 5\(I\)\(2\)](#), [\(3\)](#), and [\(5\)](#) have been satisfied, and such facilities are protected by methods that minimize flood damages during the base flood and create no additional threats to public safety; or
 - 3) any other type of development, provided it meets the requirements of this Section.
- (D) In passing upon variances, the appeal board shall consider all technical evaluations, all relevant factors, all standards specified in other sections of this chapter, and:
- 1) the danger that materials may be swept onto other lands to the injury of others;
 - 2) the danger to life and property due to flooding or erosion damage;
 - 3) the susceptibility of the proposed facility and its contents to flood damage and the effect of such damage on the individual owner;
 - 4) the importance of the services provided by the proposed facility to the community;
 - 5) the necessity to the facility of a waterfront location as defined in Chapter 7 as a functionally dependent facility, where applicable;
 - 6) the availability of alternative locations, not subject to flooding or erosion damage, for the proposed use;
 - 7) the compatibility of the proposed use with existing and anticipated development;
 - 8) the relationship of the proposed use to the comprehensive plan and floodplain management program for that area;
 - 9) the safety of access to the property in times of flood for ordinary and emergency vehicles;
 - 10) the expected heights, velocity, duration, rate of rise, and sediment transport of the floodwaters and the effects of wave action, if applicable, expected. at the site; and
 - 11) the costs of providing governmental services during and after flood conditions including maintenance and repair of public utilities and facilities such as sewer, gas, electrical and water systems, and streets and bridges.

- (E) A written report addressing each of the above factors shall be submitted with the application for a variance.
- (F) Upon consideration of the factors listed above and the purposes of this chapter, the appeal board may attach such conditions to the granting of variances as it deems necessary to further the purposes and objectives of this chapter.
- (G) Any applicant to whom a variance is granted shall be given written notice specifying the difference between the Base Flood Elevation (BFE) and the elevation to which the structure is to be built and that such construction below the BFE increases risks to life and property, and that the issuance of a variance to construct a structure below the BFE will result in increased premium rates for flood insurance up to \$25 per \$100 of insurance coverage. Such notification shall be maintained with a record of all variance actions, including justification for their issuance.
- (H) The Floodplain Administrator shall maintain the records of all appeal actions and report any variances to the Federal Emergency Management Agency and the State of North Carolina upon request.
- (I) Conditions for Variances:

 - (1) Variances shall not be issued when the variance will make the structure in violation of other Federal, State, or local laws, regulations, or ordinances.
 - (2) Variances shall not be issued within any designated floodway or non-encroachment area if the variance would result in any increase in flood levels during the base flood discharge.
 - (3) Variances shall only be issued upon a determination that the variance is the minimum necessary, considering the flood hazard, to afford relief
 - (4) Variances shall only be issued prior to development permit approval.
 - (5) Variances shall only be issued upon:

 - (a) a showing of good and sufficient cause;
 - (b) a determination that failure to grant the variance would result in exceptional hardship; and
 - (c) a determination that the granting of a variance will not result in increased flood heights, additional threats to public safety, or extraordinary public expense, create nuisance, cause fraud on or victimization of the public, or conflict with existing local laws or ordinances.
- (J) A variance may be issued for solid waste disposal facilities or sites, hazardous waste management facilities, salvage yards, and

chemical storage facilities that are located in Special Flood Hazard Areas provided that all of the following conditions are met.

- (1) The use serves a critical need in the community.
- (2) No feasible location exists for the use outside the Special Flood Hazard Area.
- (3) The reference level of any structure is elevated or floodproofed to at least the Regulatory Flood Protection Elevation.
- (4) The use complies with all other applicable federal, state and local laws.
- (5) Watauga County has notified the Secretary of the North Carolina Department of Public Safety of its intention to grant a variance at least thirty (30) calendar days prior to granting the variance.

Article IV Provisions For Flood Hazard Reduction

Section 1. General Standards.

In all Special Flood Hazard Areas the following provisions are required:

- (A) All new construction and substantial improvements shall be designed (or modified) and adequately anchored to prevent flotation, collapse, and lateral movement of the structure.
- (B) All new construction and substantial improvements shall be constructed with materials and utility equipment resistant to flood damage in accordance with the FEMA Technical Bulletin 2, Flood Damage-Resistant Materials Requirements.
- (C) All new construction and substantial improvements shall be constructed by methods and practices that minimize flood damages.
- (D) All new electrical, heating, ventilation, plumbing, air conditioning equipment, and other service equipment shall be located at or above the RFPE or designed and installed to prevent water from entering or accumulating within the components during the occurrence of the base flood. These include, but are not limited to, HVAC equipment, water softener units, bath/kitchen fixtures, ductwork, electric/gas meter panels/boxes, utility/cable boxes, hot water heaters, and electric outlets/switches.
 - a) Replacements part of a substantial improvement, electrical, heating, ventilation, plumbing, air conditioning equipment, and other service equipment shall also meet the above provisions.
 - b) Replacements that are for maintenance and not part of a substantial improvement, may be installed at the original

location provided the addition and/or improvements only comply with the standards for new construction consistent with the code and requirements for the original structure.

- (E) All new and replacement water supply systems shall be designed to minimize or eliminate infiltration of floodwaters into the system.
- (F) New and replacement sanitary sewage systems shall be designed to minimize or eliminate infiltration of floodwaters into the systems and discharges from the systems into flood waters.
- (G) On-site waste disposal systems shall be located and constructed to avoid impairment to them or contamination from them during flooding.
- (H) Nothing in this chapter shall prevent the repair, reconstruction, or replacement of a building or structure existing on the effective date of this ordinance and located totally or partially within the floodway, non-encroachment area, or stream setback, provided there is no additional encroachment below the Regulatory Flood Protection Elevation in the floodway, non-encroachment area, or stream setback, and provided that such repair, reconstruction, or replacement meets all of the other requirements of this chapter.
- (I) New solid waste disposal facilities and sites, hazardous waste management facilities, salvage yards, and chemical storage facilities shall not be permitted. A structure or tank for chemical or fuel storage incidental to an allowed use or to the operation of a water treatment plant or wastewater treatment facility may be located in a Special Flood Hazard Area only if the structure or tank is either elevated or flood proofed to at least the Regulatory Flood Protection Elevation and certified in accordance with the provisions of [Article III, Section 2\(C\)](#).
- (J) All subdivision proposals and other development proposals shall be consistent with the need to minimize flood damage.
- (K) All subdivision proposals and other development proposals shall have public utilities and facilities such as sewer, gas, electrical, and water systems located and constructed to minimize flood damage.
- (L) All subdivision proposals and other development proposals shall have adequate drainage provided to reduce exposure to flood hazards.
- (M) All subdivision proposals and other development proposals shall have received all necessary permits from those governmental agencies for which approval is required by Federal or State law, including Section 404 of the Federal Water Pollution Control Act Amendments of 1972, 33 IJ~S~C. 1334.

- (N) When a structure is partially located in a Special Flood Hazard Area, the entire structure shall meet the requirements for new construction and substantial improvements.
- (O) When a structure is located in multiple flood hazard zones or in a flood hazard risk zone with multiple base flood elevations, the provisions for the more restrictive flood hazard risk zone and the highest Base Flood Elevation (BFE) shall apply.
- (P) Buildings and structures that are located in more than one flood hazard area shall comply with the provisions associated with the most restrictive flood hazard area.

Section 2. Specific Standards.

In all Special Flood Hazard Areas where Base Flood Elevation (BFE) data has been provided, as set forth in [Article II, Section 2](#), or [Article IV, Section 5](#), the following provisions, in addition to the provisions of [Article IV, Section 1](#), are required:

- (A) Residential Construction. New construction and substantial improvement of any residential structure (including manufactured homes) shall have the reference level, including basement, elevated no lower than the Regulatory Flood Protection Elevation, as defined in [Chapter 7](#) of this Title.
- (B) Non-Residential Construction. New construction and substantial improvement of any commercial, industrial, or other non-residential structure shall have the reference level, including basement, elevated no lower than the Regulatory Flood Protection Elevation, as defined in [Chapter 7](#). Structures located in A, AE, and AI -30 Zones may be floodproofed to the Regulatory Flood Protection Elevation in lieu of elevation provided that all areas of the structure, together with attendant utility and sanitary facilities, below the Regulatory Flood Protection Elevation are watertight with walls substantially impermeable to the passage of water, using structural components having the capability of resisting hydrostatic and hydrodynamic loads and the effect of buoyancy. A registered professional engineer or architect shall certify that the floodproofing standards of this subsection are satisfied. Such certification shall be provided to the Floodplain Administrator as set forth in [Article III, Section 2\(C\)](#), along with the operational plan and the inspection and maintenance plan.
- (C) Manufactured Homes.
 - (1) New and replacement manufactured homes shall be elevated so that the reference level of the manufactured home is no lower than the Regulatory Flood Protection Elevation, as defined in [Chapter 7](#).

- (2) Manufactured homes shall be securely anchored to an adequately anchored foundation to resist flotation, collapse, and lateral movement, either by certified engineered foundation system, or in accordance with the most current edition of the State of North Carolina Regulations for Manufactured Homes adopted by the Commissioner of Insurance pursuant to NCGS 143-143.15. Additionally, when the elevation would be met by an elevation of the chassis thirty-six (36) inches or less above the grade at the site, the chassis shall be supported by reinforced piers or engineered foundation. When the elevation of the chassis is above thirty-six (36) inches in height, an engineering certification is required.
 - (3) All enclosures or skirting below the lowest floor shall meet the requirements of [Article IV, Section 2\(D\)](#).
 - (4) An evacuation plan must be developed for evacuation of all residents of all new, substantially improved or substantially damaged manufactured home parks or subdivisions located within flood prone areas. This plan shall be filed with and approved by the Floodplain Administrator and the local Emergency Management Coordinator.
- (D) Elevated Buildings. Fully enclosed area of new construction and substantially improved structures below the lowest floor:
- (1) shall not be designed or used for human habitation, but shall only be used for parking of vehicles, building access, or limited storage of maintenance equipment used in connection with the premises. Access to the enclosed area shall be the minimum necessary to allow for parking of vehicles (garage door) or limited storage of maintenance equipment (standard exterior door), or entry to the living area (stairway or elevator). The interior portion of such enclosed area shall not be finished or partitioned into separate rooms, except to enclose storage areas;
 - (2) shall not be temperature-controlled or conditioned; Watauga County has the right to inspect the enclosed area;
 - (3) shall be constructed entirely of flood resistant materials at least to the Regulatory Flood Protection Elevation; and
 - (4) shall include, in Zones A, AE, and AI-30, flood openings to automatically equalize hydrostatic flood forces on walls by allowing for the entry and exit of floodwaters. To meet this requirement, the openings must either be certified by a professional engineer or architect or meet or exceed the following minimum design criteria:

- (a) A minimum of *two* flood openings on different sides of each enclosed area subject to flooding;
- (b) The total net area of all flood openings must be at least one (1) square inch for each square foot of enclosed area subject to flooding;
- (c) If a building has more than one enclosed area, each enclosed area must have flood openings to allow floodwaters to automatically enter and exit;
- (d) The bottom of all required flood openings shall be no higher than one (1) foot above the adjacent grade;
- (e) Flood openings may be equipped with screens, louvers, or other coverings or devices. provided they permit the automatic flow of floodwaters in both directions; and
- (f) Enclosures made of flexible skirting are not considered enclosures for regulatory purposes, and, therefore, do not require flood openings. Masonry or wood underpinning, regardless of structural status, is considered an enclosure and requires flood openings as outlined above.

(E) Additions/Improvements.

- (1) Additions and/or improvements to pre-FIRM structures when the addition and/or improvements in combination with any interior modifications to the existing structure are:
 - (a) not a substantial improvement, the addition and/or improvements must be designed to minimize flood damages and must not be any more non-conforming than the existing structure.
 - (b) a substantial improvement, both the existing structure and the addition and/or improvements must comply with the standards for new construction.
- (2) Additions to post-FIRM structures with no modifications to the existing structure other than a standard door in the common wall shall require only the addition to comply with the standards for new construction.
- (3) Additions and/or improvements to post-FIRM structures when the addition and/or improvements in combination with any interior modifications to the existing structure are:
 - (a) not a substantial improvement, the addition and/or improvements only must comply with the standards for new construction consistent with the code and requirements for the original structure.

applicant must submit to the Floodplain Administrator a plan for the removal of such structure(s) in the event of a hurricane, flash flood or other type of flood warning notification. The following information shall be submitted in writing to the Floodplain Administrator for review and written approval:

- (1) a specified time period for which the temporary use will be permitted. Time specified may not exceed three (3) months, renewable up to one (1) year;
 - (2) the name, address, and phone number of the individual responsible for the removal of the temporary structure;
 - (3) the time frame prior to the event at which a structure will be removed (i.e., minimum of 72 hours before landfall of a hurricane or immediately upon flood warning notification);
 - (4) a copy of the contract or other suitable instrument with the entity responsible for physical removal of the structure; and
 - (5) designation, accompanied by documentation, of a location outside the Special Flood Hazard Area, to which the temporary structure will be moved.
- (H) Accessory Structures. When accessory structures (sheds, detached garages, etc.) are to be placed within a Special Flood Hazard Area, the following criteria shall be met:
- (1) Accessory structures shall not be used for human habitation (including working, sleeping, living, cooking or restroom areas);
 - (2) Accessory structures shall not be temperature-controlled;
 - (3) Accessory structures shall be designed to have low flood damage potential;
 - (4) Accessory structures shall be constructed and placed on the building site so as to offer the minimum resistance to the flow of floodwaters;
 - (5) Accessory structures shall be firmly anchored in accordance with the provisions of [Article IV, Section 1\(A\)](#);
 - (6) All service facilities such as electrical shall be installed in accordance with the provisions of [Article IV, Section 1\(D\)](#); and
 - (7) Flood openings to facilitate automatic equalization of hydrostatic flood forces shall be provided below Regulatory Flood Protection Elevation in conformance with the provisions of [Article IV, Section 2\(D\)\(4\)](#),

An accessory structure with a footprint less than 150 square feet satisfies the criteria outlined above is not required to meet the elevation or floodproofing certificate standards of Article IV Section 2 (b). Elevation or

floodproofing certifications are required for all other accessory structures in accordance with [Article III, Section 2\(C\)](#).

- (I)** Tanks. When gas and liquid storage tanks are to be placed within a Special Flood Hazard Area, the following criteria shall be met:
 - (1)** Underground tanks. Underground tanks in flood hazard areas shall be anchored to prevent flotation, collapse or lateral movement resulting from hydrodynamic and hydrostatic loads during conditions of the design flood, including the effects of buoyancy assuming the tank is empty;
 - (2)** Above-ground tanks, elevated. Above-ground tanks in flood hazard areas shall be elevated to or above the Regulatory Flood Protection Elevation on a supporting structure that is designed to prevent flotation, collapse or lateral movement during conditions of the design flood. Tank-supporting structures shall meet the foundation requirements of the applicable flood hazard area;
 - (3)** Above-ground tanks, not elevated. Above-ground tanks that do not meet the elevation requirements of Section B (2) of this ordinance shall be permitted in flood hazard areas provided the tanks are designed, constructed, installed, and anchored to resist all flood-related and other loads, including the effects of buoyancy, during conditions of the design flood and without release of contents in the floodwaters or infiltration by floodwaters into the tanks. Tanks shall be designed, constructed, installed, and anchored to resist the potential buoyant and other flood forces acting on an empty tank during design flood conditions.
 - (4)** Tank inlets and vents. Tank inlets, fill openings, outlets and vents shall be:
 - (a)** At or above the Regulatory Flood Protection Elevation or fitted with covers designed to prevent the inflow of floodwater or outflow of the contents of the tanks during conditions of the design flood; and
 - (b)** Anchored to prevent lateral movement resulting from hydrodynamic and hydrostatic loads, including the effects of buoyancy, during conditions of the design flood.
- (J)** Other Development.
 - (1)** Fences in regulated floodways and NEAs that have the potential to block the passage of floodwaters, such as

- stockade fences and wire mesh fences, shall meet the limitations of Article IV, Section 6 of this ordinance.
- (2) Retaining walls, sidewalks and driveways in regulated floodways and NEAs. Retaining walls and sidewalks and driveways that involve the placement of fill in regulated floodways shall meet the limitations of Article IV, Section 6 of this ordinance.
 - (3) Roads and watercourse crossings in regulated floodways and NEAs. Roads and watercourse crossings, including roads, bridges, culverts, low-water crossings and similar means for vehicles or pedestrians to travel from one side of a watercourse to the other side, that encroach into regulated floodways shall meet the limitations of Article IV, Section 6 of this ordinance.
 - (4) Commercial storage facilities are not considered "limited storage" as noted in this ordinance, and shall be protected to the Regulatory Flood Protection Elevation as required for commercial structures.

Section 3. Reserved.

Section 4. Standards For Floodplains Without Established Base Flood Elevations.

Within the Special Flood Hazard Areas designated as Approximate Zone A and established in [Article II, Section 2](#), where no Base Flood Elevation (BFE) data has been provided by FEMA, the following provisions, in addition to the provisions of [Article IV, Section 1](#), shall apply:

- (A) No encroachments, including fill, new construction, substantial improvements or new development shall be permitted within a distance of twenty (20) feet each side from top of bank or five times the width of the stream, whichever is greater, unless certification with supporting technical data by a registered professional engineer is provided demonstrating that such encroachments shall not result in any increase in flood levels during the occurrence of the base flood discharge.
- (B) The BFE used in determining the Regulatory Flood Protection Elevation shall be determined based on the following criteria:
 - (1) When Base Flood Elevation (BFE) data is available from other sources, all new construction and substantial improvements within such areas shall also comply with all applicable provisions of this ordinance and shall be elevated or floodproofed in accordance with standards in [Article IV, Sections 1](#) and [2](#).

- (2) When floodway or non-encroachment data is available from a Federal, State, or other source, all new construction and substantial improvements within floodway and non-encroachment areas shall also comply with the requirements of [Article IV, Sections 2](#) and [6](#).
- (3) All subdivision, manufactured home park and other development proposals shall provide Base Flood Elevation (BFE) data if development is greater than five (5) acres or has more than fifty (50) lots/manufactured home sites. Such Base Flood Elevation (BFE) data shall be adopted by reference in accordance with [Article II, Section 2](#) and utilized in implementing this chapter.
- (4) When Base Flood Elevation (BFE) data is not available from a Federal, State, or other source as outlined above, the reference level shall be elevated or floodproofed (nonresidential) to or above the Regulatory Flood Protection Elevation, as defined in [Chapter 7](#). All other applicable provisions of [Article IV, Section 2](#) shall also apply.

Section 5. Standards For Riverine Floodplains With Base Flood Elevations But Without Established Floodways or Non-Encroachment Areas.

Along rivers and streams where Base Flood Elevation (BFE) data is provided by FEMA or is available from another source but neither floodway nor non-encroachment areas are identified for a Special Flood Hazard Area on the FIRM or in the FIS report, the following requirements shall apply to all development within such areas:

- (A) Standards of [Article IV, Sections 1](#) and [2](#); and
- (B) Until a regulatory floodway or non-encroachment area is designated, no encroachments, including fill, new construction, substantial improvements, or other development, shall be permitted unless certification with supporting technical data by a registered professional engineer is provided demonstrating that the cumulative effect of the proposed development, when combined with all other existing and anticipated development, will not increase the water surface elevation of the base flood more than one (1) foot at any point within the community.

Section 6. Floodways and Non-Encroachment Areas.

Areas designated as floodways or non-encroachment areas are located within the Special Flood Hazard Areas established in Article II, Section 2. The floodways and non-encroachment areas are extremely hazardous areas due to the velocity of floodwaters that have erosion potential and

carry debris and potential projectiles. The following provisions, in addition to standards outlined in [Article IV, Sections 1](#) and [2](#), shall apply to all development within such areas:

- (A) No encroachments, including fill, new construction, substantial improvements and other developments shall be permitted unless:
 - (1) it is demonstrated that the proposed encroachment would not result in any increase in the flood levels during the occurrence of the base flood, based on hydrologic and hydraulic analyses performed in accordance with standard engineering practice and presented to the Floodplain Administrator prior to issuance of floodplain development permit, or
 - (2) a Conditional Letter of Map Revision (CLOMR) has been approved by FEMA. A Letter of Map Revision (LOMR) must also be obtained upon completion of the proposed encroachment
- (B) If [Article IV, Section 6\(A\)](#) is satisfied, all development shall comply with all applicable flood hazard reduction provisions of this chapter.

Article V Legal Status Provisions

Section 1. Effect on Rights and Liabilities Under the Existing Flood Damage Prevention Ordinance.

This ordinance in part comes forward by re-enactment of some of the provisions of the Flood Damage Prevention Ordinance enacted April 1, 1987 as amended, and it is not the intention to repeal but rather to re-enact and continue to enforce without interruption of such existing provisions, so that all rights and liabilities that have accrued there under are reserved and may be enforced. The enactment of this ordinance shall not affect any action, suit or proceeding instituted or pending. All provisions of the Flood Damage Prevention Ordinance of Watauga County enacted on April 1, 1987, as amended, which are not reenacted herein are repealed.

The date of the initial Flood Damage Prevention Ordinance for Watauga County is June 10, 1980; said ordinance repealed and replaced April 1, 1987. Amended December 3, 2009 and February 18, 2014.

Section 2. Effect Upon Outstanding Floodplain Development Permits.

Nothing herein contained shall require any change in the plans, construction, size, or designated use of any development or any part thereof for which a floodplain development permit has been granted by the Floodplain Administrator or his or her authorized agents before the time of passage of this ordinance; provided, however, that when construction is not begun under such outstanding permit within a period of six (6) months subsequent to the date of issuance of the outstanding permit, construction or use shall be in conformity with the provisions of this ordinance.

Section 3. Severability

See [Chapter 5, Article VII](#).

Section 4. Adoption Certification.

I hereby certify that this is a true and correct copy of the Flood Damage Prevention Ordinance as adopted by the governing body of Watauga County, North Carolina, on the 16th day of November, 2021.

CHAPTER 10 FOSCOE GRANDFATHER ZONING

Article I Purpose, Authority and Jurisdiction

Section 1. Purpose.

The zoning regulations and districts as herein set forth are being adopted in accordance with a comprehensive plan and are designed to lessen congestion in the streets; to secure safety from fire, panic and other dangers; to promote good health and the general welfare; to provide adequate light and air, to prevent the overcrowding of land; to avoid undue concentration of population; and to facilitate the adequate provision of transportation, water, sewerage, schools, parks, and other public requirements. Such regulations are being made with reasonable consideration, among other things, to the character of the district and their peculiar suitability for particular uses, with a view to conserving the value of buildings and encouraging the most appropriate use of land throughout the community, and with the goal of preserving the rural environment of the Foscoe-Grandfather Community.

Section 2. Authority.

The provisions of this chapter are enacted under authority granted by the General Assembly of North Carolina. (General Statute 160D, Article 7 and other pertinent statutes and amendments thereto.)

Section 3. Jurisdiction.

The regulations set forth in this ordinance chapter shall be applicable to all land within the boundaries of the Foscoe-Grandfather Community as established and amended by the Watauga County Board of County Commissioners.

Article II General Provisions

Section 1. Application.

The regulations set forth in this chapter shall apply to all land, every building and every use of land and/or building except bona fide farms as defined in N.C.G.S. 160D-903 within the boundaries of the Foscoe-Grandfather Community.

Section 2. New Uses or Construction.

After the effective date of these regulations, all new construction and the moving, altering and enlarging of existing structures shall conform to the use, area and bulk regulations for the district in which it is, or is to be, located.

Section 3. Conforming Uses.

After the effective date of these regulations, existing structures, or the use of land or structures which conform to the regulations for the district, may be continued, provided that any structural alteration or change in use shall conform with the regulation herein specified for the district in which it is located.

Section 4. Nonconforming Uses.

After the effective date of these regulations, existing structures, or the uses of land or structures which would be prohibited under the regulations for the district in which it is located (if they existed on the initial adoption date of these regulations), shall be considered as nonconforming. Nonconforming structures or uses may be continued provided they conform to the following provisions:

- (A) Continuing the Use of Nonconforming Land**
 - (1) Extensions of Use.** Nonconforming uses of land shall not hereafter be enlarged or extended in any way.
 - (2) Change of Use.** Any nonconforming use of land may be changed to conforming use or with the approval of the Board of Adjustment to any use more in character with the uses permitted in the district.
- (B) Continuing the Use of Nonconforming Buildings**
 - (1) Extensions of Use.** Nonconforming buildings and nonconforming uses of buildings shall not hereafter be enlarged except when such enlargement or extension is in compliance with subparagraph [\(B\)\(6\)](#) below.
 - (2) Change of Use.** If no structural alterations or enlargements are made, any nonconforming building or use of buildings may be changed (with the approval of Board of Adjustment) to any use more in character with uses permitted in the district. In permitting such change, the Board of Adjustment may require appropriate conditions and safeguards in accordance with the provisions of this ordinance.

- (3) Cessation of Use. If active operations are discontinued for a continuous period of six months with respect to a nonconforming use of building, such building or buildings shall thereafter be occupied and used only for a conforming use.
- (4) Repair and Alteration. Normal maintenance and repair in a building occupied by a nonconforming use is permitted provided it does not extend the nonconforming use.
- (5) Damage or Destruction. If a building occupied by a nonconforming use or a nonconforming building is destroyed by any means to an extent of more than 50 percent of its replacement cost at time of destruction, such building may not be restored for any nonconforming use.
- (6) Nonconforming features of buildings may be extended into the yard (setback) which is being violated by the nonconforming feature(s). However, the addition shall not be more than fifty (50) percent of the existing gross floor area and shall not extend further than the existing building line and in no case shall the addition be closer than five (5) feet to the property line. Additional screening shall be required for commercial uses if adjacent to residential uses. Additional screening shall be defined as a six (6) foot high opaque fence or an evergreen tree a minimum six (6) feet in height planted on four (4) foot centers.

Section 5. Open Space Requirements.

No part of a yard, court or other open space provided around any building or structure for the purpose of complying with the provisions of this chapter shall be included as a part of a yard or other open space required under this chapter for another building or structure.

Section 6. Reduction of Lot and Yard Areas Prohibited.

No yard or lot existing at the time of passage of these regulations shall be reduced in size or area below the minimum requirements set forth herein. Yards and lots created after the effective date of these regulations shall meet at least the minimum requirements established by these regulations.

Section 7. Projections into Public Rights-of-way.

No signs or other structures shall project beyond the curb line of any street or other public way.

Section 8. Interpretation of District Boundaries.

When uncertainty exists with respect to the boundaries or districts as shown on the Official Zoning Map, the following rules shall apply:

- (A) Delineation. District boundary lines indicated as approximately following property lines, lot lines, the center line of streets, alleys, railroads, easements, other rights-of-way, and creeks, streams, or other water channels, shall be constructed to follow such lines.
- (B) Official Zoning Map. In the absence of specified distances on the map, dimensions or distances shall be determined by scaling the distance on the Official Zoning Map

Article III Official Zoning Map

Section 1. Zoning Map.

The boundaries of each zoning district are shown on a map entitled "Foscoe Grandfather Community Official Zoning Map" which is hereby made a portion of this chapter.

Article IV Administration and Enforcement

Section 1. Administration and Enforcement.

The Watauga County Department of Planning and Inspections (hereinafter referred to as Zoning Official) shall administer and enforce this chapter.

- (A) Violations. If the Zoning Official shall find that any of the provisions of this chapter are being violated, s/he shall notify in writing the person responsible for such violation, indicating the nature of the violation and ordering the action necessary to correct it within ten (10) days. S/he shall order the discontinuance of illegal use of land, buildings, or structures; the removal of illegal buildings or structures or of addition, alterations, or structural changes thereto; the discontinuance of any illegal work being done; and shall take any other action authorized by this chapter to insure compliance with, or to prevent violation of, its provisions.
- (B) Remedies and Penalties. [Chapter 5](#) of this Title shall apply.

Section 2. Permit Process.

- (A) Zoning Permits. No building or other structures shall be erected, moved, added to, or structurally altered without a zoning permit therefore, issued by the Zoning Official. No building permit shall be issued except in conformity with the provisions of this chapter.
- (B) Application for Zoning Permit. All applications for building permits shall be accompanied by plans in duplicate, drawn to scale, showing the actual dimensions and shape of the lot to be built upon; the exact sizes and locations on the lot of buildings already existing, if any; and location and dimensions of the proposed building or alteration. The application shall include such other information as lawfully may be required by the Zoning Official including a description of all existing or proposed buildings or alterations; existing or proposed uses of the buildings and land; the number of families, housekeeping units, or rental units the buildings are designed to accommodate; conditions existing on the lot; and such other matters as may be necessary to determine conformance with, and provide for the enforcement of, this chapter.

One copy of the plans shall be returned to the applicant by the Zoning Official after s/he shall have marked such copy either as approved or disapproved and attested to the same by his/her signature on such copy. The second copy of these plans, similarly marked, shall be retained by the Zoning Official.

- (C) Zoning Permit for New, Altered, or Nonconforming Uses
- (1) It shall be unlawful to use or occupy or to permit the use or occupancy of any building or premises, or both, or any part thereof which may be hereafter created, erected, changed, converted, (or wholly or partly altered or enlarged as to its use or structure) until a zoning permit shall have been issued therefore by the Zoning Official stating that the proposed use of the building or land conforms to the requirements of this chapter.
- (2) No permit for the erection, alteration, moving, or repair of any building shall be issued until an application has been made for a zoning permit in connection therewith. Such zoning permit shall be issued in conformity with the provisions of this ordinance chapter upon the satisfactory completion of the work.
- (3) A temporary zoning permit may be issued by the Zoning Official for a period not to exceed six (6) months during alterations or construction for partial occupancy of a building pending its completion, or for bazaars, carnivals, and revivals, provided

that such temporary permit shall require such conditions and safeguards as will protect the safety of the occupants and the public.

- (4) The Zoning Official shall maintain a record of all zoning permits and copies shall be furnished upon request to any responsible and interested person.
 - (5) The Failure to obtain the necessary zoning permit shall be a violation of this chapter and shall be punishable under [Chapter 5](#) of this Ordinance.
- (D) Construction and Use to be as Stated on Zoning Permits. Zoning permits issued on the basis of plans and applications approved by the Zoning Official authorize only the use, arrangement, and construction set forth in such approved plans and applications. Any use, arrangement, or construction at variance with that authorized shall be deemed a violation of this chapter, and shall be punishable as provided by [Chapter 5](#).

Section 3. Right of Appeal.

If the zoning permit is denied, the applicant may appeal the action of the Zoning Official to the Board of Adjustment.

Article V District Regulations

For the purpose of this ordinance, the Foscoe-Grandfather Community is hereby divided into four districts:

Rural District

Rural/Residential District

Highway District

Light Industrial Conditional District

Section 1. Rural District.

The Rural District is established as a district in which the principal use of land is for low density residential and agricultural purposes. The regulations of this district are intended to protect the agricultural sections of the community from an influx of uses likely to render them undesirable for farms and future development; to ensure that residential development not having access to public water supplies and dependent upon septic tanks for sewage disposal

will occur at sufficiently low densities to insure a healthful environment; and to protect the Watauga River and tributaries from degradation.

(A) Permitted Uses

- (1) Land which is used solely for bona fide farming activities.
- (2) Construction or placement of single or two-family units in legally-platted subdivision as permitted; included are additions to these units and accessory buildings, provided that the principal use remains residential;
- (3) Placement of manufactured housing units in approved residential parks or legally platted subdivision: included are additions to these units and accessory buildings provided that the principal use remains residential;
- (4) Construction or placement of and/or addition to single or two-family dwelling units or manufactured housing units outside legally platted subdivisions or residential parks as permitted, provided that the principal use remains residential;
- (5) Conduct of a home occupation in or on the premises of single-family dwelling where the dwelling is the original use of the property;
- (6) Churches and affiliated uses (standards regarding parking, driveway access, stormwater control, and buffer areas are applicable);
- (7) Installation of sign(s) on a non-residential site (on-premise sign) in accordance with the ~~Watauga County Chapter 16~~ Sign Regulations.
- (8) Continued use of any land, structure, or development as it legally existed and was occupied on the effective date of this chapter.

(B) Special Uses

- (1) Multi-family and clustered dwellings and manufactured home parks (also subject to review under the Subdivisions and Multi-Unit Structures regulations and ~~the Watauga County Chapter 14~~ ~~Manufactured Home/Recreational Park Trailer~~ Parks regulations respectively);
- (2) Schools, public utility facilities, fire stations, recreational facilities (including golf courses, but not including driving ranges or miniature courses) and public buildings or facilities.

(C) Dimensional Requirements

Minimum required lot area for single and two-family dwellings – One (1) acre (43,560 square feet). Any lot in a residential subdivision recorded prior to June 15, 1973, or otherwise made exempt from subdivision regulation by official action of Watauga County to

“grandfather” the development, shall not be subject to the lot size or yard requirements of this chapter. However, in no case shall any structures be built closer than five (5) feet to a property line. Setbacks from stream banks required by this chapter shall apply to said developments. Preexisting recorded residential lots less than one acre may be used provided that all other requirements of the chapter can be met. In addition to one (1) acre minimum lot size, pursuant to High Quality Waters rules set forth by NC Division of Environmental Quality, all other land uses are subject to a maximum density standard of twelve (12) percent impervious surface (built-upon area), or higher density with approved storm water controls installed, if an erosion control plan due to one (1) acre or more of land-disturbing activity is required.

Minimum required mean lot width for each dwelling unit – 100 feet.

Minimum required depth of front yard – 30 feet.

Minimum required width of any side yard – 15 feet.

Minimum required depth of rear yard – 15 feet.

Off-street parking if applicable shall be provided as required in [Article VI, Section 3](#) of this chapter.

Maximum height of structure (not including chimneys, steeples, antennas, etc.) – 40 feet, measured from entrance grade, as measured under the NC Building Code. One (1) floor may be below entrance grade (basement).

Section 2. Rural/Residential District.

The Rural/Residential District is established as a more restricted, yet similar district to the Rural District. The principal use of land is for low density conventional residential structures.

(A) Permitted Uses

- (1)** Construction or placement of single-family units in legally-platted subdivision as permitted; included are additions to these units and accessory buildings, provided that the principal use remains residential,

- (2) Construction or placement of and/or addition to single family dwelling outside legally platted subdivisions as permitted, provided that the principal use remains residential;
- (3) Conduct of a home occupation in or on the premises of single-family dwelling where the dwelling is the original use of the property;
- (4) Churches and affiliated uses (standards regarding parking, driveway access, stormwater control, and buffer areas are applicable);
- (5) Installation of sign(s) on a non-residential site (on-premise sign) in accordance with the Watauga County Sign regulations.
- (6) Continued use of any land, structure, or development as it legally existed and was occupied on the effective date of these regulations.

(B) Special Uses

- (A) multi-family and clustered dwellings (also subject to review under the Watauga County Subdivisions and Multi-Unit Structures regulations);
- (B) schools, public utility facilities, fire stations, recreational facilities (including golf courses, but not including driving ranges or miniature courses) and public buildings.
- (C) public utility buildings and facilities if such use is essential for the service of the immediate area and provided that:
 - (a) all buildings shall be located at least 35 feet from any lot line.
 - (b) fences and/or other appropriate safety devices are installed to protect the public safety and welfare.
 - (c) no vehicles or equipment are stored, maintained or repaired on premises
 - (d) all structures are in keeping with the residential character of the neighborhood.
 - (e) adequate landscaping, screening and/or buffering shall be provided to insure compatibility with the neighborhood.
- (D) Radio and television transmitting stations and studios provided that:
 - (a) such facilities shall be housed in structures which are in keeping with the character of the residential neighborhood.
 - (b) No structure shall be located within 35 feet of any lot line.

(C) Dimensional Requirements

Minimum requirements for lot area, yards, parking, and building height are as described for the [Rural District](#) or as established in [Article VI](#).

Section 3. Highway District.

The Highway District is located on the major thoroughfare. It is intended to provide offices, personal services, and retailing of durable and convenience goods for the community. Because the commercial uses are subject to public view and are important to the economy, they should have an appropriate appearance, ample parking, controlled traffic movement and suitable landscaping.

(A) Permitted Uses

- (1) all uses permitted within the Rural District;
- (2) non-residential uses which are not subject to a special use permit as shown below or are prohibited by this chapter, except industrial uses which are permitted only in the industrial conditional district. These uses are subject to a site plan review and must comply with the standards of Article VI.

(B) Special Uses

- (1) multi-family and clustered dwellings and manufactured home parks as described for the Rural District;
- (2) other uses as described for the Rural District, also hospitals, police stations, libraries, circuses, carnivals, fairs, flea markets, and temporary uses;

Standards for Flea Markets

- (a) Site Plan Information: A site plan, drawn to scale, shall be submitted which legibly indicates the following:
 - (i.) Boundary survey;
 - (ii.) Hours and frequency of operation;
 - (iii.) Location and dimensions of individual booths and sale areas;
 - (iv.) Off-street parking (vendor and customer);
 - (v.) Screening, if applicable.
- (b) Off-street parking: Off-street parking will be required at one (1) space per 200 sq. ft. of commercial area used for display and sales of two (2) per booth or individual display area, whichever is greater. All parking facilities shall be provided with on-site drainage in accordance with Article VI, Section 6(C).

- (c) Screening/buffering: shall be provided as specified in [Article VI](#).
 - (d) Signs: One (1) freestanding directory sign shall be allowed provided such sign does not exceed 50 sq. ft. In addition, each vendor may have a four (4) square foot attached sign.
 - (e) Applicant shall submit a written statement setting forth the method and frequency of maintenance, repair, refuse collection and disposal along with the site plan.
- (3) Combination of residential and non-residential uses;
- (4) Non-residential uses which consist of multiple units, are greater than 5000 square feet in size, or are deemed by the Zoning Official to be potentially detrimental to the community as follows:
- (a) Could materially endanger the public health or safety, or
 - (b) Could substantially injure the value of adjoining or abutting property, or
 - (c) May not be in harmony with the area in which it is to be located, or
 - (d) May not be in general conformity with the land use plan, thoroughfare plan, or other plans officially adopted by the County.

(C) Dimensional Requirements

Minimum required lot area is one-half (1/2) acre. Preexisting recorded lots less than one-half may be used provided all other requirements of the ordinance can be met. However, if an erosion control plan is required pursuant to 15NCAC, Chapter 4, the minimum lot area for single family dwellings is one (1) acre; all other land uses are subject to a maximum density standard of twelve (12%) percent impervious surface (built upon area). Higher Density (than 12% built upon area) will be ~~permitted~~ **allowed** if stormwater control systems ~~utilizing wet detention ponds are installed, operated, and maintained which control the runoff from all built upon areas generated from one inch of rainfall. Specifications for detention ponds shall be established by the NC Division of Environmental Quality.~~ **are permitted by North Carolina Division of Environmental Quality Energy, Minerals and Land Resources** (High Quality Waters rules)

Minimum yard requirements for residential structures shall be as established for the [Rural District](#). Yard requirements for nonresidential structures are established in [Article VI, Section 4](#).

Building Height. Same as [Article V, Section 1\(C\)](#).

Off-Street parking, if applicable, shall be provided as required in [Article VI, Section 3](#).

Section 4. Light Industrial Conditional Zoning District.

The Industrial District is established as a district in which the principal use of land is for industries and certain other land use functions which can be operated in a relatively clean and quiet manner, and industries which are not obnoxious to adjacent residential or business districts. The regulations are designed to prohibit the use of land for heavy industry which should be properly segregated and to prohibit any other use which would substantially interfere with the development of industrial establishments in the district.

(A) Rezoning & Permitted Uses

Pursuant to [Chapter 5, Article XIV](#), tracts may be zoned Light Industrial Conditional District upon petition/application of all of the owners of the subject tracts, and approval by the Board of Commissioners, for any of the following land uses:

- (1) Manufacturing and/or assembly
- (2) Machine shop/welding
- (3) Furniture repair if paint/refinishing booth is included
- (4) Brewery/distillery/winery
- (5) Commercial warehouses, but not "mini-storage" warehouses, which are permitted in the Highway District
- (6) Trucking/distribution terminal
- (7) Building material and lumber storage

(B) Prohibited Uses

Uses defined as Category 1 and 2 High Impact Land Uses in [Chapter 13](#) of this Title are industrial, and are prohibited.

(C) Conditional Uses

All land uses are conditional and must comply with the Site Plan Review Standards, as well as any other conditions agreed upon by the Board of Commissioners and applicant(s).

(D) Dimensional Requirements

Minimum requirements for lot area, yards, parking, and building height are as described for the Highway District or as established pursuant to [Article VI](#).

Section 5. Accessory Uses.

- (A)** Sections 1, 2, 3, and 4 of this article describe permitted and special uses for each district. Whenever an activity is conducted in conjunction with another principal use and the former use (i) constitutes only an incidental or insubstantial part of the total activity that takes place on a lot, or (ii) is commonly associated with the principal use and integrally related to it, then the former use may be regarded as accessory to the principal use and may be carried on underneath the umbrella of the permit issued for the principal use. For example, a swimming pool/tennis court complex is customarily associated with and integrally related to a residential subdivision or multi-family development and would be regarded as accessory to such principal uses, even though such facilities, if developed apart from a residential development, would require a special use permit.
- (B)** For purposes of interpreting Subsection A:
- (1)** A use may be regarded as incidental or insubstantial if it is incidental or insubstantial in and of itself or in relation to the principal use,
 - (2)** To be “commonly associated” with a principal use it is not necessary for an accessory use to be connected with such principal use more times than not, but only that the association of such accessory use with such principal use takes place with sufficient frequency that there is common acceptance of their relatedness.
- (C)** Without limiting the generality of Subsection A and B, the following activities, so long as they satisfy the general criteria set forth above, are specifically regarded as accessory to residential principal uses:
- (1)** Offices or studios within an enclosed building and used by an occupant of a residence located on the same lot as such building to carry on administrative or artistic activities of a commercial nature, so long as such activities do not fall within the definition of a home occupations.
 - (2)** Hobbies or recreational activities of non-commercial nature.
 - (3)** The renting out of one or two rooms within a single-family residence (which one or two rooms do not themselves constitute a separate dwelling unit) to not more than two persons who are not part of the family that resides in the single-family dwelling.
 - (4)** Yard sales or garage sales, so long as such are not conducted on the same lot for more than three days (whether consecutive or not) during any 90-day period.

- (D) Without limiting the generality of Subsections A and B, the following activities shall not be regarded as accessory to a residential principal use and are prohibited in residential districts.
 - (1) Storage outside of a substantially enclosed structure of any motor vehicle that is neither licensed nor operational.
 - (2) Parking outside a substantially enclosed structure of more than four motor vehicles between the front building line of the principal building and the street on any lot used for single or two-family residences.

Article VI Site Plan Review

All ~~non-residential~~ uses **except one and two family dwellings** are subject to the standards described in this section. Compliance with the standards shall be determined through a site plan review by the Zoning Official. Standards are as follows:

Section 1. Sign Regulations

Placement of signs is regulated by the [Watauga County Sign regulations](#) with the following exceptions:

- (A) new off-premises signs are prohibited;
- (B) the setbacks for new on-premises signs shall be located beyond the right-of-way of Highway 105 and 10 feet from side property lines; and
- (C) pre-existing non-conforming on-premises signs shall be permitted to remain until the use of the property is changed or the occupancy of the use is changed. Signs must be brought into compliance with the ordinances at that time.
- (D) pre-existing off-premise signs shall be permitted to remain in their present location, however once moved from that location, the off-premise sign shall be considered a new off-premise sign.
- (E) off-premise signs shall not be re-established after damage or destruction by an act of nature in excess of sixty (60) percent of its replacement value at the time of the damage or destruction.

Section 2. Buffer Areas

- (A) Buffer areas shall be established in order to create the impression of spatial separation between adjacent land uses. The purpose of this separation is to lessen possible adverse effects of land uses upon each other and to provide within development planted/green areas

so as to maintain the rural character of the community. Buffer requirements are as follows.

- (B)** Where a commercial or multi-family use is proposed adjacent to a single-family residential use, side and rear yard setback of 30 feet shall be observed for buildings, parking, or storage. This area is to be used as a buffer and shall be landscaped as follows. Buffers shall consist of plantings of evergreen and/or deciduous trees spaced no **less more** than thirty (30) feet apart. Such trees shall be at least six to seven (6-7) feet tall for evergreens and six to eight (6-8) feet tall with a one and one half (1-1/2) inch caliper (trunk measured six (6) inches above grade) for deciduous trees at time of planting and shall reach a height of no less than twenty (20) feet as maturity. In addition, plantings of low growing shrubs, and/or trees shall be placed at ten (10) foot intervals. Plantings within buffer zones shall be staggered unless topography is prohibitive. No planting shall be placed in the road right-of-way. Lists of recommended plantings are available from the Planning and Inspections Department.
- (C)** Where a commercial or multi-family use is proposed adjacent to a commercial or multi-family use side and rear yard setback of 15 feet shall be observed for buildings, parking, or storage. This area is to be used as a buffer and shall be landscaped as follows. Buffers shall consist of plantings of evergreen and/or deciduous trees spaced no **less more** than thirty (30) feet apart. Such trees shall be at least six to seven (6-7) feet tall for evergreens and six to eight (6-8) feet tall with a one and one half (1-1/2) inch caliper for deciduous trees at time of planting and shall reach a height of no less than twenty (20) feet at maturity. In addition, permanent ground cover such as grasses shall be established.
- (D)** Wall, fences, earthen berms, or other natural features may be used in combination with ~~or in~~ lieu of planted buffers if approved as part of the **conditional special** use permit. Considerations include but are not limited to:

 - (1)** Any existing significant vegetation within the buffer(s) may be preserved and credited towards meeting the standard for the required buffer. Existing fences, berms, and/or walls within the buffer(s) may be used to fulfill the standards set forth for the buffer providing these elements are healthy and in a condition of good repair. Chain link fencing is not acceptable in meeting the performance criteria of this ordinance.
 - (2)** Installation of supplemental vegetation and/or site features may be required at the time of Site Plan review, if existing vegetation and/or site features within the buffer do not meet or exceed the requirements of this ordinance.

- (E) Open storage areas, exposed machinery and outdoor areas used for the storage and collection of rubbish must be visually screened from roads and surrounding land uses. Suitable types of screening include opaque wood fences and dense evergreen hedges of six (6) feet or more in height. Where evergreen hedges are proposed, a temporary fence should be built to provide screening until the evergreens are of sufficient height.
- (F) The recipient of any zoning or special-use permit, or his successor, shall be responsible for maintaining all common areas, improvements, or facilities required by the ordinance or any permit issued in accordance with its provisions, except those areas, improvements, or facilities with respect to which an offer of dedication to the public has been accepted by the appropriate public authority. As illustrations, and without limiting the generality of the foregoing, this means that private roads and parking areas, water and sewer lines, and recreational facilities must be properly maintained so that they can be used in the manner intended, and required vegetation and trees used for screening, landscaping, or shading must be replaced if they die or are destroyed.

Section 3. Parking Standards

All development shall be provided with adequate parking facilities to handle the expected number of automobiles for that site. Spaces shall be provided as follows; use and occupancy classifications for buildings are the same as those definitions use in the N.C. Building Code.

(A) Required Spaces

- (1) Assembly, business, educational, storage and mercantile uses and occupancies buildings shall be provided with parking spaces as follows:
 - (a) one (1) off-street parking space for each two hundred (200) square feet of gross floor area for operations designed to attract and serve customers and clients on the premises; ~~one space per 300 square feet of floor space in buildings of under 11,000 square feet; and~~
 - (b) one (1) off-street parking space for each four hundred (400) square feet of gross floor area for operations designed to attract little or no customer or client traffic other than employees of the operation. ~~one space per 200 square feet of floor space in buildings 11,000 square feet and greater.~~

- (c) One (1) off-street parking space for each one thousand (1000) square feet of gross floor area for self-service storage facilities.
- (2) Factory and Industrial and High Hazard uses and occupancies buildings shall be provided with 1.5 spaces per three employees, computed on the total employment.
- (3) Institutional buildings uses and occupancies shall be provided with one space per five person identified in the building's occupant load figures.
- (4) Residential buildings uses and occupancies, primarily permanent, shall be provided with 1.5 spaces per bedroom two (2) spaces per dwelling unit.
- (5) Residential uses and occupancies, primarily transient (motels, hotels and inns), shall be provided with one and one-half (1.5) spaces per bedroom.

Parking spaces shall be calculated as being 162 square feet each, broken down to 9 by 18 feet. Once the total required square footage has been determined as required by (1) through ~~(4)~~(5), developers shall be permitted to increase the numbers of spaces by downsizing some for use by smaller automobiles. Total space requirements of (1) through ~~(4)~~ (5) shall, however, be met in any case. Paving is not required, unless required by Subdivisions and Multi-Unit Structures regulations. 4" compacted crusher-run or DOT-approved ABC stone is adequate.

(B) Loading/Unloading Space

Loading/unloading space for non-residential uses shall consist of one (1) space at least three hundred (300) square feet in size for each five thousand (5000) square feet of gross floor area. A minimum of one (1) loading/unloading space is required, regardless of floor area square footage.

(C) Location and Buffering of Parking

In order to preserve the rural environment, developers are encouraged to place parking and loading/unloading areas at the rear or side of buildings. ("Front" is defined as the face of the building which is paralleled to a public road or a county standard road as defined in the Watauga County Subdivisions and Multi-Unit Structures regulations. By this definition, buildings on multiple public road or county standard road frontage would have multiple "front yards".) In any event, parking areas which are exposed to a public road or county standard road shall include a ten (10) foot buffer strip

along the front. At a minimum, such strips shall be grassed and/or mulched and shall be planted with low growing trees, or shrubs no more than twenty (20) feet apart. Incentive to place parking areas to the side or rear of buildings is provided in the form of lessened front yard setback requirements. ([See Article VI, Section 4](#))

Section 4. Yard Requirements – Highway and Industrial Districts

- (A) Front Yard (side or rear parking) – 20 feet from edge of road right-of-way.
- (B) Front Yard (front parking) – 40 feet from edge of right-of-way (includes buffer strip).
- (C) Side and rear yards – 30 feet or 15 feet depending upon use of adjacent property (see buffer area requirements)

Section 5. Driveway Connections

Driveway access to Highway 105 shall be limited to two (2) per development; one (1) is preferred. Channelization will be required (unless waived by Watauga County) as part of driveway and parking lot design so that the driveway(s) can be specifically located. Use of the entire frontage as a single driveway connection is prohibited.

NC DOT “Policy on Street and Driveway Access to North Carolina Highways” requires County site plan approval prior to DOT review and approval of driveway connection applications. No building or **grading** permit, however, shall be issued unless DOT has issued a driveway connection permit or has indicated in writing that a permit can be issued.

Section 6. Drainage, Erosion Control, Storm Water Management

- (A) Natural Drainage. To the extent practicable, all development shall conform to the natural contours of the land and natural and pre-existing man-made drainage way shall remain undisturbed.
- (B) Erosion Control. All developments which involve one-half (1/2) acre or more of grading (land-disturbing activity) shall comply with the requirements of the Watauga County Erosion Control regulations. All developments which involve less than one-half (1/2) acre of land-disturbing activity shall take adequate measures to prevent sediment from being washed off-site or into waterways during construction, and shall restore permanent vegetative ground cover within **seven (7) days after ceasing land disturbance or within** 120 days of the date the site is first disturbed. This 120 day period may be extended by Watauga County in the event of inclement weather.


- (C) Storm Water Management. All developments shall be constructed and maintained so that adjacent properties are not reasonably burdened with surface waters as a result of such developments. More specifically:
- (1) No development may be constructed or maintained so that such development unreasonably impedes the natural flow of water from higher adjacent properties across such development, thereby unreasonably causing substantial damage to such higher adjacent properties; and
 - (2) No development may be constructed or maintained so that surface waters from such development are unreasonably collected and channeled onto lower adjacent properties at such locations or at such volumes as to cause substantial damage to such lower adjacent properties.

Section 7. Stream Protection, Flood Plain Protection

- (A) Stream Protection. A minimum vegetative buffer of 50 feet shall be maintained between the top of the banks of Watauga River and Boone Fork Creek and new built upon areas. A minimum vegetative buffer of 40 feet shall be maintained between the top of the banks of Valley Creek, Moody Mill Creek, Spice Bottom Creek and tributaries to the five (5) named streams and new built upon areas. New developments large enough to warrant an erosion control plan pursuant to the Watauga County Erosion Control regulations shall also maintain a 25 foot undisturbed area adjacent to the top of the banks of designated trout streams and their tributaries as required by the N.C. Sedimentation Pollution Control Act of 1973 as amended (all of the named streams are designated). The undisturbed area is not required for smaller developments. However erosion control measures approved by the Department of Planning and Inspections shall be installed and maintained within the required buffer until permanent vegetation is established. The Zoning Official shall keep lists/map of stream classifications on file.

The buffers (and undisturbed areas, if applicable) may be penetrated by driveways/stream crossings, which are necessary to access property. Under those circumstances, the penetration and any land disturbing activity shall be kept to a minimum and approved erosion control measures shall be installed and maintained. The requirements for buffers or undisturbed areas does not preclude the construction, when necessary, of storm drainage facilities such as detention ponds.

Streams are perennial streams as depicted by a solid blue line on USGS 7 1/2 minute scale topographic sheets. Top of stream bank is the nearest point at the top of the natural stream channel which is the beginning point of an imaginary horizontal line that forms a 90 degree angle with an imaginary vertical line perpendicular to the stream at the low water line. (see diagram) Often, it appears that streams have multiple banks. In most cases, the top of the bank for purposes of this ordinance will be the bank closest to the water's edge.



~~Built-upon area means that portion of a development project that is covered by impervious or partially impervious cover including buildings, pavement, gravel roads, recreation facilities (e.g. tennis courts), etc.~~

- (B) Flood Plain Protection. In addition to the requirements of stream classifications, development adjacent to the Watauga River shall comply with the Watauga County Flood Damage Prevention regulations. Dredging or filling activity in or adjacent to the Watauga River, Boone Fork Creek, or other wetland areas potentially requires a Section 404 permit from the U.S. Army Corps of Engineers. The Zoning Official shall inform developers of this potential. It is the responsibility of the developer to contact the Corps of Engineers.

CHAPTER 11 INSTALLATION AND MAINTENANCE OF ELECTRONIC ACCESS GATES FOR GATED COMMUNITIES

Article I Authority and Purpose

These regulations are enacted pursuant to the general police powers granted to Watauga County by North Carolina Gen. Stat. §153A-121, N.C. Gen. Stat. §160D-1104, and Section 503 of the 2009 North Carolina State Fire Prevention Code, as amended periodically. The purpose of these regulations is to establish rules and standards for the installation of electronic access gates for gated communities in order to provide for the safe and efficient ingress and egress for fire, law enforcement, and other emergency personnel.

Article II Requirements

New and existing, when applicable, gated communities shall comply with the following requirements:

- (A) All streets in the gated community must be private streets.
- (B) The location of the gate(s) shall comply with [Article III](#) of this chapter and the North Carolina State Fire Prevention Code, as applicable.
- (C) The gates shall be maintained in working order and inspected as needed.
- (D) Gates pre-existing to the adoption of these regulations shall not be affected by this chapter provided they are maintained and in working order. If such gates are replaced or modified, they shall conform to the requirements of [Article III, parts C through K](#), of this chapter and the North Carolina State Fire Prevention Code as applicable.
- (E) Applicants shall adhere to [Article IV](#) regarding the process for obtaining approval for gates.

Article III Gate Development Specifics

- (A) Entrance gates shall be located a minimum of 40' from the adjacent public road right-of-way to allow for emergency vehicle clearance at entry.
- (B) Combined entry and exit ways shall provide a minimum unobstructed width of twenty (20) feet. Entry and exit ways separated by landscape medians, guard houses, or other obstructions shall provide a minimum unobstructed width of twelve (12) feet. Entry and exit ways shall have a minimum unobstructed vertical clearance of not less than thirteen feet six inches (13'6").
- (C) It shall be determined if the gates are to be manual or electrical in

operation. All electrical vehicular gates shall be provided with access control using a Radio Transceiver for public safety and authorized users. This transceiver will allow emergency vehicles to open the gate from a mobile or portable radio, and must be pre-approved by Watauga County.

- (D) All electrical vehicular gates shall be provided with a fail-open device in the event of power failures unless secondary power is provided by battery back-up or generator. During a power failure, the gates will open and remain open. These devices should restore the gate(s) to the closed position after the power is restored. Any residential gated communities consisting of three (3) or less dwelling units are not subject to this requirement.
- (E) Gates need to be opened for appropriate personnel to enter the community during an emergency. A fire service recognized/approved dual key activating switch or padlock shall be installed to allow emergency personnel access through vehicular gates.
- (F) An approved dual key lock box containing cards, keys, pass codes and operating instructions shall be provided at each entrance gate.
- (G) Gates shall be designed so that when fully opened do not obstruct the path of travel for vehicles or pedestrians, whether emergency and non-emergency. Gates shall remain fully open during an emergency event, when activated by responding agency, until reset. A 'Hold Open' code must be included in design and functioning of the gate.
- (H) If there are two or more gates in any single development, all gates shall be operated in the same fashion.
- (I) Gate activation shall not be altered or placed out of service without prior notification to the Watauga County Fire Marshal's Office, Watauga County Planning and Inspections Department and the Local Fire Department.
- (J) Each entrance gate shall be provided with an "override" feature to allow the gate(s) to remain open so that multiple fire apparatus can enter without having to wait for intermittent opening of the gate(s).
- (K) Each entrance gate shall be equipped with a manual override feature so as to permit opening during power failures or other emergency.

Article IV Application and Approval Process

- (A) The applicant shall submit a detailed plan, including but not limited to, scaled drawings showing the location of the gates, turn radius, dimensions of the gates, pavement, sidewalks, curbs, etc. Information such as topography lines, vegetation, site triangles, etc. shall also be included with the submittal.
- (B) The applicant shall submit these plans for review by the Planning & Inspections Department, who shall forward the plans to the Sheriff's

Department, Fire Marshal's Office, EMS, and Local Fire Department for approval.

- (C) The Department of Planning & Inspections shall verify approval by the agencies listed in [Section B.](#) of the gate plan prior to issuance of a permit.
- (D) All property owners shall notify the Watauga County Emergency Services Department of any gate access code changes prior to such changes taking effect.
- (E) All gated communities applying for a permit to install a gate shall acknowledge that if the affected properties gate fails to operate in its intended operational capacity, and such failure results in damage to the gate or constitutes the responding emergency agency to alter normal entrance procedures, the responding agency, mutual aid departments and Watauga County shall not be held liable for damages incurred.

Article V Maintenance

Gates subject to this chapter shall be kept in their original working order and shall be repaired and/or replaced in the event they are disabled and/or damaged. It shall not be the responsibility of the County to maintain these gates. Gates subject to this chapter shall be monitored annually by the Local Fire Department and verified by the Watauga County Fire Marshal's Office every three (3) years of their operation or as deemed appropriate by the Watauga County Fire Marshal's Office.

Article VI Modifications

Any gate (new or existing) altered outside the scope of their original installation and/or permitting, will be considered a modification. Notification and plans for modification shall be submitted to the Watauga County Office of Planning and Inspections for review and decision upon compliance with this chapter.

CHAPTER 12 HEIGHT OF STRUCTURES

WHEREAS, the Board of Commissioners of Watauga County are concerned about the health, safety and general welfare of the general public; and

WHEREAS, the fire departments of Watauga County together with other appropriate agencies have stated that structures higher than forty (40) feet are hazardous to the people in them in case of fire or other disasters; and

WHEREAS, the Watauga County Planning Board and Board of Soil and Water Conservation have requested the Board of Commissioners of Watauga County to exercise its ordinance making power to protect the fragile lands of Watauga County in order to promote the general welfare and safety of the citizens of Watauga County and the people who might visit the County; and

WHEREAS, the Board of Commissioners are authorized to enact ordinances for safety and general welfare by North Carolina General Statute 153A-121;

NOW, THEREFORE, the Watauga County Board of Commissioners have enacted the following:

Article I Regulation of Height of Structures

No building or structure intended for dwelling use may be constructed, reconstructed, or remodeled with a vertical height of more than 40 feet. For purposes of calculating vertical height, the applicant may elect to use either of the following two methods:

- (A) 40 feet measured vertically from the highest point of the roof to the highest point of finished grade within 6 feet horizontally of an exterior wall, or
- (B) 40 feet measured vertically from the average height of the highest roof surface to the "grade plane" as defined in the NC Residential Code and NC Building Code.

Excluded from this ordinance are the following:

- (1) Water, radio, television, or telephone towers or any equipment for the transmission of electricity or communications, or both.
- (2) Structures which are slender in nature and minor vertical projections of a parent building including chimneys, flag poles, flues, spires, steeples, belfries, cupolas, antennas, poles, wires or windmills, provided that part of the structure which is higher than 40 feet is no intended for human habitation.

Article II Permits

In the event any person, partnership, or corporation requests a building permit for a structure that is in violation of this **chapter ordinance** the Watauga County Planning and Inspections Department shall deny the issuance of a building permit.

CHAPTER 13 HIGH IMPACT LAND USES

Article I Introduction

Section 1. General Purpose.

The following regulations of High Impact Land Uses (HILU) are adopted for the purpose of promoting the health, safety and general welfare of the citizens of Watauga County, and to promote the peace and dignity of the county; the Watauga County Commissioners hereby establish certain criteria relating to high impact land uses. These uses by their very nature produce objectionable levels of noise, odors, vibrations, fumes, light, smoke, and other impacts upon the lands adjacent to them. These standards shall allow for the placement and growth of such uses, while maintaining the health, safety, and general welfare standards of established residential and commercial areas in Watauga County.

Section 2. Legal Authority.

These regulations are enacted under the general ordinance authority granted to counties by the General Assembly of North Carolina. (General Statutes 153A-121 *et seq.*, and other pertinent statutes and amendments thereto).

Section 3. Territorial Coverage.

Pursuant to NCGS § 153A-122, this chapter shall apply to all areas of unincorporated Watauga County which are not within the extraterritorial planning jurisdictions of any municipalities. All municipalities, their respective corporate limits, and extra-territorial jurisdiction shall be exempted from the chapter, unless they choose to adopt this chapter or some form thereof. This chapter does not apply to Watauga County owned and operated solid waste facilities or container sites.

Article II Regulated Land Uses

Section 1. Regulated Uses.

This chapter applies to the following High Impact Land Uses:

- (A) Category 1. Asphalt Plants, Cement Mixing Facilities, Quarries/Stone Crushers, Chemical Manufacturing, Chemical Storage Facilities, Explosives Manufacturing, and Explosives Storage Facilities, Chip

Mills, and Electricity Generating Facilities (excluding Wind and Solar Power Farms), Motor Sports Facilities.

- (B) Category 2. Automotive Graveyards, Propane, Gasoline, or Fuel Oil Bulk Storage Facilities, and Junk/Scrap Yards.
- (C) Category 3. Electric Substations, Commercial/Industrial Development with aggregate building footprint 50,000 square feet or greater, Recycling Facilities, and Solar Power Farms. (Note: Wind Power Farms are regulated by separate Watauga County Ordinance.)

Section 2. Regulations and Standards Imposed.

- (A) Parking Space Requirements. Adequate parking facilities shall be provided to accommodate the type and intensity of vehicles likely to frequent High Impact Land Uses. Spaces shall be provided as follows; use and occupancy classifications for buildings are the same as those definitions used in the N.C. Building Code. Standards for specific land uses are as follows:
 - ~~(1)~~ Retail uses shall provide a minimum of three (3) spaces per 1,000 square feet of floor area for buildings up to 10,000 SF in size, and (5) spaces per each 1,000 square feet of floor area in excess of 10,000 square feet.
 - ~~(2)~~ Overnight accommodations shall provide a minimum of one and one-half (1.5) spaces per bedroom.
 - ~~(3)~~ Factory, Industrial and Commercial (other than specified in (1) and (2) above) uses shall provide one and one-half (1.5) spaces per three employees computed on the total employment.
 - (1) Assembly, business, educational, storage and mercantile uses and occupancies shall be provided with parking spaces as follows:
 - (i.) one (1) off-street parking space for each two hundred (200) square feet of gross floor area for operations designed to attract and serve customers and clients on the premises;
 - (ii.) one (1) off-street parking space for each four hundred (400) square feet of gross floor area for operations designed to attract little or no customer or client traffic other than employees of the operation;
 - (iii.) one (1) off-street parking space for each one thousand (1000) square feet of gross floor area for mini-warehouse uses.
 - (2) Factory Industrial uses and occupancies shall be provided with 1.5 spaces per three employees, computed on the total employment.

- (3) Institutional uses and occupancies shall be provided with one space per five persons identified in the building's occupant load figures.
- (4) Residential uses and occupancies, primarily permanent, shall be provided with 2 spaces per dwelling unit
- (5) Residential uses and occupancies, primarily transient (motels, hotels and inns), shall be provided with one and one-half (1.5) spaces per bedroom.


Parking spaces shall be at least nine (9) by eighteen (18) feet. Accessible spaces shall be provided in accordance with NC Building Code requirements. The Ordinance Administrator may permit deviations from the preceding specified standards based upon the expected parking needs of the establishment while recognizing the desire to limit excess parking area.

- (B) Building Height Limits. In order to allow for adequate fire protection, no building shall exceed a height of forty (40) feet, measured as defined by the Watauga County Height of Structures regulations.
- (C) Outdoor Lighting Standards. High Impact Land Uses shall use outdoor lighting that does not create a nuisance on adjacent property, roadways, or pollute the night sky. These objectives are easily accomplished by choosing good quality, shielded fixtures.
 - (1) All parking lot lighting shall use full cutoff lighting fixtures;
 - (2) Wall-packs and floodlights shall be either full cutoff design or have shields such that they do not put any light above the horizon and will be mounted to not shine on roadways and neighboring properties. Use of floodlights is discouraged;
 - (3) Typical pole-mounted "dusk-to-dawn" security lights shall use reflecting "sky caps" instead of clear plastic refractors;
 - (4) Building façade lighting shall not shine above the facades; and
 - (5) For buildings required by the NC Building Code to have plans prepared by a design professional, the lighting levels shall be determined as defined by the Recommended Practices of the Illuminating Engineering Society of North America, or other recognized lighting publication. All other buildings comply with the requirement by virtue of compliance with (1) through (4) of this section.
- (D) Setbacks Required.
 - (1) Category 1 & Category 2 High Impact Land Uses shall be set back 200 feet from side and rear property lines.

- (2)** Category 3 High Impact Land Uses shall be set back 100 feet from side and rear property lines.
- (3)** Where High Impact Land Uses adjoin each other, the required setbacks along common boundary lines for each High Impact Use may be reduced as follows:

 - (a)** Category 1 & Category 2 High Impact Land Uses – 50 feet;
 - (b)** Category 3 High Impact Land Uses – 25 feet.
- (4)** Category 1 & 2 High Impact Land Uses shall be set back 200 feet from the edge of travelled area (stone or paved) of all public roads, unless spacing requirements (subsection F) apply. In no instance shall such setbacks be less than 20 feet from any recorded right of way or NCDOT property boundary.
- (5)** High Impact Land Uses shall be set back from all perennial waters indicated by blue lines on the most recent versions of USGS 1:24,000 (7.5 minute) scale topographic maps as follows:
There shall be a 100-foot vegetative buffer (measured from the top of the stream bank as indicated below) for all “blue line” streams; the 30 feet closest to the top of the stream bank being undisturbed and 70 feet managed vegetation. Publicly accessible walkways may be allowed within the managed vegetation area.

Typical variation in water level correlated with vegetative zones (modified from: *Importance of Natural Vegetation for the Protection of Banks of Streams, Rivers and Canals*, Seibert).



- (6) No part of a yard provided around any building or structure for the purpose of complying with the provisions of this chapter shall be included as a part of a yard required under this chapter for any other building or structure.
- (E) Landscape Buffers Required. Each High Impact Land Use shall be effectively buffered by landscaping which lessens the visual impact of the development at road grade level and from all sides with non-High Impact Uses in place and increases the buffering of noise and particulate matter. Each applicant shall submit a landscape plan which describes in detail how the above objectives will be met. The Ordinance Administrator may reasonably require adjustments and/or alterations to any proposed landscape plan necessary to comply with the provisions of this chapter.
- (1) Category 1 & Category 2 Landscape Buffers. All Category 1 & Category 2 High Impact Land Uses shall be buffered utilizing the following combination of landscape material designed for screening effect:
- (a) Deciduous trees – three (3) per 100 lineal feet of property boundary line; and
 - (b) Evergreen trees – six (6) per 100 lineal feet of property boundary line; and
 - (c) Shrubs – ten (10) per 100 lineal feet of property boundary line.
- (2) Category 3 Landscape Buffers. All Category 3 High Impact Land Uses shall be buffered utilizing the following combination of landscape material designed for aesthetic effect:

- (a) Deciduous/Evergreen trees – four (4) per 100 lineal feet of property boundary line; and
- (b) Shrubs – ten (10) per 100 lineal feet of property boundary line.

Opaque fencing made from conventional material or masonry walls and existing healthy trees and shrubs may be used in combination with a reduced number of required trees and shrubs when landscape buffer objectives are met and plans are approved by the Ordinance Administrator.

- (3) Plant material shall be inspected and approved prior to planting and must meet the following minimum size requirements:
 - (a) Deciduous trees shall be a minimum of 6 feet tall with a 1 ½ -inch caliper measured six inches above grade upon planting;
 - (b) Evergreen trees shall be a minimum of 6 feet tall upon planting;
 - (c) Shrubs shall be a minimum of 1 foot tall upon planting.

(F) Spacing Requirements.

- (1) Category 1 & Category 2 High Impact Land Uses may not be established within 1,500 feet of a public or private Educational Facility, NC licensed Child Care Facility, NC licensed Assisted Living Facility, NC licensed Nursing Home, Public Outdoor Recreation Area, or Religious Facility. In order to establish required spacing, measurement shall be made in a straight line, without regard to intervening structures or objects, from the nearest portion of the building, structure, or outdoor storage area utilized by Category 1 or 2 Land Uses, to the nearest property line of the above-listed facilities.
- (2) Category 1 High Impact Land Uses may not be established within 750 feet of a dwelling. In order to establish required spacing, measurement shall be made in a straight line, without regard to intervening structures or objects, from the nearest portion of the building, structure, or outdoor storage area utilized by a Category 1 Land Use, to the nearest property line of a dwelling.
- (3) Category 1 High Impact Land Uses may not be established within 1,500 feet of the right-of-way line of a roadway designated by NCDOT as a NC Scenic Byway or a roadway designated by Watauga County as a Gateway, or within 1,500 feet of the Blue Ridge Parkway. Presence of a city, county or other political subdivision boundary shall be irrelevant for purposes of calculating and applying the spacing requirements of this Section.

- (4) The recipient of any High Impact Land Use permit, or their successor, shall be responsible for maintaining all common areas, improvements, or facilities required by the ordinance or any permit issued in accordance with its provisions. As illustrations, and without limiting the generality of the foregoing, this means that private roads and parking areas, water and sewer lines, and recreational facilities must be properly maintained so that they can be used in the manner intended, and required vegetation and trees used for screening, landscaping, or shading must be replaced if they die or are destroyed.
- (G) Driveway Connection Permit Required: A driveway connection permit issued by NC Department of Transportation shall be obtained. A Traffic Impact Analysis shall be required from the applicant under the following circumstances, unless the Ordinance Administrator and NCDOT concur that one is unnecessary:
- (1) The development proposes to have access to any public road at a location where sight distance in any direction along the road is less than 500 feet; or
 - (2) The development proposes access onto a public road that does not have a paved width of at least 18 feet; or
 - (3) The development proposes access to a public road with current NCDOT traffic counts that are 85% of capacity shown in the most recent Watauga County Comprehensive Transportation Plan and based upon ITE trip generation rates is projected to generate 1,500 or more weekday trips; or
 - (4) The Ordinance Administrator determines that the proposed project will have a potential negative impact on the public road system due to the size of the project or existing transportation system or determines that there are safety concerns with the driveway location and design. If a traffic impact analysis is performed and that analysis concludes that improvements are required to the transportation system, the applicant may be required to complete those improvements in connection with the project as a condition of issuing a permit. Unless an agreement is executed by the County in which the time for the improvement is specified, the improvement shall be completed prior to issuance of a certificate of occupancy.
- (H) Federal and State Permits: The developer shall obtain all applicable Federal and State Permits as a condition of issuance of a HILU Special Use Permit. Failure to obtain said permits shall result in revocation of the conditional Special Use Permit.

Article III Pre-Existing High Impact Land Uses

Section 1. Grandfathering of Pre-existing High Impact Land Uses.

Any High Impact Land Use existing upon the date of adoption of these regulations which does not conform to the requirements of These regulations may continue so long as the use is not discontinued for more than One Hundred Eighty (180) days. In cases where repair or renovation is necessary to re-occupy a vacant building, a permit for such construction must be obtained within one hundred eighty (180) days of last occupancy and repairs must proceed continuously to completion. A High Impact Land Use shall not be deemed to be discontinued during such time as the owner or operator thereof has temporarily suspended operations solely due to the seasonal nature of the business.

- (A) **Expansion.** Grandfathered nonconforming High Impact Land Uses may be expanded provided the degree of nonconformity is not increased. In addition, the expansion shall comply with the standards of [Article II](#), and the pre-existing development shall comply with the standards of Article II to the extent physically practicable as determined by the Ordinance Administrator, and upon issuance of a Special Use Permit pursuant to [Article IV](#).
- (B) **Reconstruction.** In cases of damage to grandfathered nonconforming buildings to the extent of seventy-five percent (75%) or less of the replacement value, repairs may be made, provided the original building footprint is maintained. When such damage exceeds seventy-five percent (75%) of the replacement value, repairs may be made only if the original building footprint is maintained and the standards of [Article II](#) are met to the extent physically practicable as determined by the Ordinance Administrator, and upon issuance of a Special Use Permit pursuant to [Article IV](#).
Compliance with a requirement of this chapter is not physically practicable if compliance cannot be achieved without adding land to the lot where the nonconforming situation is maintained or moving a substantial structure that is on a permanent foundation. Mere financial hardship caused by the cost of meeting requirements does not constitute grounds for finding that compliance is not physically practicable.

Section 2. New High Impact Land Uses Regulated.

After the effective date of this chapter all new High Impact Land Uses as well as any pre-existing High Impact Land Uses which are moved, altered or enlarged shall conform to the regulations contained in this chapter except as set forth in [Article III, Section 1](#).

Section 3. Pre-existing Regulated Land Uses.

After the effective date of this chapter, new permits or approvals for any of the protected land uses listed in [Article II, Section 2 \(F\)](#) Spacing Requirements shall not have the effect of creating new non-conformities for any lawfully existing High Impact Land Use.

Article IV Permit Required

Section 1. Permitting Process.

- (A) Special Use Permit Required. No use subject to this chapter shall be established, reconstructed or expanded, and no building used or occupied without a Special Use Permit having been issued pursuant to [Chapter 3](#).
- (B) Applications for Special Use Permits. All applications for Special Use permits shall be accompanied by plans in duplicate, drawn to scale, showing the actual dimensions and shape of the lot to be built upon; the exact sizes and locations on the lot of any buildings already existing; the location and dimensions of the proposed building or alteration; and compliance with the standards of [Article II](#). The application shall include such other information as may reasonably be required by the Ordinance Administrator, including a description of all existing or proposed buildings or alterations; existing and proposed uses of the buildings and land; conditions existing on the land parcel; and such other matters as may be necessary to determine conformance with, and provide for the enforcement of, this chapter.
- (C) Administrator to Maintain Permit Records. The Ordinance Administrator shall maintain a record of all Special Use Permits and copies shall be furnished upon request to any interested person.
- (D) Building Permit. No permit required under the North Carolina State Building Code Shall be issued for any activity for which a HILU Special Use Permit is required until the Special Use Permit has been issued.

Section 2. Permit Expiration.

A HILU Special Use Permit shall expire if a Building Permit or High Impact Land Use Occupancy Permit for such use is not obtained by the applicant within twelve (12) months from the date of issuance.

Section 3. High Impact Land Use Occupancy Permit.

- (A)** The Ordinance Administrator shall issue a High Impact Land Use Occupancy Permit certifying that all requirements of this ordinance have been met prior to the occupancy or use of a building hereafter erected, altered or moved and/or prior to the change of use of any building or land.
- (B)** A High Impact Land Use Occupancy Permit, either for the whole or part of a building, shall be applied for coincident with the application for a Special Use Permit and shall be issued or denied within ten (10) days after the construction or structural alterations of the building, provided all ordinance requirements are met.

Should any Federal or State regulation or statute incorporated herein by reference or otherwise referred to herein, be changed or amended, or should either require or mandate a different procedure or change or impose new, different or additional requirements, then, in that event, this chapter shall be deemed to have been amended without further action to have complied with such new, additional or amended requirements.

CHAPTER 14 MANUFACTURED HOME AND RECREATIONAL PARK TRAILER PARKS

Article I Authority and Purpose

Pursuant to the authority granted to counties in North Carolina General Statute 153A-121 and for the purpose of establishing minimum standards for the design and construction of manufactured home and recreational park trailer parks in order to protect and promote the health, safety, and general welfare of the public, the Board of Commissioners of Watauga County enact the following.

Article II Health Department Review

Unless connecting to public or community water and sewer systems, each proposed manufactured home and recreational park trailer park shall be reviewed and approved by AppHealthCare (health department) for well and septic system design and usage. Applicants are advised to work simultaneously with the County Department of Planning and Inspections and AppHealthCare to devise plans for proposed parks.

Article III Preliminary Site Plan Submission

No person, firm, or corporation shall commence construction or alteration of a manufactured home or recreational park trailer park within Watauga County without first securing the approval of a preliminary site plan from the Watauga County Planning Board. ~~One (1) copy of said site plan shall be submitted to the Department of Planning and Inspections at least ten (10) working days prior to the regular monthly meeting of the Planning Board to allow for staff review and placement on the meeting agenda. Subsequent to staff review but prior to the Board meeting, the developer shall submit eight (8) copies of the preliminary site plan.~~

Section 1. Preliminary Site Plan Specifications.

The preliminary site plan shall be drawn at a scale of not less than one hundred (100) feet to the inch on sheets 18 x 24 inches and shall include the following:

- (A) Items specified by AppHealthCare.
- (B) Sketch vicinity map of the park's location.
- (C) Landscaping, buffering, open space plans.
- (D) Designated parking areas.
- (E) AppHealthCare certificate indicating approval of the plan.

Article IV Park Development Standards

The standards of the AppHealthCare approval shall be met. In addition, the following standards shall apply:

- (A) Maximum permissible density for a manufactured home and recreational park trailer park is six (6) spaces per acre.
- (B) Minimum setbacks:
 - (1) from right-of-way of roads bordering park 20 feet.
 - (2) from right-of-way of roads inside park 10 feet, but at least 15 feet from the edge of the road travel surface.
 - (3) between all manufactured homes and recreational park trailers and attachments thereto including porches, decks, storage areas, etc. - 25 feet.
 - (4) from exterior property line – 20 25 feet.
- (C) Parking space sufficient to accommodate at least two (2) automobiles shall be constructed for each manufactured home and recreational park trailer space.
- (D) Roads within manufactured home and recreational park trailer parks shall be constructed to either NC DOT standards or "county standards" as defined in the Watauga County Subdivisions and Multi-Unit Structures regulations as amended from time-to-time, with the exception that right-of-way may be reduced to thirty (30) feet.
- (E) A minimum of four hundred (400) square feet of common open space per lot shall be required. Common open space shall be exclusive of road right-of-way, parking areas, or any areas set aside for solid waste collection or utility equipment.
- (F) A twenty-five (25) foot-wide buffer shall be provided around the perimeter of the park. The purpose of the buffer is to create the impression of spatial separation between parks and adjacent land uses without eliminating visual contact. Buffers shall consist of plantings of evergreen and/or deciduous trees spaced no more than thirty (30) feet apart. Such trees shall be at least six to seven (6-7) feet tall for evergreens and six to eight (6-8) feet tall with a one and one-half (1-1/2) inch caliper (trunk measured six (6) inches above grade) for deciduous trees at time of planting and shall reach a height of no less than twenty (20) feet a maturity. In addition, plantings of low-growing shrubs, bushes, and/or trees shall be placed at ten (10) foot intervals.
Plantings within buffer areas shall be staggered unless topography is prohibitive. No planting shall be placed in a public road right-of-way. Lists of recommended plantings are available from the Planning and Inspections Department.
In combination with or in lieu of a buffer, the following may be provided: A ten (10) foot-wide screening strip shall be provided

around the perimeter of the park. The purpose of screening is to eliminate visual contact between the park and adjacent land uses. Screening shall consist of plantings of evergreen trees at ten (10) foot intervals. Such trees shall meet the height and caliper standards described in this section for buffer areas.

- (G)** The recipient of any Manufactured Home and Recreational Park Trailer Park permit, or their successor, shall be responsible for maintaining all common areas, improvements, or facilities required by the ordinance or any permit issued in accordance with its provisions, except those areas, improvements, or facilities with respect to which an offer of dedication to the public has been accepted by the appropriate public authority. As illustrations, and without limiting the generality of the foregoing, this means that private roads and parking areas, water and sewer lines, and recreational facilities must be properly maintained so that they can be used in the manner intended, and required vegetation and trees used for screening, landscaping, or shading must be replaced if they die or are destroyed.

Article V Individual Manufactured Homes and Recreational Park Trailers Within a Park

Individual manufactured homes within a park shall be set-up, connected to utilities, and tied down in compliance with the State of North Carolina Regulations for Manufactured Homes and shall be inspected for compliance by the Planning and Inspections Department in order to be approved for permanent electrical power.

Individual recreational park trailers within a park shall only be set-up temporarily. They cannot have any permanent electrical, plumbing or mechanical connections. However, for safety reasons these units can be temporarily blocked up and anchored against overturning forces, but to remain classified as a temporary structure, the wheels and axles must remain on the unit at all times

Prior to performing any individual manufactured home or recreational park trailer inspections, the Planning and Inspections department shall confirm compliance with this and all other applicable regulations. Such regulations may include (when applicable) but are not limited to Soil Erosion and Sedimentation Control, Flood Damage Prevention, Structures Located on Land Adjacent to National Park Service Land.

Article VI Applicability to Existing Manufactured Home Parks

All manufactured home parks in operation on the effective date of this chapter shall not be affected by this chapter, except for expansions or additions, which must comply.

Article VII Registration

It shall be the duty of the owner of a manufactured home park to keep an accurate register containing a record of all manufactured homes, recreational park trailers, owners, and occupants of the park. Said information shall be reported annually to the Watauga County Tax Supervisor in accordance with NCGS 105-316.

Should any Federal or State regulation or statute incorporated herein by reference or otherwise referred to herein, be changed or amended, or should either require or mandate a different procedure or change or impose new, different or additional requirements, then, in that event, this ordinance shall be deemed to have been amended without further action to have complied with such new, additional or amended requirements.

CHAPTER 15 SEXUALLY ORIENTED BUSINESSES

REGULATIONS REQUIRING THE DISPERSING OF SEXUALLY ORIENTED BUSINESSES AND LIMITING THEM TO SPECIFIED PLACES; PRESCRIBING DEFINITIONS OF SEXUALLY ORIENTED BUSINESSES; PROVIDING FOR LICENSING AND REGULATION OF SEXUALLY ORIENTED BUSINESSES AND EMPLOYEES; AND PROVIDING FOR ADDITIONAL MISCELLANEOUS REGULATIONS FOR SEXUALLY ORIENTED BUSINESSES.

WHEREAS, the Watauga County Board of Commissioners enacted on September 10, 1999 an Ordinance establishing a moratorium on Sexually Oriented Businesses in Watauga County pursuant to North Carolina General Statute 160A-181.1 (superseded by 160D-902 in 2020) expressly authorizing county regulation of sexually oriented businesses, being authority in addition to that contained in North Carolina General Statutes 153A-45 and 153A-121; and

WHEREAS, the Watauga County Planning Board and staff of the Department of Planning and Inspections have studied the secondary impacts of sexually oriented businesses and conducted a public hearing, all of which is a matter of record; and

WHEREAS, sexually oriented businesses require special supervision from the public safety agencies of the County in order to protect and preserve the health, safety, morals and welfare of the patrons of such businesses as well as the citizens of the County; and

WHEREAS, the Planning Board has found by study of impacts in other counties and municipalities that sexually oriented businesses are frequently used for unlawful sexual activities, including prostitution and sexual liaisons of a casual nature; and

WHEREAS, the concern over sexually transmitted diseases is a legitimate health concern of the County which demands reasonable regulation of sexually oriented businesses in order to protect the health and well-being of the citizens; and

WHEREAS, licensing is a legitimate and reasonable means of accountability to ensure that operators and employees of sexually oriented businesses comply with reasonable regulations and to ensure that operators do not allow their establishments to be used improperly or as places of illegal sexual activity or solicitation; and

WHEREAS, there is convincing documented evidence that sexually oriented businesses, because of their very nature, have a deleterious effect on the existing uses, including but not limited to businesses, schools, daycare facilities, religious institutions, parks and rural fire departments around them and the surrounding residential areas adjacent to them, causing increased crime and the downgrading of property values; and

WHEREAS, it is recognized that sexually oriented businesses, due to their nature, have serious objectionable operational characteristics, particularly when they are located in close proximity to each other, thereby downgrading the quality of life in the adjacent area; and

WHEREAS, family-oriented tourism is an important aspect of the local economy that would be negatively affected by increased crime and downgraded quality of life resulting from sexually oriented businesses; and

WHEREAS, the Board of Commissioners desires to minimize and control these adverse effects and thereby protect the health, safety, and welfare of the citizenry; protect the citizens from increased crime; preserve the quality of life; preserve the property values and character of surrounding neighborhoods; and

WHEREAS, the Board of Commissioners has determined that locational criteria alone do not adequately protect the health, safety, and general welfare of the people of this County; and

WHEREAS, it is not the intent of this ordinance to suppress any speech activities protected by the First Amendment, but to enact a content neutral ordinance which addresses the secondary effects of sexually oriented businesses; and

WHEREAS, it is not the intent of the Board of Commissioners to condone or legitimize the distribution of obscene material, and the Board recognizes that state and federal law prohibits the distribution of obscene materials and expects and encourages state law enforcement officials to enforce state obscenity statutes against any such illegal activities in the County.

THEREFORE, pursuant to the authority granted by the Constitution and the legislature of the State of *NORTH CAROLINA*, BE IT ENACTED BY THE BOARD OF COMMISSIONERS OF WATAUGA COUNTY, NORTH CAROLINA, February 22, 2000:

Article I Purpose and Findings

Section 1. Purpose.

It is the purpose of this chapter to regulate sexually oriented businesses in order to promote the health, safety, morals, and general welfare of the citizens of the County, and to establish reasonable and uniform regulations to prevent the deleterious location and concentration of sexually oriented businesses within the County. The provisions of this chapter have neither the purpose nor effect of imposing a limitation or restriction on the content of any communicative materials, including sexually oriented materials. Similarly, it is not the intent nor effect of this chapter to restrict or deny access by adults to sexually oriented materials protected by the First Amendment, or to deny access by the distributors and exhibitors of sexually oriented entertainment to their intended market. Neither is it the intent nor effect of this ordinance chapter to condone or legitimize the distribution of obscene material.

Section 2. Findings.

Based on evidence concerning the adverse secondary effects of adult uses on the community presented in hearings and in reports made available to the Board, and on findings incorporated in the cases of *City of Renton v. Playtime Theatres, Inc.*, 475 U.S. 41 (1986), *Young v. American Mini Theatres*, 426 U.S. 50 (1976), and *Barnes v. Glen Theatre, Inc.*, 501 U.S. 560 (1991), and on studies in other communities including, but not limited to, Horry County and Myrtle Beach, S.C.; Richland County, S.C.; Charlotte-Mecklenburg County, N.C.; Winston Salem-Forsyth County, N.C.; Broward County, Florida; St. Johns County, Florida; Kansas City, Missouri; and also on findings from the Report of the Attorney General's Working Group On The Regulation Of Sexually Oriented Businesses, (June 6, 1989, State of Minnesota), the Board finds:

- (A) Sexually oriented businesses lend themselves to ancillary unlawful and unhealthy activities, the control of which elsewhere presents challenges to the operators of such establishments. Further, there is presently no mechanism in this County to make the owners of such establishments responsible for the activities that would occur on their premises.
- (B) Certain employees of sexually oriented businesses defined in this chapter as adult theatres and cabarets engage in higher incidence of certain types of illicit sexual behavior than employees of other establishments.

- (C) Sexual acts, including masturbation, and oral and anal sex, occur at sexually oriented businesses, especially those which provide poorly lit, overly crowded private or semi-private areas, booths or cubicles for viewing films, videos, or live sex shows.
- (D) Offering and providing such space encourages such activities, which creates unhealthy conditions.
- (E) Persons frequent certain adult theatres, adult arcades, and other sexually oriented businesses for the purpose of engaging in sex within the premises of such sexually oriented businesses.
- (F) At least 50 communicable diseases may be spread by activities occurring in sexually oriented businesses, including, but not limited to, syphilis, gonorrhea, human immunodeficiency virus infection (HIV-AIDS), genital herpes, hepatitis B, Non A, Non B amebiasis, salmonella infections and shigella infections.
- (G) The surgeon general of the United States in his report of October 22, 1986, has advised the American public that AIDS and HIV infection may be transmitted through sexual contact, intravenous drug abuse, exposure to infected blood and blood components, and from an infected mother to her newborn.
- (H) According to the best scientific evidence, AIDS and HIV infection, as well as syphilis and gonorrhea, are principally transmitted by sexual acts.
- (I) Sanitary conditions in some sexually oriented businesses are unhealthy, in part, because the activities conducted there are unhealthy, and, in part, because of the unregulated nature of the activities and the failure of the owners and the operators of the facilities to self-regulate those activities and maintain those facilities.
- (J) Numerous studies and reports have determined that semen is found in the areas of sexually oriented businesses where persons view "adult" oriented films.
- (K) The findings noted in (A) through (J) raise substantial governmental concerns.
- (L) Sexually oriented businesses have operational characteristics which should be reasonably regulated in order to protect those substantial governmental concerns.
- (M) A reasonable licensing procedure is an appropriate mechanism to place the burden of that reasonable regulation on the owners and the operators of the sexually oriented businesses. Further, such a licensing procedure will place a heretofore nonexistent incentive on the operators to see that the sexually oriented business is run in a manner consistent with the health, safety and welfare of its patrons and employees, as well as the citizens of the County. It is appropriate to require reasonable assurances that the licensee is the actual operator

- of the sexually oriented business, fully in possession and control of the premises and activities occurring therein.
- (N) Prohibition of doors on adult booths and requiring sufficient lighting on premises with adult booths advances a substantial governmental interest in curbing the illegal and unsanitary sexual activity occurring in adult theatres.
 - (O) Requiring licensees of sexually oriented businesses to keep information regarding current employees and certain past employees will help reduce the incidence of certain types of criminal behavior by facilitating the identification of potential witnesses or suspects and by preventing minors from working in such establishments.
 - (P) The disclosure of certain information by those persons ultimately responsible for the day-to-day operation and maintenance of the sexually oriented business, where such information is substantially related to the significant governmental interest in the operation of such uses, will aid in preventing the spread of sexually transmitted diseases.
 - (Q) It is desirable in the prevention of the spread of communicable diseases to obtain a limited amount of information regarding employees who may engage in the conduct which this ordinance is designed to prevent or who are likely to be witnesses to such activity.
 - (R) The fact that an applicant for an adult use license has been convicted of a sexually related crime leads to the rational concern that the applicant may engage in that conduct in contravention of this chapter.
 - (S) The barring of such individuals from the management of adult uses for a period of years serves as a deterrent to and prevents conduct which leads to the transmission of sexually transmitted diseases.
 - (T) The general welfare, health, morals and safety of the citizens of the County will be promoted by the enactment of this chapter.

Article II Classification

Sexually oriented businesses are classified as follows:

- (A) adult arcades;
- (B) adult bookstores, adult novelty stores, or adult video stores;
- (C) adult cabarets;
- (D) adult motels;
- (E) adult motion picture theaters;
- (F) adult theaters;
- (G) escort agencies;
- (H) nude model studios; and
- (I) sexual encounter centers.

Article III License Required

Section 1. Unlawful Operation and Employment Without License

It is unlawful:

- (A) For any person to operate a sexually oriented business without a valid sexually oriented business license issued by the County Official pursuant to this chapter.
- (B) For any person who operates a sexually oriented business to employ a person to work for the sexually oriented business who is not licensed as a sexually oriented business employee by the County Official pursuant to this chapter.
- (C) For any person to obtain employment with a sexually oriented business without having secured a sexually oriented business employee license pursuant to this chapter.
- (D) For any person who operates a sexually oriented business to allow any person to perform or participate in any contest or exhibition who does not have a valid and current sexually oriented business employee license pursuant to this chapter.

Section 2. Application.

An application for any license must be made on a form provided by the County Official.

Section 3. Qualified Applicant.

All applicants must be qualified according to the provisions of this chapter. The application may request and the applicant shall provide such information (including fingerprints) as to enable the County Official to determine whether the applicant meets the qualifications established in this chapter.

Section 4. Signatures.

If a person who wishes to operate a sexually oriented business is an individual, the person must sign the application for a license as applicant. If a person who wishes to operate a sexually oriented business is other than an individual, each individual who has a financial percent or greater interest in the business must sign the application for a license as applicant. Each applicant must be qualified under the following Section and each applicant shall be considered a licensee if a license is granted.

Section 5. Application Contents.

The completed application for a sexually oriented business license shall contain the following information and shall be accompanied by the following documents:

- (A)** If the applicant is:
 - (1)** an individual, the individual shall state his/her legal name and any aliases and submit proof that he/she is 21 years of age;
 - (2)** a partnership, the partnership shall state its complete name, and the names of all partners, whether the partnership is general or limited, and a copy of the partnership agreement, if any;
 - (3)** a corporation, the corporation shall state its complete name, the date of its incorporation, evidence that the corporation is in good standing under the laws of its state of incorporation, the names and capacity of all officers, directors and principal stockholders, and the name of the registered corporate agent and the address of the registered office for service of process.
- (B)** If the applicant intends to operate the sexually oriented business under a name other than that of the applicant; he or she must state 1) the sexually oriented business's fictitious name and 2) submit the required registration documents.
- (C)** Whether the applicant, or a person residing with the applicant, has been convicted of a specified criminal activity as defined in this chapter, and, if so, the specified criminal activity involved, the date, place, and jurisdiction of each.
- (D)** Whether the applicant, or a person residing with the applicant, has had a previous license under this chapter or other similar sexually oriented business regulations from another city or county denied, suspended or revoked, including the name and location of the sexually oriented business for which the permit was denied, suspended or revoked, as well as the date of the denial, suspension or revocation, and whether the applicant or a person residing with the applicant has been a partner in a partnership or an officer, director or principal stockholder of a corporation that is licensed under this chapter whose license has previously been denied, suspended or revoked, including the name and location of the sexually oriented business for which the permit was denied, suspended or revoked as well as the date of denial, suspension or revocation.
- (E)** Whether *the applicant or a person residing with the applicant* holds any other licenses under this chapter or other similar sexually oriented business regulations from another city or county and, if so, the names and locations of such other licensed businesses.
- (F)** The single classification of license for which the applicant is filing.

- (G) The location of the proposed sexually oriented business, including a legal description of the property, street address, and telephone number(s), if any.
- (H) The applicant's mailing address and residential address.
- (I) A recent photograph of the applicant(s).
- (J) The applicant's driver's license number, Social Security number, and/or his/her state or federally issued tax identification number.
- (K) A sketch or diagram showing the configuration of the premises, including a statement of total floor space occupied by the business. The sketch or diagram need not be professionally prepared, but it must be drawn to a designated scale or drawn with marked dimensions of the interior of the premises to an accuracy of plus or minus six (6) inches.
- (L) A current certificate and straight-line drawing prepared within thirty (30) days prior to application by a registered land surveyor accurately depicting the property lines and the structures containing any existing sexually oriented businesses within 1500 feet of the property to be certified; the property lines of any established religious institution/synagogue, school, public park or recreation area, nursing home, daycare establishment, or fire department, within 1500 feet of the property to be certified and the location of all residential structures within 660 feet of the property to be certified. For purposes of this Section, a use shall be considered existing or established if it is in existence at the time an application is submitted.
- (M) If an applicant wishes to operate a sexually oriented business, other than an adult motel, which shall exhibit on the premises, in a viewing room or booth of less than one hundred fifty (150) square feet of floor space, films, video cassettes, other video reproductions, or live entertainment which depict specified sexual activities or specified anatomical areas, then the applicant shall comply with the application requirements set forth in [Article XII](#).

Section 6. Employee Application.

Before any applicant may be issued a sexually oriented business employee license, the applicant shall submit on a form to be provided by the County Official the following information:

- (A) The applicant's name or any other name (including "stage" names) or aliases used by the individual;
- (B) Age, date, and place of birth;
- (C) Height, weight, hair and eye color;
- (D) Present residence address and telephone number;

- (E) Present business address and telephone number;
- (F) Date, issuing state and number of driver's permit or other identification card information;
- (G) Social Security number; and
- (H) Proof that the individual is at least twenty-one (21) years of age.

Section 7. Additional Requirements.

Attached to the application form for a sexually oriented business employee license as provided above, shall be the following:

- (A) A color photograph of the applicant clearly showing the applicant's face, and the applicant's fingerprints on a form provided by the sheriff's department. Any fees for the photographs and fingerprints shall be paid by the applicant.
- (B) A statement detailing the license history of the applicant for the five (5) years immediately preceding the date of the filing of the application, including whether such applicant previously operated or is seeking to operate, in this or any other county, city, state, or country has ever had a license, permit, or authorization to do business denied, revoked, or suspended, or had any professional or vocational license or permit denied, revoked, or suspended. In the event of any such denial, revocation, or suspension, state the name, the name of the issuing or denying jurisdiction, and describe in full the reason for the denial, revocation, or suspension. A copy of any order of denial, revocation, or suspension shall be attached to the application.
- (C) A statement whether the applicant has been convicted of a specified criminal activity as defined in this ordinance and, if so, the specified criminal activity involved, the date, place and jurisdiction of each.

Article IV Issuance of License

Section 1. Investigation.

Upon the filing of said application for a sexually oriented business employee license, the application shall be referred to the appropriate county departments for an investigation to be made on such information as is contained on the application. The investigation process shall be completed within thirty (30) calendar days from the date the completed application is filed. After the investigation, the County Official shall issue a license, unless he/she determines by a preponderance of the evidence that one or more of the following findings is true, whereupon the application must be denied:

- (A) The applicant has failed to provide information reasonably necessary for issuance of the license or has falsely answered a question or request for information on the application form;
- (B) The applicant is under the age of twenty-one (21) years;
- (C) The applicant has been convicted of a "specified criminal activity" as defined in this ordinance;
- (D) The sexually oriented business employee license is to be used for employment in a business prohibited by local or state law, statute, rule or regulation, or prohibited by a particular provision of this chapter; or
- (E) The applicant has had a sexually oriented business employee license revoked by the County Official or comparable license in any jurisdiction within two (2) years of the date of the current application. If the sexually oriented business employee license is denied, the temporary license previously issued is immediately deemed null and void. Denial, suspension, or revocation of a license issued pursuant to this subsection shall be subject to appeal as set forth in Article VIII.
- (F) Each such determination and denial shall be documented in writing, a copy of which shall be mailed to the applicant by first class mail to the address shown on the application.

Section 2. Annual Renewal.

A license granted pursuant to Section 1 shall be subject to annual renewal upon the written application of the applicant received not less than thirty (30) calendar days before the license expires and a finding by the County that the applicant has not been convicted of any specified criminal activity as defined in this ordinance or committed any act during the existence of the previous license, which would be grounds to deny the initial license application. The renewal of the license shall be subject to the payment of the fee as set forth in Article V.

Section 3. Approval/Denial.

Within 30 calendar days after receipt of a completed sexually oriented business application, the County Official shall approve or deny the issuance of a license to an applicant. The County Official shall approve the issuance of a license to an applicant unless he determines by a preponderance of the evidence that one or more of the following findings is true, whereupon the application must be denied:

- (A) An applicant is under twenty-one (21) years of age.
- (B) An applicant or a person with whom applicant is residing is overdue in payment to the County of taxes, fees, fines, or penalties assessed against or imposed upon him/her in relation to any business.

- (C) An applicant has failed to provide information reasonably necessary for issuance of the license or has falsely answered a question or request for information on the application form.
- (D) An applicant or a person with whom the applicant is residing has been denied a license by the County Official to operate a sexually oriented business within the preceding twelve (12) months or whose license to operate a sexually oriented business has been revoked within the preceding twelve (12) months.
- (E) An applicant or a person with whom the applicant is residing has been convicted of a specified criminal activity defined in this ordinance.
- (F) The premises to be used for the sexually oriented business have not been approved by the health department, fire marshal's office, and the planning and inspections department as being in compliance with applicable laws and ordinances.
- (G) The license fee required by this ordinance has not been paid.
- (H) An applicant of the proposed establishment is in violation of or is not in compliance with any of the provisions of this chapter.
- (I) Each such determination and denial shall be documented in writing, a copy of which shall be mailed to the applicant by first class mail to the address shown on the application.

Section 4. Posted License.

The license, if granted shall state on its face the name of the person or persons to whom it is granted, the expiration date, the address of the sexually oriented business and the classification for which the license is issued pursuant to [Article II](#). All licenses shall be posted in a conspicuous place at or near the entrance to the sexually oriented business so that they may be easily read at any time.

Section 5. Timeline for Review.

The health department, fire marshal's office, and the planning and inspections department shall complete their certification that the premises is in compliance or not in compliance within twenty (20) days of receipt of the application by the County Official.

Section 6. License Classification.

A sexually oriented business license shall be issued for only one classification as found in [Article II](#).

Article V Fees

Every application for a sexually oriented business license (whether for a new license or for renewal of an existing license) shall be accompanied by a \$1000.00 non-refundable application and investigation fee.

In addition to the application and investigation fee required above, every sexually oriented business that is granted a license (new or renewal) shall pay to the County Official an annual non-refundable license fee of \$ 1000.00 within thirty (30) days of license issuance or renewal.

Every application for a new sexually oriented business employee license shall be accompanied by \$ 250.00 non-refundable application, investigation, and license fee.

In addition to the application and investigation fee required above, every sexually oriented business employee that is granted a license shall pay to the County Official an annual non-refundable license fee of \$150.00 within thirty (30) days of license issuance or renewal.

All license applications and fees shall be submitted to the County Official.

Article VI Inspection

An applicant or licensee shall permit representatives of the Sheriff's Department, Health Department, Fire Marshal's Office, Planning and Inspections Department, or other County departments or agencies to inspect the premises of a sexually oriented business for the purpose of insuring compliance with the law.

A person who operates a sexually oriented business or his agent or employee shall be subject to civil penalties if he refuses to permit such lawful inspection of the premises at any time.

Article VII Expiration of License

Each license shall expire one year from the date of issuance and may be renewed only by making application as provided in [Article III](#). Application for renewal shall be made at least thirty (30) days before the expiration date, and when made less than thirty (30) days before the expiration date, the license will expire.

When the County Official denies renewal of a license, the applicant shall not be issued a license for one year from the date of denial.

Article VIII Suspension

The County Official shall suspend a license for a period not to exceed thirty (30) days if he/she determines that a licensee or an employee of a licensee has:

- (A) violated or is not in compliance with any section of this chapter;
- (B) refused to allow an inspection of the sexually oriented business premises as authorized by this chapter.

Each such determination and denial shall be documented in writing, a copy of which shall be mailed to the applicant by first class mail to address shown on the application.

Article IX Revocation

Section 1. Previous Suspension

The County Official shall revoke a license if a cause of suspension in [Article VIII](#) occurs and the license has been suspended within the preceding twelve (12) months.

Section 2. Evidence.

The County Official shall revoke a license if he/she determines by a preponderance of the evidence that one or more of the following findings is true that:

- (A) a licensee gave false or misleading information in the material submitted during the application process;
- (B) a licensee has allowed possession, use, or sale of controlled substances on the premises;
- (C) a licensee has allowed prostitution on the premises;
- (D) a licensee operated the sexually oriented business during a period of time when the licensee's license was suspended;
- (E) except in the case of an adult motel, a licensee has allowed any act of sexual intercourse, sodomy, oral copulation, masturbation, or other sex act to occur in or on the licensed premises; or
- (F) a licensee is delinquent in payment to the County or State for any taxes or fees past due.

Each such revocation under Section 1 or 2 shall be documented in writing, a copy of which shall be mailed to the licensee by first class mail to the address shown on the license.

Section 3. Length of Revocation.

When the County Official revokes a license, the revocation shall continue for one (1) year, and the licensee shall not be issued a sexually oriented business license for one (1) year from the date the revocation became effective.

Section 4. Judicial Review.

After denial of an application, or denial of a renewal of an application, or suspension or revocation of any license, the applicant or licensee may seek judicial review of such administrative action in any court of competent jurisdiction.

Article X Transfer of License

A licensee shall not transfer his/her license to another, nor shall a licensee operate a sexually oriented business under the authority of a license at any place other than the address designated in the application.

Article XI Location of Sexually Oriented Businesses

Section 1. Residential Structures.

A person commits a misdemeanor if that person operates or causes to be operated a sexually oriented business within 660 feet of any residential structure.

Section 2. Non-Residential Structures.

No sexually oriented business shall be operated within 1500 feet of:

- (A) A church, synagogue, mosque, temple or building which is used primarily for religious worship and related religious activities;
- (B) A public or private educational facility including but not limited to child day care facilities, nursery schools, preschools, kindergartens, elementary schools, private schools, intermediate schools, junior high schools, middle schools, high schools, vocational schools, secondary schools, continuation schools, special education schools, junior colleges, and universities; school includes the school grounds, but does not include facilities used primarily for another purpose and only incidentally as a school.
- (C) A public park or recreational area which has been designated for park or recreational activities including but not limited to a park, playground, nature trails, swimming pool, reservoir, athletic field, basketball or tennis courts, pedestrian/bicycle paths, wilderness areas,

or other similar public land within the county which is under the control, operation, or management of the county park and recreation authorities;

- (D) A fire department
- (E) An entertainment business which is oriented primarily towards children or family entertainment; or
- (F) A licensed premises, licensed pursuant to the alcoholic beverage control regulations of the State.

Section 3. Proximity to Existing Sexually Oriented Business.

No person shall cause or permit the operation, establishment, substantial enlargement, or transfer of ownership or control of a sexually oriented business within 1500 feet of another sexually oriented business.

Section 4. Highway.

No person shall cause or permit the operation or establishment of a sexually oriented business on any road in Watauga County other than a federal aid primary system highway as designated by the federal government.

Section 5. Existing Sexually Oriented Business

No person shall cause or permit the operation, establishment, or maintenance of more than one sexually oriented business in the same building, structure, or portion thereof, or the increase of floor area of any sexually oriented business in any building, structure, or portion thereof containing another sexually oriented business.

Section 6. Measurement to Property Line.

For the purpose of [Section 2](#) of this Article, measurement shall be made in a straight line, without regard to the intervening structures or objects, from the nearest portion of the building or structure used as the part of the premises where a sexually oriented business is conducted, to the nearest property line of the premises of a use listed in [Section 2](#). Presence of a city, county or other political subdivision boundary shall be irrelevant for purposes of calculating and applying the distance requirements of this Section.

Section 7. Measurement to Structure.

For purposes of [Section 1](#) & [3](#) of this Article, the distance between a residence and a sexually oriented business or between two sexually oriented businesses

shall be measured in a straight line, without regard to the intervening structures or objects or political boundaries, from the closest exterior wall of the structure in which each residence or business is located.

Section 8. Applicably to Other Ordinances.

Nothing herein is intended to or shall be construed to preempt, modify, or repeal any other land use regulation applicable to any property or its use in the County, but instead this Ordinance is intended to and shall be in addition thereto.

Article XII Additional Regulations For Adult Motels

Section 1. Adult Motel.

Evidence that a sleeping room in a hotel, motel, or a similar commercial establishments has been rented and vacated two or more times in a period of time that is less than ten (10) hours creates a rebuttable presumption that the establishment is an adult motel as that term is defined in this ordinance.

Section 2. Penalties.

A person shall be subject to civil penalties or other appropriate remedies if, as the person in control of a sleeping room in a hotel, motel, or similar commercial establishment that does not have a sexually oriented license, he rents or sub-rents a sleeping room to a person and, within ten (10) hours from the time the room is rented, he rents or sub-rents the same sleeping room again.

Section 3. Word Interpretation.

For purposes of Section 2 of this Article, the terms "rent" or "sub-rent" mean the act of permitting a room to be occupied for any form of consideration.

Article XIII Regulation Pertaining To Exhibition of Sexually Explicit Films, Videos or Live Entertainment

Section 1. Requirements.

A person who operates or causes to be operated a sexually oriented business, other than an adult motel, which exhibits on the premises in a viewing room of less than one hundred fifty (150) square feet of floor space, a film, video cassette, live entertainment, or other video reproduction which depicts specified sexual activities or specified anatomical areas, shall comply with the following requirements:

- (A) Upon application for a sexually oriented business license, the application shall be accompanied by a diagram of the premises showing a plan thereof specifying the location of one or more manager's stations and the location of all overhead lighting fixtures and designating any portion of the premises in which patrons will not be permitted. A manager's station may not exceed thirty-two (32) square feet of floor area. The diagram shall also designate the place at which the permit will be conspicuously posted, if granted. A professionally prepared diagram in the nature of an engineer's or architect's blueprint shall not be required; however, each diagram should be oriented to the north or to some designated street or object and should be drawn to a designated scale or with marked dimensions sufficient to show the various internal dimensions of all areas of the interior of the premises to an accuracy of plus or minus six (6") inches. The County may waive the foregoing diagram for renewal applications if the applicant adopts a diagram that was previously submitted and certifies that the configuration of the premises has not been altered since it was prepared.
- (B) The application shall be sworn to be true and correct by the applicant.
- (C) No alteration in the configuration or location of a manager's station may be made without the prior approval of the County.
- (D) It is the duty of the licensee of the premises to ensure that at least one licensed employee is on duty and situated in each manager's station at all times that any patron is present inside the premises.
- (E) The interior of the premises shall be configured in such a manner that there is an unobstructed view from a manager's station of every area of the premises to which any patron is permitted access for any purpose, excluding restrooms. Restrooms may not contain video reproduction equipment. If the premises has two or more manager's stations designated, then the interior of the premises shall be configured in such a manner that there is an unobstructed view of each area of the premises to which any patron is permitted access for any purpose from at least one of the manager's stations. The view required in this subsection must be by direct line of sight from the manager's station.
- (F) It shall be the duty of the licensee to ensure that the view area specified in (E) remains unobstructed by any doors, curtains, partitions, walls, merchandise, display racks or other materials and, at all times, to ensure that no patron is permitted access to any area of the premises which has been designated as an area in which patrons will not be permitted in the application filed pursuant to [\(A\)](#).
- (G) No viewing room may be occupied by more than one person at any time.

- (H) Regardless of the square footage of the premises or any section thereof, each sexually oriented business other than an adult motel shall be equipped with overhead lighting fixtures of sufficient intensity to illuminate every place to which patrons are permitted access at an illumination of not less than five (5.0) foot-candles as measured at the floor level.
- (I) No licensee shall allow openings of any kind to exist between viewing rooms or booths.
- (J) No person shall make or attempt to make an opening of any kind between viewing booths or rooms.
- (K) The licensee shall, during each business day, regularly inspect the walls between the viewing booths to determine if any openings or holes exist.
- (L) The licensee shall cause all floor coverings in viewing booths to be nonporous, easily cleanable surfaces, with no rugs or carpeting.
- (M) The licensee shall cause all wall surfaces and ceiling surfaces in viewing booths to be constructed of, or permanently covered by, nonporous, easily cleanable material. No wood, plywood, composition board or other porous material shall be used within forty eight (48") inches of the floor.

Section 2. Maintenance.

It shall be the duty of the licensee to ensure that the illumination described above is maintained at all times that any patron is present in the premises.

Section 3. Penalties.

A person having a duty under Section 1 or 2 above shall be subject to civil penalties or other appropriate remedies if he knowingly fails to fulfill that duty.

Article XIV Additional Regulations

Section 1. For Escort Agencies.

- (A) An escort agency shall not employ any person under the age of 21 years.
- (B) A person commits an offense if the person acts as an escort or agrees to act as an escort for any person under the age of 21 years.

Section 2. For Nude Model Studios.

- (A) A nude model studio shall not employ any person under the age of 21 years.

- (B) A person under the age of 21 years commits an offense if the person appears semi-nude or in a state of nudity in or on the premises of a nude model studio. It is a defense to prosecution under this subsection if the person under 21 years was in a restroom not open to public view or visible to any other person.
- (C) A person commits an offense if the person appears in a state of nudity, or knowingly allows another to appear in a state of nudity in an area of a nude model studio premises which can be viewed from the public right of way.
- (D) A nude model studio shall not place or permit a bed, sofa, or mattress in any room on the premises, except that a sofa may be placed in a reception room open to the public.

Section 3. Concerning Public Nudity.

- (A) It shall be a violation for a person who knowingly and intentionally, in a sexually oriented business, appears in a state of nudity or depicts specified sexual activities.
- (B) It shall be a violation for a person who knowingly or intentionally in a sexually oriented business appears in a semi-nude condition unless the person is an employee who, while semi-nude, shall be at least ten (10) feet from any patron or customer and on a stage at least two feet from the floor.
- (C) It shall be a violation for an employee, while semi-nude in a sexually oriented business, to solicit any pay or gratuity from any patron or customer or for any patron or customer to pay or give any gratuity to any employee, while said employee is semi-nude in a sexually oriented business.
- (D) It shall be a violation for an employee, while semi-nude, to touch a customer or the clothing of a customer.

Article XVII Prohibition Against Youth in a Sexually Oriented Business

A person commits a misdemeanor if the person allows a person under the age of 21 years on the premises of a sexually oriented business.

Article XVIII Prohibition Of Sale or Consumption of Alcohol

Sale or consumption of alcohol on the premises of sexually oriented business shall be prohibited. Violations shall be a misdemeanor.

Article XIX Exterior Portions of Sexually Oriented Businesses

Section 1. Visibility.

It shall be unlawful for an owner or operator of a sexually oriented business to allow the merchandise or activities of the establishment to be visible from a point outside the establishment.

Section 2. Exterior Appearance.

Except as permitted by Article XIX, it shall be unlawful for the owner or operator of a sexually oriented business to allow the exterior portion of the sexually oriented business to have flashing lights, or any words, lettering, photographs, silhouettes, drawings, or pictorial representations of any manner.

Section 3. Parking

One (1) parking space per one hundred (100) square feet of gross floor area shall be provided upon the premises immediately adjoining the structure housing the sexually oriented business.

- (A) Parking spaces shall be not less than nine (9) feet in width and eighteen (18) feet in length.
- (B) Aisle width between rows of parking spaces shall be not less than twelve (12) feet in width (to accommodate maneuvering and one-way traffic) where angled parking spaces are used and not less than twenty-four (24) feet (to accommodate maneuvering and two-way traffic) where perpendicular parking spaces are used.
- (C) Handicapped parking spaces shall be provided in accordance with the North Carolina State Building Code.

Section 4. Lighting.

All parking areas and exterior entrance/exits shall be fully illuminated with night-lighting to deter criminal activities.

Section 5. Buffering.

Perimeter buffer areas shall be established in order to create spatial separation and to lessen the possible adverse impacts upon adjacent land uses.

- (A) Side and rear yard setbacks of thirty (30) feet shall be observed for buildings or parking. This area is to be used as a buffer and shall be landscaped as follows. Buffers shall consist of planting of evergreen

and/or deciduous trees spaced no **more less** than thirty (30) feet apart. Such trees shall be at least six (6) feet high and one (1") inch caliper (trunk diameter at chest height) at time of planting and shall reach a height of no less than twenty (20) feet at maturity. In addition, plantings of low growing shrubs, and/or trees shall be placed at ten (10) foot intervals. Plantings within buffer zones shall be staggered unless topography is prohibitive. No planting shall be placed in the road right-of-way. Lists of recommended plantings are available from the Planning and Inspection Department.

(B) Walls, fences, earthen berms, or other natural features may be used in combination with ~~or in lieu of~~ planted buffers if approved by County Official. Considerations include but are not limited to:

(1) Any existing significant vegetation within the buffer(s) may be preserved and credited towards meeting the standard for the required buffer. Existing fences, berms, and/or walls within the buffer(s) may be used to fulfill the standards set forth for the buffer providing these elements are healthy and in a condition of good repair. Chain link fencing is not acceptable in meeting the performance criteria of this ordinance.

(2) Installation of supplemental vegetation and/or site features may be required if existing vegetation and/or site features within the buffer do not meet or exceed the requirements of this ordinance.

(C) The recipient of any Sexually Oriented Business permit, or their successor, shall be responsible for maintaining all common areas, improvements, or facilities required by the ordinance or any permit issued in accordance with its provisions, except those areas, improvements, or facilities with respect to which an offer of dedication to the public has been accepted by the appropriate public authority. As illustrations, and without limiting the generality of the foregoing, this means that private roads and parking areas, water and sewer lines, and recreational facilities must be properly maintained so that they can be used in the manner intended, and required vegetation and trees used for screening, landscaping, or shading must be replaced if they die or are destroyed.

Section 6. Maintenance

The sexually oriented business licensee shall be responsible for proper maintenance of parking and buffer areas required by this ordinance.

Section 7. Penalties.

Any violation of this Section shall be a misdemeanor.

Article XX Signage

No owner or operator of any sexually oriented business or any other person shall erect, construct, or maintain any sign for the sexually oriented business other than as permitted in the sign regulations of Watauga County.

Primary signs shall contain no photographs, silhouettes, drawings, or pictorial representations in any manner, and may contain only the name of the enterprise.

Article XXI Hours of Operation

No sexually oriented business, except for an adult motel, may remain open at any time between the hours of eleven o'clock (11:00) P.M. and eight o'clock (8:00) A.M. on weekdays and Saturdays, or during the period from eleven o'clock (11:00) P.M. Saturday until eight o'clock (8:00) A.M. Monday.

Article XXII Exemptions

It is a defense to prosecution under [Article XIV Section 2](#) that a person appearing in a state of nudity did so in a modeling class operated:

- (A) by a proprietary school, licensed by the State of North Carolina; a college, junior college, or university supported entirely or partly by taxation;
- (B) by a private college or university which maintains and operates educational programs in which credits are transferable to a college, junior college, or university supported entirely or partly by taxation; or
- (C) in a structure:
 - (1) which has no sign visible from the exterior of the structure and no other advertising that indicates a nude person is available for viewing; and
 - (2) where, in order to participate in a class a student must enroll at least three (3) days in advance of the class; and
 - (3) where no more than one nude model is on the premises at any one time.

Article XXIII Injunction

A person who operates or causes to be operated a sexually oriented business without a valid license or in violation of this chapter is subject to a suit for injunction as well as civil penalties of \$100.00. Each day any such violation continues or occurs in is a separate offense or violation.

Notwithstanding the foregoing, licensing decisions including issuance, revocation, and suspension, based upon violations of this chapter, shall be made by the County Official based upon a preponderance of the evidence.

CHAPTER 16 SIGNS

Article I Purpose and Legislative Intent

The purpose of this chapter is to provide for the public health, safety and welfare pursuant to the general ordinance authority granted to counties by the General Assembly of North Carolina. (NCGS §153A-121 *et seq.* and other pertinent statutes and amendments thereto). By enacting this chapter, it is the County's intent to:

- (A)** To promote the creation of an attractive visual environment that promotes a healthy economy by:
 - (1)** Permitting businesses to inform, identify, and communicate effectively; and
 - (2)** Directing the general public through the use of signs while maintaining attractive and harmonious application of signs on buildings and sites.
- (B)** To protect and enhance the physical appearance of the community in a lawful manner that recognizes the rights of property owners by:
 - (1)** Encouraging the appropriate design, scale, and placement of signs.
 - (2)** Encouraging the orderly placement of signs on buildings while avoiding regulations that are so rigid and inflexible that all signs in a series are monotonously uniform.
 - (3)** Assuring that the information displayed on a sign is clearly visible, conspicuous, legible and readable so that the sign achieves the intended purpose.
- (C)** To foster public safety along public and private streets within the community by assuring that all signs are in safe and appropriate locations.
- (D)** To have administrative review procedures that is the minimum necessary to:
 - (1)** Balance the community's objectives and regulatory requirements with the reasonable advertising and way finding needs of businesses.
 - (2)** Allow for consistent enforcement of the Sign regulations.
 - (3)** Minimize the time required to review a sign application.
 - (4)** Provide flexibility as to the number and placement of signs so the regulations are more responsive to business needs while maintaining the community's standards.

Article II Sign Review Procedures.

- (A) A sign permit shall be required for all permanent signage.
- (B) A sign permit shall be required for all temporary signage permitted under Article IV Section 6, except no permit is required for Article IV Section 6(C) and (D).
- ~~(C) All sign permit applications shall be reviewed for compliance with these regulations and the North Carolina State Building Code within 10 business days from the time a completed application has been accepted by the Administrator.~~
- (D) All appeals and variances regarding the sign ordinance regulations shall be heard by the Board of Adjustment in accordance with Watauga County's Planning & Development Ordinance [Chapter 3](#) Board of Adjustment.

Article III Sign Regulations

Section 1. Exempt from these Regulations.

The following shall be exempt from regulation under this Ordinance:

- (A) Government Signs.
- (B) Works of Art.
- (C) Holiday Decorations, when displayed during the appropriate time of the year.
- (D) Flags, except feather flags.
- (E) Building Identification Signs
- (F) Directional sign as defined in the NC Dept of Transportation Outdoor Advertising Manual Rule .0201(10)(a)(b)(c) and less than 6 feet above finished grade.
- (G) Political and Farm signs in accordance with NCGS §136-32.
- (H) Fence Wraps in accordance with NCGS §160D-908.

Section 2. Prohibited Signs.

The following signs are prohibited in the County:

- (A) Abandoned Signs.
- (B) Animated Signs.
- (C) Roof Signs.
- (D) Signs containing any words or symbols that would cause confusion because of their resemblance to highway traffic control or direction signals.
- (E) Signs located on trees, utility poles, public benches or any other form of public property or within any public right-of-way unless explicitly permitted by the regulations.

- (F) Off-Premises temporary signs, other than those explicitly permitted by [Article IV Section 6](#).
- (G) Any signs placed on public property without consent or placed in violation of local, state, or federal requirements.
- (H) Signs containing words or graphics that are obscene as defined by NCGS §14-190.1.
- (I) Vehicle Signs.

Article IV Development Standards

Section 1. Wall Signs.

- (A) The basic allowance for wall signs shall be limited to 1.5 square feet of sign area for each lineal foot of building or tenant frontage.
- (B) Each tenant may have multiple wall signs as long as the total wall sign area does not exceed the basic allowance established for wall signs.
- (C) The wall sign or signs shall not be greater than 80% of the length of the tenant space or the length of the building frontage for single tenant buildings.
- (D) The area of any wall sign may be increased by 25% when the building is setback at least 200 feet from the public right-of-way.
- (E) Additional wall sign area is permitted for a secondary frontage (see Definitions) which shall be equal to 100% of the primary sign area allowance.
- (F) The following additional wall signs may be permitted:
 - (1) Projecting Signs - In addition to the allowances for wall signs, projecting signs are permitted when designed and placed for the purpose of identifying the businesses for a pedestrian walking along the same side of the street as the business they seek or under a continuous rain canopy projecting from the building. Projecting signs shall have a maximum area of 16 square feet; the bottom of the sign shall be a minimum of 8 feet above the sidewalk; the sign shall not project more than 4 feet from the wall; and adjacent projecting signs shall not be closer than 20 feet.
 - (2) Building Directory – In addition to the allowances for wall signs, a directory sign may be permitted up to a maximum of 16 square feet for the purpose of identifying first floor tenants that do not have outside building frontage or upper floor tenants.
- (G) Additional Wall Signs for Multiple Story Buildings – An additional building sign is permitted on each of the building’s primary and secondary frontages according to the following:

- (1) For a building with two floors, the area of any wall sign may be increased by 25% for each eligible wall.
- (2) This additional permitted sign area may be increased by 10% for each additional building floor.
- (3) The sign must be placed at the height for which the bonus has been granted.

Section 2. Freestanding signs.

- (A) One freestanding sign is permitted for each 200 feet of primary road frontage with a maximum of 3 freestanding signs per parcel.
- (B) The permitted area of each freestanding sign shall not exceed 50 square feet except for: Properties entitled to more than one freestanding sign based on primary frontage. In this instance the sign area of a single sign may be increased to a maximum area of 100 or 150 square feet in lieu of erecting a second or third sign.
- (C) No portion of a freestanding sign shall be in, or project over, the public right-of-way.
- (D) The maximum height of a freestanding sign shall be 35 feet in height above the road grade or natural grade level, whichever is higher.

Section 3. On-Premise Electronic Message Center/Changeable Copy Signs.

- (A) Changeable copy by non-electronic means may be utilized on any permitted sign.
- (B) Only one EMC sign is permitted on each road on which the development fronts.
- (C) EMCs may not contain or display flashing, intermittent, or moving lights, including animated or scrolling advertising.
- (D) EMCs are permitted provided that the copy does not change more than once every 8 seconds.
- (E) Copy changes must be accomplished within a one second interval.
- (F) EMCs are required to have automatic dimming capability that adjusts the brightness to the ambient light at all times of the day and night.
- (G) EMCs may not exceed 50% of the total sign area.

Section 4. Instructional signs.

On-premises instructional signs shall be permitted in addition to all other signs when they are of such size and location that satisfy the intended instructional purpose and based on their size, location, and intended purpose will not constitute additional advertising. Instructional signs may include the name of the establishment and logos.

Section 5. Window Signs.

Permanent window signs shall not exceed 25% of the area of a window and the total area of all window signs, including both permanent and temporary, shall not exceed 50% of the window area.

Section 6. Temporary Signs.

- (A) Temporary signs related to Special Events are allowed on private property for a time period not to exceed 30 days. Such signs are permitted on and off-premises.
- (B) Temporary signs related to a single event for commercial enterprises are allowed on private property for a time period not to exceed 30 days, with a limit of 4 events per calendar year. Such signs are permitted on-premises only.
- (C) Temporary Political signs containing any message are allowed on private property during an election period subject to the area limitations stated herein. An election period begins on the 30th day before the beginning date of one-stop early voting and ends ten days after any election conducted under federal, state, county, or city laws or ordinances in which residents of Watauga are entitled to vote, including elections or votes regarding selection or recall of any federal, state, county or city officials, any ballot questions, referendum, constitutional amendments, or advisory vote.
- (D) Temporary signs located on property offered for sale or lease are allowed for time periods exceeding those listed herein provided such signs are promptly removed following the sale or lease closing date. All signs are subject to the area limitations stated in this Section.
- (E) Temporary construction signs located on property for which a building permit has been issued may remain throughout construction but shall be removed upon issuance of certificate of occupancy. There shall be no more than one (1) sign per construction site.
- (F) ~~Temporary directional signs are allowed off-premises for a time period not to exceed 60 days as a navigational aid to a special event.~~
- (G) Temporary sign(s) located in residential subdivisions may not exceed a total area of 16 square feet per parcel.
- (H) Temporary sign(s) located in areas other than residential subdivisions may not exceed a total area of 32 square feet per parcel.
- (I) No temporary signs may be illuminated.
- (J) All temporary signs must be secured to prevent them from becoming a hazard to pedestrians, vehicles or adjacent property during high winds.

Section 7. Highway Signs.

- (A)** Highway signs shall not exceed 200 square feet in area. This square footage includes both sign face and border.
- (B)** Highway signs shall:
 - (1)** Be located outside the right-of-way of all roads, or 35 feet from the center line if there is no recorded right-of-way, provided that on corner lots no part of a highway sign may be located within a triangular area formed by the street right-of-way lines and a line connecting them at points 70 feet from the right-of-way intersection.
 - (2)** Be located only in "Unzoned Commercial Areas" as defined in the North Carolina DOT Outdoor Advertising Manual. Highway signs shall be spaced at least 500 feet apart. Both sides of the road shall be included in this spacing. This paragraph shall be applicable on all streets/roads in Watauga County which are not within the jurisdiction of a municipality.
 - (3)** Be located not closer than 100 feet to a pre-existing residential structure on an adjoining lot. This does not prevent the owner of a residence from placing a highway sign on the same lot as the residence provided that the placement of such sign complies with subparagraph "b" above.
 - (4)** Be located not closer than 15 feet to a property line.
 - (5)** Not exceed 35 feet in height above the street/road grade level.
 - (6)** Not exceed a width of 30 feet.
 - (7)** Be located in such a way that they maintain horizontal and vertical clearance of all overhead electrical conductors in accordance with the National Electric Code and local electric utilities' requirements.
 - (8)** Be located only on primary highway systems (i.e. 105, 221, 321, and 421) with evidence of NCDOT approval.
 - (9)** Not be located on designated scenic byways.
- (C)** No existing highway sign may be converted to, or replaced with, an EMC billboard.
- (D)** No new locations for automatic changeable face billboards shall be permitted.
- (E)** Side-by-side signs shall be prohibited.
- (F)** Only one highway sign shall be permitted per parcel.

Article V Measurement Standards

Section 1. Determining Sign Area and Dimensions.

- (A) For a wall sign which is framed, outlined, painted or otherwise prepared and intended to provide a background for a sign display, the area and dimensions shall include the entire portion within such background or frame.
- (B) For a wall sign comprised of individual letters, figures or elements on a wall or similar surface of the building or structure, the area and dimensions of the sign shall encompass a regular geometric shape (rectangle, circle, trapezoid, triangle, etc.), or a combination of regular geometric shapes, which form, or approximate, the perimeter of all elements in the display, the frame, and any applied background that is not part of the architecture of the building.
- (C) When separate elements are organized to form a single sign, but are separated by open space, the sign area and dimensions shall be calculated by determining the geometric form, or combination of forms, which comprises all of the display areas, including the space between different elements.
- (D) Minor appendages to a particular regular shape, as determined by the Ordinance Administrator, shall not be included in the total area of a sign.
- (E) For a freestanding sign, the sign area shall include the frame, if any, but shall not include:
 - (1) A pole or other structural support unless such pole or structural support is internally illuminated or otherwise so designed to constitute a display device, or a part of a display device.
 - (2) Architectural features that are either part of the building or part of a freestanding structure, and not an integral part of the sign, and which may consist of landscaping, building or structural forms complementing the site in general.
- (F) When two identical sign faces are placed back to back so that both faces cannot be viewed from any point at the same time, and are part of the same sign structure, the sign area shall be computed as the measurement of one of the two faces. When the sign has more than two display surfaces, the area of the sign shall be the area of largest display surfaces that are visible from any single direction.
- (G) In the event of a dispute in determining the area or dimensions of any sign, a negative decision of the Ordinance Administrator may be appealed to the Board of Adjustment.

Section 2. Determining Sign Height.

- (A) The height of a freestanding sign shall be measured from the base of the sign or supportive structure at its point of attachment to the ground, to the highest point of the sign. A freestanding sign on a man-made base, including a graded earth mound, shall be measured from the grade of the nearest pavement or top of any pavement curb.
- (B) Clearance for freestanding and projecting signs shall be measured as the smallest vertical distance between finished grade and the lowest point of the sign, including any framework or other embellishments.

Section 3. Determining Building Frontages and Frontage Lengths.

- (A) Building Unit - The building unit is equivalent to the tenant space. The frontage of the tenant space on the first floor shall be the basis for determining the permissible sign area for wall signs.
- (B) Primary and Secondary Frontage - The frontage of any building unit shall include the elevation(s) facing a public street, facing a primary parking area for the building or tenants, or containing the public entrance(s) to the building or building units.
 - (1) The primary frontage shall be considered the portion of any frontage containing the primary public entrance(s) to the building or building units.
 - (2) The secondary frontage shall include those frontages containing secondary public entrances to the building or building units, and all building walls facing a public street or primary parking area that are not designated as the primary building frontage by subsection (A) above.

Section 4 . Length of Building Frontage.

- (A) The length of any primary or secondary building frontage as defined in Watauga County's Planning & Development Ordinance [Chapter 7](#) Definitions, shall be the sum of all wall lengths parallel, or nearly parallel, to such frontage, excluding any such wall length determined by the Administrator as clearly unrelated to the frontage criteria.
- (B) For buildings with two or more frontages, the length of the wall and allowable sign area shall be calculated separately for each such building frontage.
- (C) The building frontage for a building unit shall be measured from the centerline of the party walls defining the building unit.

Article VI Non-Conforming Signs

Section 1. General Provisions.

- (A) Nonconforming signs shall be maintained in good condition pursuant to Article VII.
- (B) A Nonconforming sign shall not be altered, modified or reconstructed except:
 - (1) When such alteration, modification or reconstruction would bring such sign into conformity with these regulations;
 - (2) When the existing use has new ownership which results in a change in the name or logo of the use or business on the property, and such change complies with subsection (4) below;
 - (3) When the space is re-occupied by a similar use and the new occupant requires no external building or site renovation, and such change complies with subsection (4) below;
 - (4) Any alteration, modification or reconstruction permitted in this section shall be limited to the replacement of a sign panel, replacing individual letters and logos within the same area or repainting a sign face, and does not permit changes to the structure, framing, erection or relocation of the sign unless such changes conform to subsection (1) above.
- (C) Nonconforming highway signs for which there is in effect a valid NCDOT permit may be repaired or reconstructed without limitation so long as the square footage of the sign face is not increased.
- (D) A nonconforming sign shall be removed upon verification that the use to which such non-conforming sign refers has been abandoned for more than 180 consecutive days.

Article VII Supplemental Considerations

Section 1. Construction Standards.

The construction, erection, safety and maintenance of all signs shall comply with the North Carolina State Building Code and all of the following:

- (A) Signs shall be structurally sound and located so as to pose no reasonable threat to pedestrian or vehicular traffic.
- (B) All permanent freestanding signs shall have self-supporting structures erected on, or permanently attached to, concrete foundations.
- (C) If possible, signs should not be in locations that obscure architectural features such as pilasters, arches, windows, cornices, etc.
- (D) Signs shall not be in locations that interfere with safe vehicular and pedestrian circulation or public safety signals and signs.

- (E) No signs shall be erected, constructed or maintained so as to obstruct any fire escape, required exit, window, or door opening used as a means of egress.
- (F) Signs shall be structurally designed in compliance with ANSI and ASCI standards. All electric signs shall be constructed according to the technical standards of UL or other certified testing laboratory.
- (G) Signs may be illuminated – by external or internal means -- provided that:
 - (1) The brightness and intensity shall not be greater than necessary to meet reasonable needs of the business or use served;
 - (2) Light sources shall be shielded from all adjacent buildings and streets; and
 - (3) The lighting shall not create excessive glare to pedestrians and/or motorists, and will not obstruct traffic control or any other public informational signs.

Section 2. Maintenance.

- (A) All signs shall be maintained in accordance with the following:
- (B) The property owner shall maintain signs in a condition appropriate to the intended use and to all County standards.
- (C) The property owner has a continuing obligation to comply with all building code requirements.
- (D) If the sign is deemed by the Ordinance Administrator to be in an unsafe condition, the owner of the business shall be immediately notified in writing, and shall, within 48 hours of receipt of such notification, respond to the county with a plan to correct the unsafe condition, remove the unsafe sign, or cause it to be removed. If after 30 days, the unsafe condition has not been corrected through repair or removal, the Ordinance Administrator may cause the repair or removal of such sign, at the expense of the property owner or lessee. If the total costs are not paid in full within 60 days of the repairs or removal, the amount owed shall be certified as an assessment against the property of the sign owner, and lien upon that property, together with an additional 10 percent penalty for collection as prescribed for unpaid real estate taxes.
- (E) In cases of emergency, the Ordinance Administrator may cause the immediate removal of a dangerous or defective sign without notice.
- (F) Whenever any sign, either conforming or nonconforming to these regulations, is required to be removed for the purpose of repair, re-lettering or repainting, the same may be done without a permit or without any payment of fees provided that all of the following conditions are met:

- (1) There is no alteration or remodeling to the structure or the mounting of the sign itself;
- (2) There is no enlargement or increase in any of the dimensions of the sign or its structure; and
- (3) The sign is accessory to a legally permitted or nonconforming use.

Article VIII Jurisdiction

The provisions of this chapter shall be applicable only to unincorporated areas of Watauga County which are not included in the extraterritorial jurisdiction of a municipality. The Valle Crucis Historic District and Foscoe-Grandfather Community have additional regulations concerning allowable signage.

CHAPTER 17 STRUCTURES LOCATED ON LAND ADJACENT TO NATIONAL PARK SERVICE LAND

WHEREAS, the Board of Commissioners are concerned with protecting National Parks Service Lands from encroachment which could damage the unique scenic importance of such lands; and

WHEREAS, the economy of Watauga County is partially dependent upon maintaining the quality of such scenic lands; and

WHEREAS, the Board of Commissioners are authorized to enact ordinances to promote the general welfare generally by N.C.G.S. 153A-121 and specifically to regulate the location of buildings, structures, etc. by N.C.G.S. 160D;

NOW, THEREFORE, the Watauga County Board of Commissioners do enact the following:

Article I Regulation of Location of Structures

No building or structure which is located upon land which is adjacent to National Park Service Land shall be located closer than fifteen (15) feet to the Park Service property line.

Article II Permit

Prior to issuance of a building permit for structure(s) located upon land adjacent to National Park Service Land, National Park Service personnel, upon notification by the County Department of Planning and Inspection, shall determine said property line and shall establish the required fifteen(15) foot setbacks within fifteen(15) days of the application for a building permit.

Article III Jurisdiction and Effective Date

This chapter shall be applicable within all areas of Watauga County not within the jurisdiction of a municipality and shall be effective upon enactment.

CHAPTER 18 SUBDIVISION, PLANNED UNIT DEVELOPMENT AND MULTI-UNIT STRUCTURES

Article I Title

This chapter is known and may be cited as the Subdivisions, Planned Unit Development and Multi-Unit Structures Regulations for Watauga County, North Carolina

Article II Authority and Enactment Clause

The County Commissioners of the County of Watauga, pursuant to the authority conferred by Chapter 160D, Article 8, of the General Statutes of the State of North Carolina, do hereby enact into law these Articles and Sections.

Article III Jurisdiction and Purpose

Section 1. Jurisdiction

On and after the date of adoption, these regulations shall govern each and every subdivision of land, **planned unit development** and/or multi-unit structure within Watauga County (hereinafter referred to as the "County") and outside the jurisdiction of any incorporated municipality. However, this ordinance may also regulate territory within the subdivision regulation jurisdiction of any municipality whose governing body by resolution agrees to such regulation provided, however, that any such municipal governing body may, upon written notice, withdraw its approval of these County Regulations, and those regulations shall not have further effect within the municipality's jurisdiction 30 days after the day the County receives the written notice. (N.C.G.S. 153A-122)

Section 2. Purpose

The purpose of these subdivision regulations is to guide and regulate the subdivision of land, **planned unit development** and/or multi-unit structures within the county in order to preserve the public health, safety, and welfare. The regulations included herein are designed to insure an adequately planned street system and to avoid hazardous conditions; to avoid overcrowding of the land and extreme concentration of population; to secure safety from fire, panic, and other dangers; to provide for adequate water and sewage systems, schools, parks and playgrounds; to insure against flood damage and soil erosion; to facilitate an orderly system for the design, layout, and use of the land; to insure the proper legal description and monumentation of subdivided land; and to provide for the re-subdivision of large land parcels.

Article IV Planning Board Review and Legal Status Provisions

Section 1. Planning Board Review and Approval.

Pursuant to N.C.G.S. 160D, Article 8 unless otherwise noted, no real property within the jurisdiction of this chapter shall be subdivided and offered for sale or a plat thereof recorded until a preliminary and final plat have been reviewed and approved by the Watauga County Planning Board as provided hereinafter. Plans of group developments for housing, commercial, industrial, or other uses, or for any combination of uses shall be submitted in the same manner as other plats for review by the Planning Board.

Section 2. Exemptions.

- (A) The combination or recombination of portions of previously subdivided and recorded lots where the total number of lots is not increased and the resultant lots are equal to or exceed the standards of the local government as shown in its subdivision regulations.
- (B) The division of land into parcels greater than 10 acres where no street right-of-way dedication is involved.
- (C) The public acquisition by purchase of strips of land for the widening or opening of streets or for public transportation system corridors.
- (D) The division of a tract in single ownership whose entire area is no greater than 2 acres into not more than three lots, where no street right-of-way dedication is involved and where the resultant lots are equal to or exceed the standards of the local government, as shown in its subdivision regulations.
- (E) The division of land solely among members of the same family, which shall include all lineal descendants or ancestors plus brothers, sisters, aunts, uncles, fathers-in-law, mothers-in-law, brothers-in-law, sisters-in-law, nieces, nephews and stepchildren by any method of transfer except where the parties contemplate development for resale, and where the resultant lots are equal to or exceed the standards of the county as shown in this chapter.
- (F) The division of a tract into parcels in accordance with the terms of a probated will or in accordance with intestate succession under Chapter 29 of the General Statutes.

Section 3. Building Permits.

Approval of the final plat by the Planning Board shall be required before issuance of any building permit for a structure to be erected in a subdivision, except in Planned Unit Developments, or up to two (2) may be issued in any

subdivision to the owner/developer only, when the owner is also the developer.

Section 4. Recording of Plats.

No subdivision plat of land within the County's jurisdiction shall be filed or recorded until it has been submitted to and approved by the Watauga County Planning Board or Staff, and until this approval is entered in writing on the face of the plat by the designated representative of the County Planning Board.

Section 5. Duty of Register of Deeds.

The Register of Deeds shall not file or record a plat of a subdivision of land located within the territorial jurisdiction of the County that has not been approved in accordance with these provisions, nor shall the Clerk of Superior Court order or direct the recording of a plat if the recording would be in conflict with this section. No subdivision plat of land within a Public Water Supply Watershed shall be filed or recorded by the Register of Deeds until it has been approved in accordance with the provisions of Watauga County's Watershed Protection regulations. Likewise, the Clerk of Superior Court shall not order or direct the recording of a plat if the recording of such plat would be in conflict with the watershed protection regulations.

Section 6. Relationship to Effective Changes in the Chapter.

It is not intended that this chapter will in any way repeal, annul, or interfere with any valid permits or approvals which were legally issued under previous ordinances for the use or development of land or structures. In addition, future changes in this chapter shall not repeal, annul, or interfere with any valid permits or approvals issued pursuant to this chapter prior to said changes. This provision shall include approved master plans for phased developments. If the density in the approved master plan is not increased, any plats and extensions thereof shall be subject to the regulations under which the original master plan was approved.

Article V Procedures For Review and Approval of Subdivisions

Section 1. Plat Required on Any Subdivision of Land.

Pursuant to N.C.G.S. 160D-803, a final plat shall be prepared, approved, and recorded pursuant to the provisions of this chapter whenever any subdivision of land takes place. Prior to recording, such plat shall be approved pursuant to Article V. To secure such approval, the subdivider shall follow the procedures established in this Article as applicable.

Section 2. Submission of Preliminary Plat.

- (A) A preliminary plat meeting the requirements of this ordinance shall be submitted for review and shall be approved by the Planning Board before any improvements or land disturbing activities are made in a subdivision. ~~One (1) copy of this plat, plus at least one-half plat fee shall be submitted to the Planning Staff at least two (2) weeks before the meeting of the Planning Board at which time it is to be reviewed. One week prior to the meeting and subsequent to staff review, an electronic version of the plat shall be provided to the Planning Staff; eight (8) full-size copies shall be submitted no later than 9:00 AM the day of the Planning Board meeting, unless deemed unnecessary by the Planning Staff.~~
- (B) A Developer Authorization Form ([Appendix M](#)) must accompany the Preliminary Plat application when the application is made by person(s) other than the land owner(s).
- (C) The Planning Staff shall provide that the following agencies be given an opportunity to make recommendations as appropriate concerning an individual subdivision plat before the plat is approved: AppHealthCare, Department of Transportation, County Board of Education, County Fire Marshal. The Planning Staff shall transmit copies of the plat to those agencies and others upon their request.
- (D) The Planning Board shall review the preliminary plat and identify any changes required in order that the subdivision may comply with the provisions of this ~~ordinance chapter~~. ~~The Planning Board shall take formal action on the preliminary plat at the first regular meeting date (Normally the 3rd Monday evening of each month) after receipt of the plat. Within five (5) days after its action on the plat, the Staff shall notify the subdivider by letter indicating the action taken.~~
- (E) After receiving approval of the preliminary plat by the Planning Board, ~~providing evidence of N.C.D.O.T. driveway connection permit and issuance of the grading permit~~ the erosion control plan by the staff (and not before that time), the subdivider may proceed to construct the proposed road and other improvements in accordance

with the requirements of this chapter and as shown on the approved preliminary plat.

- (A) Fees. The developer shall pay a review fee of an amount specified from time to time by the Watauga County Commissioners. At least half of said fee shall be paid at the time of submission of the preliminary plat (the fee shall be paid before the plat will be placed on the Planning Board meeting agenda); the remainder, if any, shall be paid at submission of the final plat.
- (B) For a planned unit development the developer shall pay a review fee at the rate provided above for each structure in the development. No fees are required for master plan review.

Section 3. Specifications for Preliminary Plat.

The preliminary plat shall be at a scale of one-hundred (100) feet to one (1) inch or larger and shall be on a sheet, 18" x 24". However, if the size and shape of the property is such that a sheet 18" x 24" will not accommodate the entire tract, a sheet not larger than 24" x 36" may be used, and in unusual circumstances may be at a scale of no smaller than 1"=200'. In addition, the developer shall provide an electronic version of the plat.

The following information shall be required as applicable:

- (A) A sketch vicinity map showing the relationship of the proposed subdivision with the surrounding area.
- (B) The location of existing property lines, streets, buildings, water courses, transmission lines, sewers, bridges, and water mains, city and county lines (if adjoining) and any public utility easements.
- (C) Boundaries of the tract shown with distances and approximate acreage.
- (D) Evidence of access right-of-way from state road.
- (E) Names of adjoining property owners and/or subdivisions.
- (F) Zoning classification, if any, both on the land to be subdivided and on adjoining land.
- (G) Proposed streets, street names, rights-of-way, roadway widths, approximate grades, curve radiuses, and proposed drainage facilities.
- (H) Other proposed rights-of-way or easements showing locations, widths and purposes.
- (I) Proposed lot lines, lot numbers, and approximate area. Statement that all lots will comply with the Subdivision Regulations.
- (J) Proposed minimum building set back lines.
- (K) Proposed utility layouts (sewer, water, electricity) showing connections to existing systems or plans for central water system or

package sewage system, or designation for individual water and sewage.

- (L) Proposed parks, open spaces, or any other public areas.
- (M) Name of owner, developer, engineer and registered surveyor.
- (N) Title, date, north point, and graphic scale.
- (O) Statement of intended use of the lots (single or multi-family).
- ~~(P) Evidence of N.C.D.O.T. driveway connection permit shall be submitted prior to commencement of construction.~~
- (Q) When an area covered in the plan includes or abuts a water area (stream, river or lake) the following additional information is required:
 - (1) Relationship with floodway and flood plain as delineated by the flood insurance rate maps.
 - (2) Any proposed dock lines beyond which no dock structure may be constructed.
 - (3) Methods of providing ingress and egress from uplands to water area.
 - (4) Names of the owners of the water area.
- ~~(R) A soil erosion control plan (3 copies) shall be submitted to the Planning Staff. Grading shall not commence until the erosion control plan is reviewed and approved by the Planning Staff and the Soil and Water Conservation District and a grading permit is issued. See Appendix B – D for further detail.~~
- (S) If road (s) are to be "county standard", the developer shall maintain the road(s) until such time as a property owners association assumes maintenance. Prior to final plat approval, the developer shall comply with Article VI, Section 2(A)(1) concerning recording of property owner's association road maintenance provisions.

Section 4. Minor Subdivisions.

- (A) Procedures set forth here for handling applications for approval of minor subdivisions are intended to simplify processing of routine small subdivisions with due regard to protection of the public interest.
- (B) For the purpose of these regulations, a minor subdivision is defined as any subdivision requiring no variances and consisting of not more than ten (10) lots. One phase of a phased development cannot be considered a minor subdivision unless the entire development is not more than 10 lots.
- (C) After January 1, 2006, all new divisions of land shall comply with all of the requirements of this ordinance, with the exception of the following: The division of one (1) lot or tract out of a larger tract will be allowed provided 1) the new lots meet the size, dimensional, and setback requirements of this or any applicable ordinance; 2) no public

street or road dedication or change in existing public streets or road is involved; 3) the original lot or tract was created prior to January 1, 2006 and is over ten (10) acres in size; or 4) if the original tract is less than ten (10) acres, it shall have been created prior to June 15, 1973, or be otherwise exempt from this ordinance; 5) only one (1) such division shall be allowed from the original tract without total compliance with this ordinance.

- (D)** The Watauga County Planning Staff shall review the preliminary plat of each minor subdivision and shall find that it either is or is not a minor subdivision and shall find that it either does or does not meet the requirements of this ordinance. Said findings shall be stated in writing and recorded in the records of the Planning Board. Based upon said findings the Staff shall either approve, not approve, or approve conditionally the proposed minor subdivision.
- (E)** ~~A decision by the Planning Staff shall be made within fifteen days of submission of the proposed minor subdivision to the Staff and~~ The decision of the Staff is subject to appeal by the subdivider to the Planning Board. ~~which must act on appeals at its next regular meeting.~~
- (F)** A final plat shall be submitted to the Watauga County Planning Staff for consideration and approval before the conveyance of any of the property or the recording of the plat.
- (G)** The County may require only a plat for recordation for the division of a tract or parcel of land in single ownership if all of the following criteria are met:

 - (1)** The tract or parcel to be divided is not exempted under [Article IV, Section 2](#). (i.e. no resultant tract is 10 acres or more)
 - (2)** No part of the tract or parcel to be divided has been divided under this subsection in the 10 years prior to division.
 - (3)** The entire area of the tract or parcel to be divided is greater than five acres.
 - (4)** After division, no more than three lots results from the division.
 - (5)** After the division, all resultant lots comply with all of the following:

 - a)** Any lot dimension size requirements of the applicable land-use regulations, if any.
 - b)** The use of the lots is in conformity with the applicable zoning requirements, if any.
 - c)** A permanent means of ingress and egress is recorded for each lot.

Section 5. Phased Developments.

If a developer proposes that a subdivision (including PUD's) will be constructed in phases, the following procedure shall apply.

- (A) A master plan showing the entire proposed subdivision and the phases of development, proposed density, proposed type and location of utilities, and proposed development timetable shall be submitted to the Planning Board for approval.
- (B) Each phase of development shall be preceded by submission and approval of a preliminary plat as outlined in Section 3 unless such plat submission is waived by the Planning Board. The master plan may be submitted prior to or simultaneously to submission of the preliminary plat for the first phase of development.
- (C) As each phase is completed, a final plat must be submitted and approved for that phase as outlined in Sections 6 and 7.
- ~~(D) Approval of the master plan need not be renewed unless density increases are proposed.~~

Section 6. Submission of Final Plat.

Unless a final plat is submitted to the Planning Board within eighteen (18) months from the date on which the preliminary plat was approved, such action on the preliminary plat shall become void and of no effect, and will necessitate the resubmission of the preliminary to the Planning Board for consideration, except in the case of preliminary plats for Multi-Phased Development shall be valid for seven years from the time of initial site plan approval. ~~Planned Unit Developments, which do not expire.~~ One (1) copy of this plat, plus plat fee, if any remains unpaid, shall be submitted to the Planning Staff at least two (2) weeks before the meeting of the Planning Board at which time it is to be reviewed. One week prior to the meeting and subsequent to staff review, one electronic copy shall be provided to the Planning Staff; eight (8) full size copies of the plat shall be submitted no later than 9:00 AM day of the Planning Board meeting. Roads and lots shall be clearly marked in the field upon submission of the final plat.

- (A) Final Plat. ~~The final plat shall be drawn on reproducible mylar.~~ The final plat shall constitute only that portion of the approved preliminary sketch plan which the subdivider proposes to record provided that such portion conforms to all requirements of this ordinance. All final plats shall be on sheets with overall measurements of 18" x 24" and shall be on a scale no smaller than 1" = 100'. ~~In addition, the developer shall provide one electronic version of the plat.~~

The final plat shall show as applicable:

- (1)** A sketch vicinity map showing the location of the subdivision in relation to the surrounding area.
- (2)** The right-of-way lines and easements of all streets and roads, and access right-of-way to state road.
- (3)** Lot lines and lot numbers showing bearings and distances, and lot sizes. All dimensions should be to the nearest one-hundredth (0.01) of a foot and angles to the nearest minute.
- (4)** Minimum building setback lines. (Show typical lot setback; not required on all lots.)
- (5)** Relationship with floodway and flood plain as delineated by the flood insurance maps.
- (6)** Sufficient data to determine readily and reproduce on the ground the location, bearing and length of every street line, lot line, boundary line, and block line whether curved or straight.
- (7)** Accurate location and description of all monuments and markers and block tie lines.
- (8)** The names and locations of adjoining subdivisions and streets, and the location and ownership of adjoining un-subdivided property, including water areas.
- (9)** Title, date, name, and location of subdivision, graphic scale, and true north point.
- (10)** Name of owner, developer, surveyor, engineer and land planner.
- (11)** Reservations for easements, and areas to be dedicated to public use or sites for other than residential use shall be shown on the plat with notes stating their purposes.
- (12)** One of the following statements:
 - a)** Drinking water source to be individual or shared wells (not a community or public water supply). Wastewater disposal method to be septic tanks. Individual lots have/have not been approved by App HealthCare for septic system.
 - b)** Drinking water source to be a public water supply (name system if to be connected to existing system, or indicate proposed new supply). Wastewater disposal method to be septic tanks. Individual lots have/have not been approved by AppHealthCare for septic system.
 - c)** Drinking water source to be a community water system (name system if to be connected to existing system, or indicate proposed new supply). Wastewater disposal method to be septic tanks. Individual lots have/have not been approved by AppHealthCare for septic system.
 - d)** Drinking water source to be individual or shared wells (not a community or public water system). Wastewater

disposal method to be NPDES sewer (name system if to be connected to existing system, or indicate proposed new system).

e) Drinking water source to be a public water supply (name system if to be connected to existing system, or indicate proposed new supply). Wastewater disposal method to be NPDES sewer (name system if to be connected to existing system, or indicate proposed new system).

f) Drinking water source to be a community water supply (name system if to be connected to existing system, or indicate proposed new supply). Wastewater disposal method to be NPDES sewer (name system if to be connected to existing system, or indicate proposed new system).

(13) Statement of intended use of the lots (single or multi-family).

(14) Location and size of culverts/ drainage facilities.

(15) Density in units per acre if PUD.

(16) Variances granted, if any.

(17) Reference shall be made on final plat to deed book and page number of recorded Restrictive Covenants and/or Road Maintenance Agreement.

(B) The following certificates shall be shown on the final plat as applicable:

(1) Certificate of Ownership and Dedication

I (We) hereby certify that I am (we are) the owner(s) of the property shown and described here on, that the property is within the regulatory jurisdiction of Watauga County, and that I (we) hereby adopt this plan of subdivision with my (our) free consent, establish all lots, and dedicate all streets, alleys, walks, parks, easements, right-of way, and other open spaces to public or private use as noted.

_____ DATE _____ OWNER

(2) Certificate of Accuracy

The undersigned surveyor, being duly sworn, deposes and says that the plat upon which this certificate appears was prepared in accordance with N.C.G.S.47-30 as amended, is in all respects correct according to the best of his knowledge and belief, and was prepared from an actual survey made by him on the _____ day of _____ 20____, with maximum _____ linear error of _____ closure of _____ and a maximum field error of angular closure of _____.

Pursuant to N.C.G.S. 47-30, the surveyor shall certify to one of the following.

- (a) That this survey creates a subdivision of land within the area of a county or municipality that has an ordinance that regulates parcels of land;
- (b) That this survey is located in a portion of a county or municipality that is unregulated as to an ordinance that regulates parcels of land;
- (c) Any one of the following:
 - i. That the survey is of an existing parcel or parcels of land and does not create a new street or change an existing street;
 - ii. That the survey is of an existing building or other structure, or natural feature, such as a watercourse; or
 - iii. That the survey is a control survey.
- (d) That this survey is of another category, such as the recombination of existing parcels, a court ordered survey, or other exception to the definition of subdivision;
- (e) That the information available to the surveyor is such that the surveyor is unable to make a determination to the best of the surveyor's professional ability as to provisions contained in (a) through (d) above.

(3) Certificate of the Approval of Water and Sewage System

I hereby certify that the water supply and sewage disposal utility system installed, or proposed for installation, in each lot of the subdivision entitled _____ fully meets the requirements of the undersigned agency(ies), and are hereby approved as shown.

DATE

APPHEALTHCARE

NC PUBLIC WATER SUPPLY SECTION

NC DEPT. OF ENVIRONMENTAL QUALITY

(4) Certification of the Approval of Streets and Utilities

hereby certify: (1) that streets, utilities and other improvements have been installed in an acceptable manner and according to County specifications in the subdivision entitled _____ or

(2) that a security guarantee in the amount of \$_____ or

cash in the amount of \$_____ has been posted with the county to assure completion of all required improvements in case of default.

DATE WATAUGA COUNTY AUTHORIZED REPRESENTATIVE

(5) Certificate of Approval of Recording.

I hereby certify that the subdivision plat shown hereon has been found to comply with the subdivision regulations of Watauga County, North Carolina, with the exception of such variances, if any, as are noted in the Minutes of the Planning Board and are recorded on the plat and that it has been approved by the Watauga County Planning Board at their regular meeting of _____ for recording in the office of the County Register of Deeds.

DATE WATAUGA COUNTY AUTHORIZED REPRESENTATIVE

(6) Certificate of Approval of Recording.

(watershed; can be combined with (5) or (10))

I certify that the plat shown here on complies with the Watershed Protection regulations and is approved by the Watauga County Planning Board or Staff (choose which is applicable) for recording in the Register of Deeds Office.

DATE WATAUGA COUNTY AUTHORIZED REPRESENTATIVE

NOTICE: This property is located within a Public Water Supply Watershed – development restrictions may apply.

(7) Certificate of Approval and Acceptance of Dedications

I, _____, the Authorized Representative of Watauga County, North Carolina, do certify that Watauga County approved of this plat or map and has accepted the dedication of the streets, easements, right-of-way, and public parks shown thereon, but assume no responsibility to open or maintain the same until, in the opinion of the governing body of Watauga County it is in the public interest to do so.

DATE WATAUGA COUNTY AUTHORIZED REPRESENTATIVE

(8) Certification of Approval of N.C.D.O.T Division of Highways

NCDOT DIVISION OF HIGHWAYS
PROPOSED SUBDIVISION ROAD

CONSTRUCTION STANDARDS CERTIFICATION

APPROVED _____

DISTRICT ENGINEER

DATE _____

(or as otherwise specified by D.O.T.)

(9) Certificate of Exemption

I hereby certify that the plat shown hereon is exempt from the Watauga County subdivision regulations pursuant to _____ of the Planning & Development Ordinance. No approval is required.

DATE WATAUGA COUNTY AUTHORIZED REPRESENTATIVE

(10) Certificate of Approval of Minor Subdivision

I hereby certify that the subdivision plat shown hereon has been found to comply with the subdivision regulations of Watauga County, North Carolina. It has been approved as a minor subdivision as defined in **Chapter 18 Article V Section 4** of the Planning & Development Ordinance for recording in the office of the County Register of Deeds.

DATE WATAUGA COUNTY AUTHORIZED REPRESENTATIVE

(NOTE: Authorized representatives shall be the Director of Planning and Inspections and Planner/Property Development Coordinator, and in their absence, the Chair and Vice Chair of the Planning Board.)

Section 7. Approval of Final Plat.

Upon receipt of the final plat, the Planning Board and Staff shall review it for compliance with the provisions of the ordinance. The Planning Board may approve the plat in whole or in part, or subject to modifications. ~~Failure of the Planning Board to take formal action on the final plat after receipt of the plat at least two (2) weeks prior to the regular meeting date (3rd Monday evening of each month) shall be deemed approval of submitted plat. (The regular meeting may be postponed, but for no more than one (1) week).~~ The approval of the final plat by the Planning Board shall be on the condition that such plat be recorded in the office of the Register of Deeds within **one (1) year ninety (90) days after such approval.** ~~The original tracing of the final shall be made available by the subdivider for authentication when the Planning Board takes final action approving the plat.~~

Section 8. Advisory Opinion.

A subdivider is encouraged to submit a sketch to the Planning Staff prior to submission of a preliminary plat if s/he wishes to ascertain the feasibility of development of his property.

Article VI General Requirements and Minimum Standards of Design

Section 1. General Requirements.

The subdivider shall observe the following general requirements and principles of land subdivision.

- (A) Suitability of Land. Land which has been determined by the Watauga County Planning Board on the basis of engineering and/or other studies prepared by licensed professionals to pose an ascertainable danger to life or property by reason of its unsuitability for the use proposed shall not be platted for that purpose, unless and until the subdivider has taken the necessary measures to correct said conditions and to eliminate said dangers.
- (1) Land subject to flooding may be considered unsuitable for building development. The decision by the Planning Board shall be based on flooding history of the area and survey information furnished by Federal Emergency Management Agency (FEMA) as delineated on the Watauga County Floodway Boundary and Flood Rate Insurance Maps. Subdivision developments shall comply with the Watauga County Flood Damage Prevention regulations.
 - (2) Generally, property which has a natural cross slope of fifty (50) percent or more is considered unfeasible for subdivision development. Any variance beyond a fifty (50) percent slope shall require the approval of the Planning Board. See Appendix H for method of defining average cross slope.
- (B) Conformity to Existing Plans. All proposed subdivisions shall conform to any adopted plans for the county and to any applicable regulations of any existing county zoning regulations. Whenever a tract to be subdivided embraces any part of a state maintained road, as designated on any officially adopted plan, such part of such public right-of-way shall be platted by the subdivider in the location and at the width indicated by said plan and provisions of this ordinance.
- (C) Driveway Connection Permit. A driveway connection permit issued by NC Department of Transportation shall be obtained. A Traffic Impact Analysis shall be required from the applicant under the following circumstances, unless the Planning **Staff Board** and NCDOT concur that one is unnecessary:
- (1) The development proposes to have access to any public road at a location where sight distance in any direction along the road is less than 500 feet; or
 - (2) The development proposes access onto a public road that does not have a paved width of at least 18 feet; or

- (3) The development proposes access to a public road with current NCDOT traffic counts that are 85% of capacity shown in the most recent Watauga County Comprehensive Transportation Plan and based upon ITE trip generation rates is projected to generate 1,500 or more weekday trips; or
- (4) The Planning **Staff Board** determines that the proposed project will have a potential negative impact on the public road system due to the size of the project or existing transportation system or determines that there are safety concerns with the driveway location and design. If a traffic impact analysis is performed and that analysis concludes that improvements are required to the transportation system, the applicant may be required to complete those improvements in connection with the project as a condition of issuing a permit. Unless an agreement is executed by the County in which the time for the improvement is specified, the improvement shall be completed prior to issuance of final plat approval.
- (D) Coordination and Continuation of Streets. The proposed street layout within a subdivision shall be coordinated with the existing street system of the surrounding area and where possible, existing principal streets shall be extended.
- (E) Access to Adjacent Properties. Where, in the opinion of the Planning Board it is necessary to provide for street access to an adjoining property, proposed streets shall be extended by dedication to the boundary of such property and a temporary turnaround shall be provided. This provision shall apply only to roads which will be state maintained (dedicated to the public).
- (F) Access Right-of-Way. Where a right-of-way, less than forty-five (45) feet, which provides access to property proposed for subdivision had been granted prior to June 15, 1973, and the developer presents proof in writing that s/he cannot feasibly obtain a forty-five (45) foot right-of-way to the property then s/he may be permitted to develop the property provided s/he secure at least a thirty (30) foot right-of-way into the property proposed for subdivision. If the right-of-way is less than thirty (30) feet, the Planning Board may grant a variance for development provided that the road width will meet county standards. Less-than-county-standard-width may be permitted under extreme circumstances in the judgment of the Planning Board, provided the access right-of-way is no greater than 300 feet in length and there are no view obstructions from either end of the access. Roads providing access to subdivisions shall meet the same standard as the roads within the subdivision unless a variance specifying otherwise is granted by the Planning Board. In all cases where less

than a forty-five (45) foot right of-way is used for access to a subdivision, this fact shall be contained in the disclosure statement and shown on the final plat as specified in Article V, Section 7. For purposes of this section, access road shall not include any state-maintained road. When an access road passes by an existing structure, the subdivision developer shall make efforts to protect the structure(s) from visual, noise, stormwater and other impacts potentially caused by the access road.

- (G) Large Tracts or Parcels. Where land is subdivided into larger parcels than ordinary building lots, such parcels should be arranged so as to allow for the opening of future streets and logical further re-subdivisions.
- (H) Marginal Access Streets. Where a tract of land to be subdivided adjoins a principal arterial street or a major arterial street, the subdivider may be required to provide a marginal access street parallel to the arterial street or reverse frontage on a minor street for the lots to be developed adjacent to the arterial. Where reverse frontage is established, private driveways shall be prevented from having direct access to the expressway.
- (I) Lots. All lots shall front, except as provided in Article VI, Section 3(F), with a minimum of forty (40) feet on a dedicated through street; thirty (30) feet on cul-de-sacs. Double frontage lots shall be encouraged where terrain necessitates double frontage for reasonable access to property.
- (J) Street Names. Proposed streets which are obviously in alignment with existing streets shall be given the same name. In assigning new names, the provisions of the Ordinance Establishing Names For Public And Private Roads In Watauga County shall apply. Street names shall be subject to the approval of the Watauga County Emergency Services Department.
- (K) Name of Subdivision. The name of a subdivision shall not duplicate nor closely approximate the name of an existing subdivision within the county. Subdivision names shall be subject to the approval of the Watauga County Emergency Services Department.
- (L) Natural Assets. In any subdivision due consideration will be given to preserving natural features such as trees, ponds, streams, rivers, lakes and for any historical sites which are of value not only to the subdivision but to the county as a whole.
- (M) Erosion Control. In order to prevent soil erosion and sedimentation of streams, springs, flat water bodies, or other drainage networks, the subdivider shall retain the natural vegetation cover wherever possible. Further, land cleared of the natural vegetation shall be reseeded or replanted with an appropriate vegetative cover which shall be approved by the Planning Staff and Soil and Water

Conservation District. In all cases of street construction, or land disturbing activity of one half (1/2) acre or more, the subdivider shall comply with the Watauga County Soil Erosion Control Regulations. In addition, the grading plan and specifications controlling execution of land-disturbing activities shall adhere to the following standards:

- (1) Maximum cut slopes shall be 2H:1V.
- (2) Maximum fill slopes shall be 2H:1V.
- (3) Innovative designs exceeding the slope standards specified herein may be approved when accompanied by a site-specific subsurface investigation, report and recommendation performed by a registered professional engineer competent in geotechnical engineering. All grades shall be sloped to drain surface water away from buildings, pavements, slopes and structures as applicable.

Also see Appendix B-D for further detail.

(N) Storm Water Drainage. The subdivider shall provide an adequate drainage system for the proper drainage of all surface water. The design of such a system shall be subject to the approval of the Planning Staff.

- (1) No surface water shall be channeled or directed into a sanitary sewer.
- (2) Where feasible, the subdivider shall connect to an existing storm drainage system.
- (3) Where an existing storm drainage system cannot feasibly be extended to the subdivision, a surface drainage system shall be designed to protect the proposed development and adjoining property from water damage.

(O) Proposed Water and Sewage Systems. The preliminary subdivision plat must be accompanied by satisfactory evidence as to the proposed method and system of water supply and sanitary sewage collection and disposal.

- (1) Where the system is to be connected to the system owned and operated by the Towns of Boone, Blowing Rock, Beech Mountain, Seven Devils, or any associated sanitary district, or any sanitary facility of Watauga County, but not constructed by the municipalities or county, the preliminary subdivision plat shall be accompanied by a letter of approval from the proper official representing the owner of the existing system to which the proposed system is to be connected. After preliminary approval but prior to installation of a public water or sewer system, the developer shall present to the Planning Board plans for the proposed system, prepared by a registered engineer and approved by the proper official representing the owner of

the system to which the proposed system is to be connected, and by the designated state agency.

- (2) Where community water/sewer systems are proposed, the preliminary plat shall be accompanied by a letter of approval from the proper official of the designated state agency or AppHealthCare, whichever is applicable. The developer shall note the type of systems to be utilized on the preliminary and final plat and shall record with the Watauga County Register of Deeds an instrument setting forth provisions for the establishment of a property owner's association for the purpose of assessing dues for maintenance of the community systems by purchasers of property which will be served within the development. The developer shall maintain community systems at least until such time that the property owner's association assumes maintenance.
 - (3) Where the proposed system does not contemplate the use of facilities owned and operated by any of the above, the developer shall note on the preliminary and final plat that each lot shall have an individual water supply and sewage disposal facility to be approved by the AppHealthCare. The developer shall note further which lot(s) have or have not received prior approval for septic tank use by AppHealthCare.
- (P) Cemeteries: Where a subdivision plat encompasses an existing cemetery - whether active or abandoned - existing cemeteries shall be deeded as a separate lot in the subdivision and shall be accessed by a minimum twenty (20) foot wide private or public easement. Major Subdivisions shall provide access with a minimum twenty (20) foot wide right-of-way (road construction not required).

Section 2. Design Standards for Streets.

The design standards for subdivision streets shall meet either the minimum construction standards for secondary roads as required by the N.C. Department of Transportation or the minimum construction requirements for county standard roads. When state standards are to be met, the developer shall submit proposed road specifications for the approval of the local Department of Transportation office prior to submitting a preliminary plat. It is recommended that subdivision roads be constructed to meet D.O.T. requirements in all areas where terrain is suitable for D.O.T. approval.

- (A) County Standard Roads. County standards may be utilized under the following conditions:
 - (1) Prior to the recording of the final plat, the developer shall record a Declaration of Restrictions and/or approved Road

Maintenance Agreement having provisions for the establishment of a property owner's association for the purpose of assessing dues for road maintenance. The developer shall maintain the road at least until such time that the property owner's association assumes maintenance.

- (2) County standard roads shall be maintained to the original graveled or paved width.
- (3) The Planning Staff may perform periodic inspections to ensure that the roads are being maintained to the required width.

(B) Design Requirements for County Standard Roads.

(1) Right-of-Way Width. Right of way width for County standard roads shall be not less than forty-five (45) feet.

(2) Width of Road Bed. Graded width of road bed including ditch and shoulder areas shall have a minimum width of twenty-five (25) feet. This amount may be reduced pursuant to Article VI, Section 2(B)(4)

(3) Stoned or Paved Area. Road travel area may be either stoned or paved, shall have a minimum width of twenty (20) feet.

(a) Where stone is used, it shall be "crusher-run" or DOT approved "ABC" stone compacted to a minimum of four (4) inches. In locations where soil conditions require additional stone to attain a stable road bed, the developer shall add the required amount of stone before attaining approval of the final plat.

(b) If the developer elects to pave county standard roads, s/he shall meet requirements of the State Department of Transportation pertaining to stone base and top surface.

(c) In the case of roads which were approved and for which construction began prior to the adoption of the 20-foot width requirement on May 15, 2012 the Planning Board may allow 18-foot road width provided the Board determines the following:

(i.) the subject road received a preliminary plat approval prior to May 15, 2012, and

(ii.) the road was substantially completed to the formerly-required 18 foot width, and

(iii.) it is impractical from an engineering or environmental perspective to increase the width to 20 feet. Examples include, but are not limited to: 1) underground utilities have been placed in the road right-of-way, 2) cut and fill slopes have been stabilized and additional grading would unnecessarily affect

the slopes, and 3) the subject road segment is the final segment of an existing road.

- (4) Shoulder Areas and Ditches. Shoulder area on cut side shall be a minimum of four (4) feet in width and shall provide a drainage ditch of adequate size to accommodate storm water run-off based on terrain and location. Shoulder width on fill side shall be a minimum width of three (3) feet. In locations where cuts are required on both sides of the road, drainage ditches and shoulders shall occupy approximately three and one-half (3 1/2) feet wide on each side. The Planning Staff may recommend shoulder design which differs from the above during site inspection and depending upon terrain and cut and fill. In addition, the staff may approve a reduction in shoulder area on the ditch side of up to one and one-half (1 1/2) feet where the road is paved and "roll type" curb and gutter is used. The total reduction in shoulder area could be three (3) feet if there is a ditch on both sides. This reduction is dependent upon adequacy of this design to handle runoff as calculated by the erosion control plan.
- (5) Road Grades. Maximum grade shall be fifteen (15) percent. A variance up to eighteen (18) percent may be granted by the Planning Board in extreme cases where terrain prohibits a lesser grade to attain access to a nearby area, if in the opinion of the Planning Board such variance will not create a hazardous or destructive condition. In no case shall a variance be granted for road grades exceeding eighteen (18) percent. In addition, for any road containing grade(s) exceeding fifteen (15) percent, the entire road network shall be paved unless deemed unnecessary by the Planning Board in considering the variance. The Planning Board may require the placement of safety barriers on curves of such roads. The Planning Board shall also require a slope stake road profile for roads (or portions of roads where practical) with grade(s) fourteen (14) to eighteen (18) percent subsequent to preliminary plat approval. Certification of road grade by a NC licensed surveyor shall be required when deemed necessary by the Planning Board or Staff.
- (6) Culverts and Drainage. Culverts shall be of adequate size to discharge storm water from any given area depending upon terrain and location. Minimum culvert size shall be eighteen (18) inches (may be reduced at the discretion of the Planning Staff) inside diameter and shall be located and installed as recommended by the project engineer or as recommended by the Planning Staff.

- (a) Culverts may be made of any NCDOT approved material and design and shall be installed on a constant grade of a sufficient degree to insure proper drainage and a minimum danger of becoming clogged with debris or mud.
 - (b) All culverts shall have a minimum cover of twelve (12) inches of well compacted earth. The first six (6) inches of earth surrounding the culvert shall be free of stones larger than two (2) inches square.
- (7) Curve Radius. All curves in county standard roads shall have a radius of no less than thirty five (35) feet.
- (8) Bridges. Proposed bridges which will be part of a county standard road or bridges used by more than one house, townhouse or duplex shall be constructed and maintained in accordance with AASHTO HB-17 and designed to accommodate two (2) lanes of traffic unless a variance for a one (1) lane bridge is granted by the Planning Board. Factors to be considered by the Board in deciding upon such variances are: (1) environmental impact of a one (1) lane bridge as opposed to a two (2) lane bridge; (2) density (number of houses to be served by bridge); (3) traffic flow (one lane bridges should not be placed so as to cause traffic to back up onto a major thoroughfare). In any event, bridges serving more than one house, townhouse or duplex shall be permitted and constructed to meet NC Department of Transportation specifications, except that the width may be reduced to twenty (20) feet. Confirmation that bridges meet such specifications may be provided by either Department of Transportation engineer or a registered private engineer. In addition, one-lane bridges shall include gravel or paved turnouts on each side of the bridge(s) to provide access to the water body for fire-fighting equipment where feasible. Developers proposing bridges should request an advisory opinion from the Planning Staff to assist in designing appropriate and adequate bridges. Private bridges shall be maintained by the developer or property owners association. Suggested maintenance procedures are found in Appendix I. It is recommended that these or similar procedures be adopted as an annual procedure.
- (9) Cul-de-sacs. Turn-around right-of-way width shall be a minimum of one hundred (100) feet in diameter for round-design cul-de-sacs; the travel surface shall be a minimum of seventy (70) feet in diameter. Provided, however, that if terrain prevents construction of a round-design cul-de-sac, "tee" and "y" types of turn-arounds may be constructed; right-

of-way shall be forty-five (45)feet in width; travel surface shall be twenty (20)feet. See Appendix K for drawings.— Dead-End Turnarounds: Turnarounds shall be provided for all county standard roads in excess of 150 feet in length. Requirements can be found in Appendix K or NC Fire Code.

(10) Turnarounds. County standard roads shall be provided with turnarounds located as near as practical to the first 1000-foot point and each 1000-foot point thereafter, but not to vary by more than 100 feet longer. Road right-of-way shall be established so as to encompass turnarounds.

(11) Property Lines - - Concerning County Standard Roads. Roads which are to have a forty-five (45) foot right-of-way may also have the property line located along and with the centerline of the road with a twenty-two and one-half (22 1/2) foot road right-of-way measured from the centerline to each side of the road. If this method is used, it shall be clearly indicated on the plats and incorporated in all deed conveyances. If the developer elects, s/he may place property line(s) twenty-two and one-half (22 1/2) feet from the centerline of the road(s) thereby providing a forty-five (45) foot right-of way.

(a) Property line markers (iron rod, granite, or concrete monument) shall be placed on the side property lines at a point measured twenty-two and one-half (22 1/2) feet from the center of the road where a forty-five (45) foot right-of-way is provided.

(b) The minimum building set-back distance from the road abutting the front of the property shall be forty (40) feet from the center of a forty-five (45) foot right-of-way. This will place the structure 17 1/2 feet behind the right-of-way line.

(12) Designation of Road Status. All roads shown on the preliminary and final plats shall be clearly noted as to which roads are county standard and which are constructed to meet N.C. Department of Transportation requirements.

(a) It is permissible to have both county standard and state approved roads within a subdivision. It is suggested that for a subdivision of substantial size with a main entrance road entering from an existing state road which will have a length of one thousand (1000) feet or more and may be extended in the foreseeable future, the entrance road should be constructed to meet N.C. Department of Transportation standards. This plan is suggested in order to insure mail delivery, state road maintenance and school bus service to a closer proximity of property

owners located on county standard roads which may intersect the new public road.

- (b) Construction of a county standard road intersecting an existing state road with the intention of connecting and serving a new state approved road is prohibited.
- (13) Disclosure. The developer shall comply with N.C.G.S.136-102.6 which provides for a Disclosure Statement from the developer to the purchaser setting forth the status (whether public or private) of the road on which the property is located. The disclosure statement shall also fully disclose the party or parties upon whom responsibility for maintenance of such roads shall rest.

Section 3. Design Standards for Lots.

The lot size, width, depth, shape and orientation, shall be appropriate for the location and terrain of the subdivision and for the type of development and use contemplated.

(A) Lot Area. (SEE ALSO TABLE 1)

- (1) Lots served by public/community water and NPDES sewer shall have an area of at least eight thousand (8000) square feet.
- (2) Lots served by NPDES sewer but individual water shall have an area of at least ten thousand (10,000) square feet.
- (3) Lots served by individual sewer shall have an area of at least twenty-one thousand, seven hundred eighty (21,780) square feet (one-half acre). These requirements shall be increased on the recommendation of the ~~Appalachian District Health Department~~ AppHealth Care based on site investigations or percolation rates and subsoil conditions.
- (4) Lots located within drinking water supply watersheds shall comply with the size requirements specified for WS-I, WS-II, WS-III, or WS-IV found in the Watauga County Watershed Protection regulations.
- (5) Individual lots within townhouse developments or townhome conversions must include an individual dwelling, together with front and rear yards or rights to yards in common areas, but are otherwise exempt from minimum lot area and setback requirements.

TABLE 1 - LOT AREA REQUIREMENTS

	PUBLIC/COMMUNITY WATER, NPDES & NON-DISCHARGE SEWER SYTEMS	PUBLIC/COMMUNITY/ INDIVIDUAL WATER, INDIVIDUAL SEPTIC SYSTEMS	INDIVIDUAL WATER, SHARED INDIVIDUAL SEPTIC SYSTEMS	INDIVIDUAL WATER NPDES SEWER SYSTEMS
Minimum Lot area in square feet	8,000	21,780	21,780	10,000
Minimum Lot width in feet	75-average 40-street line**	75-average 40-street line	75-average 40-street line	75-average 40-street line
Minimum lot depth in feet	125-average	125-average	125-average	125-average
Density in units per acres	5.4 (conventional) 6.155 (PUD***)	2 (conventional) 2.261 (PUD***)	4 (conventional) 4.522 (PUD***)	4.3 (conventional) 4.924 (PUD***)

** Street line width for cul-de-sacs may be 30 feet.

*** Multiply gross area by figures shown here. These figures have 15% deduction for roadways built in. These figures do not apply where the average cross slope is 30% or greater.

NOTES:

- ~~a) PUDs served by shared individual sewer systems (see definitions) shall be permitted density of 4.522 units per acre (this figure has 15% roadway deduction built it); density permitted where average cross slope exceeds 30% shall be 4 units per acre.~~
- b) Minimum lot size requirements may exceed those shown above if subdivision is located in areas of the County affected by the following state and local regulations:
 - (i.) Valle Crucis Historic District
 - (ii.) Foscoe-Grandfather Zoning
 - (iii.) Watershed Protection
 - (iv.) High Quality Waters (HQW)
 - (v.) Outstanding Resource Waters (ORW)
- ~~c) Setback: 15 feet from side and rear property lines; 40 feet from center of 45 foot right-of-way.~~
- ~~d) AppHealthCare regulations require that 1 unit = 2 bedrooms for individual sewer systems.~~
- e) Minimum lot areas are exclusive of road right-of-way.
- f) Formula for units per acre: #units divided by total acres.
Example: 10 units on 2 acres = 10/2= 5 units per acre.

- g)** Except as set forth as follows in Subsection (F), A residential lot, meeting the minimum standards of this ordinance, or being a lot which was established prior to June 15, 1973, may accommodate a single residence, a duplex, or a single residence and a detached secondary residence such as a garage apartment, provided there are no more than two (2) units.
- (B)** Lot Width. All lots shall have an average width of seventy-five (75) feet and a minimum width at the street line of forty (40) feet, thirty (30) feet on a cul-de-sac.
- (C)** Lot Depth. All lots shall have an average depth of at least one hundred twenty-five (125) feet.
- (D)** Orientation of Lot Lines. Side lot lines are encouraged to be designed substantially at right angles or radial to street lines depending upon terrain.
- (E)** Panhandle Lots. The Planning Board or Staff may approve panhandle lots where it is impractical to serve an isolated lot by a state or county standard road. The frontage of the panhandle lot shall have a minimum width of thirty-five (35) feet which will provide an access strip between two standard lots to the isolated building site. The area of such strip shall be excluded in computing the lot area and the length of said strip shall not exceed three-hundred (300) feet. If the panhandle widens to seventy (70) feet or more, it shall be included in the acreage calculation.
- (F)** Access to Lots. All lots within a subdivision shall have direct vehicular access to state or county standard roads, provided however that access to a maximum of three (3) lots (each lot containing no more than one residential unit) may be provided through use of a shared private driveway.—A shared private driveway shall not exceed eighteen (18) percent grade, shall be contained within a 20 foot or greater right-of-way, and shall have a 35 foot minimum curve radii. Driveway travel area may be either stoned or paved and shall have a minimum width of ten (10) feet with a vertical clearance of not less than 13 feet 6 inches. The travel area must be designed to support the loads imposed by fire apparatus and provide all weather driving capabilities. Driveways that exceed 1,000 feet in length shall have an approved pullout area with a minimum width of 10 feet and minimum length of 40 feet to allow for two-way traffic. Shared driveways shall be constructed at the time of final plat submission. There shall be no obstructions within the right-of-way of shared driveways. The developer shall record with the Watauga County Register of Deeds an instrument setting forth provisions for maintenance of the shared driveway and shall maintain the driveway at least until such time that the maintenance is assumed by others.

The provisions of this subsection are applicable to shared driveways serving more than one subdivision, or a subdivision and property outside of the subdivision. ~~Decisions of the staff may be reviewed by the Planning Board upon written appeal submitted to the Clerk to the Planning Board within thirty (30) days of the staff decision.~~

(G) Building Setback Lines. The minimum building setback distance shall be as stipulated in Table 2. Structures subject to setback requirements may be completed without regard to older, more stringent setback requirements found in older subdivisions. Building setbacks shall be measured from the property line to any part of the structure above ground, including eaves and overhangs, but not including walkways or driveway/parking areas. The owner or contractor shall certify compliance with setbacks prior to inspection of the building footings.

TABLE 2 - BUILDING SETBACK REQUIREMENTS

<u>Type of Setback</u>	<u>Amount of Setback</u>
1. Distance from center of right-of-way on Highways 321,421,221,105,194. (includes all frontages on multiple frontage lots)	80 feet, but shall in all cases be at least 15 feet from the street right-of-way line.
2. Distance from center of right-of-way on all other streets. (includes all frontages on multiple frontage lots)	45 feet, or 40 feet per Article VI Section 2 (B) (11) (b)
3. Distance from cul-de-sac right-of-way.	15 feet
4. Distance from side property line.	15 feet
5. Distance from rear property line. (If rear property line does not front on a road)	15 feet
6. Distance (horizontal) from a stream, river or lake.	To be determined by Watauga County Flood Damage Prevention Chapter 9 Ordinance or other applicable regulations including but not limited to High Quality Waters, Outstanding Resource Waters, and Watershed Protection.
7. Pre-existing Situations. Setback requirements contained herein are not applicable to structures and lots lines which pre-existed this ordinance and/or pre-existed the subdivision of land upon which the structures are located. The setbacks contained herein shall apply to any new or rebuilt structures located on the subject land.	

Section 4. Design Standards for Easements.

Easements shall be provided as follows:

- (A) Utility Easements. Easements for underground or above ground utilities shall be provided where necessary across lots or preferably centered on rear or side lot lines and shall be at least ten (10) feet in width.
- (B) Drainage Easements. Where a subdivision is traversed by a stream or drainage way, a minimum easement of fifteen (15) feet shall be provided conforming to the lines of such stream.

Article VII Planned Unit Development

Section 1. Definition.

A "planned unit development" (PUD) is a tract of land under single, corporate, firm, partnership, or association ownership which is planned and developed as an integral unit. It is established in a single development operation or a definitely programmed series of development operations according to an approved master development plan and a preliminary site plan.

Section 2. Purpose.

It is the objective of this Article to encourage PUD proposals that exhibit such special qualities or concepts that they may deviate from standard requirements. These regulations are established in order that each PUD proposal will be evaluated on its own merits. It is recognized that some proposals or concepts will be more successful than others and the approval of a specific proposal in one situation does not mean that a similar proposal would be acceptable in other circumstances. It is also recognized that only through ingenuity, imagination, and high quality design can residential or commercial developments be produced which are in keeping with the intent of this article but which are not constrained by the strict application of conventional use and dimensional requirements of the subdivision regulations.

A Voluntary Alternate Procedure

Use of the PUD procedure is not mandatory for the development of any site or area. Rather, this process will provide a voluntary alternate development procedure which has one or more of the advantages listed below.

- (a) Permit creative approaches to the development of residential or commercial land, reflecting changes in the technology of land development.

- (b) Accomplish a more desirable environment than would otherwise be possible, by providing for a variety of housing types, designs and arrangements.
- (c) Provide for an efficient use of land which can result in smaller networks of utilities and streets and reduce development costs.
- (d) Enhance the appearance of neighborhoods through the preservation of natural features, and the provision of recreational and open space areas.
- (e) Provide an opportunity for new approaches to home ownership.
- (f) Provide an environment of stable character compatible with surrounding residential and natural areas.

(A) Minimum Requirements.

- (1) The normal lot size, setbacks and frontage requirements are hereby waived for lots or building sites within the planned unit development, provided that the spirit and intent of this article are complied with in the total development plan, as determined by the Planning Board. Compliance with the buffering and screening requirements found in Appendix J along the perimeter of a PUD is required.
- (2) Height limitations: All buildings shall comply with the Watauga County Height of Structures regulation or the NC Ridge Law, whichever is applicable.
- (3) All streets providing access to a PUD and streets within a PUD shall be constructed to at least County standards regarding right-of-way and width, and must be paved per NCDOT Subdivision Roads minimum construction standards.
- (4) Every dwelling unit shall have access to a public or private street, walkway or other area dedicated to common use, and there shall be provision for adequate vehicular circulation to all development properties, in order to ensure acceptable levels of access for emergency vehicles.
- (5) All development shall be provided with adequate parking facilities to handle the expected number of automobiles for that site. Spaces shall be provided as follows; use and occupancy classifications for buildings are the same as those definitions used in the N.C. Building Code. ~~Every planned unit development shall provide at least two (2) off-street parking spaces per dwelling unit and~~

~~commercial/office parking and loading space according to the following schedule:~~

- (a)** Assembly, business, educational, storage and mercantile uses and occupancies shall be provided with parking spaces as follows:
 - (i.)** one (1) off-street parking space for each two hundred (200) square feet of gross floor area for operations designed to attract and serve customers and clients on the premises;
 - (ii.)** one (1) off-street parking space for each four hundred (400) square feet of gross floor area for operations designed to attract little or no customer or client traffic other than employees of the operation;
 - (iii.)** one (1) off-street parking space for each one thousand (1000) square feet of gross floor area for mini-warehouse uses.
- (b)** Factory Industrial uses and occupancies shall be provided with 1.5 spaces per three employees, computed on the total employment.
- (c)** Institutional uses and occupancies shall be provided with one space per five persons identified in the building's occupant load figures.
- (d)** Residential uses and occupancies, primarily permanent, shall be provided with 2 spaces per dwelling unit.
- (e)** Residential uses and occupancies, primarily transient (motels, hotels and inns), shall be provided with one and one-half (1.5) spaces per bedroom.

~~Parking space for commercial/office shall consist of one (1) off-street parking space for each two hundred (200) square feet of gross floor area for operations designed to attract and serve customers and clients on the premises; one (1) space for each four hundred (400) square feet of gross floor area for operations designed to attract little or no customer or client traffic other than employees of the operation; one and one half (1.5) spaces per bedroom for hotels, motels, and inns; one and one half (1.5) spaces per three employees for industrial and warehouse uses.~~

- (6) Parking spaces shall be a minimum of nine feet by eighteen feet (9' x 18') in size.
 - (7) Loading/unloading space for commercial/ office uses shall consist of one (1) space at least three hundred (300) square feet in size for each five thousand (5000) square feet of gross floor area.
 - (8) Parking and loading areas for all multi-unit buildings shall be accessible to fire department apparatus through the use of fire lanes or other means of access approved by the County Fire Marshal /Emergency Management Office.
 - (9) Grading and erosion control shall be undertaken in accordance with Article VI, Section 1(M).
- (B) Land Development Standards.** Subject to the provisions set forth herein, residential, office, commercial, or mixed use PUD's are permitted uses. Common land must be an essential element of the PUD, provided in lieu of standard individual lots. A minimum of thirty – three percent (33%) of the total land area must be permanently dedicated as any combination of common space, open space or green space. Road and parking areas and buildings shall not be included in common land for purposes of this subsection; areas designated for septic drain fields and repair areas and well buffers shall be included. Also included, for example, are outdoor recreation areas and no-wall structures such as picnic shelters.
- (1) Residential Uses. Residential units within a PUD may include single family detached or attached units, townhouse developments, garden apartments, patio homes, and other type residential units. Condominium, cooperative, individual, municipal, or any other type of ownership development may be recorded, and the plan shall be approved as a preliminary and final plat according to the requirements of the subdivision regulations.
 - (2) Non-Residential Uses. Non-residential uses (commercial and office) within residential PUD's shall not constitute the primary use in the PUD, and non-residential uses shall be carefully designed to complement the residential uses within the PUD. Commercial/office PUD's are permitted, and are subject to the same requirements as residential PUD's including the preceding subsection.
 - (3) Privacy. Each development shall provide reasonable visual and acoustical privacy for all dwelling units. Fences, insulation, walkways, barriers, and landscaping shall be used, as appropriate, for the protection and

aesthetic enhancement of property and the privacy of its occupants.

(4) Perimeter Requirements. The standards of Appendix J shall apply.

(C) Density. The density which may be constructed within the Planned Unit Development shall be determined by dividing the gross project area minus fifteen percent (15%) of the total (to account for roadways) by the required lot area per unit which is required on Table 1 for conventional subdivisions, and modified by the increases in density permitted under this Section. Density (units per acre) may be increased (see Table 1) if the character of the development and/or amenities incorporated in the development warrant such increases provided that in no case shall the density increase cause the density of the Planned Unit Development to be more than thirty-three percent (33%) in excess of the density which would be achieved under standard subdivision regulations.

(1) Limits Upon Density Increases. If the Planning Board finds that any of the following conditions would be created by an increase in density, it may either deny an application for increase in density, or limit the increase in density by an amount sufficient to avoid the creation of any of the following conditions:

(a) Inconvenient or unsafe access to the development.

(b) Traffic congestion in streets adjoining the development.

(c) An excessive burden imposed on parks, recreational areas, schools, and other public facilities which serve or are proposed to serve the development.

(2) Denial of Density Increases. The increases in density shall not apply where the average cross slope is thirty (30) percent or greater. See Appendix H for method of determining average cross slope.

(D) Conveyance and Maintenance of Common Land. Conveyance and maintenance of common land, common elements, open space, green space, recreational areas and other facilities owned in common shall be in accordance with the Unit Ownership Act (Chapter 47-A of the North Carolina General Statutes), the Condominium Act (Chapter 47-C), the Planned Community Act (Chapter 47-F) and/or any other applicable state or federal law.

(E) Improvements

(1) Circulation Facilities. The arrangement of public and common ways for pedestrian and vehicular circulation in relation to other existing or planned streets in the area,

together with provisions for street improvements, shall be in compliance with standards set forth in Article VI, Section 2(B)(3)&(4) (unless a variance for one lane traffic has been granted).—Upon application by the developer and good cause shown, the Planning Board may permit changes or alterations of such standards which are consistent with the spirit and intent of this section.

- (2) Utilities. Whenever reasonably possible, all Planned Unit Developments shall provide for underground installation of utilities (including electricity and telephone) in both public ways and private extensions thereof. Provisions shall be made for acceptable design and construction of storm water facilities including grading, gutters, piping, treatment of turf to handle storm waters and erosion prevention. Utilities and maintenance of facilities shall be in accordance with the requirements and regulations of the appropriate governmental authority having jurisdiction thereof.

A planned unit development application shall not be approved unless adequate assurance is given that public or community water and sanitary sewer service will be available, except that upon application by the developer and good cause shown, the Planning Board may modify or waive this requirement provided such action is consistent with the spirit and intent of this section.

- (3) Pedestrian Circulation. Any pedestrian circulation system and its related walkways shall be insulated as completely and as reasonably as possible from the vehicular street system in order to provide separation of pedestrian and vehicular movement. This shall include where deemed to be necessary by the Planning Board pedestrian underpass or overpass in the vicinity of schools, playgrounds, local shopping areas, and other neighborhood uses which generate a considerable amount of pedestrian traffic.

(F) PUD Reviewed as Subdivision.

It is the intent of this regulation that subdivision review be carried out as an integral part of the review of a Planned Unit Development under the Section. The plans required under this Section must be submitted in a form which substantially will satisfy requirements of these regulations for the preliminary and final plat approvals. The plans may also be subject to review by the County Board of

Adjustment if the PUD is proposed in a zoned area. Approval of a Special Use Permit for a PUD by the Board of Adjustment shall constitute preliminary plat approval; Planning Board approval of preliminary plat(s) is not required. The Planning Board shall approve all final plats. The Planning Staff has the authority to approve final plats consisting of up to ten (10) lots or buildings. The Planning Board shall approve all other final plats.

- (1) Phased Developments. If the proposed PUD is to be developed in phases, the developer shall submit a master plan as specified in **Chapter 24**. ~~Article V Section 5 of this chapter.~~
- (2) Advisory Opinion. Prior to formal master plan or a preliminary plat submission, the developer is encouraged to submit a sketch plan of the PUD to the Planning Staff in order to obtain an advisory opinion of the project's feasibility.

Use the following certificate for final plats being approved by Planning Staff:

Certificate of Approval of Recording

I hereby certify that the plat shown heron complies with the Watauga County subdivision regulations. It is approved for recording in the office of the Watauga County Register of Deeds pursuant to Article VII Section 2 (F) of Chapter 18 of the Planning & Development Ordinance.

DATE

WATAUGA COUNTY AUTHORIZED REPRESENTATIVE

Section 3. Affordable Housing PUD.

It is the objective of this section to encourage the provision of housing that is affordable to low and moderate income households. These regulations are established in support of Watauga County's adopted Affordable Workforce Housing policy (See [Appendix "L"](#)) and provide a voluntary alternative procedure to encourage development of housing affordable to all income levels, particularly first time home buyers.

The following are definitions of the words or terms utilized in this Section:

Affordable Dwelling Unit. A dwelling unit that is offered for sale or rent at a total monthly mortgage or rental price (including utilities) which is no greater than 1/12 of 30% of the Area Median Income as established annually by the United States Department of Housing and Urban Development, adjusted for assumed household size based on unit size. The assumed household size shall

be (2) persons in a one bedroom unit, (3) persons in a two bedroom unit, and (4) persons in units containing three or more bedrooms.

Affordable Housing PUD. A Planned Unit Development, as defined by [Article VII Section 1](#), in which 51% or more of the included dwelling units meet the definition of an Affordable Dwelling Unit.

(A) Minimum Requirements.

The minimum requirements for development of an Affordable Housing PUD shall be as established in Article VII, Section 2(A), with the exception of the following:

- (1)** Streets within an Affordable Housing PUD shall be constructed in accordance with Article VI, Section 2(B)(3). The right-of-way shall not be less than thirty (30) feet.
- (2)** Affordable Dwelling Units within an Affordable Housing PUD shall provide one (1) off-street parking space per unit.
- (3)** When an Affordable Housing PUD contains both Affordable Dwelling Units and market rate housing, the Affordable Dwelling Units shall be intermixed with the market rate units.
- (4)** When an Affordable Housing PUD contains both Affordable Dwelling Units and market rate housing, the general exterior design and appearance of the Affordable Dwelling Units shall be compatible with the market rate units.

(B) Land Development Standards.

The land development standards for an Affordable Housing PUD shall be as established in Article VII, Section 2(B).

(C) Density.

The density which may be constructed within an Affordable Housing PUD shall be determined by the capacity of the proposed water and sewer systems, provided that the proposed density does not result in the any of the following conditions:

- (1)** Inconvenient or unsafe access to the development.
- (2)** Traffic congestion in the streets adjoining the development.
- (3)** An excessive burden imposed on parks, recreation areas, schools and other public facilities which serve or are proposed to serve the development.

(D) Conveyance and Maintenance of Common Land.

Conveyance and maintenance of common land within an Affordable Housing PUD shall be as established in Article VII, Section 2(D).

(E) Improvements.

Required improvements within an Affordable Housing PUD shall be as established in Article VII, Section 2 (E).

(F) Procedure.

Applications for an Affordable Housing PUD shall be reviewed by Planning Board or Board of Adjustment in accordance with Article VII, Section 2(F). In addition:

- (1) Applications containing Affordable Dwelling Units shall be processed with priority over others.
- (2) Highest priority for processing shall be given to applications involving partnerships with a community land trust or other non-profit organization responsible for ensuring long-term retention of affordable housing.
- (3) The County shall waive review fees associated with Affordable Housing PUDs meeting the criteria established herein.
- (4) If market rate housing units are included within an Affordable Housing PUD constructed in phases or over a time period exceeding 12 months, a proportional amount of Affordable Dwelling Units must be completed concurrently with the market rate housing units.
- (5) An agreement in a form approved by the County must be recorded with the Register of Deeds requiring Affordable Dwelling Units which are provided under this section to remain as affordable housing for the life of the project. This agreement shall be a covenant running with the land, binding on the assigns, heirs and successors of the applicant.

Article VIII Installation of Permanent Reference Points and Improvements

Section 1. Permanent Reference Points.

Prior to the approval of the final plat, permanent reference points shall have been placed in accordance with N.C.G.S. 89C and N.C.G.S. 47-30, which provide regulations for surveyors for the mapping of subdivisions. Additionally, the following requirements shall be met:

- (A) Block Tie Lines. Each block shall have adequate tie line(s) showing bearing and distance between one established point on each side of the road.
- (B) Certificate. A certificate signed by the surveyor meeting the requirements of N.C.G.S. 47-30 et. seq. for proof upon oath that the plat is in all respects correct, written as shown in Article V, Section 6(B)(2).

Section 2. Installation of Improvements.

Prior to the approval of the final plat, the subdivider shall have complied with the following requirements.

- (A) Streets and Storm Drainage Facilities. All streets and storm drainage facilities in the subdivision shall be constructed in accordance with specifications and standards of the State Department of Transportation, Division of Highways, or the Watauga County Road Standards.
- (B) Water Lines. Where public water is reasonably accessible, the subdivider shall connect with the public supply and shall provide water mains and a suitable water connection to each lot. Where a public water supply is not reasonably accessible, the subdivider may provide for connection to a community system, establishment of a new public or community system, or for shared or individual wells. Water source shall be noted on the final plat.
- (C) Sanitary Sewers. Where a public sanitary sewer system is reasonably accessible, the subdivider shall connect with the public system and shall provide a connection for each lot. Where a public sanitary sewer system is not accessible, the subdivider may provide for connection to an existing private system, establishment of a new private system, or for shared or individual septic systems. Sewage disposal method shall be noted on the final plat.
- (D) Installation at time of Final Plat. In the event that any public or community utilities are not installed at the time of final plat approval, bond or other security guarantee may be required by the Planning Board as specified in Article VIII, Section 3.

Section 3. Deferment of Improvements.

Where it is in the best interest of all parties concerned to defer the installation or completion of some required improvement, and in accordance with N.C.G.S. 160D-804.1, the Planning Board may approve the final plat if the subdivider posts a bond with surety or other guarantees satisfactory to the County Commissioners in an amount equal to the estimated cost of the deferred improvements plus ~~twenty (20)~~ **twenty-five (25)** percent. **The guaranteed improvements shall be accomplished within one year of the Planning Board approval of the final plat. The Planning Board may, upon proof of difficulty, grant an extension of the completion date set forth in its approval for a maximum period of six (6) additional months.** Such guarantees shall assure either the performance of the specified work or payment of the specified sum to the County if such improvements have not been installed within the time specified on the final plat. At least fifty percent (50%) of the required

improvements shall be completed prior to submission of a request for approval of a performance guarantee by a subdivider.

ARTICLE IX - Regulation Of Multi-Unit Structures

Section 1. Definition.

A "multi-unit" structure is a building containing three (3) or more separate and independent dwellings, offices, or commercial establishments (excluding hotels/motels). This definition shall apply whether the building and/or individual units contained within are for sale, lease, or rent.

An "Affordable Housing Multi-Unit Structure" is a multi-unit structure containing at least (3) dwelling units, 51% or more of which are offered for sale or rent at a total monthly mortgage or rental price (including utilities) which is no greater than 1/12 of 30% of the Area Median Income as established annually by the United States Department of Housing and Urban Development, adjusted for assumed household size based on unit size. The assumed household size shall be (2) persons in a one bedroom unit, (3) persons in a two bedroom unit, and (4) persons in units containing three or more bedrooms.

Section 2. Purpose.

The purpose of this article is to provide for a site plan review of multi-unit structures in order to regulate density, parking/loading, building setbacks, and other public health, safety, and general welfare concerns.

Section 3. Application of Article.

This Article shall apply to any multi-unit construction which consists of one (1) building only. Any multi-unit development consisting of two (2) or more building sites or any townhouse development regardless of the number of buildings, shall comply with Article VII (Planned Unit Development) of this Ordinance, including phased developments where each phase consists of one (1) building only.

Section 4. Standards of Design.

The developer shall observe the following standards of design.

(A) Density.

The number of units per acre allowed shall depend upon the availability of public/community water and sewer facilities and shall be determined as described in Article VII, Section 2(C) and depicted

on Table 1. If no roadway is to be constructed, the same method of calculating density shall be used, except that the gross area will not be required to be reduced by fifteen (15) percent. A minimum of thirty three percent (33%) of the total land area must be permanently dedicated as any combination of common space, open space or green space. Road and parking areas and buildings shall not be included in common land for purposes of this subsection; areas designated for septic drain lines and repair areas and well buffers shall be included. Also included, for example, are outdoor recreation areas and no-wall structures such as picnic shelters.

For Affordable Housing Multi-Unit Structures, the number of units per acre allowed shall depend upon the capacity of proposed water and sewer system(s), provided that the proposed density does not result in the any of the following conditions:

- (1) Inconvenient or unsafe access to the development.
- (2) Traffic congestion in the streets adjoining the development.
- (3) An excessive burden imposed on parks, recreation areas, schools and other public facilities which serve or are proposed to serve the development.

(B) Off-Street Parking/Loading.

The provisions of Article VII, Section 2(A) shall apply. At a minimum, parking areas shall be graveled. For Affordable Multi-Unit Structures, one (1) required off-street parking space may be eliminated for each Affordable Dwelling Unit provided. Additional parking reductions may be allowed when development:

- (1) Is an adaptive re-use of previously developed property, or
- (2) Is located within 1 mile of Appalachian State University or other major employment center, or
- (3) Is located on an established AppalCart Route, or
- (4) Has transit service or other acceptable alternative transportation provided by the developer.

(C) Streets and Private Drives.

All multi-unit structures shall front on a state maintained road or a county standard road as defined in this chapter. A private drive may be used to provide access to one three (3) unit structure.

(D) Height Requirements.

All multi-unit structures shall comply with the Watauga County Height of Structures regulation or the North Carolina Ridge Law, whichever is applicable. Building height will be determined by the Watauga County Building Inspector.

(E) Building Setback Requirements.

Building setbacks shall conform with Table 2 (Article VI, Section 3), unless superseded by Appendix J.

(F) Utilities.

Developers of multi-unit structures are encouraged to provide public/community water and sewer facilities whenever feasible. Developers are also encouraged to provide underground electric and telephone lines where feasible.

(G) Buffers.

It is the intent of this chapter to promote high quality multi-unit developments which do not create a nuisance, aesthetic or otherwise, for existing adjacent residential areas. Therefore, the provisions of Appendix J shall apply.

Section 5. Submission of Site Plans.

Developers of proposed multi-unit structures which will be regulated by this Article shall submit a site plan to the Planning Staff. If the proposed structure contains ten (10) or less units, the Staff shall approve or disapprove said plan. If the proposed structure contains eleven (11) or more units, or the developer is requesting a variance, the Planning Board shall approve or disapprove said plan. Construction may begin upon such approval. Site plans shall show how the requirements of the preceding Section 4 will be met. Specifically, site plans shall include as applicable:

- (A)** A sketch vicinity map showing the relationship of the proposed development with the surrounding area.
- (B)** The location of existing and platted property lines, streets, buildings, water courses, transmission lines, sewers, bridges, culverts, and drain pipes, water mains, city and county line (if adjoining) and any public utility easements.
- (C)** Boundaries of the tract shown with distances and approximate acreage.
- (D)** Names of adjoining property owners or subdivisions.
- (E)** Zoning classification, if any, both on the land to be developed and on adjoining land.
- (F)** Proposed streets, street names, rights-of-way, roadway widths, approximate grades and proposed drainage facilities.
- (G)** Other proposed rights-of-way or easements showing locations, widths and purposes.
- (H)** Proposed building set back lines.
- (I)** Proposed utility layouts (sewer, water, electricity showing connections to existing systems or plans for central water system or package sewage system, or designation for individual water and sewage.
- (J)** Proposed parks, open spaces, or any other public areas.

- (K) Name of owner, developer, engineer and registered surveyor.
- (L) Title, date, north point and graphic scale.
- (M) When an area covered by the plan includes or abuts a water area (stream, river or lake) the following additional information is required:
 - (1) Relationship with floodway and flood plain as delineated by the county floodway boundary and flood insurance rate maps.
 - (2) Any proposed dock lines beyond which no dock structure may be constructed.
 - (3) Methods of providing ingress and egress from uplands to water area.
 - (4) Names of the owners of the water area.
- (N) Grading and erosion control shall be undertaken in accordance with Article VI, Section 1(M).

Section 6. Inspections.

Prior to issuance of an Inspection Certificate for a final building inspection, the Planning Staff shall conduct a site inspection to assure that the multi-unit structure meets the requirements of this Article. The developer of a multi-unit structure shall pay an inspection fee (in addition to purchase of a building permit) in the same amount per structure as is assessed for Planned Unit Developments.

Section 7. Building Permits.

No permits for any building or structures will be issued upon any land requiring approval as a subdivision under the conditions set forth herein, unless a final plat is recorded, except as set forth elsewhere in this chapter.

Should any Federal or State regulation or statute incorporated herein by reference or otherwise referred to herein, be changed or amended, or should either require or mandate a different procedure or change or impose new, different or additional requirements, then, in that event, this ordinance shall be deemed to have been amended without further action to have complied with such new, additional or amended requirements.

Appendix A Guide For Sub-Division Development In Watauga County

1. Evaluate your property for either sub-dividing or planned unit development (resorts, clusters, time-shares, condominiums, townhouses, apartments, etc.) suitability.
2. Evaluate your capital outlay for road(s) and other improvement and environmental protection measures.
3. Consult the Department of Planning and Inspections at (828)265-8043 to ascertain the legal aspects and requirements for any such projects.
4. Consult a licensed surveyor and/or professional engineer for project drawings and layout.
5. Maintain close contact with those persons contracted for the planning phase of the project so as to have a working knowledge of the project.
6. Solicit bids and/or contract a grading contractor to complete all planned construction.
7. The developer will be responsible for environmental protection measures during development and also will be financially responsible for all work on the project.
8. Present a finished development that complies with all local and state ordinances concerning land use and also one that is appealing to the consumer.
9. In working with the Watauga County Ordinance to Govern Subdivisions and Multi-Unit Structures, the Watauga County Soil Erosion and Sedimentation Control Ordinance and the Watauga County Building Inspectors and Fire Marshal, those persons responsible for each area will assist you in the construction stages of development.
10. Obtain copies of the following additional regulations from the Department of Planning and Inspections as needed:

Flood Damage Prevention.

N.C. Ridge Law.

The Height of Structures.

Mobile Home Parks.

Subdivision Regulations for Recreational Vehicle Parks.

Valle Crucis Historic District.

Foscoe Grandfather Zoning.

Watershed Protection.

Appendix B Guidelines For Developing Erosion and Sediment Control Plans

Section 1. Introduction.

Extensive amounts of sediment are produced from grading streets and roads in the mountain sections of North Carolina when erosion control measures are not properly designed and installed. Irreversible damage to land, streams and lakes is occurring from acceleration of development in this area. This is offered as a minimal guideline, but the developer must keep in mind that the Sediment and Pollution Control Act and the Watauga County Soil Erosion and Sedimentation Control regulations are performance oriented and s/he must do whatever is necessary to prevent off-site damage.

This guide is developed to assist planners and developers to protect land and streams from sedimentation as required by the Watauga County Soil Erosion and Sedimentation Control regulations.

Said regulations require that an erosion control plan be prepared and its measures installed where one-half acre or more is disturbed by grading. This also applies to all subdivision roads and any land disturbing activity which causes off-site erosion damage regardless of acreage.

The practices in this guide, when properly installed and maintained, are methods used in the past that have minimized erosion and sedimentation and meet the mandatory standards required by the Sedimentation Pollution Control Act of 1973 and the Watauga County Soil Erosion and Sedimentation Control regulations. The mandatory standards are listed on the following page.

Section 2. Mandatory Standards For Land Disturbing Activity

No land disturbing activity subject to this article shall be undertaken except in accordance with the following mandatory requirements:

Buffer Zone

- (A)** No land-disturbing activity during periods of construction or improvement to land shall be permitted in proximity to a lake or natural watercourse unless a buffer zone is provided along the margin of the watercourse of sufficient width to confine visible siltation within the twenty-five percent (25%) of the buffer zone nearest the land-disturbing activity. Waters that have been classified as trout waters by the Environmental Management Commission shall have an undisturbed buffer zone 25 feet wide or of sufficient width to confine visible siltation within the twenty-five (25%) of the buffer

zone nearest the land-disturbing activity, whichever is greater. Provided, however, that the county may approve plans which include land-disturbing activity along trout waters when the duration of said disturbance would be temporary and the extent of said disturbance would be minimal. This subdivision shall not apply to a land-disturbing activity in connection with the construction of facilities to be located on, over, or under a lake or natural watercourse.

- (B) Unless otherwise provided, the width of a buffer zone is measured from the edge of the water to the nearest edge of the disturbed area, with the 25 percent of the strip nearer the land-disturbing activity containing natural or artificial means of confining visible siltation.
- (C) The 25 foot minimum width for an undisturbed buffer zone adjacent to designated trout waters shall be measured horizontally from the top of the bank.
- (D) Where a temporary and minimal disturbance is permitted as an exception by Chapter 8 of this Title, land-disturbing activities in the buffer zone adjacent to designated trout waters shall be limited to a maximum of 10% of the total length of the buffer zone within the tract to be distributed such that there is not more than 100 linear feet of disturbance in each 1000 linear feet of buffer zone. Larger areas may be disturbed with the written approval of the Director.
- (E) No land-disturbing activity shall be undertaken with a buffer zone adjacent to designated trout waters that will cause adverse temperature fluctuations, as set forth in 15A NCAC 2B.0211 "Fresh Surface Water Classification and Standards", in these waters.

(1) Graded Slopes and Fills -The grading plan and specifications controlling execution of land disturbing activities shall adhere to the following standards:

- a) Maximum cut slopes shall be 2H:1V.
- b) Maximum fill slopes shall be 2H:1V.

Innovative designs exceeding the slope standards specified herein may be approved when accompanied by a site-specific subsurface investigation, report and recommendation performed by a registered professional engineer competent in geotechnical engineering. All grades shall be sloped to drain surface water away from buildings, pavements, slopes and structures, as applicable.

Slopes left exposed will, within ~~15 working days or 30 calendar days of completion of any phase of grading, whichever period is shorter,~~ within seven (7) days of ceasing land disturbance for slopes steeper than 3:1 and fourteen (14) days of ceasing land disturbance for slopes less than 3:1 be planted or otherwise provided with ground cover, devices, or structures sufficient to restrain erosion.

- (2) Ground Cover - Whenever land-disturbing activity is undertaken on a tract comprising more than one-half acre, if more than one-half acre is uncovered, the person conducting the land-disturbing activity shall install such sedimentation and erosion control devices and practices as are sufficient to retain the sediment generated by the land-disturbing activity within the boundaries of the tract during construction upon and development of said tract, and shall plant or otherwise provide a permanent ground cover sufficient to restrain erosion after completion of construction or development. Except as provided in Chapter 8, provisions for a ground cover sufficient to restrain erosion must be accomplished within ~~15 working days or 90 calendar days following completion of construction or development whichever period is shorter.~~ **within 14 days of ceasing land disturbance.**
- (3) Prior Plan Approval - No person shall initiate any land-disturbing activity on a tract if more than one-half acre is to be uncovered unless, thirty or more days prior to initiating the activity, an erosion and sedimentation control plan for such activity is filed with and approved by Watauga County, or unless for land-disturbing activity or more than a half acre but less than an acre the requirement for such plan had been waived as specified in Chapter 8. The County will attempt to review plans as quickly as possible. The initiation of land-disturbing activities shall not be restricted when the plan is approved and permit issued in less than 30 days.

Section 3. Design and Performance Standards

- (A) Except as provided in Chapter 8 erosion and sedimentation control measures, structures, and devices shall be so planned, designed, and constructed as to provide protection from the calculated maximum peak rate of runoff from the 10-year storm. Runoff rates shall be calculated using the procedures in the USDA, Soil Conservation Service's "National Engineering Field Manual for Conservation Practices", or other acceptable calculation procedures.
- (B) In High Quality Water (HQW) zones the following design standards shall apply:
- (1) Uncovered areas in HQW zones shall be limited at any time to a maximum total area within the boundaries of the tract of 20 acres. Only the portion of the land-disturbing activity within a HQW zone shall be governed by this section. Larger areas may be uncovered within the boundaries of the tract with the written approval of the Director.

- (2) Erosion and sedimentation control measures, structures, and devices within HQW zones shall be so planned, designed and constructed to provide protection from the run off of the 25-year storm which produces the maximum peak rate of run off as calculated according to procedures in the United States Department of Agriculture Soil Conservation Service's "National Engineering Field Manual for Conservation Practices" or according to procedures adopted by any other agency of this state or the United States or any generally recognized organization or association.
- (3) Sediment basins within HQW zones shall be designed and constructed such that the basin will have a settling efficiency of at least 70% for the 40 micron (0.04 mm) size soil particle transported into the basin by the runoff of that 2-year storm which produces the maximum peak rate of runoff as calculated according to procedures in the United States Department of Agriculture Soil Conservation Service's "National Engineering Field Manual for Conservation Practices" or according to procedures adopted by any other agency of this state or the United States or any generally recognized organization or association.
- (4) Newly constructed open channels in HQW zones shall be designed and constructed with side slopes no steeper than 2 horizontal to 1 vertical if a vegetative cover is used for stabilization unless soil conditions permit a steeper slope or where the slopes are stabilized by using mechanical devices, structural devices or other acceptable ditch liners. In any event, the angle for side slopes shall be sufficient to restrain accelerated erosion.
- (5) Ground cover sufficient to restrain erosion must be provided for any portion of a land-disturbing activity in a HQW zone within ~~15 working days or 60 calendar days following completion of construction or development, whichever period is shorter.~~ **seven (7) days of ceasing land disturbance.**

Section 4. Planning and Design Considerations to Control Erosion and Sedimentation

The following list of considerations, activities, and techniques of development within Watauga County should all be taken into account during the planning phase of a development:

- A. Reducing the Potential for Off-site Sediment Damage
- B. Location of Roads
- C. Soil Types and Properties
- D. Buffer Zones
- E. Construction Techniques
- F. Sequence of Construction and Time of Soil Exposure
- G. Seasonal Construction Scheduling
- H. Clearing and Grubbing
- I. Stream Crossings and Stream Protection
- J. Road Grades and Side Ditches
- K. Road Cut & Fill Slopes
- L. Underground Seepage or Wetlands
- M. Culvert Placement and Sizing
- N. Borrow and Waste Areas
- O. Utility Placement
- P. Roadbed Stabilization
- Q. Floodplain/Floodway
- R. Specifications Guide for Application of Temporary Seeding
- S. Permanent Vegetation
- T. Specifications Guide for Permanent Planting of Vegetation on Road and Right-of-Way

When planning for the considerations listed above, minimum acceptable standards must be adhered to. These standards have been established to control erosion and sedimentation during construction, and also to control erosion during the life-time operation of roads built in Watauga County.

Appendix C Erosion and Sedimentation Plan Checklist

EROSION and SEDIMENTATION CONTROL PLAN PRELIMINARY REVIEW CHECKLIST

The following items shall be incorporated with respect to specific site conditions, in an erosion & sedimentation control plan:

NPDES Construction Stormwater General Permit NCG010000

- _____ Designation on the plans where the 7 or 14 day ground stabilization requirements apply per Section II.B.2 of the permit.
- _____ Design of basins with one acre or more of drainage area for surface withdrawal as per Section II.B.4 of the permit.

LOCATION INFORMATION

- _____ Project location & labeled vicinity map (roads, streets, landmarks)
- _____ North arrow and scale
- _____ Identify River Basin.
- _____ Provide a copy of site located on applicable USGS quadrangle and NRCS Soils maps if it is in a River Basin with Riparian Buffer requirements.

GENERAL SITE FEATURES (Plan elements)

- _____ Property lines & ownership ID for adjoining properties
- _____ Existing contours (topographic lines)
- _____ Proposed contours
- _____ Limits of disturbed area (provide acreage total, delineate limits, and label). Be sure to include all access to measures, lots that will be disturbed, and utilities that may extend offsite.
- _____ Planned and existing building locations and elevations
- _____ Planned & existing road locations & elevations, including temporary access roads
- _____ Lot and/or building numbers
- _____ Hydrogeologic features: rock outcrops, seeps, springs, wetland and their limits, streams, lakes, ponds, dams, etc. (include all required local or state buffer zones and any DWQ Riparian Buffer determinations)
- _____ Easements and drainageways, particularly required for offsite affected areas. Include copies of any recorded easements and/or agreements with adjoining property owners.
- _____ Profiles of streets, utilities, ditch lines, etc.
- _____ Stockpiled topsoil or subsoil locations
- _____ If the same person conducts the land-disturbing activity & any related borrow or waste activity, the related borrow or waste activity shall constitute part of the land-disturbing activity unless the borrow or waste activity is regulated under the Mining Act of 1971, or is a landfill regulated by the Division of Waste Management. If the land-disturbing activity and any related borrow or waste activity are not conducted by the same person, they shall be considered separate land-disturbing activities and must be permitted either through the Sedimentation Pollution Control Act as a one-use borrow site or through the Mining Act.
- _____ Location and details associated with any onsite stone crushing or other processing of material excavated. If the affected area associated with excavation, processing, stockpiles and transport of such materials will comprise 1 or more acres, and materials will be leaving the development tract, a mining permit will be required.
- _____ Required Army Corps 404 permit and Water Quality 401 certification (e.g. stream disturbances over 150 linear feet)

EROSION & SEDIMENT CONTROL MEASURES (on plan)

- _____ Legend (provide appropriate symbols for all measures and reference them to the construction details)
- _____ Location of temporary measures
- _____ Location of permanent measures
- _____ Construction drawings and details for temporary and permanent measures. Show measures to scale on plan and include proposed contours where necessary. Ensure design storage requirements are maintained through all phases of construction.
- _____ Maintenance requirements for measures
- _____ Contact person responsible for maintenance

SITE DRAINAGE FEATURES

- _____ Existing and planned drainage patterns (include off-site areas that drain through project and address temporary and permanent conveyance of stormwater over graded slopes)
- _____ Method used to determine acreage of land being disturbed and drainage areas to all proposed measures (e.g. delineation map)
- _____ Size, pipe material and location of culverts and sewers
- _____ Soil information: type, special characteristics
- _____ Soil information below culvert storm outlets

- _____ Name and classification of receiving water course or name of municipal operator (only where stormwater discharges are to occur)

STORMWATER CALCULATIONS

- _____ Pre-construction runoff calculations for each outlet from the site (at peak discharge points). Be sure to provide all supporting data for the computation methods used (rainfall data for required storm events, time of concentration/storm duration, and runoff coefficients).
- _____ Design calculations for peak discharges of runoff (including the construction phase & the final runoff coefficients for the site)
- _____ Design calcs for culverts and storm sewers (include HW, TW and outlet velocities)
- _____ Discharge and velocity calculations for open channel and ditch flows (easement & rights-of-way)
- _____ Design calcs for cross sections and method of stabilization for existing and planned channels (include temporary linings). Include appropriate permissible velocity and/or shear stress data.
- _____ Design calcs and construction details for energy dissipaters below culvert and storm sewer outlets (include stone/material specs & apron dimensions). Avoid discharges on fill slopes.
- _____ Design calcs and dimension of sediment basins (note current surface area and dewatering standards as well as diversion of runoff to the basins). Be sure that all surface drains, including ditches and berms, will have positive drainage to the basins.

VEGETATIVE STABILIZATION

- _____ Area & acreage to be stabilized with vegetation
- _____ Method of soil preparation
- _____ Seed type & rates (temporary & permanent)
- _____ Fertilizer type and rates
- _____ Mulch type and rates (include mulch anchoring methods to be used)

NOTE: Plan should include provisions for groundcover in accordance with NPDES Construction Stormwater General Permit NCG010000 and permanent groundcover for all disturbed areas within 15 working days or 90 calendar days (whichever is shorter) following completion of construction or development.

FINANCIAL RESPONSIBILITY/OWNERSHIP FORM

- _____ Completed, signed & notarized FR/O Form
- _____ Accurate application fee payable to NCDENR (\$65.00 per acre rounded up the next acre with no ceiling amount)
- _____ Certificate of assumed name, if the owner is a partnership
- _____ Name of Registered Agent (if applicable)
- _____ Copy of the most current Deed for the site. Please make sure the deed(s) and ownership information are consistent between the plan sheets, local records and this form.
- _____ Provide latitude & longitude (in decimal degrees) at the project entrance.

NOTE: For the Express Permitting Option, inquire at the local Regional Office for availability.

NARRATIVE AND CONSTRUCTION SEQUENCE

- _____ Narrative describing the nature & purpose of the construction activity
- _____ Construction sequence related to erosion and sediment control (including installation of critical measures prior to the initiation of the land-disturbing activity & removal of measures after areas they serve are permanently stabilized). Address all phases of construction and necessary practices associated with temporary stream bypasses and/or crossings.
- _____ Bid specifications related only to erosion control

Appendix D Ownership/Financial Responsibility Form

FINANCIAL RESPONSIBILITY/OWNERSHIP FORM SEDIMENTATION POLLUTION CONTROL ACT

No person may initiate any land-disturbing activity on one or more acres as covered by the Act before this form and an acceptable erosion and sedimentation control plan have been completed and approved by the Land Quality Section, N.C. Department of Environmental Quality. Submit the completed form to the appropriate Regional Office. (Please type or print and, if the question is not applicable or the e-mail and/or fax information unavailable, place N/A in the blank.)

Part A.

1. Project Name _____
2. Location of land-disturbing activity: County _____ City or Township _____
Highway/Street _____ Latitude _____ Longitude _____
3. Approximate date land-disturbing activity will commence: _____
4. Purpose of development (residential, commercial, industrial, institutional, etc.): _____
5. Total acreage disturbed or uncovered (including off-site borrow and waste areas): _____
6. Amount of fee enclosed: \$ _____.
7. Has an erosion and sediment control plan been filed? Yes _____ No _____ Enclosed _____
8. Person to contact should erosion and sediment control issues arise during land-disturbing activity:
Name _____ E-mail Address _____
Telephone _____ Cell # _____ Fax # _____
9. Landowner(s) of Record (attach accompanied page to list additional owners):

Name	Telephone	Fax Number
Current Mailing Address	Current Street Address	
City State Zip	City State Zip	
10. Deed Book No. _____ Page No. _____ Provide a copy of the most current deed.

Part B.

1. Company (ies) or firm(s) who are financially responsible for the land-disturbing activity (Provide a comprehensive list of all responsible parties on an attached sheet.) *If the company or firm is a sole proprietorship the name of the owner or manager may be listed as the financially responsible party.*

Name	E-mail Address
Current Mailing Address	Current Street Address
City State Zip	City State Zip

Telephone _____ Fax Number _____

2. (a) If the Financially Responsible Party is not a resident of North Carolina, give name and street address of the designated North Carolina Agent:

_____ Name	_____ E-mail Address
_____ Current Mailing Address	_____ Current Street Address
_____ City	_____ City
_____ State	_____ State
_____ Zip	_____ Zip
_____ Telephone	_____ Fax Number

- (b) If the Financially Responsible Party is a Partnership or other person engaging in business under an assumed name, **attach a copy of the Certificate of Assumed Name**. If the Financially Responsible Party is a Corporation, give name and street address of the Registered Agent:

_____ Name of Registered Agent	_____ E-mail Address
_____ Current Mailing Address	_____ Current Street Address
_____ City	_____ City
_____ State	_____ State
_____ Zip	_____ Zip
_____ Telephone	_____ Fax Number

The above information is true and correct to the best of my knowledge and belief and was provided by me under oath (This form must be signed by the Financially Responsible Person if an individual or his attorney-in-fact, or if not an individual, by an officer, director, partner, or registered agent with the authority to execute instruments for the Financially Responsible Person). I agree to provide corrected information should there be any change in the information provided herein.

_____ Type or print name	_____ Title or Authority
_____ Signature	_____ Date

I, _____, a Notary Public of the County of _____

State of North Carolina, hereby certify that _____ appeared personally before me this day and being duly sworn acknowledged that the above form was executed by him.

Witness my hand and notarial seal, this _____ day of _____, 20_____

Seal

Notary
My commission expires _____

Appendix E Preliminary Plat Checklist

FOR SUBDIVISION RECORD _____ DATE SUBMITTED _____

NAME OF SUBDIVISION _____

LOCATION _____

OWNER _____

LAND PLANNER _____ ADDRESS _____

SURVEYOR _____ ADDRESS _____

CHECKLIST

1. Surveyor shall submit CHECKLIST with signed certification stating that plat complies with Subdivision Regulations.
2. Vicinity map embracing subdivision and surrounding area.
3. SCALE: 1" = 100' or larger. In EXTREME cases may be 1" = 200'. One (1) electronic copy of plat.
4. Name of subdivision and owner.
5. North point, graphic scale, date.
6. Boundaries of the tract shown with distances and approximate acreage.
7. Names of adjoining property owners or subdivisions.
8. The locations of existing sewers and water facilities and other utilities if any.
9. The locations of existing streets, easements, bridges, culverts, watercourses, etc.
10. Name, location and approximate dimensions of proposed streets, easements, parks and reservations, lot lines, etc.
11. Proposed lot lines, building lines and approximate area.
12. Lot numbers, if any.
13. Types of proposed utilities shown or described.
14. Proposed minimum building setbacks (typical section).
15. Location of existing water areas/floodway/floodplain, if applicable, as delineated by the flood insurance rate maps.
16. Upon approval of Preliminary Plat, 3 copies of a sufficient soil erosion plan shall be submitted to the planning staff.

17. This plat conforms to general requirements and minimum design standards.

~~18. Evidence of NCDOT driveway connection permit.~~

19. Evidence of access right-of-way.

20. Statement of average cross slope if applicable.

COMMENTS:

Appendix F Final Plat Checklist

FOR SUBDIVISION RECORD _____ DATE SUBMITTED _____

PRELIMINARY APPROVAL DATE _____

NAME OF SUBDIVISION _____

LOCATION _____

OWNER _____ ADDRESS _____ TEL. _____

ENGINEER _____ ADDRESS _____ TEL. _____

SURVEYOR _____ ADDRESS _____ TEL. _____

CHECKLIST

1. Submitted to the Planning Staff within 18 months of preliminary approval ~~and two (2) weeks prior to the scheduled meeting of the Planning Board.~~
2. Eight (8) copies of final plat. One reproducible (Sepia) and seven paper copies. One (1) electronic copy of plat.
3. A sketch vicinity map showing location in relation to the surrounding area.
4. SCALE: 1" = 100' or larger.
5. Names, right-of-way, lines and easements of streets and roads.
6. Minimum building setback lines when applicable.
7. Lot lines, numbers, and/or tract numbers.
8. Reservations, easements, public areas, of sites for other than residential use with explanation of purpose.
9. North point, graphic scale, date.
10. Location and description of monuments.
11. Names and location of adjoining subdivisions and streets and the location and ownership of adjoining unsubdivided property.
12. Conforms to general requirements and minimum design standards.
13. Required improvements have been made or \$_____ bond posted.
14. Required certificate for Recordation.
15. Location of existing water Areas/Floodway/Floodplain, if applicable, as delineated by the Flood Insurance Rate Maps.

16. Types of proposed utilities shown or statement that individual lots have or have not been approved for septic tank use by AppHealthCare.
17. Density in units per acre.
18. Culvert/drainage facility location and size.
19. Variances granted, if any.

ON-SITE FIELD INSPECTION (DATE) _____

PERSONS MAKING INSPECTION _____

COMMENTS:

Appendix G Subdivision Specifications Checklist

1. Plat fee paid.
2. Variance requested in writing.
3. Bond to be submitted.
4. Meets floodplain regulations.
5. Acceptable average cross slope.
6. Roads:
 - (a) State
 - (b) County. If County then:
 - _____Meets criteria permitting county standards.
 - _____Meets right-of-way requirements.
 - _____Meets road bed requirements.
 - _____Sufficient drainage provided.
 - _____Meets grade requirements.
 - _____Meets curve radius requirements.
 - _____Sufficient turnarounds provided.
 - _____Meets bridge requirements.
 - (c) Access road meets right-of-way requirements.
7. Lots:
 - _____Meet frontage requirements.
 - _____Meet area requirements.
 - _____Panhandles used.
 - _____Meet access requirements.
 - _____Private drives used.
8. Meets building setback requirements.
9. Sufficient erosion control plan submitted.
10. Property owner's association rules established.
11. Compliance with other applicable local regulations (zoning, etc.).

Appendix H Method of Defining Slope

The chief source of information for determination of slope is a contour map. The contour map supplies the necessary data for using the following formula to determine the average slope of a parcel:

$$S = \frac{.0023 \times I \times L}{A}$$

Where .0023 is a conversion factor, of square feet to acres, "I" is the contour interval (or the distance between adjacent contour lines on the map) in feet, "L" is the total length of the contour lines within the subject parcel, and "A" is the area in acres of the subject parcel.

Step 1. Determine "I", the contour interval, by examining the interval, using the key on the map. For purposes of this example, an interval of five feet is used. (To achieve accuracy within one percent, the contour interval must be 10 feet or less).

Step 2. Determine "L", the total length of the contour lines within the subject area, by tracing each line with a planimeter or similar device and converting to feet. In this example, "L" is 1,000 feet.

Step 3. Determine "A", area (in acres) from the development plans or permit application. In this example, "A" is 5 acres.


Step 4. Determine "S" by using the equation:

$$S = \frac{.0023 \times 5 \times 1,000}{5} = 2.3 \text{ percent average slope}$$

NOTE: Other methods of calculating average cross slope - using computer mapping/GIS technology - may be acceptable.

Slope Measurement

Use this slope measuring aid in the field. Hold the dashed line horizontal and match the slope of the embankment to one of the slopes here. A transparent version of this aid, that can be lined up directly on the slope, can be made by copying this page onto clear transparency film.



Appendix I Minor Bridge Maintenance Checklist

(A) Bridge Approach

- (1)** Check Signs on both ends of bridge.
Warning and Information Signs (straighten, clean, and cut weeds).
Bridge End Markers (clean and visible).
Check Guard Rails along approach (repair and straighten).
- (2)** Clear Weed, Brush, and Overhanging Limbs.
Require clear visibility of bridge.
Police and clean area around bridge.
Remove all debris from site.

(B) Side Ditches and Stream Channel

- (1)** Clear side ditches of all brush, weeds and debris.
- (2)** Clear debris and obstructions from stream channel through full width of R.O.W.
- (3)** Eliminate all brush growing under the bridge.

(C) Erosion of Bridge Approach

- (1)** At gutter line on shoulder - fill any eroded areas.
- (2)** At gutter line, build (if needed) paved channel to carry water to side ditch at non-erosive velocity.
- (3)** Check shoulders for erosion signs - fill and tamp erosion channels.

(D) Condition of Approach Road Traffic Lanes

- (1)** Fill all ruts.
- (2)** Check transition from road to bridge - must be smooth.
- (3)** Build short bituminous ramp to provide transition in difficult cases.

(E) Bridge Structure

(1) Cleaning Deck

Clean all dirt, gravel, trash and debris from deck. Clear all gutters and all drainage outlets.
Remove any obstructions causing ponding of water. Direct deck drains away from all structural components.

(2) Deck Maintenance (Wood Decks)

Check transverse planking for breaks, rotting, or any weakness. Replace individual planks if needed. Check longitudinal "tread" planks for damage, excessive wear, breaks, shattering, looseness or rot. Replace damaged planks - re-nail old planks if required. Pull any protruding nails and replace.

(3) Deck Maintenance (Concrete Decks)

Clean, check depth, and flush all open cracks. Dry such cracks and fill totally with liquid asphalt or other such sealing

compound. Make notes on any system of patterned crack and report them to road supervisor. For small shrinkage cracks (those not fully opened) check with road supervisor about a spray coat sealant. Pop-outs, surface deterioration, or chuck holes in deck must be cleaned thoroughly and packed smooth with bituminous road surface mixture. Provide a mechanical "lock" to hold patch in place. Eliminate "low" spots to prevent water ponding.

(F) Expansion Joints

Deck expansion joints should be identified and cleaned. Remove dirt, gravel, debris and other obstructions from expansion joint opening. Do this when bridge is cool so joint is as wide open as possible. For open expansion joint slot, fill the opening with an elastic joint sealer compound or a special compressible composite joint filler. For plate covered joint slot, clean the sliding surface of any obstructions and treat sliding surface if necessary to make it free operating.

(G) Bridge Structural Components

(1) Truss Bridges

Clear debris from truss joints, flanges of truss members, or any pockets that have collected debris, gravel or dirt.

(2) Girders and Beams

Clear any debris found on flanges or on any bracing occurring on the structure.

(3) Handrails and Curbs

Repair any bent, broken, or missing parts of the bridge handrail or curbs.

(4) Bearing Devices

Bearing devices are points where bridge structure is attached to the substructure (piers, abutments, or other supports). Identify the "fixed" and movable bearings. Clear all dirt, disintegrated concrete, debris of any kind which collects around the bearings - fixed or movable. Especially clear any obstruction that would prevent movable support from being able to function. Once cleared, spray with oil to prevent rusting and to assist movement.

(H) Substructure

(1) Abutments

Note cracking of main wall or wing wall. Assess serious movement of any part of the abutment. Report out-of-plumb components and any serious deterioration of the abutment. Note any erosion of stream that may undermine the abutment, and eliminate cause. Fill and tamp any rodent holes along base of the abutment and its wing walls.

(2) Piers

Note and correct any water drainage on pier or the pier cap. Note any cracks or deterioration of pier. Repair where possible. Check for undermining of pier foundation and correct cause if possible. Check pier for "plumb-ness" or any signs of movement.


Source: Minor Maintenance Manual For County Bridges, Highway Extension and Research Project for Indiana Counties and Cities, Purdue University, 1984.

Appendix J Buffering and Screening


- (A) Where a PUD is proposed adjacent to a single family residential use, side and rear yard setback of 30 feet shall be observed for buildings, parking, or storage. This area is to be used as a buffer and shall be landscaped as follows. Buffers shall consist of plantings of evergreen and/or deciduous trees spaced no more than thirty (30) feet apart. Such trees shall be at least six to seven (6-7) feet tall for evergreens and six to eight (6-8) feet tall with a one and one half (1-1/2) inch caliper (trunk diameter 6 inches above grade) for deciduous trees at time of planting and shall reach a height of no less than twenty (20) at maturity. Where utility easements conflict with this height requirement, the requirement may be lessened at the discretion of the Planning Staff. In addition, plantings of low growing shrubs, and/or trees shall be placed at ten (10) foot intervals. Plantings within buffer zones shall be staggered unless topography is prohibitive. No planting shall be placed in the road right-of-way. Lists of recommended plantings are available from the Planning and Inspections Department.
- (B) Where a PUD is proposed adjacent to a commercial or multi-family use side and rear yard setback of 15 feet shall be observed for buildings, parking, or storage. This area is to be used as a buffer and shall be landscaped as follows. Buffers shall consist of plantings of evergreen and/or deciduous trees spaced no more than thirty (30) feet apart. Such trees shall be at least six to seven (6-7) feet tall for evergreens and six to eight (6-8) feet tall with a one and none half (1-1/2) inch caliper for deciduous trees at time of planting and shall reach a height of no less than twenty (20) feet at maturity, unless reduced by staff due to utility easements. In addition, permanent ground cover such as grasses shall be established.
- (C) Walls, fences, earthen berms, or other natural features may be used in combination with or in lieu of planted buffers if approved as part of a permit. Considerations include but are not limited to:
- (1) Any existing significant vegetation within the buffer(s) may be preserved and credited towards meeting the standard for the required buffer. Existing fences, berms and or walls within the buffer(s) may be used to fulfill the standards set forth for the buffer providing these elements are healthy and in a condition of good repair. Chain link fencing is not acceptable in meeting the performance criteria of this ordinance.
 - (2) Installation of supplemental vegetation and/or site features may be required at the time of site plan review, if existing

vegetation and/or site features within the buffer do not meet or exceed the requirements of this ordinance.


- (D) Open storage areas, exposed machinery and outdoor areas used for the storage and collection of rubbish must be visually screened from roads and surrounding land uses. Suitable types of screening include opaque wood fences and dense evergreen hedges of six (6) feet or more in height. Where evergreen hedges are proposed, a temporary fence should be built to provide screening until the evergreens are of sufficient height.




Appendix K Fire Apparatus Access Roads



96' CUL-DE-SAC




60-foot Y



120' HAMMERHEAD

**Acceptable
Alternative to 120'
HAMMERHEAD**
(Drawings not to scale)



Appendix L Affordable Workforce Housing Policy

Section 1. Background.

The generally accepted definition of affordability is for a household to pay no more than 30 percent of its annual income on housing. An estimated 12 million renter and homeowner households now pay more than 50 percent of their annual income on housing. The lack of affordable housing is a significant hardship for low-income and working households and prevents them from meeting other basic needs, such as food, clothing, transportation and medical care.

Availability of housing for all income levels is critical for balanced and healthy growth of the County. Employers seeking to locate in Watauga County need to first attract and then maintain a workforce. A key component to workforce recruitment and retention is affordable and centrally located housing. Job satisfaction becomes more of a challenge when workers can only find affordable housing by living far from their jobs and enduring long commutes.

Section 2. Policy.

The county will seek to work with the developers and nonprofit housing organizations to provide for affordable units in developments and ensure that such units are compatible with other homes in the development. Affordable units should include both units for sale and units for rent. Developers should promote a design criterion that disperses affordable homes throughout a development and encourages a variety of housing types.

Section 3. Streamlined Permitting Process.

Improved coordination of the permitting process at the state and local levels could result in lower housing costs. The permitting process often involves dealing with city, county and state approval boards, all of which require a variety of permits and approvals (i.e. – fire protection, sewer hookup, plumbing, environmental, road construction, electrical, building, etc.). Often the various levels of governmental authorities do not have effective communication and co-approval systems, which cause unnecessary delays, increase construction costs and ultimately hinder affordable housing.

Section 4. Density.

Real estate of all types flourishes best in livable communities that offer a high quality of life at a reasonable cost. Livable communities offer a variety of affordable housing choices, good schools, quality public services, open space, and a strong employment base. One of the most challenging aspects to promoting these essential livable community elements is density. Building at higher densities in the appropriate locations is vital to provide greater choice and affordability in housing.

Section 5. Employer-Assisted Housing.

Employer-assisted housing (EAH) refers to benefits that enable employees to purchase homes or secure affordable rental housing, often within designated neighborhoods located near the workplace. Benefits can take a number of forms, including grants or forgivable loans for down payments and closing costs, reduced-cost financing, and matched savings plans. Providing an EAH benefit can help employers reduce turnover, leading to lower training and hiring costs. In addition, EAH can increase loyalty and morale, support bottom-line business goals, and strengthen links with the local community.

Appendix M Developer Authorization Form

For projects being developed by person(s) other than land owner(s)

Name of Project: _____

Land Owner(s) _____

Developer(s) _____

The above-named Developer(s) is/are authorized to submit the subject project to Watauga County for development approval on behalf of the above-named Land Owner(s).

Land Owner(s) Signature

Date

_____	_____
_____	_____
_____	_____

STATE of _____, COUNTY of _____

I _____, Notary Public for said County and State, do hereby certify that _____ personally appeared before me this day and acknowledged that the above form was executed by him / her.

This _____ day of _____, 20__.

(notary signature)

My commission expires: _____, 20__. PLACE NOTARY SEAL ABOVE

CHAPTER 19 REGULATION OF RECREATIONAL VEHICLE SUBDIVISIONS

Article I Authority and Enactment Clause

The County Commissioners of the County of Watauga, pursuant to the authority conferred by Chapter 160D-Article 8 and Chapter 130 Section 17 of the General Statutes of the State of North Carolina, enact into law these Articles and Sections.

Article II Jurisdiction and Purpose

Section 1. Jurisdiction.

On and after the date of adoption, these regulations shall govern each and every subdivision of land to be developed and sold for use by recreational vehicles within Watauga County (hereinafter referred to as the "county") and outside the subdivision regulation jurisdiction of any incorporated municipality. As used herein the term "sell", in addition to its standard meaning, shall also mean the rental or lease of any real property, the term of which or any pre-existing renewal thereof shall total twelve months or more.

Section 2. Purpose.

The purpose of these regulations for recreational vehicle subdivisions is to guide and regulate the subdivision of land within the county in order to preserve the public health, safety and welfare. The regulations included herein are designed to insure an adequately planned street system and to avoid sharp curves, hazardous intersections; to secure safety from fire, panic, and other dangers; to provide for adequate water and sewage systems; to facilitate an orderly system for the design, layout, and use of the land; to insure the proper legal description and monumenting of subdivided land; and to provide for the resubdivision of large land parcels.

Section 3. Permits.

- (A) No person shall operate a recreational vehicle subdivision within the County of Watauga unless s/he holds a valid certification from the Health Department in the name of such a person for the specific recreational vehicle subdivision. Final plat approval will be made by the Planning Board provided all requirements of this chapter are met.
- (B) Recreational Vehicle Permanent Occupancy Prohibited.

- (1) No recreational vehicle shall be used as permanent place of abode, dwelling or business.
 - (2) Any action toward removal of wheels of a recreational vehicle except for temporary purposes of repair is hereby prohibited.
 - (3) No recreational vehicle shall be anchored or permanently affixed in a flood plain area.
- (C) No person shall construct, alter or extend any recreational vehicle subdivision within the County of Watauga until the following has been obtained:
- (1) Proper certification from the Health Department,
 - (2) Final plat approval from the Watauga County Planning Board, and
 - (3) A building permit from the Building Inspector.

Article III Planning Board Review

No real property within the jurisdiction of this chapter shall be subdivided and offered for sale or a plat thereof recorded until a preliminary and final plan has been reviewed and approved by the Planning Board as provided hereinafter.

Article IV Procedures For Review And Approval Of Subdivisions

Section 1. Submission of Preliminary Plan to Planning Board.

A preliminary plan meeting the requirements of these regulations shall be submitted for review and shall be approved by the Planning Board before any improvements are made in a subdivision. ~~Two copies of this plan shall be submitted to the Planning Staff at least ten (10) working days before the meeting of the Planning Board at which time it is to be reviewed. One of these copies shall be transmitted to the Health Department for recommendations concerning water and sewerage systems.~~

After receiving approval of the preliminary plan by the Planning Board (and not before that time), the subdivider may proceed to construct improvements in accordance with the requirements of the regulations and as shown on the approved preliminary plan, and to prepare and submit the final plat. ~~The subdivider shall submit the final plat to the Planning Board within eighteen (18) months from the approval of the preliminary plan.~~

Section 2. What the Preliminary Plat Shall Show.

The preliminary plat shall be drawn at a scale of not less than one hundred (100) feet to the inch on sheets 18 x 24 inches and shall show the following on one (1) or more sheets:

- (A) A sketch vicinity map showing the relationship between the proposed subdivision and the surrounding area.
- (B) The name of the RV subdivision, the names and addresses of the owner(s) and designer.
- (C) Date, approximate north arrow and scale.
- (D) The boundary line of the tract with bearings and distances drawn to scale.
- (E) The locations of existing and platted property lines, streets, buildings, water courses, railroads, bridges, water mains, sewers, culverts, drain pipes, and utility easements, both in the proposed recreational vehicle park and on land immediately adjoining 100 feet in all directions and the names of adjoining subdivisions or the names of owners of record of adjoining parcels of unsubdivided land.
- (F) The names, proposed location and dimension of proposed streets, alleys, driveways, entrances, exits, walkways, easements, recreation areas, and other spaces, reservations, proposed lot lines, lot and block numbers with approximate dimensions, and parking lines within the park. This information should be graphical only, not requiring detailed computations of field work above that required to obtain the above information.
- (G) Plans and proposed location of a service building consisting of toilet and shower facilities if required by Health Department.
- (H) Plans of proposed utility layouts (sewer lines, septic tank drainfields, water line and storm drainage) showing feasible connections to existing and proposed utility systems.
- (I) Where public water or public sewer is not available, a written statement from the Health Department shall be submitted with the recreational vehicle subdivision preliminary plan indicating that the recreational vehicle subdivision has adequate land area and suitable soil characteristics and topography to accommodate the proposed methods of water supply and sewage disposal.
- (J) Location and number of garbage receptacles.
- (K) Plan for electric lighting.
- (L) Plan showing measures to be taken to prevent soil erosion and off-site sedimentation damage.

Section 3. Submission of Final Plat to Planning Board.

Prior to the submission of the final plat all improvements proposed and approved on the preliminary plat shall be completed to meet the requirements. ~~Unless a final plat is submitted to the Planning Board within eighteen (18) months from the date on which the preliminary plat was approved, such action on the preliminary plat shall become void and of no effect, unless prior to the expiration of said time the Planning Board extends the time for good cause shown. A final plat meeting the requirements of these regulations shall be submitted least ten (10) working days prior to the meeting of the Planning Board at which it is to be considered. Copies of the plat shall be distributed in the same manner as copies of the preliminary plan.~~

Section 4. What the Final Plat Shall Show.

The final plat shall be drawn upon a reproducible material such as linen or mylar on sheets of 18 x 24 inches in size to a scale of not less than one inch equals one hundred (100) feet. It shall contain the following:

- (A) A vicinity map showing the location of the subdivision in relation to the surrounding area.
- (B) The name of the recreational vehicle subdivision, the names and addresses of the owner(s) and the engineer or registered surveyor who prepared the plat.
- (C) Date, north arrow, and scale.
- (D) The boundary line of the tract with bearings and distances drawn to scale.
- (E) The names, location and dimensions of streets, alleys, driveways, entrances, exits, walkways, easements, recreation areas, parks and other open spaces, reservations, lot lines, lot and block numbers with accurate bearings and distances, and parking lines within the park. The information shall be drawn accurately with details, computations, and fieldwork completed with all lot corners established on the ground with an iron pin or other permanent marker.
- (F) If the RV subdivision is located in a flood plain area, developer shall submit to the Planning Board with the final plat a workable evacuation plan in accordance with the Flood Damage Prevention regulations.

_____ for recording in the Office of the County Register of Deeds.

DATE Watauga County Authorized Representative

(D) Surveyors Certificate
NORTH CAROLINA
WATAUGA COUNTY

_____ being duly sworn says the plat shown hereon is in all respects correct to the best of his knowledge and belief and was prepared from an actual field survey supervised by him and completed _____.

REGISTERED LAND SURVEYOR NO.

Subscribed and sworn to before me this the _____ day of _____, 20____.

Notary Public

My commission expires:

Section 7. Appeal by Developer.

If either a preliminary or final plat is not approved by the Planning Board the subdivider may appeal his case to the Superior Court of Watauga County within 30 days.

Section 8. Feasibility Plan.

A subdivider may submit a sketch to the Ordinance Administrator prior to submission of a preliminary plan if s/he wishes to ascertain the feasibility of development of his/her property.

Section 9. Minor Subdivisions.

- (A) Procedures set forth herein for handling applications for approval of minor subdivisions are intended to simplify processing of routine small subdivision with due regard to protection of the public interest.
- (B) For the purpose of these regulations, a minor subdivision is defined as any subdivision requiring no variances and consisting of not more than ten (10) lots.

- (C) In lieu of the procedures set forth in this ordinance, the subdivider may receive preliminary approval for any minor subdivision through procedures set forth as follows:
- (1) The Ordinance Administrator shall review the preliminary plat of each minor subdivision and shall find that it either is or is not a minor subdivision and that it either does or does not meet the requirements of these regulations. Said findings shall be stated in writing and recorded in the records of the Planning Board. Based upon said findings the Department shall either approve, not approve, or approve conditionally the proposed minor subdivision.
 - (2) ~~A decision by the Administrator shall be made within fifteen (15) days of submission of the proposed minor subdivision and The decision of the administrator is subject to appeal in writing by the subdivider to the Planning Board., which must act on appeals at its next regular meeting provided said written appeal is filed with the Planning Board or their designee ten (10) working days prior to said meeting.~~
- (D) A final plat shall be submitted to the Watauga County Planning Board for their consideration and approval before the conveyance of any of the property or the recordation of the plat.
- (E) After approval, the Subdivision Plat shall be recorded with the Watauga County Register of Deeds within thirty (30) days.

Article V Environmental, Open Space and Access Requirements

Section 1. Environmental, Open Space and Access Requirements.

- (A) General Requirements. Conditions of soil, groundwater level, drainage and topography shall not create hazards to the property or the health or safety of the occupants.
- (B) Floodplain Development. Recreational Vehicle Subdivisions may be permitted to develop in designated floodplain areas but not permitted in the floodway. Developer shall indicate the floodplain and floodway on the plat and evacuation plans shall be established and submitted to the Planning Board for approval consideration prior to approval of final plat. Any improvements shall meet the applicable requirements of the Watauga County Flood Damage Prevention Regulations.
- (C) Soil and Ground Cover Requirements. All ground areas in all parts of every Recreational Vehicle Subdivision shall be paved or covered with stone screenings or other solid material or protected with a vegetative growth that is capable of preventing soil erosion and of eliminating objectionable dust.

- (D) Required Separation Between Recreational Vehicles. Recreational vehicles shall be separated from each other and from other structures by at least 20 feet. Any accessory structure such as attached awnings or individual storage facilities shall, for the purposes of this separation requirement, be considered to be part of the recreational vehicle.
- (E) Required Recreation Area. In all Recreational Vehicle Subdivisions there shall be at least one recreation area which shall be easily accessible from all recreational vehicle spaces. A minimum of twenty percent (20%) of the total lot area of the park shall be dedicated for open, undeveloped recreational use.
- (F) Required Setbacks from Public Streets. All recreational vehicles shall be located at least 30 feet from the right-of-way of a public street or highway.
- (G) RV Subdivision Street System
 - (1) General Requirements. All parking areas shall be provided with safe and convenient vehicular access from abutting public streets or roads to each recreational vehicle space. All roads shall be constructed to meet the requirements of the county standard roads as specified in the Watauga County Subdivision Regulations, with the exception of the road right-of-way which may be 30 feet.
 - (2) Access. Access to recreational vehicle subdivisions shall be designed to minimize congestion and hazards at their entrance and exit and to allow free movement of traffic on adjacent streets. All traffic into and out of the parking areas shall be through such entrances and exits.
 - (3) Off-Street Parking and Maneuvering Space. Each lot in a recreational vehicle subdivision shall provide one vehicle parking space in addition to the space occupied by the towing vehicle (if any). Sufficient maneuvering space shall be provided so that parking, loading or maneuvering of recreational vehicles incidental to parking shall not necessitate the use of any public street, sidewalk, or right-of-way or any private grounds not part of the recreational vehicle subdivision.
 - (4) Traffic Signs. For safety purposes, traffic signs shall be erected designating traffic flow and speed limits. Such signs shall be constructed of permanent material and shall conform substantially to acceptable traffic speeds and sign applications in semi-congested areas.

Section 2. Miscellaneous Requirements.

- (A) Supervision and Continued Maintenance. The person to whom a permit is issued shall be the responsible party for operation and maintenance of the recreational vehicle subdivision in compliance with these regulations and shall further provide adequate supervision to maintain the recreational vehicle subdivision, its facilities and equipment in good repair and in a clean and sanitary condition at all time until at such time an Owners Association shall assume responsibilities as designated by the Developer.
- (B) Owners Association Agreement and Declaration of Restrictions for Recreational Vehicle Subdivisions. Prior to approval of the final plat the subdivider/developer shall submit to the County Planning Board copies of an Owners Association Agreement and Declaration of Restrictions, Conditions, Easements, Covenants, Liens and Charges. Said Agreement shall provide that membership in the Owners Association shall be appurtenant to ownership of land in the subdivision and that the Association is empowered to assess the members for their respective portion of costs of continued maintenance, including but not restricted to road and all utilities, grounds and other improvements and property owned by the Association and the payment of taxes.

Article VI Effective Date.

These regulations shall be in full force and effect from and after June 7, 1982.

The foregoing regulations were initially adopted at meetings of Watauga County Board of Commissioners at Boone, North Carolina, on May 18 and June 7, 1982.

CHAPTER 20 VALLE CRUCIS HISTORIC DISTRICT

Article I General Provisions

Section 1. Purposes.

The Watauga County Board of County Commissioners, mindful of the historic significance of the Valle Crucis community and in furtherance of the protection of the public health, safety, morals and general welfare, enacts this chapter for the following purposes:

- (A) To preserve and protect the heritage of the Valle Crucis community in Watauga County.
- (B) To protect and conserve individual properties within the Valle Crucis community that embody important elements of Valle Crucis' and Watauga County's social, economic, cultural, political or architectural history.
- (C) To promote the conservation of the Valle Crucis Historic District for the education, pleasure and enrichment of the Valle Crucis community, Watauga County and the State of North Carolina.
- (D) To foster civic beauty and amenity within the Valle Crucis Historic District.
- (E) Contribute to the improvement of the general health and welfare of the residents of the Valle Crucis Historic District and Watauga County.

Section 2. Legislative Authority.

This chapter is enacted pursuant to Chapter 160D, Article 9, Part 4 as amended, North Carolina General Statutes, for the purposes enunciated therein.

The regulations contained in this chapter are made with reasonable consideration, among other things, as to the character of the District and its peculiar suitability for particular uses and with a view to conserving the value and integrity of buildings and encouraging the most appropriate use of land throughout the District.

Article II Historic District and Historic Preservation Commission

Section 1. Historic District Established.

The Valle Crucis Historic District is hereby established.

The boundaries of the Historic District are as shown on the map entitled "Map of the Valle Crucis Historic District". This map, together with all lawfully adopted explanatory matters shown thereon or therewith, is hereby adopted by reference and declared to be a part of this chapter.

Section 2. Application of Regulations.

No building, structure, or land shall hereafter be used or occupied and no building, structure or part hereof shall be hereafter erected, reconstructed, moved, demolished, located or the exterior structurally altered except in conformity with regulations set out herein for the District.

Section 3. Exemption of Bonafide Farms and Public Schools.

This ordinance shall not be applicable to bonafide farms, as set forth in NCGS 160D-903, but any use of farm property for non-farm purposes is subject to the regulation. Bona fide farm purposes include production of crops, fruits, vegetables, ornamental and flowering plants, dairy, poultry, and all other forms of agricultural products having a domestic or foreign market. Sections 4 and 5 shall not be applicable to public schools.

Section 4. Area, Height and Placement Standards.

Standards governing minimum lot area and width, required yards and maximum height shall be as shown below:

	Residential Uses	All Other Uses
Minimum Lot Size	21,780 Sq. Ft.	21,780 Sq. Ft.
Minimum Lot Width	75'	75'
Minimum Required Yards:		
Front (Edge of Pavement)	50'	50'
Side	15'	30'
Rear	20'	20'
Maximum Building Height	30'	30'

Additional requirements may also be applicable for some development (e.g. development consisting of more than one unit)

Section 5. Performance Standards.

All land uses subject to this ordinance shall comply with the performance standards defined herein.

(A) Buffer Zones

Where a commercial or multi-family use is proposed adjacent to a single-family residential use, a side yard setback of 30 feet shall be observed for buildings, parking, or storage. This area is to be used as a buffer zone and shall be landscaped as follows. Buffers shall consist of plantings of evergreen and/or deciduous trees spaced no less more than thirty (30) feet apart. Such trees shall be at least six to seven (6-7) feet tall for evergreens and six to eight (6-8) feet tall with a one and one half (1-1/2) inch caliper (trunk measured six (6) inches above grade) for deciduous trees at time of planting and shall reach a height of no less than twenty (20) feet at maturity. In addition, plantings of low growing shrubs, and/or trees shall be placed at ten (10) foot intervals. Plantings within buffer zones shall be staggered unless topography is prohibitive. No planting shall be placed in the road right-of-way. Lists of recommended plantings are available from the Planning and Inspections Department. Where commercial or multi-family use is proposed adjacent to commercial or multi-family use the same requirements apply with the exception of the low growing shrubs.

The recipient of any permit, or his successor, shall be responsible for maintaining all common areas, improvements of facilities required by this ordinance or any permit issued in accordance with its provisions, except those areas, improvements, or facilities with respect to which an offer of dedication to the public has been accepted by the appropriate public authority. As illustrations, and without limiting the generality of the foregoing, this means that private roads and parking areas, water and sewer lines, and recreational facilities must be properly maintained so that they can be used in the manner intended, and required vegetation and trees used for screening, landscaping, or shading must be replaced if they die or are destroyed.

(B) Parking

~~All uses other than single-family residential shall have at least two (2) off-street parking spaces per dwelling unit or as follows:~~

- ~~(1) Parking space for commercial uses shall consist of one (1) off street parking space for each two hundred (200) square feet of gross floor area.~~
- ~~(2) Bed and breakfasts, hotels, motels, or and commercial use of this nature shall have parking based on one and one half (1-1/2) parking spaces per bedroom (fractions shall be rounded up to next whole number).~~
- ~~(3) Loading/unloading space for commercial uses shall consist of one (1) space at least three hundred (300) square feet in size for each five thousand (5000) square feet of gross floor area. A minimum of one (1) loading/unloading space is required regardless of floor area square footage.~~

All development shall be provided with adequate parking facilities to handle the expected number of automobiles for that site. Spaces shall be provided as follows; use and occupancy classifications for buildings are the same as those definitions used in the N.C. Building Code.

(a) Assembly, business, educational, storage and mercantile uses and occupancies shall be provided with parking spaces as follows:

- (i.) one (1) off-street parking space for each two hundred (200) square feet of gross floor area for operations designed to attract and serve customers and clients on the premises;
- (ii.) one (1) off-street parking space for each four hundred (400) square feet of gross floor area for operations designed to attract little or no customer or client traffic other than employees of the operation;
- (iii.) one (1) off-street parking space for each one thousand (1000) square feet of gross floor area for mini-warehouse uses.

(b) Factory Industrial uses and occupancies shall be provided with 1.5 spaces per three employees, computed on the total employment.

(c) Institutional uses and occupancies shall be provided with one space per five persons identified in the building's occupant load figures.

(d) Residential uses and occupancies, primarily permanent, shall be provided with 2 spaces per dwelling unit.

(e) Residential uses and occupancies, primarily transient (motels, hotels and inns), shall be provided with one and one-half (1.5) spaces per bedroom.

(C) Screening of Parking

Parking and loading/unloading areas shall be located at the rear or side of buildings. ("Front" is defined as the face of the building that is parallel to a public road. By this definition, buildings or multiple public road frontage lots would have multiple "front yards" thereby limiting the location of parking areas to the remaining side or rear yards.) Side-yard parking areas that are exposed to a public road shall be screened so as to eliminate visual contact from the road(s). Such screening shall consist of a ten (10) foot wide planting of evergreen trees at ten (10) foot intervals. The trees shall be at least four (4) feet high at planting (2" caliper) and shall reach a height of no less than twenty (20) feet at maturity.

(D) Density

Any proposed development consisting of more than one unit shall comply with the Watauga County Subdivisions and Multi-Unit Structures regulations, Articles VIII and X as applicable as well as any additional or stricter requirements imposed by this ordinance. However, the maximum overall density shall not exceed one (1) unit per acre. The goal sought by this standard is the reservation of perpetual open (green) space. To that end, an impervious surface ratio of twelve (12) percent is established. Impervious surface is defined as surfaces that do not absorb water. They consist of all buildings, parking areas, driveways, road, sidewalks, and any areas of concrete, gravel or asphalt. The impervious surface ratio is applicable to any new commercial building regardless of the number of units.

(E) Signage

In order to maintain the rural historic character of the District, signs must be limited in size and number. Therefore, off-premises advertising signs are prohibited.

On-premises signs are limited as follows:

- (1) Signs shall not be placed within a public road right-of-way.
- (2) Signs located fifteen (15) feet to twenty five (25) feet from the centerline of a road shall be limited to ten (10) square feet in size.

- (3) Signs located twenty five (25) to thirty five (35) feet from the centerline of a road shall be limited to twenty (20) square feet in size.
 - (4) Signs located thirty five (35) feet or more from the centerline of a road shall have a maximum size of thirty two (32) square feet.
 - (5) Each establishment is limited to a maximum of two signs (one (1) detached and one (1) attached). However, in a situation where a detached sign is not visible from both directions due to topography or other obstruction, two (2) detached signs may be permitted and shall have a maximum size of ten (10) square feet each.
 - (6) The maximum height of detached signs is ten (10) feet measured from the ground.
 - (7) Signs shall not be internally illuminated – i.e. translucent plastic signs prohibited.
 - (8) Where street or site lighting does not provide sufficient illumination, signs may be externally illuminated by low level, shielded stationary bulbs installed in compliance with North Carolina Statutes §136-32.2. Sign lighting shall be turned off by 11 pm.
- (F) Lighting
Lighting of nonresidential land uses must be controlled in both height and intensity to maintain rural character. Under no circumstances may the light level at the lot line exceed 0.2 foot candles, measured at ground level. To achieve this, luminaries shall be shielded to prevent light shining beyond the lot lines onto neighboring properties or public roads. Where there is a mix of residential and commercial uses, light standards are restricted to a maximum of twenty (20) feet in height. In addition, all lighting (except for security purposes) should be turned off between 11 pm and 6 am. Exceptions will be granted for those businesses that are operating during these hours.
- (G) Placement of Buildings
Buildings should be sited so that obstruction of views from the public roads will be minimized. This can be achieved by taking advantage of topographic changes or existing vegetation.
- (H) Facades
It is particularly important that new construction meet minimum design criteria in order that it may blend with the surroundings. New construction throughout the District should be compatible with

surrounding properties, in terms of formal characteristics such as height, massing, roof shapes and window proportions.

Where new construction is contiguous with or within 100' of existing historic buildings, building height and exterior materials shall be harmonious with those of adjacent properties. In the interests of maintaining a sense of history, vertical siding shall be discouraged, and synthetic siding should imitate the character and dimensions of traditional clapboards. Masonry block buildings should be faced in an appropriate material, such as horizontal wooden siding or brick of a consistent traditional red color (not "used" brick or any varieties doctored to appear old), and have pitched roofs.

Section 6. Historic Preservation Commission.

~~There is hereby established the Valle Crucis Historic Preservation Commission (hereafter referred to as the Commission) to consist of five members appointed by the Watauga County Board of Commissioners. Members of the Commission shall serve without compensation.~~

~~(H)~~ Tenure

~~Initially members shall be appointed for staggered terms with one member being appointed for one year, two members for two years and two members for three years. Thereafter, all appointments shall be for a term of three years.~~

~~(I)~~ Qualifications

~~Three (3) members of the Commission shall be resident property owners of the Historic District, two (2) shall be members of the Valle Crucis Community Council and residents of Watauga County, and the majority of the members shall have special interest, experience or education in history or architecture.~~

~~(J)~~ Meetings

~~The Commission shall establish a meeting time and shall meet monthly and more or less often as it shall determine and require. All meetings of the Commission shall be open to the public and reasonable notice of the time and place thereof shall be given to the public. All meetings shall conform to the North Carolina Open Meeting Law. (See North Carolina General Statutes 143, Article 33C).~~

~~(K)~~ Attendance at Meetings

~~Any member of the Commission who misses more than three consecutive regular meetings or more than half of the regular meetings in a calendar year shall lose status with the Commission~~

~~and shall be replaced or reappointed by the Watauga County Board of County Commissioners.~~

~~Absence due to sickness, death or emergencies of like nature shall be recognized as approved absences and shall not affect a member's status on the Commission, except in the event of long illness or other such cause for prolonged absence a member shall be replaced.~~

~~(L) Rules of Procedure~~

~~The Commission shall adopt and publish Rules of Procedure for the conduct of its business.~~

~~(M) Annual Report~~

~~An annual report shall be prepared and submitted by February 1st of each year to the Board of County Commissioners. Such report shall include a comprehensive review of the activities, problems, and actions of the Commission as well as any budget requests or recommendations.~~

~~(N) Meeting Minutes~~

~~The Commission shall keep permanent minutes of all its meetings. The minutes shall record attendance of its members, its resolution, findings, recommendations and actions.~~

~~The minutes of the Commission shall be a public record.~~

Section 7. Commission Powers:

~~The Commission shall seek to promote, enhance and preserve the character of the Valle Crucis Historic District, provided however that the Commission shall not require the reconstruction of individual or original buildings or structures or portion thereof.~~

~~The Commission is authorized and empowered to undertake such action as is reasonably necessary to the discharge and conduct of its duties and responsibilities as outlined in this Ordinance and Chapter 160D of the General Statutes of the State of North Carolina including but not limited to the following:~~

~~(L) Undertake an inventory of properties of historical, prehistorical, architectural, and/or cultural significance.~~

~~(M) Recommend to the governing board areas to be designated by ordinance as "Historic Districts" and individual structures, buildings, sites, areas, or objects to be designated by ordinance as "Landmarks."~~

~~(N) Acquire by any lawful means the fee or any lesser included interest, including options to purchase, to properties within established~~

- ~~districts or to any such properties designated as landmarks to hold, manage, preserve, restore, and improve such properties, and to exchange or dispose of the property by public or private sale, lease or otherwise, subject to covenants or other legally binding restrictions that will secure appropriate rights of public access and promote the preservation of the property.~~
- ~~(O) Restore, preserve, and operate historic properties.~~
 - ~~(P) Recommend to the governing board that designation of any area as a historic district or part thereof, or designation of any building, structure, site, area, or object as a landmark, be revoked or removed for cause.~~
 - ~~(Q) Conduct an educational program regarding historic properties and districts within its jurisdiction.~~
 - ~~(R) Cooperate with the State, federal, and local governments in pursuance of the purposes of this Part. The governing board or the commission, when authorized by the governing board, may contract with the State, or the United States of America, or any agency of either, or with any other organization provided the terms are not inconsistent with State or federal law.~~
 - ~~(S) Enter, solely in performance of its official duties and only at reasonable times, upon private lands for examination or survey thereof. However, no member, employee, or agent of the commission may enter any private building or structure without the express consent of the owner or occupant thereof.~~
 - ~~(T) Prepare and recommend the official adoption of a preservation element as part of the local government's comprehensive plan.~~
 - ~~(U) Review and act upon proposals for alterations, demolitions, or new construction within historic districts, or for the alteration or demolition of designated landmarks, pursuant to this Part.~~
 - ~~(V) Negotiate at any time with the owner of a building, structure, site, area, or object for its acquisition or its preservation, when such action is reasonably necessary or appropriate.~~

Section 8 6. Certificate of Appropriateness.

- (A) Required
No exterior portion of any building or other structure (including masonry walls, fences, light fixtures, steps and pavement or other appurtenant features) nor above ground utility structure shall be erected, altered, restored, moved or demolished within the Valle Crucis Historic District until after an application for a Certificate of Appropriateness as to exterior features has been submitted to and approved by the Valle Crucis Historic Preservation Commission.

For purposes of this chapter, "exterior features" include the architectural style, general design, and general arrangement of the exterior of a building or other structure, including the kind and texture of the building material, the size and scale of the building, and the type and style of all windows, doors, light fixtures, signs, and other appurtenant fixtures. In the case of outdoor advertising signs, "exterior features" mean the style, material, size, and location of all such signs. Such "exterior features" may include important landscape and natural features of the District. Such a Certificate of Appropriateness must be issued by the Commission prior to the issuance of a building permit intended for the purposes of constructing, altering, moving or demolishing structures.

The Certificate of Appropriateness may be issued subject to reasonable conditions necessary to carry out the purposes of this chapter.

A Certificate of Appropriateness shall be required whether or not a building permit is required.

Any building permit or other such permit not issued in conformity with this chapter shall be invalid.

(B) Required Procedures

The following procedures shall be observed in the submission, review, action and administration of applications for approval of Certificates of Appropriateness:

(1) Applications Submitted to Department of Planning and Inspections

An application for a Certificate of Appropriateness shall be obtained from and, when completed, filed with the County Department of Planning & Inspections.

(2) Minor Works

The Planning and Inspections Director or his designee may issue a Certificate of Appropriateness on behalf of the Commission for the following Minor Works when they are in conformance with the adopted guidelines from new construction and rehabilitation in the Valle Crucis Historic District:

a) Removal of carports;

- b)** Removal of accessory buildings which are not architecturally or historically significant;
- c)** Repair or replacement of exposed foundation walls including installation of vents, infill panels between piers, access doors;
- d)** Repair or replacement of asphalt or fiber-glass shingle roofs;
- e)** Repair or replacement of flat roofs;
- f)** Construction, alteration or removal of temporary features that are necessary to ease difficulties associated with a medical condition but do not permanently alter exterior features;
- g)** Construction or replacement of storage and accessory buildings;
- h)** Construction or replacement of patios and decks (ground floor only);
- i)** Installation or replacement of storm windows and doors that feature one of the following treatments:
 - (i.)** baked-on finish on the metal surrounds.
 - (ii.)** mill-finish aluminum painted with zinc chromate primer and top coated with a color to match the window sash or window trim, as appropriate;
 - (iii.)** painted wood;
- j)** Installation or replacement of shutters or blinds original to the building;
- k)** Installation of mechanical equipment such as heating and air conditioning units.
- l)** Installation of identification signs;
- m)** Replacement of missing architectural details, provided that at least one of the following conditions are met:
 - (i.)** At least one example of detail to be replaced exists on the house; or
 - (ii.)** Physical documentary evidence exists which illustrates or describes the missing detail or details; or
 - (iii.)** The proposed detail is very similar to original details found on at least one building or structure within Watauga County that is comparable in terms of style, size and age;

~~Application for Certificates of Appropriateness shall be considered by the Commission at its next regular meeting provided they have been filed, complete in form and content, at least twenty eight (28) calendar days before the regularly~~

scheduled meeting; otherwise consideration shall be deferred until the following meeting.

~~(3) Contents of Application~~

~~The Commission shall require data as are reasonably necessary to determine the nature of the application. An application for a Certificate of Appropriateness shall not be considered complete until all required data are submitted.~~

~~Nothing shall prevent the applicant from filing with the application additional relevant information bearing on the application.~~

~~(4) Notification of Commission~~

~~Upon the receipt of an application, the Department of Planning & Inspections shall notify the Commission at least fourteen calendar days before its regularly scheduled meeting of the contents of the application and its conformance to the provisions of this chapter.~~

~~(5) Notification of Property Owners and Commission Action on Application~~

~~Decisions on Certificates of Appropriateness are quasi-judicial and shall follow the procedure of NCGS 160D-406, including notification of property owners and conduct of an evidentiary hearing. The Commission shall apply the Review Criteria contained in this chapter as well as the "Rural Historic District Standards for Valle Crucis, NC" to aid in making the decision.~~

~~(6) Reasons for Commission Actions to Appear in Minutes and Written Decision~~

~~The Commission shall cause to be entered into the minutes of its meeting the reasons for its actions whether it be approval, approval with modifications or denial. A written decision shall be prepared and signed by the Commission Chair and delivered to the applicant within a reasonable time.~~

~~(7) Time for Review~~

~~All applications for certificates of appropriateness shall be reviewed and acted upon within a reasonable time, not to exceed 180 days from the date the application for a certificate of appropriateness is filed, as defined by the commission's rules of procedure. As part of its review procedure, the commission may view the premises and seek the advice of the Division of~~

~~Archives and History or such other expert advice as it may deem necessary under the circumstances.~~

(8) Submission of New Applications

If the Commission determines that a Certificate of Appropriateness should not be issued, a new application affecting the same property may be submitted only if substantial changes are made in plans for the proposed construction, reconstruction, alteration, restoration or moving.

(9) Interior Arrangement Not Considered

The Commission shall not consider interior arrangement, except as set forth in N.C.G.S. 160D-947(b).

(10) Certain Changes Not Prohibited

Nothing in this chapter shall be construed to prevent the ordinary maintenance or repair of any exterior architectural feature in the Valle Crucis Historic District which does not involve a substantial change in design, material, or outer appearance thereof nor to prevent the construction, reconstruction, alteration, restoration or demolition of any such feature which the Watauga County Building Inspector shall certify in writing to the Commission as required by his/her duty to protect the public safety because of its unsafe or dangerous condition.

(11) Delay in Demolition of Buildings Within the District

- (a)** An application for a certificate of appropriateness authorizing the relocation, demolition, or destruction of a designated landmark or a building, structure, or site within the district may not be denied, except as provided in subsection (b) of this section. However, the effective date of such a certificate may be delayed for a period of up to 365 days from the date of approval. The maximum period of delay authorized by this section shall be reduced by the preservation commission where it finds that the owner would suffer extreme hardship or be permanently deprived of all beneficial use of or return from such property by virtue of the delay. During such period, the preservation commission shall negotiate with the owner and with any other parties in an effort to find a means of preserving the building or site. If the preservation commission finds that a building or site within a district has no

special significance or value toward maintaining the character of the district, it shall waive all or part of such period and authorize earlier demolition or removal. If the preservation commission or planning board has voted to recommend designation of a property as a landmark or designation of an area as a district, and final designation has not been made by the governing board, the demolition or destruction of any building, site, or structure located on the property of the proposed landmark or in the proposed district may be delayed by the preservation commission or planning board for a period of up to 180 days or until the governing board takes final action on the designation, whichever occurs first.

- (b)** An application for a certificate of appropriateness authorizing the demolition or destruction of a building, site, or structure determined by the State Historic Preservation Officer as having statewide significance as defined in the criteria of the National Register of Historic Places may be denied except where the preservation commission finds that the owner would suffer extreme hardship or be permanently deprived of all beneficial use or return by virtue of the denial.

(12) Appeal of Decision

An appeal may be taken to the Superior Court of Watauga County, pursuant to N.C.G.S. 160D-1402.

(13) Compliance

Compliance with the terms of the Certificate of Appropriateness shall be enforced by the Watauga County Department of Planning and Inspections.

Failure to comply with a Certificate of Appropriateness shall be a violation of this chapter.

To ensure continued compliance with the provisions of this chapter, each approved Certificate of Appropriateness shall expire 12 months from the date on which final action was taken to approve the application, unless otherwise identified in the certificate, if the alteration, construction, demolition, relocation, or removal has not been initiated. Time extensions

may be granted in accordance with the Commission's Rules of Procedure.

Nothing contained in this chapter shall prohibit, impair or limit in any way the power of Watauga County to prevent the construction, reconstruction, alteration, or removal of building structures, appurtenant fixtures or outdoor signs in the Historic District in violation of the provisions of this chapter.

(14) Review Criteria

(a) Intent

It is the intention of these regulations to insure, in so far as possible, that buildings or structures in the Valle Crucis Historic District shall be in harmony with other buildings or structures located therein. However, it is not the intention of the regulations to require the reconstruction or restoration of individual or original buildings or prohibit demolition or removal of the same or to impose architectural styles of particular historic periods. In considering new construction, the Commission shall encourage contemporary design that is harmonious with the character of the District.

In granting a Certificate of Appropriateness, the Commission shall take into account the historic or architectural significance of the structure under consideration and the exterior form and appearance of any proposed additions or modifications to that structure, as well as the effect of such changes or additions upon other structures in the vicinity.

(b) Exterior Form and Appearance

The following criteria should be considered, when relevant, by the Commission in reviewing applications for Certificates of Appropriateness:

- (i.)** New construction and alteration should reflect the atmosphere, existing landscape characteristics and appearance of the District.
- (ii.)** New buildings should have a definite relationship to existing buildings; that is, they should be compatible but not imitative.

- (iii.) Wood, brick and stone are traditional building materials in the District and should be employed whenever possible, as should metal roofs.
- (iv.) Remodeling and alterations to buildings should be in the style of the existing building and be compatible in size, scale, color and material.
- (v.) Double-wide mobile homes are preferred. All mobile homes should be placed on permanent solid masonry foundations, unpierced except for required access and ventilation openings. The chassis and towing bar should be removed.
- (vi.) If cinder blocks are used in the foundations, the surface should be treated with masonry paint or other suitable material.
- (vii.) Outbuildings should be compatible with the main building and with the rural atmosphere of the District.
- (viii.) Native plant materials should be used in landscaping around buildings.
- (ix.) Signs should reflect good taste in size and materials.

Article III Nonconformities

Section 1. Classification.

Any building, structure or use of land existing at the time of enactment of this ordinance or any amendment thereto which was lawful but would be prohibited, regulated or restricted by such enactment or amendment is a nonconformity.

Section 2. Repair, Reconstruction, Expansion, Reinstatement.

It is the intent of this chapter to permit nonconformities to continue until they are removed or cease. Such continuance shall include routine maintenance and repair, reconstruction in case of total or partial destruction, and expansion, provided that such expansion meets all other requirements of this chapter (yard requirements, Certificate of Appropriateness, etc.). A nonconforming use shall not be reinstated after discontinuance for a period of

one (1) year unless the Historic Preservation Commission finds that such reinstatement will not have a detrimental effect upon the District.

Section 3. Nonconforming Lots.

In the District, structures may be erected, occupied and used on separate, nonconforming lots of record, in accord with all other requirements applying in the District.

Article IV Public Buildings

As set forth in N.C.G.S 160D-947(f), all of the provisions of [Article 2, Section 8](#) are hereby made applicable to construction, alteration, moving, and demolition by the State of North Carolina, its political subdivisions, agencies, and instrumentalities, provided, however, they shall not apply to interiors of buildings or structures owned by the State of North Carolina. The State and its agencies shall have a right of appeal to the North Carolina Historical Commission or any successor agency assuming its responsibilities under N.C.G.S. 121-12(a) from any decision of a local preservation commission.

CHAPTER 21 WATERSHED PROTECTION (WINKLERS CREEK, HOWARDS CREEK, NORRIS BRANCH, FLAT TOP BRANCH, SOUTH FORK NEW RIVER, AND POND CREEK)

Article I Authority and General Regulations

Section 1. Authority and Enactment.

The Legislature of the State of North Carolina has, in Chapter 160D, Zoning Authority; and in Chapter 143, Article 21, Watershed Protection Rules, delegated the responsibility or directed local governmental units to adopt regulations designed to promote the public health, safety, and general welfare of its citizenry. The Watauga County Board of Commissioners enacts into law the following chapter as the **Water Supply** Watershed Protection Zoning Regulations of Watauga County.

Section 2. Jurisdiction.

The provisions of this chapter shall apply within the area designated as a Public Water Supply Watershed by the N.C. Environmental Management Commission and shall be defined and established on the most recent officially adopted by the NC Environmental Commission version of the map entitled, "Watershed Protection Map of Watauga County North Carolina" ("the Watershed Map"), which is adopted simultaneously herewith. The Watershed Map and all explanatory matter contained thereon accompanies and is hereby made a part of this chapter.

Section 3. Exceptions to Applicability.

- (A) Nothing contained herein shall repeal, modify, or amend any Federal or State law or regulation, or any ordinance or regulation pertaining thereto except any ordinance which these regulations specifically replace; nor shall any provision of this chapter amend, modify, or restrict any provisions of the Code of Ordinances of Watauga County however, the adoption of this chapter shall and does amend any and all ordinances, resolutions, and regulations in effect in the county at the time of the adoption of this chapter that may be construed to impair or reduce the effectiveness of this chapter or to conflict with any of its provisions.
- (B) It is not intended that these regulations interfere with any easement, covenants or other agreements between parties. However, if the provisions of these regulations impose greater restrictions or higher standards for the use of a building or land, then the provision of these regulations shall control.

- (C) Existing development, as defined in this ordinance, is not subject to the requirements of this ordinance.
- (D) Expansions to structures classified as existing development must meet the requirements of this ordinance, except single family residential development or unless expansion is part of common plan of development. In an expansion, the built-upon area of the existing development is not required to be included in the density calculations. Where there is a net increase of built upon area, only the area of net increase is subject to this ordinance. Where existing development is being replaced with new built upon area, and there is a net increase of built upon area, on area areas of net increase shall be subject to this ordinance. ~~However, the built-upon area of the existing development is not required to be included in the density calculations.~~
- ~~(E) A pre-existing lot owned by an individual prior to the effective date of this ordinance, regardless of whether or not a vested right has been established, may be developed for single family residential purposes without being subject to the restrictions of this ordinance.~~
- (F) If a Non-Conforming Existing Lot of Record is not contiguous to any other lot owned by the same party, then that lot of record shall not be subject to the development restrictions of this ordinance if it is developed for single-family residential purposes. Local governments may require the combination of contiguous nonconforming lots of record owned by same party to establish a lot or lots that meet requirements in Article II of this ordinance.
- (G) Any lot or parcel created as part of a family subdivision after the effective date of these rules shall be exempt from these rules if it is developed for one single-family detached residence and if it is exempt from local subdivision regulation. If a local government does not enforce subdivision regulations, then that local government may or may not allow the exemption for family subdivisions.
- (H) Any lot or parcel created as part of any other type of subdivision that is exempt from a local subdivision ordinance shall be subject to the land use requirements (including impervious surface requirements) of these rules, except that such a lot or parcel must meet the minimum buffer requirements to the maximum extent practicable.
- (I) An applicant may exceed the density limits in Article IV if all of the following circumstances apply:
- a. The property was developed prior to the effective date of the local water supply watershed program.
 - b. The property has not been combined with additional lots after January 1, 2021.
 - c. The property has not been a participant in a density averaging transaction under G.S. 143- 214.5(d2).

- d. The current use of the property is nonresidential.
- e. In the sole discretion, and at the voluntary election, of the property owner, the stormwater from all of the existing and new built-upon area on the property is treated in accordance with all applicable local government, state, and federal laws and regulations.
- f. The remaining vegetated buffers on the property are preserved in accordance with the requirements of this Ordinance.

Section 4. Applicability to Agricultural Uses.

~~This chapter shall not affect bona fide farms, as cited in Chapter 6 of this Title and N.C.G.S. 160D-903.~~

~~The following paragraph is provided for information only. Agricultural activities are regulated by the Watershed Protection Act (NCGS 143, Chapter 21) as follows:~~

~~"Agriculture is subject to the provisions of the Food Security Act of 1985 and the Food, Agriculture, Conservation and Trade Act of 1990. Agricultural activities conducted after January 1, 1993 shall maintain a minimum ten (10) foot vegetative buffer, or equivalent control as determined by the Soil and Water Conservation Commission, along all perennial waters indicated on the most recent versions of U.S.G.S. 1:24,000 (7.5 minute) scale topographic maps or as determined by local government studies."~~

Article II Subdivision Regulations

Section 1. General Provisions.

- (A) No subdivision plat of land within the Public Water Supply Watershed shall be filed or recorded by the Register of Deeds until it has been approved in accordance with the provisions of this Article. Likewise, the Clerk of Superior Court shall not order or direct the recording of a plat if the recording of such plat would be in conflict with this Article.
- (B) All subdivisions of land within Watauga County are subject to the provisions of the Watauga County Subdivisions and Multi-Unit Structures regulation and shall be reviewed pursuant to that chapter. Subdivisions within Public Water Supply Watersheds shall comply with the provisions of both chapters except where the two (2) conflict. In that case, the more restrictive provisions shall apply.
- (C) Compliance with this chapter shall be indicated on both copies of the plat by the following certificate and signed by the authorized representative:

system that diverts stormwater runoff away from surface waters and incorporates best management practices to minimize water quality impacts.

- (H) Erosion and Sedimentation Control. The application shall, where required, be accompanied by a written statement that a sedimentation and erosion control plan will be submitted to and approved by Watauga County.

Article III Development Regulations

Section 1. Establishment of Watershed Areas.

For purposes of this chapter, the following watershed areas are established:

- WS-II-CA (Critical Area)
- WS-II-BW (Balance of Watershed)
- WS-III-(Balance of Watershed)
- WS-IV-CA (Critical Area)
- WS-IV-PA (Protected Area)

Section 2. Watershed Areas – Allowed and Not Allowed Uses

Activity/Use	Water Supply Watershed Classification				
	WS-II CA	WS-II BW	WS-III BW	WS-IV CA	WS-IV PA
New landfills	No	Yes	Yes	No	Yes
New permitted residual land application	No	Yes	Yes	No	Yes
New permitted petroleum contaminated soils sites	No	Yes	Yes	No	Yes
NPDES General or Individual Stormwater discharges	Yes	Yes	Yes	Yes	Yes
NPDES General Permit Wastewater Discharges pursuant to 15A NCAC 02H .0127	Yes	Yes	Yes	Yes	Yes
NPDES Individual Permit trout farm discharges	Yes	Yes	Yes	Yes	Yes
New NPDES Individual Permit domestic treated wastewater discharge	No	No	Yes	Yes	Yes
New NPDES Individual Permit industrial treated wastewater discharge	No	No	No ^a	Yes	Yes
Non-process industrial waste	No	No	Yes	Yes	Yes
New industrial connections and expansions to existing municipal discharge with pretreatment program pursuant to 15A NCAC 02H .0904	No	No	No	Yes	Yes
Sewage	No ^b	No ^b	No ^b	No ^b	No ^b
Industrial Waste	No ^b	No ^b	No ^b	No ^b	No ^b
Other wastes	No ^b	No ^b	No ^b	No ^b	No ^b
Groundwater remediation project discharges ^c	Yes	Yes	Yes	Yes	Yes
Agriculture ^d	Yes	Yes	Yes	Yes	Yes
Silviculture ^e	Yes	Yes	Yes	Yes	Yes
Residential Development ^f	Yes	Yes	Yes	Yes	Yes
Non-residential Development ^g	Yes	Yes	Yes	Yes	Yes

Nonpoint Source Pollution ^h	Yes	Yes	Yes	Yes	Yes
Animal Operations ⁱ	Yes	Yes	Yes	Yes	Yes

Notes:

^a Except non-process industrial discharges are allowed

^b Only allowed if specified in 15A NCAC 02B .0104

^c Where no other practical alternative exists

^d In WS-I watersheds and Critical Areas of WS-II, WS-III, and WS-IV watersheds, agricultural activities conducted after 1/1/1993 shall maintain a minimum 10 foot vegetated setback or equivalent control as determined by SWCC along all perennial waters indicated on most recent version of USGS 1:24000 scale (7.5 minute) topographic maps or as determined by local government studies

^e Subject to Forest Practice Guidelines Related to Water Quality (02 NCAC 60C .0100 to .0209) Effective 4/1/2018

^f See density requirements in 15A NCAC 02B .0624

^g See different allowed and not allowed in this table

^h NPS pollution shall not have adverse impact, as defined in 15A NCAC 02H .1002, on use as water supply or any other designated use

ⁱ Deemed permitted, as defined in 15A NCAC 02T .0103 and permitted under 15A NCAC 2H .0217

NOTE: Source of table is Model Water Supply Watershed Protection Ordinance published by NCDEMLR, Stormwater program.

Section 3. ~~Cluster Development~~ Watershed Areas- Density and Built-Upon Limits

(A) PROJECT DENSITY. The following maximum allowable project densities and minimum lot sizes shall apply to a project according to the classification of the water supply watershed where it is located, its relative location in the watershed, its project density, and the type of development:

Water Supply Classification	Location in the Watershed	Maximum Allowable Project Density or Minimum Lot Size		
		Low Density Development		High Density Development
		Single-family detached residential	Non-residential and all other residential	All types
WS-II	Critical Area	1 dwelling unit (du) per 2 acres or 1 du per 80,000 square foot lot excluding roadway right-of-way or 6% built-upon area	6% built-upon area	6 to 24% built-upon area
	Balance of Watershed	1 du per 1 acre or 1 du per 40,000 square foot lot excluding roadway right-of-way or 12% built-upon area	12% built-upon area	12 to 30% built-upon area
WS-III	Balance of Watershed	1 du per one-half acre or 1 du per 20,000 square foot lot excluding roadway right-of-way or 24% built-upon area	24% built-upon area	24 to 50% built-upon area
WS-IV	Critical Area	1 du per one-half acre or 1 du per 20,000 square foot lot excluding roadway right-of-way or 24% built-upon area	24% built-upon area	24 to 50% built-upon area
	Protected Area	1 du per one-half acre or 1 du per 20,000 square foot lot excluding roadway right-of-way or 24% built-upon; or 3 dus per acre or 36% built-upon area without curb and gutter street system	24% built-upon area; or 36% built-upon area without curb and gutter street system	24 to 70% built-upon area

NOTE: Source of table is Model Water Supply Watershed Protection Ordinance published by NCDEMLR, Stormwater program.

(B) CALCULATION OF PROJECT DENSITY. The following requirements shall apply to the calculation of project density:

- (1)** Project density shall be calculated as the total built-upon area divided by the total project area;
- (2)** A project with "existing development," as that term is defined in [Chapter 7](#), may use the calculation method in Sub-Item (1) of this Item or may calculate project density as the difference of total built-upon area minus existing built-upon area divided by the difference of total project area minus existing built-upon area.
- (3)** Expansions to existing development ~~are excluded unless the expansion is part of a larger common plan of development that is subject to these regulations and~~ shall be subject to 15A NCAC 02B .0624 except as excluded in Rule 15A NCAC 02B .0622 (1)(d).
- (4)** Where there is a net increase of built-upon area, only the area of net increase shall be subject to ~~the regulations, density and built-upon area limits.~~
- (5)** Where existing development is being replaced with new built-upon area, and there is a net increase of built-upon area, only the area of net increase shall be subject to the regulations.
- (6)** Total project area shall exclude the areas below the Normal High Water Line (NHWL).
- (7)** Projects under a common plan of development shall be considered as a single project for purposes of density calculation except that on a case-by-case basis, local governments may allow projects to be considered to have both high and low density areas based on one or more of the following criteria:
 - (a)** natural drainage area boundaries;
 - (b)** variations in land use throughout the project; or
 - (c)** construction phasing.

(C) LOW DENSITY PROJECTS. In addition to complying with the project density requirements of Item (A) of this Rule, low density projects shall comply with the following:

- (1) VEGETATED CONVEYANCES.** Stormwater runoff from the project shall be released to vegetated areas as dispersed flow or transported by vegetated conveyances to the maximum extent practicable. In determining whether this criteria has been met, the local government shall take into account site-specific factors such as topography and site layout as well as protection of water quality. Vegetated conveyances shall be

maintained in perpetuity to ensure that they function as designed. Vegetated conveyances that meet the following criteria shall be deemed to satisfy the requirements of this Sub-Item:

- (a)** Side slopes shall be no steeper than 3:1 (horizontal to vertical) unless it is demonstrated to the local government that the soils and vegetation will remain stable in perpetuity based on engineering calculations and on-site soil investigation; and
 - (b)** The conveyance shall be designed so that it does not erode during the peak flow from the 10-year storm event as demonstrated by engineering calculations.
- (2)** CURB OUTLET SYSTEMS. In lieu of vegetated conveyances, low density projects shall have the option to use curb and gutter with outlets to convey stormwater to grassed swales or vegetated areas. Requirements for these curb outlet systems shall be as follows:
 - (a)** The curb outlets shall be located such that the swale or vegetated area can carry the peak flow from the 10-year storm and at a non-erosive velocity;
 - (b)** The longitudinal slope of the swale or vegetated area shall not exceed five percent except where not practical due to physical constraints. In these cases, devices to slow the rate of runoff and encourage infiltration to reduce pollutant delivery shall be provided;
 - (c)** The swale's cross section shall be trapezoidal with a minimum bottom width of two feet;
 - (d)** The side slopes of the swale or vegetated area shall be no steeper than 3:1 (horizontal to vertical);
 - (e)** The minimum length of the swale or vegetated area shall be 100 feet; and
 - (f)** Low density projects may use treatment swales designed in accordance with 15A NCAC 02H .1061 in lieu of the requirements specified in Sub-Items (a) through (e) of this Sub-Item.
- (3)** 10/70 OPTION. Outside of the critical areas of WS-II and WS-IV watersheds, new development under the "10/70 option" is allowed in accordance with the following requirements:
 - (a)** A maximum of 10 percent of the land area of a water supply watershed outside of the critical area and within Watauga County's planning jurisdiction may be developed with new development projects and

expansions of existing development of up to 70 percent built-upon area.

- (b) The beginning amount of acreage available under this option shall be based on the County's jurisdiction as delineated on the date the water supply watershed classification became effective. The acreage within the critical area shall not be counted towards the allowable 10/70 option acreage;
 - (c) Projects that are covered under the 10/70 option shall comply with the low density requirements set forth in Item (C) above.
 - (d) The maximum built-upon area allowed on any given new development project shall be 70 percent;
 - (e) When the water supply watershed is composed of public lands, such as National Forest land, local governments may count the public land acreage within the watershed outside of the critical area in calculating the acreage allowed under this provision.
- (4) New development shall meet the development requirements on a project-by-project basis

Section 4. Density Averaging

An applicant may average development density on up to two noncontiguous properties for purposes of achieving compliance with the water supply watershed development standards if all of the following circumstances exist:

- (A) The properties are within the same water supply watershed. However, if one of the properties is located in the critical area of the watershed, the critical area property shall not be developed beyond the applicable density requirements for its classification.
- (B) Overall project density meets applicable density or stormwater control requirements under 15A NCAC 2B .0200.
- (C) Vegetated setbacks on both properties meet the minimum statewide water supply watershed protection requirements.
- (D) Built upon areas are designed and located to minimize stormwater runoff impact to the receiving waters, minimize concentrated stormwater flow, maximize the use of sheet flow through vegetated areas, and maximize the flow length through vegetated areas.
- (E) Areas of concentrated density development are located in upland areas and, to the maximum extent practicable, away from surface waters and drainage ways.

- (F) The property or portions of the properties that are not being developed will remain in a vegetated or natural state and will be managed by a homeowners' association as common area, conveyed to a local government as a park or greenway, or placed under a permanent conservation or farmland preservation easement unless it can be demonstrated that the local government can ensure long-term compliance through deed restrictions and an electronic permitting mechanism. A metes and bounds description of the areas to remain vegetated and limits on use shall be recorded on the subdivision plat, in homeowners' covenants, and on individual deed and shall be irrevocable.
- (G) Development permitted under density averaging and meeting applicable low density requirements shall transport stormwater runoff by vegetated conveyances to the maximum extent practicable.
- (H) A special use permit or other such permit or certificate shall be obtained from the local Watershed Review Board or Board of Adjustment to ensure that both properties considered together meet the standards of the watershed ordinance and that potential owners have record of how the watershed regulations were applied to the properties.

Section 5. Cluster Development

Clustering of development is allowed in all Watershed Areas under the following conditions:

- (A) Minimum lot sizes are not applicable to single family cluster development projects; however, the total number of lots shall not exceed the number of lots allowed for single family detached developments in [Section 2](#). Built-upon area or stormwater control requirements of the project shall not exceed that allowed for the critical area or balance of watershed, whichever applies.
- (B) All built-upon area shall be designed and located to minimize stormwater runoff impact to the receiving waters and minimize concentrated stormwater flow, maximize the use of sheet flow through vegetated areas, and maximize the flow length through vegetated areas.
- (C) Areas of concentrated density development are located in upland areas and away, to the maximum extent practicable, from surface waters and drainage ways.
- (D) ~~If common open space is the method used to meet the standards of~~ [Section 2](#), The remainder of the tract not included in individual lots shall remain in a vegetated or natural state. The title to the open space area shall be conveyed to an incorporated homeowner's association for management; to a local government for preservation

as a park or open space; or to a conservation organization for preservation in a permanent easement. Where a property association is not incorporated, a maintenance agreement shall be filed with the property deeds.

~~(E) In reviewing and approving a development plan for a Planned Unit Development (PUD) or mixed use development, the County shall have the option of determining built-upon area for the entire development or for each type of land use within the development. Cluster developments that meet the applicable low density requirements shall transport stormwater runoff by vegetated conveyances to the maximum extent practicable~~

Section 6. Vegetated Setbacks Required.

- (A) A minimum one hundred (100) foot vegetative buffer is required for all new development activities ~~that exceed the low density option under the 10%-70% provision;~~ otherwise a minimum thirty (30) foot vegetative buffer for development activities is required along all perennial waters indicated on the most recent versions of U.S.G.S. 1:24,000 (7.5 minute) scale topographic maps or as determined by local government studies. Desirable artificial streambank or shoreline stabilization is permitted.
- (B) Where USGS topographic maps do not distinguish between perennial and intermittent streams, an on-site stream determination may be performed by an individual qualified to perform such stream determinations.
- (C) No new development is allowed in the buffer except for water dependent structures or other structures such as flag poles, signs, and security lights which result in only ~~diminimal~~ increases in impervious ~~surface area~~, and public projects such as road crossings and greenways where no practical alternative exists. These activities should minimize built-upon surface area, direct runoff away from the surface waters and maximize the utilization of stormwater Best Management Practices.

Section 7. Application of Regulations.

- (A) No building or land shall hereafter be used and no development shall take place except in conformity with the regulations herein specified for the watershed area in which it is located.
- (B) No area required for the purpose of complying with the provisions of this ordinance shall be included in the area required for another building.

- (C) Every residential building hereafter erected, moved or structurally altered shall be located on a lot which conforms to the regulations herein specified, except as permitted in [Article I, Section 3\(c\)](#).
- (D) If a use or class of use is not specifically indicated as being allowed in a watershed area, such use or class of use is prohibited.

Section 8. Rules Governing the Interpretation of Watershed Area Boundaries.

- (A) Where uncertainty exists as to the boundaries of the watershed areas, as shown on the Watershed Map, the following rules shall apply:
- (B) Where area boundaries are indicated as approximately following either street, alley, railroad or highway lines or centerlines thereof, such lines shall be construed to be said boundaries.
- (C) Where area boundaries are indicated as approximately following lot lines, such lot lines shall be construed to be said boundaries. However, a surveyed plat prepared by a registered land surveyor may be submitted to the county as evidence that one or more properties along these boundaries do not lie within the watershed area.
- (D) Where the watershed area boundaries lie at a scaled distance more than twenty-five (25) feet from any parallel lot line, the location of watershed area boundaries shall be determined by use of the scale appearing on the watershed map.
- (E) Where the watershed area boundaries lie at a scaled distance of twenty-five (25) feet or less from any parallel lot line, the location of watershed area boundaries shall be construed to be the lot line.
- (F) Where other uncertainty exists, the Watershed Administrator shall interpret the Watershed Map as to location of such boundaries. This decision may be appealed to the Board of Adjustment.

Section 9. Existing Development.

Existing development as defined in [Chapter 7](#) may be continued and maintained subject to the provisions provided herein. Expansions to structures classified as existing development must meet the requirements of this chapter; however, the built-upon area of the existing development is not required to be included in the density calculations. Please see [Section 3 \(B\)](#) Calculation of Project Density. This section deals with all existing development as defined in the EMC rules. All existing development, whether or not it meets the statewide minimum standards, is exempt from the provisions of this ordinance.

- (A) Uses of Land. This category consists of uses existing at the time of adoption of this ordinance where such use of the land is not permitted to be established hereafter in the watershed area in which it is located. Such uses may be continued except as follows:
 - (1) When such use of land has been changed to an allowed use, it shall not thereafter revert to any prohibited use.
 - (2) Such use of land shall be changed only to an allowed use.
 - (3) When such use ceases for a period of at least one year, it shall not be reestablished.
- (B) Reconstruction of Buildings or Built-upon Areas. Any existing building or built-upon area not in conformance with the restrictions of this chapter that has been damaged or removed may be repaired and/or reconstructed, except that there are no restrictions in single family residential development, provided:
 - (1) Repair or reconstruction is initiated within twelve (12) months and completed within two (2) years of such damage.
 - (2) The total amount of space devoted to built-upon area may not be increased unless stormwater control that equals or exceeds the previous development is provided.

Section 10. Watershed Protection Permit.

- (A) ~~Except where for a single-family residence is constructed on a lot deeded prior to the effective date of this chapter residential redevelopment,~~ no building or built-upon area shall be erected, moved, enlarged or structurally altered, nor shall any building permit be issued nor shall any change in the use of any building or land be made until a Watershed Protection Permit has been issued by the Watershed Administrator. No Watershed Protection Permit shall be issued except in conformity with the provisions of this chapter.
- (B) Watershed Protection Permit applications shall be filed with the Watershed Administrator. The application shall include a completed application form and supporting documentation deemed necessary by the Watershed Administrator.
- (C) Prior to issuance of a Watershed Protection Permit, the Watershed Administrator may consult with qualified personnel for assistance to determine if the application meets the requirements of this chapter.
- (D) A Watershed Protection Permit shall expire if a Building Permit or Watershed Occupancy Permit (when no building permit is required) for such use is not obtained by the applicant within twelve (12) months from the date of issuance.

Section 11. Building Permit Required.

~~Except for a single family residence constructed on a lot deeded prior to the effective date of this ordinance,~~ No permit required under the North Carolina State Building Code shall be issued for any activity for which a Watershed Protection Permit is required until that permit has been issued.

Section 12. Watershed Protection Occupancy Permit.

- (A) The Watershed Administrator shall issue a Watershed Protection Occupancy Permit certifying that all requirements of this chapter have been met prior to the occupancy or use of a building hereafter erected, altered or moved and/or prior to the change of use of any building or land.
- (B) A Watershed Protection Occupancy Permit, either for the whole or part of a building, shall be applied for coincident with the application for a Watershed Protection Permit and shall be issued or denied within ten (10) days after the erection or structural alterations of the building. ~~The applicant should notify the Watershed Administrator and request the issued Watershed Protection Occupancy Permit when building is complete.~~
- (C) When only a change in use of land or existing building occurs, the Watershed Administrator shall issue a Watershed Protection Occupancy Permit certifying that all requirements of this chapter have been met coincident with the Watershed Protection Permit.
- (D) If the Watershed Protection Occupancy Permit is denied, the Watershed Administrator shall notify the applicant in writing stating the reasons for denial.
- (E) No building or structure which has been erected, moved, or structurally altered may be occupied until the Watershed Administrator has approved and issued a Watershed Protection Occupancy Permit.

Article IV Public Health Regulations

Section 1. Public Health, in general.

No activity, situation, structure or land use shall be allowed within the watershed which poses a threat to water quality and the public health, safety and welfare. ~~Such conditions may arise from inadequate on-site sewage systems which utilize ground absorption; inadequate sedimentation and erosion control measures; the improper storage or disposal of junk, trash or other refuse within a buffer area; the absence or improper implementation of a spill containment plan for toxic and hazardous materials; the improper~~

management of stormwater runoff; or any other situation found to pose a threat to water quality.

Section 2. Abatement.

- (A) The Watershed Administrator shall monitor land use activities within the watershed areas to identify situations that may pose a threat to water quality.
- (B) The Watershed Administrator shall report all findings to the Board of Commissioners. The Watershed Administrator may consult with any public agency or official and request recommendations. The Watershed Administrator may also coordinate with local inspections department, since local governments can abate most threatening nuisances.
- (C) Where the Board of Commissioners finds a threat to water quality and the public health, safety and welfare, the Board shall institute any appropriate action or proceeding to restrain, correct or abate the condition and/or violation.

Article V Administration, Enforcement and Appeals

Section 1. Watershed Administrator and Duties thereof.

The county shall appoint a Watershed Administrator, who shall be duly sworn in. It shall be the duty of the Watershed Administrator to administer and enforce the provisions of this chapter as follows:

- (A) The Watershed Administrator shall issue Watershed Protection Permits and Watershed Protection Occupancy Permits as prescribed herein. A record of all permits shall be kept on file and shall be available for public inspection during regular office hours of the Administrator.
- (B) The Watershed Administrator shall serve as staff to the Board of Adjustment for cases involving this chapter.
- (C) The Watershed Administrator is granted the authority to administer and enforce the provisions of this chapter, exercising in the fulfillment of his responsibility the full police power of the county. The Watershed Administrator, or his duly authorized representative, may enter any building, structure, or premises, as provided by law, to perform any duty imposed upon him/her by this chapter.
- (D) The Watershed Administrator shall keep records of all amendments to the local Water Supply Watershed Protection Regulations and shall provide copies of all amendments upon adoption to the Watershed Protection Section Stormwater Branch of the Division of Energy, Mineral and Land Resources.

- (E) The Watershed Administrator shall keep records of the jurisdiction's use of the provision that a maximum of ten percent (10%) of the non-critical area of WS-II, WS-III, and, WS-IV watersheds may be developed with new development at a maximum of seventy percent (70%) built-upon surface area. Records for each watershed shall include the total acres of non-critical watershed area, total acres eligible to be developed under this option, total acres approved for this development option, and individual records for each project with the following information: location, number of developed acres, type of land use and stormwater management plan (if applicable).
- (F) The Watershed Administrator shall keep a record of variances to the local Water Supply Watershed Protection Regulations. ~~This record shall be submitted to the Watershed Protection Section of the Division of Energy, Mineral and Land Resources. on or before the 1st of January every calendar year and shall provide a description of each project receiving a variance and the reasons for granting the variance.~~
- (G) The Watershed Administrator is responsible for ensuring that Stormwater Control Measures are inspected at least once a year and shall keep a record of SCM inspections.

Article VI Appearance Standards

Multi-family and non-residential uses are subject to the standards described in this section. The standards do not apply to bona fide farming operations, which are exempt from this ordinance, or to temporary uses which are not required to be connected to a permanent wastewater disposal system. Compliance with the standards shall be determined through a site plan review by the Watershed Administrator. Standards are as follows.

Section 1. Buffer Areas.

Buffer areas shall be established in order to create the impression of spatial separation between adjacent land uses. The purpose of this separation is to lessen possible adverse effects of land uses upon each other and to provide within development planted/green areas so as to maintain the rural character of the community. Buffer requirements are as follows:

- (A) Where a commercial or multi-family use is proposed adjacent to single family residential use, side and rear yard setback of 30 feet shall be observed for buildings, parking, or storage. This area is to be used as a buffer and shall be landscaped as follows. Buffers shall consist of plantings of evergreen and/or deciduous trees spaced no more than thirty (30) feet apart. Such trees shall be at least six to

seven (6-7) feet tall for evergreens and six to eight (6-8) feet tall with a one and one half (1-1/2) inch caliper (trunk diameter 6 inches above grade) for deciduous trees at time of planting and shall reach a height of no less than twenty (20) feet at maturity. Where utility easements conflict with this height requirement, the requirement may be lessened at the discretion of the Watershed Administrator. In addition, plantings of low growing shrubs, and/or trees shall be placed at ten (10) foot intervals. Plantings within buffer zones shall be staggered unless topography is prohibitive. No planting shall be placed in the road right-of-way. Lists of recommended plantings are available from the Planning and Inspections Department.

- (B)** Where a commercial or multi-family use is proposed adjacent to a commercial or multi-family use side and rear yard setback of 15 feet shall be observed for buildings, parking, or storage. This area is to be used as a buffer and shall be landscaped as follows. Buffers shall consist of plantings of evergreen and/or deciduous trees spaced no more than thirty (30) feet apart. Such trees shall be at least six to seven (6-7) feet tall for evergreens and six to eight (6-8) feet tall with a one and one half (1-1/2) inch caliper for deciduous trees at time of planting and shall reach a height of no less than twenty (20) feet at maturity, except as described in subsection (A). In addition, permanent ground cover such as grasses shall be established.
- (C)** Walls, fences, earthen berms, or other natural features may be used in combination with or in lieu of planted buffers if approved as part of a permit. Considerations include but are not limited to:

 - (1)** Any existing significant vegetation within the buffer(s) may be preserved and credited towards meeting the standard for the required buffer. Existing fences, berms, and/or walls within the buffer(s) may be used to fulfill the standards set forth for the buffer providing these elements are healthy and in a condition of good repair. Chain link fencing is not acceptable in meeting the performance criteria of this ordinance.
 - (2)** Installation of supplemental vegetation and/or site features may be required at the time of site plan review, if existing vegetation and/or site features within the buffer do not meet or exceed the requirements of this ordinance.
- (D)** Open storage areas, exposed machinery and outdoor areas used for the storage and collection of rubbish must be visually screened from roads and surrounding land uses. Suitable types of screening include opaque wood fences and dense evergreen hedges of six (6) feet or more in height. Where evergreen hedges are proposed, a temporary fence should be built to provide screening until the evergreens are of sufficient height.

- (E) The recipient of a Watershed Occupancy Permit, or his successor, shall be responsible for maintaining all common areas, improvements, or facilities required by the ordinance or any permit issued in accordance with its provisions, except those areas, improvements, or facilities with respect to which an offer of dedication to the public has been accepted by the appropriate public authority. As illustrations, and without limiting the generality of the foregoing, this means that private roads and parking areas, water and sewer lines, and recreational facilities must be properly maintained so that they can be used in the manner intended, and required vegetation and trees used for screening, landscaping, or shading must be replaced if they die or are destroyed.

Section 2. Location and Buffering of Parking.

In order to preserve the rural environment, developers are encouraged to place parking and loading/unloading areas at the rear or side of buildings. ("Front" is defined as the face of the building which is parallel to a public road. By this definition, buildings on multiple public road frontage lots would have multiple "front yards"). In any event, parking areas which are exposed to a public road shall include a ten (10) foot buffer strip along the front. At a minimum, such strips shall be grassed and/or mulched and shall be planted with low growing trees or shrubs no more than twenty (20) feet apart.

Article VII Changes and Amendments to the Watershed Protection Regulations

The Watauga County Board of Commissioners may, on its own motion or on petition, after public notice and hearing, amend, supplement, change or modify the watershed regulations and restrictions as described herein.

Under no circumstances shall the Board of Commissioners adopt such amendments, supplements or changes that would cause this ordinance to violate the watershed protection rules as adopted by the N.C. Environmental Management Commission. All amendments must be filed with the N.C. Division of Energy, Mineral, and Land Resources., ~~N.C. Division of Environmental Health, and other State of NC agencies as required.~~

Article VIII Variances

The Board of Adjustment shall have the power to authorize, in specific cases, minor variances from the terms of this chapter ~~as will not be contrary to the public interests where, owing to special conditions, a literal enforcement of this chapter will result in unnecessary hardship, so that the spirit of this~~

chapter shall be observed, public safety and welfare secured, and substantial justice done. and may review major variance requests and make recommendations to the Environmental Management Commission regarding the same. In addition, the county shall notify and allow a reasonable comment period _____ days for all other local governments having jurisdiction in the designated watershed where the variance is being considered.

(A) Applications for a variance shall be made on the proper form obtainable from the Watershed Administrator and shall include the following information:

(1) A site plan, drawn to a scale of at least one (1) inch to forty (40) feet, indicating the property lines of the parcel upon which the use is proposed; any existing or proposed structures; parking areas and other built-upon areas; and surface water drainage. The site plan shall be neatly drawn and indicate north point, name and address of person who prepared the plan, date of the original drawing, and an accurate record of any later revisions.

(2) A complete and detailed description of the proposed variance, together with any other pertinent information which the applicant feels would be helpful to the Watershed Review Board in considering the application.

(3) Evidence or proposed witness testimony that tends to support a finding that each of the factors listed in subsection (C), below, are met.

(B) The Watershed Administrator shall notify in writing each local government having jurisdiction in the watershed and the entity using the water supply for consumption. Such notice shall include a description of the variance being requested. Local governments receiving notice of the variance request may submit comments to the Watershed Administrator prior to a decision by the Watershed Review Board. Such comments shall become a part of the record of proceedings of the Watershed Review Board.

(C) Before the Watershed Review Board may grant a variance, it shall make the following three findings, which shall be recorded in the permanent record of the case, and shall include the factual reasons on which they are based:

(1) There are practical difficulties or unnecessary hardships in the way of carrying out the strict letter of the Ordinance. In order to determine that there are practical difficulties or unnecessary

hardships, the Board must find that the five following conditions exist:

(a) If he complies with the provisions of the Ordinance, the applicant can secure no reasonable return from, nor make reasonable use of, his property. Merely proving that the variance would permit a greater profit to be made from the property will not be considered adequate to justify the Board in granting a variance. Moreover, the Board shall consider whether the variance is the minimum possible deviation from the terms of the Ordinance that will make possible the reasonable use of his property.

(b) The hardship results from the application of the Ordinance to the property rather than from other factors such as deed restrictions or other hardship.

(c) The hardship is due to the physical nature of the applicant's property, such as its size, shape, or topography, which is different from that of neighboring property. (

(d) The hardship is not the result of the actions of an applicant who knowingly or unknowingly violates the Ordinance, or who purchases the property after the effective date of the Ordinance, and then comes to the Board for relief.

(e) The hardship is peculiar to the applicant's property, rather than the result of conditions that are widespread. If other properties are equally subject to the hardship created in the restriction, then granting a variance would be a special privilege denied to others, and would not promote equal justice.

(2) The variance is in harmony with the general purpose and intent of the Ordinance and preserves its spirit.

(3) In the granting of the variance, the public safety and welfare have been assured and substantial justice has been done. The Board shall not grant a variance if it finds that doing so would in any respect impair the public health, safety, or general welfare.

(D) In granting the variance, the Board may attach thereto conditions regarding the location, character, and other features of the proposed building, structure, or use that relate to the purpose and standards of this ordinance. If a variance for the construction, alteration or use of

property is granted, such construction, alteration or use shall be in accordance with the approved site plan.

(E) The Board of Adjustment shall refuse to hear an appeal or an application for a variance previously denied if it finds that there have been no substantial changes in conditions or circumstances bearing on the appeal or application.

(F) A variance issued in accordance with this Section shall be considered a Watershed Protection Permit and shall expire if a Building Permit or Watershed Occupancy Permit for such use is not obtained by the applicant within six (6) months from the date of the decision.

(G) If an applicant requests a major variance as defined in this Article, and if the Board of Adjustment decides in favor of granting the variance, the Board shall prepare a preliminary record of the hearing with all deliberate speed. The preliminary record of the hearing shall include:

(A) The variance application;

(B) The hearing notices;

(C) The evidence presented;

(D) Motions, offers of proof, objections to evidence, and rulings on them;

(E) Proposed findings and exceptions;

(F) The proposed decision, including all conditions proposed to be added to the permit.

The preliminary record shall be sent to the NC Environmental Management Commission for its review. as follows:

~~**(A)** If the Commission concludes from the preliminary record that the variance qualifies as a major variance and that (1) the property owner can secure no reasonable return from, nor make any practical use of the property unless the proposed variance is granted, and (2) the variance, if granted, will not result in a serious threat to the water supply, then the Commission shall approve the variance as proposed or approve the proposed variance with conditions and stipulations. The Commission shall prepare a Commission decision and send it to the Watershed Review Board. If the Commission approves the variance as proposed, the Board shall prepare a final decision granting the proposed variance. If the Commission approves the variance with conditions and stipulations, the Board shall prepare a final decision, including such conditions and stipulations, granting the proposed variance.~~

~~**(B)** If the Commission concludes from the preliminary record that the variance qualifies as a major variance and that (1) the property owner can secure a reasonable return from or make a practical use~~

~~of the property without the variance or (2) the variance, if granted, will result in a serious threat to the water supply, then the Commission shall deny approval of the variance as proposed. The Commission shall prepare a Commission decision and send it to the Watershed Review Board. The Board shall prepare a final decision denying the variance as proposed.~~

~~The Watershed Administrator shall notify in writing each local government having jurisdiction in the watershed. Such notice shall include a description of the variance being requested. Local governments receiving notice of the variance request may submit comments to the Watershed Administrator prior to a decision by the Board of Adjustment. Such comments shall become a part of the record of proceedings of the Board.~~

CHAPTER 22 WIND ENERGY SYSTEMS

Article I Authority and Purpose.

Inasmuch as Watauga County has determined that single wind power turbines are exempt from the North Carolina Mountain Ridge Protection Act, and pursuant to the authority granted to counties by NC General Statute 153A-121 et seq. and other pertinent statutes and amendments thereto, it is the purpose of this ordinance to regulate the use of wind energy systems and to describe the conditions by which a permit for installing a system could be obtained.

Article II Findings.

Wind power is a clean, inexhaustible, reliable, and economical source of energy that can help us reduce our dependence on fossil fuels, help to preserve and protect the environment, and help to create new jobs and sustainable forms of development. As a result of these benefits, wind power has become the fastest growing energy source in the world and is helping to satisfy the growing demand for electricity cleanly and affordably.

The State of North Carolina has enacted a number of laws and programs to encourage the use of small-scale renewable energy systems including a state tax credit, net metering law, property tax exemptions, and a state wide green power program.

Article III Small Wind Energy Systems.

Small wind energy systems shall be a permitted use by right subject to the requirements set forth in this section:

Section 1. Wind Turbine Height.

Height shall be limited to 135 feet.

Section 2. Setback.

The base of the wind turbine shall not be closer to surrounding property lines than the height of the wind turbine unless a NC Registered Professional Engineer certifies the fall zone of the wind turbine and appurtenances will be within the setback area proposed. In addition, no wind turbine shall be located closer to an inhabited structure on adjacent property than 1.5 times the height

of the wind turbine. Relief from this section may be granted if the applicant can secure a permanent easement from the adjoining property owner(s) providing for a fall zone.

Section 3. Building Permit Requirements.

A building permit shall be required and building permit applications for small wind energy systems shall be accompanied by standard drawings of the wind turbine structure, including the tower, base, and footings. An engineering analysis of the tower certified by a licensed professional engineer including standards for ice/wind loading shall also be submitted. This analysis may be supplied by the manufacturer. Wet stamps shall not be required.

Section 4. Compliance with FAA Regulations.

Small wind energy systems must comply with applicable FAA regulations, including any necessary approvals for installations close to airports. Evidence of compliance or non-applicability shall be submitted with the application.

Section 5. Utility Notification.

No small wind energy system shall be installed until evidence has been given that the utility company has been informed of the customer's intent to install an interconnected customer-owned generator. Off-grid systems shall be exempt from this requirement.

Section 6. Appearance.

Small wind energy towers shall maintain a galvanized finish or be painted to conform the tower color to the surrounding environment to reduce visual obtrusiveness. No wind tower should have any signage, or writing or pictures that may be construed as advertising placed on it at any time. In addition, no flags, streamers or decorative items may be attached to the wind energy system tower or turbine.

Section 7. Removal of Defective or Abandoned Wind Energy Systems.

Any wind energy system that is not functional shall be repaired by the owner or removed. In the event that the County becomes aware of any wind energy system that is not operated for a continuous period of 6 months, the County will notify the landowner by registered mail and provide 45 days for a written response. In such a response, the landowner shall set forth reasons for the

operational difficulty and provide a reasonable timetable for corrective action. If the County deems the timetable for corrective action as unreasonable, the County shall notify the landowner and such landowner shall remove the turbine with 120 days of receipt of said notice.

Article IV Large Wind Energy Systems

Large wind energy systems shall be a use permitted by review subject to the requirements of this Article IV as well as Article III, except that the height limits in Article III Section 1 may be increased if approved as necessary by the Board of Adjustment.

Section 1. Permit Application.

- (A) A person seeking a site permit for a wind turbine over 20 KW shall file an application with the County for review. The application must provide the following background information regarding the applicant:
- (1) A letter of transmittal signed by an authorized representative or agent of the applicant.
 - (2) The complete name, address, telephone number, and e-mail address of the applicant and any authorized representative.
 - (3) The signature of the person who prepared the application, if prepared by an agent or consultant of the applicant.
 - (4) The role of the permit applicant in the construction and operation of the wind power project.
 - (5) The identity of any other wind power project located in the State in which the applicant, or a principal of the applicant, has an ownership or other financial interest; the operator of the wind power project if different from the applicant; and the name of the person or persons to be the permittee if a site permit is issued.
- (B) The applicant shall state in the application whether a certificate of public convenience and necessity for the system is required from the North Carolina Utilities Commission and, if so, the anticipated schedule for obtaining the certificate. The County may ask the Utilities Commission to determine whether a certificate of public convenience and necessity is required for a particular wind power project for which the County has received a site permit application. The County shall not approve a project requiring a certificate unless and until such certificate is issued by the Utilities Commission. If a certificate is not required from the Utilities Commission, the permit applicant shall include with the application a discussion of what the applicant intends to do with the power that is generated.

- (C) The applicant shall describe in the application how the proposed wind power project furthers State policy to site such projects in an orderly manner compatible with environmental preservation, sustainable development, and the efficient use of resources.
- (D) The permit applicant shall include the following information about the site proposed for the wind power project and any associated facilities:
 - (1) The surveyed boundaries of the site proposed for the wind power project.
 - (2) The location of other wind turbines in the general area of the proposed wind power project.
 - (3) The applicant's land rights within the boundaries of the proposed site.
- (E) The permit applicant shall provide the following information regarding the design of the proposed wind power project:
 - (1) A project layout, prepared by a design professional, including a map showing the proposed location of the turbine(s).
 - (2) A description of the turbine(s) and tower(s) and other equipment proposed to be used in the wind power project, including the name of the manufacturers of the equipment.
 - (3) A description of the project electrical system, including transformers at both low voltage and medium voltage.
 - (4) A description and location of associated facilities.
- (F) An applicant for a site permit shall include with the application an analysis of the potential impacts of the wind power project, proposed mitigative measures, and any adverse environmental effects that cannot be avoided, in the following areas:
 - (1) Demographics, including people, homes, and businesses.
 - (2) Noise.
 - (3) Visual impacts.
 - (4) Public services and infrastructure
 - (5) Cultural and archaeological impacts.
 - (6) Recreational resources.
 - (7) Public health and safety, including air traffic, electromagnetic fields, and security and traffic.
 - (8) Hazardous materials.
 - (9) Land-based economics, including agriculture, forestry, and mining.
 - (10) Tourism and community benefits.
 - (11) Topography.
 - (12) Soils.
 - (13) Geologic and groundwater resources.
 - (14) Surface water and floodplain resources.
 - (15) Wetlands.
 - (16) Vegetation.

- (17) Avian, impact assessment that includes an indication of the type and number of birds that are known or suspected to use a project site and the area surrounding that site.
- (18) Wildlife.
- (19) Rare and unique natural resources.
- (G) The permit applicant shall describe all of the following:
 - (1) The manner in which the wind power project, including associated facilities, will be constructed.
 - (2) How the wind power project will be operated and maintained after construction, including a maintenance schedule.
 - (3) The anticipated schedule for completion of the wind power project, and shall identify the expected date of commercial operation.
 - (4) The energy expected to be generated by the wind power project.
- (H) The permit applicant shall include the following information regarding decommissioning of the wind power project and restoring the site:
 - (1) The anticipated life of the wind power project.
 - (2) The estimated decommissioning costs in current dollars.
 - (3) The method and schedule for updating the costs of decommissioning and restoration.
 - (4) The method of ensuring that funds will be available for decommissioning and restoration.
 - (5) The anticipated manner in which the wind power project will be decommissioned and the site restored.
- (I) The permit applicant shall include in the application a list of all known federal, state, and local agencies or authorities, and titles of the permits they issue that are required for the proposed wind power project.
- (J) Blue Ridge Parkway: If a proposed wind energy site is within the Blue Ridge Parkway viewshed the applicant shall inform the National Park Service of the proposed wind turbine siting. Park Service recommendations shall be given reasonable consideration and documentation of this consideration shall be provided to the County. The Park Service shall be afforded 30 days to respond to the applicant's written intention to erect a wind turbine. No answer to the notification within the 30 days shall be considered as an affirmation of the site as proposed. Viewshed shall be determined by the County using maps and documents prepared for that purpose by the Design Research Laboratory at NC State University and the Blue Ridge Parkway Division of Resource Planning and Professional Services.

Section 2. Special Use Permit Required.

Prior to granting or denying a permit for a large wind energy system, the Board of Adjustment shall conduct a hearing as set forth in Chapter 3.

CHAPTER 23 WIRELESS TELECOMMUNICATIONS

Article I Purpose and Legislative Intent

The purpose of this Wireless Telecommunications chapter is to provide for the public health, safety and welfare by ensuring that residents, businesses and public safety operations in Watauga County have reliable access to telecommunications networks and state of the art mobile broadband communications services while also minimizing adverse impacts created by wireless facilities and structures. To accomplish the above stated objectives and to ensure that the placement, construction or modification of wireless telecommunications facilities complies with all applicable federal and state laws, including without limitation Section 6409 of the federal Middle Class Tax Relief and Job Creation Act of 2012, 47 U.S.C. 1455(a), and NCGS §160D, Article 9, Part 3, Watauga County enacts these single comprehensive wireless telecommunications regulations. This chapter is enacted pursuant to the general police powers granted by NCGS §153A-121. By enacting this chapter, it is the County's intent to:

- (A) Minimize external impacts (i.e. visual impacts and generator noise) on surrounding areas;
- (B) Encourage cooperation among carriers and joint use of new and existing wireless structures in an effort to minimize the necessity for new structures;
- (C) Encourage use of existing buildings and suitable alternative structures for wireless facility use in an effort to minimize the number of new structures;
- (D) Encourage concealed wireless structures;
- (E) Encourage concealed antenna designs;
- (F) Encourage concealed cables and feed lines;
- (G) Minimize visual impacts on Major Mountain Ridges to the greatest extent possible.

Article II Approvals Required for Wireless Facilities and Wireless Support Structures

Section 1. Administrative Review and Approval.

The following types of applications are subject to the review process as provided in Article III. No other type of site plan review is necessary:

- (A) New wireless support structures that are 60 feet or less in height.
- (B) New wireless support structures that are 100 feet or less in height and separated from residential dwellings by a distance of 300 feet or more.

- (C) New wireless support structures that are 140 feet or less in height located within commercial or industrial areas and separated from residential dwellings by a distance of 300 feet or more.
- (D) Concealed wireless facilities that are 140 feet or less in height and separated from residential dwellings by a distance of 300 feet or more.
- (E) Monopoles or replacement poles located on public property or within utility easements or rights-of-way.
- (F) COWs, if the use of the COW is either not in response to a declaration of an emergency or disaster by the Governor, or will last in excess of one hundred-twenty (120) days.
- (G) Substantial modifications.
- (H) Collocations.

Section 2. Board Review and Approval.

Any application for wireless facilities and/or wireless support structures not subject to administrative review and approval pursuant to this chapter shall be permitted upon the granting of a Special Use Permit by the Watauga County Board of Adjustment.

Section 3. Exempt from Review and Approval.

The following are exempt from all County approval processes and requirements:

- (A) Removal or replacement of transmission equipment on an existing wireless tower or base station that does not result in a substantial modification as defined in this ordinance.
- (B) Ordinary maintenance of existing wireless facilities and wireless support structures, as defined in this Article.
- (C) Wireless facilities placed on utility poles.
- (D) COWs placed for a period of not more than one hundred twenty (120) days at any location within the County or after a declaration of an emergency or a disaster by the Governor.
- (E) Antennas or antenna support structures of amateur radio operators 90 feet or less in height.
- (F) New and existing wireless support structures and facilities owned by governmental agencies and designed for non-commercial emergency communications.

Article III Administrative Review and Approval Process

Section 1. Content of Application Package for New Sites.

All administrative review application packages must contain the following:

- (A) Administrative review application form signed by the owner, or the applicant in accordance with item (B) below;
- (B) Non-owner applicants must provide a copy of a lease or letter of authorization from the property owner evidencing applicant's authority to pursue the application. Such submissions need not disclose financial lease terms; and
- (C) Site plans detailing proposed improvements which comply with this ordinance. Drawings must depict improvements related to the applicable requirements including property boundaries, setbacks, topography, elevation sketch, and dimensions of improvements.
- (D) Documentation from a North Carolina licensed professional engineer including calculation of the fall zone and certification that the wireless support structure has sufficient structural integrity to accommodate the required number of additional users as provided in this ordinance. Design of the support structure shall be in accordance with the latest ANSI/EIA/TIA-222 standards. Tower foundation design shall be in accordance with Chapter 18 of the NC Building Code. Grounding and electrical service equipment shall be in accordance with the National Electric Code. Watauga County is located within a *Special Wind Region* that will impact structural design of wireless structures and foundations.

Section 2. Content of Application Package for Other Sites/Facilities.

All administrative review application packages must contain the following:

- a) Administrative review application form signed by the owner, or the applicant in accordance with item Section 1 (B) above;
- b) For collocations and substantial modifications, written verification from a North Carolina licensed professional engineer certifying that the host support structure is structurally and mechanically capable of supporting the proposed additional antenna or configuration of antennas. Watauga County is located within a *Special Wind Region* that will impact structural design of wireless structures and foundations.
- c) For substantial modifications, drawings depicting the improvements along with their dimensions.

Section 3. Fees.

Permit fees are pursuant to the Planning & Inspections Fee Schedule. The fees for Collocation, Substantial Modifications, New Wireless Support Structures and Special Use permit applications include the Building Inspector's review and approval of structural and electrical systems that are subject to the North Carolina State Building Code and the National Electric Code respectively.

Section 4. Procedure and Timing.

(A) Applications for Collocation, Monopole or Replacement Pole, Concealed Wireless Facility, Non-exempt COW or Substantial Modification. Within thirty (30) days of the receipt of an application for a collocation, a monopole or replacement pole, a concealed wireless facility, a non-exempt COW or a substantial modification, the Administrator will:

- (1)** Review the application for conformity with this chapter. An application under this Section D.1 is deemed to be complete unless the Administrator notifies the applicant in writing, within fourteen (14) calendar days of submission of the application of the specific deficiencies in the application which, if cured, would make the application complete. Upon receipt of a timely written notice that an application is deficient, an applicant may take fourteen (14) calendar days from receiving such notice to cure the specific deficiencies. If the applicant cures the deficiencies within ten fourteen (14) calendar days, the application shall be reviewed and processed within thirty (30) calendar days from the initial date the application was received. If the applicant requires a period of time beyond fourteen (14) calendar days to cure the specific deficiencies, the thirty (30) calendar days deadline for review shall be extended by the same period of time;
- (2)** Make a final decision to approve the collocation application or approve or disapprove other applications under Section 4 (A); and
- (3)** Advise the applicant in writing of the final decision. If the Administrator denies an application, written justification of the denial, which must be based on substantial evidence of inconsistencies between the application and this chapter, must be provided.
- (4)** Failure to issue a written decision within thirty (30) calendar days shall constitute an approval of the application.

(B) Applications for New Wireless Support Structures That Are Subject to Administrative Review and Approval. Within forty five (45) calendar

days of the receipt of an application for a new wireless support structure that is subject to administrative review and approval under this chapter, the Administrator will:

- ~~(1)~~ Review the application for conformity with this chapter. An application under Section 4 (B) is deemed to be complete unless the Administrator notifies the applicant in writing, within fifteen (15) calendar days of submission of the application of the specific deficiencies in the application which, if cured, would make the application complete. Upon receipt of a timely written notice that an application is deficient, an applicant may take fifteen (15) calendar days from receiving such notice to cure the specific deficiencies. If the applicant cures the deficiencies within fifteen (15) calendar days, the application shall be reviewed and processed within forty five (45) calendar days from the initial date the application was received. If the applicant requires a period of time beyond fifteen (15) calendar days to cure the specific deficiencies, the forty five calendar days deadline for review shall be extended by the same period of time;
 - ~~(2)~~ Make a final decision to approve or disapprove the application; and
 - ~~(3)~~ Advise the applicant in writing of the final decision. If the Administrator denies an application, written justification of the denial, which must be based on substantial evidence of inconsistencies between the application and this chapter, must be provided.
 - ~~(4)~~ Failure to issue a written decision within forty five (45) calendar days shall constitute an approval of the application.
- (C) Building Permits associated with (A) and (B) above. A Building Inspector shall issue a building permit following approval of the application under administrative review in accordance with the process and standards of this chapter and the North Carolina State Building Code.

Article IV Special Use Permit Process.

Section 1. Special Use Permit.

Any wireless facility or wireless support structures not meeting the requirements of Article II Section 1 or 3 may be permitted upon the granting of a Special Use permit, subject to:

- (A) The submission requirements of Section IV.B below; and
- (B) The applicable standards of Section V below; and
- (C) The requirements of the Special Use permit approval.

Section 2. Content of Special Use Permit Application Package.

All Special Use permit application packages must contain the following:

- (A) Special Use Permit application form signed by the owner, or the applicant in accordance with (B) below;
- (B) Non-owner applicants must provide a copy of lease or letter of authorization from the property owner evidencing applicant's authority to pursue the application. Such submissions need not disclose financial lease terms;
- (C) Written description and scaled drawings of the proposed wireless support structure or wireless facility, including structure height, ground and structure design, and proposed materials;
- (D) Number of proposed antennas and their height above ground level, including the proposed placement of antennas on the wireless support structure;
- (E) Line-of-sight diagram or photo simulation, showing the proposed wireless support structure set against the skyline and viewed from at least four (4) directions within the surrounding areas;
- (F) A statement that the proposed wireless support structure will be made available for collocation to other service providers at commercially reasonable rates, provided space is available and consistent with Article V Section 1 (A) of this chapter.

Section 3. Fees.

~~The total fees for reviewing a Special Use permit application with proposed wireless facilities shall be considered together as one application requiring only a single application fee.~~

Section 4. Procedure and Timing.

~~Within one hundred fifty (150) calendar days of the receipt of an application under Article IV of this chapter, the Administrator and Board of Adjustment will:~~

- ~~(A) Complete the process for reviewing the application for conformity with this chapter. An application under this Article IV. is deemed to be complete unless the Administrator notifies the applicant in writing, within thirty (30) calendar days of submission of the application of the specific deficiencies in the application which, if cured, would make the application complete. Upon receipt of a timely written notice that an application is deficient, an applicant may take thirty (30) calendar days from receiving such notice to cure the specific deficiencies. If the applicant cures the deficiencies within thirty (30) calendar days, the application shall be reviewed and processed within one hundred~~

fifty (150) calendar days from the initial date the application was received. If the applicant requires a period of time beyond thirty (30) calendar days to cure the specific deficiencies, the one hundred fifty (150) calendar days deadline for review shall be extended by the same period of time;

- ~~(B)~~ Conduct a quasi-judicial hearing pursuant to Chapter 3;
- ~~(C)~~ Make a final decision to approve or disapprove the application; and
- ~~(D)~~ Advise the applicant in writing of its final decision.
- ~~(E)~~ Failure to issue a written decision within one hundred fifty (150) calendar days shall constitute an approval of the application.

Article V General Standards and Design Requirements.

Section 1. Design.

- (A)** Wireless support structures:
 - (1)** Shall be engineered and constructed to accommodate a minimum number of collocations based upon their height as follows:
 - (a)** Support structures 60 to 100 feet in height shall support at least two (2) telecommunications providers;
 - (b)** Support structures greater than 100 feet shall support at least three (3) telecommunications providers;
 - (2)** The equipment compound area surrounding the wireless support structure must be of sufficient size to accommodate accessory equipment for the appropriate number of telecommunications providers in accordance with Article V Section 1(A)(1).
- (B)** Concealed wireless facilities are required on Major Mountain Ridges. Concealed wireless facilities shall be designed to accommodate the collocation of other antennas whenever economically and technically feasible. Antennas must be enclosed, camouflaged, screened, obscured or otherwise not readily apparent to a casual observer.
- (C)** Upon request of the applicant, the Board or Administrator may waive the requirement that new wireless support structures accommodate the collocation of other service providers if it finds that collocation at the site is not essential to the public interest, or that the construction of a shorter support structure with fewer antennas will promote community compatibility.
- (D)** A monopole or replacement pole shall be permitted within utility easements or rights-of-way, in accordance with the following requirements:
 - (1)** The utility easement or right-of-way shall be a minimum of one hundred (100) feet in width.

- (2) The easement or right-of-way shall contain overhead utility transmission and/or distribution structures that are eighty (80) feet or greater in height.
 - (3) The height of the monopole or replacement pole may not exceed by more than thirty (30) feet the height of existing utility support structures.
 - (4) Monopoles and the accessory equipment shall be set back a minimum of fifteen (15) feet from all boundaries of the easement or right-of-way.
 - (5) Single carrier monopoles may be used within utility easements and rights-of-way due to the height restriction imposed by Subsection (3) above.
 - (6) Poles that use the structure of a utility tower for support are permitted. Such poles may extend up to twenty (20) feet above the height of the utility tower.
- (E) Generators shall be located within equipment shelters or enclosed to limit noise levels.

Section 2. Setbacks.

Unless otherwise stated herein, each wireless support structure shall be set back from all property lines a distance equal to its engineered fall zone.

Section 3. Height.

Substantial Modifications and newly erected Wireless Support Structures shall not exceed the permitted height except by Special Use Permit granted by the Board of Adjustment.

Section 4. Aesthetics.

- (A) Lighting and Marking. Wireless facilities or wireless support structures shall not be lighted or marked unless required by the Federal Communications Commission (FCC) or the Federal Aviation Administration (FAA).
- (B) Signage. Signs located at the wireless facility shall be limited to ownership and contact information, FCC antenna registration number (if required) and any other information as required by government regulation. Commercial advertising is strictly prohibited. Notwithstanding the foregoing, nothing in this chapter shall prohibit signage that is approved for other uses on property on which wireless facilities are located (*e.g.*, approved signage at locations on which concealed facilities are located).

Section 5. Accessory Equipment.

Accessory equipment, including any buildings, cabinets or shelters, shall be used only to house equipment and other supplies in support of the operation of the wireless facility or wireless support structure. Any equipment not used in direct support of such operation shall not be stored on the site.

Section 6. Fencing.

- (A) Ground mounted accessory equipment and wireless support structures shall be secured and enclosed with a fence not less than six (6) feet in height as deemed appropriate by the Board or Administrator.
- (B) The Board or Administrator may waive the requirement of Article V Section 6 (A) if it is deemed that a fence is not appropriate or needed at the proposed location.

Section 7. Landscaping.

The equipment compound shall be screened with landscaping native to the area and suitable for planting in USDA Hardiness Zone 6a. All plants, including the root ball dimensions or container size to trunk caliper ratio, shall conform to ANSI Z60.1 "American Standard for Nursery Stock" latest edition. Quantity, ratio and minimum sizes of trees and shrubs shall be as follows:

- (A) Deciduous and/or Evergreen trees – twenty (20) feet maximum spacing. Trees shall have a minimum height of six (6) feet upon planting. Deciduous trees shall have a minimum two (2) inch caliper.
- (B) Shrubs – six (6) feet maximum spacing. Shrubs shall be a minimum height of eighteen (18) inches upon planting.
- (C) The recipient of any wireless communication or special-use permit, or their successor, shall be responsible for maintaining all common areas, improvements, or facilities required by the ordinance or any permit issued in accordance with its provisions. As illustrations, and without limiting the generality of the foregoing, this means that private roads and parking areas, and required vegetation and trees used for screening, landscaping, or shading must be replaced if they die or are destroyed.

Article VI Miscellaneous Provisions.

Section 1. Abandonment and Removal.

If a wireless support structure is abandoned, and it remains abandoned for a period in excess of twelve (12) consecutive months, the County may require that such wireless support structure be removed only after first providing

written notice to the owner of the wireless support structure and giving the owner the opportunity to take such action(s) as may be necessary to reclaim the wireless support structure within sixty (60) days of receipt of said written notice. In the event the owner of the wireless support structure fails to reclaim the wireless support structure within the sixty (60) day period, the owner of the wireless support structure shall be required to remove the same within six (6) months thereafter. The County shall ensure and enforce removal by means of its existing regulatory authority, with costs of removal charged to the owner.

Section 2. Multiple Uses on a Single Parcel or Lot.

Wireless facilities and wireless support structures may be located on a parcel containing another principal use on the same site or may be the principal use itself.

Article VII Wireless Facilities and Wireless Support Structures in Existence on the Date of Adoption of this Ordinance.

Section 1. Existing Wireless Facilities.

Wireless facilities and wireless support structures that were legally permitted on or before the date this chapter was enacted shall be considered a permitted and lawful use as long as they remain compliant with the permit issued.

Section 2. Activities at Non-Conforming Wireless Support Structures.

Notwithstanding any provision of this chapter:

- (A) Ordinary maintenance may be performed on a non-conforming wireless support structure or wireless facility.
- (B) Collocation of wireless facilities on an existing non-conforming wireless support structure shall not be construed as an expansion, enlargement or increase in intensity of a non-conforming structure and/or use and shall be permitted through the administrative approval process defined in Article II; provided that the collocation does not substantially modify the size of the equipment compound at that location or otherwise substantially modify the existing non-conformity.
- (C) Substantial modifications may be made to non-conforming wireless support structures utilizing the Special Use permit process defined in Article IV of this chapter.

Article VIII Jurisdiction

The provisions of this chapter shall be applicable only to unincorporated areas of Watauga County which are not included in the extraterritorial jurisdiction of a municipality.

Article IX National Park Service Review

When new wireless support structures or substantial modifications are proposed within one mile of the Blue Ridge Parkway centerline and within the Parkway viewshed, the applicant shall inform the National Park Service and seek recommendations. Park Service recommendations shall be given reasonable consideration and documentation of this consideration shall be provided to the Administrator. The Park Service shall be afforded thirty (30) days to respond to the applicant's initial request.

Article X Valle Crucis Historic District

Wireless support structures shall be prohibited within the Valle Crucis Historic District.

CHAPTER 24 ADMINISTRATIVE PROCEDURES

Article I Purpose and Intent

This Chapter establishes the procedures used by Watauga County's Planning and Inspection Department for the processing of applications for development permits or approvals. It is the intent of this Chapter to establish a uniform set of processes to foster greater efficiency and predictability for applicants, County residents, County staff, and elected and appointed officials during the review of development applications.

Article II Application Submittal, Acceptance, and Withdrawal

Section 1. Authority to File Applications

- (A) Unless expressly stated otherwise in this Ordinance, development applications associated with a particular lot or site reviewed under this Ordinance shall be filed by the landowner, contract purchaser, or other person having a recognized property interest in the land on which development is proposed.
- (B) Applications for amendments to the text of this Ordinance may only be initiated by the Ordinance Administrator, the Planning Board, the Board of County Commissioners, or a landowner.

Section 2. Application Content

The County shall establish development application content and forms, which shall be maintained by the Ordinance Administrator. The presumption shall be that all of the information required in the application forms is necessary to satisfy the requirements of this section. However, it is recognized that each application is unique, and therefore more or less information may be required according to the needs of the particular case. The applicant may rely on the recommendations of the Ordinance Administrator as to whether more or less information should be submitted.

Section 3. Application Fees

- (A) The Board of Commissioners shall establish application fees and may amend and update those fees as necessary. Fees shall cover the costs of review, including public notification, as required.

- (B) No action shall be taken on an application and no application approval shall be issued until all required application fees are paid in full.

Section 4. Application Filing

- (A) Applications shall be filed with the County in the form established by the County, along with the appropriate application fee.
- (B) An application shall not be considered to be submitted until determined to be complete in accordance with Section 6, Determination of Application Completeness.
- (C) No application shall be reviewed or decided until after it is determined to be complete.

Section 5. Application Deadline

Applications sufficient for processing shall be submitted in accordance with the published calendar schedule. Schedules indicating submittal dates shall be developed each year and made available to the public.

Section 6. Burden of Presenting Complete Application

The burden of presenting and maintaining a complete application shall be solely upon the applicant.

Section 7. Determination of Application Completeness

Upon development application filing, the Ordinance Administrator shall determine, within ten (10) business days, whether the application is complete or incomplete. A complete application is one that:

- (A) Contains all information and materials identified in this Ordinance and all supporting documentation, as required for submittal of the particular type of application;
- (B) Is in the form and number of copies required by the County;
- (C) Is legible and printed to scale, where appropriate;
- (D) Is signed by the person(s) with the authority to file the application;
- (E) Includes information in sufficient detail to evaluate whether or not the application complies with the applicable review standards in this Ordinance;
- (F) Is accompanied by the fee established for the particular type of application.

However, it is recognized that each application is unique, and therefore more or less information may be required according to the needs of the particular case. In general, an application shall be complete and sufficient for processing when it contains all of the information necessary to decide whether or not the development as proposed will comply with all of the requirements of this ordinance.

Section 8. Application Incomplete

If the application is incomplete, the Ordinance Administrator shall notify the applicant of the deficiencies in writing. The applicant may correct the deficiencies and resubmit the application for completeness determination in accordance with Article II Application Filing and Acceptance.

Section 9. Application Complete

- (A) On determining that the application is complete, it shall be considered as submitted, and the Ordinance Administrator shall notify the applicant and commence review in accordance with the procedures and standards of this Ordinance.
- (B) Nothing shall preclude the Ordinance Administrator or a review authority from re-evaluating an application for completeness in the event application inadequacies are revealed at a date subsequent to an application being declared complete.

Section 10. Application Withdrawal

- (A) After an application has been accepted for review, the applicant may withdraw the application at any time by submitting a letter of withdrawal to the Ordinance Administrator. No application fee shall be refunded.
- (B) If the applicant fails to resubmit a complete application within forty-five (45) calendar days after being first notified of submittal deficiencies, the application shall be considered withdrawn and applicable fees shall not be refunded.

Article III Staff Review and Action

Section 1. Initial Staff Review

- (A) Following application completeness determination, development application materials shall be distributed by the Ordinance

- Administrator to all appropriate staff and review agencies for review and comment.
- (B) Applications shall be reviewed during the review cycle in place when the application is determined to be complete.
 - (C) In considering the application, the Ordinance Administrator or other County staff (as appropriate), shall review the application, relevant support material, and any comments from other staff and review agencies to which the application was referred.
 - (D) If deficiencies in complying with applicable standards of this Ordinance are identified, the Ordinance Administrator shall notify the applicant of such deficiencies in writing and provide the applicant a reasonable opportunity to discuss them and revise the application accordingly.

Section 2. Staff Report and Recommendation

- (A) The Ordinance Administrator shall prepare a written staff report on any application to be reviewed or decided by the Planning Board, Board of County Commissioners, Board of Adjustment., or the Valle Crucis Historic Preservation Commission
- (B) The staff report shall conclude whether the application complies with all applicable review standards of this Ordinance.
- (C) In cases where the Ordinance Administrator finds an application does not comply with the provisions of this Ordinance the staff report shall cite the specific code section(s) in question and the reasons why the application fails to comply.
- (D) A staff report is not required for applications decided by the Ordinance Administrator, though one may be prepared.

Section 3. Distribution of Application and Staff Report

In cases where a staff report is prepared, the Ordinance Administrator shall take the following actions within a reasonable time period before the application is scheduled for review:

- (A) Schedule and ensure any required public notice of the application (if appropriate) is prepared in accordance with Article IV, Public Notification;
- (B) Transmit the application, related materials, and staff report to the appropriate review authority(ies);

- (C) Transmit a copy of the staff report and any related materials to the applicant, the appellant, and the landowner (if the landowner is different from the appellant or the applicant) at the same time they are transmitted to the appropriate review authority(ies); and
- (D) Make the application, related materials, and staff report available for examination by the public.

Section 4 Applications Subject to Decision by Staff

- (A) In cases where a development application is decided by the Ordinance Administrator or other designated County staff member, the appropriate County staff member shall make one of the following decisions, based on the review standards set forth for the application type:
 - (1) Approve the application;
 - (2) Disapprove the application; or
 - (3) Delay decision making for a specified time to allow the applicant to revise the application for compliance with the requirements in this Ordinance.
- (B) In some instances, The Ordinance Administrator or other designated County staff may decide an application contingent upon further revision by the applicant in accordance with the direction provided in the decision.

Article IV Public Notification

The following procedures have been established for development applications/petitions that require notification of the public prior to consideration and/or approval.

Section 1. Quasi-judicial Hearing Level 1

- (A) Mailed Notice: Notice of evidentiary hearings conducted pursuant to Chapter 3 shall be mailed to the person or entity whose appeal, application, or request is the subject of the hearing; to the owner of the property that is the subject of the hearing if the owner did not initiate the hearing; to the owners of all parcels of land abutting the parcel of land that is the subject of the hearing; and to any other persons entitled to receive notice as provided by the local development regulation. The notice must be deposited in the mail at

least 10 days, but not more than 25 days, prior to the date of the hearing.

- (B) Within that same time period, the local government shall also prominently post a notice of the hearing on the site that is the subject of the hearing or on an adjacent street or highway right-of-way.

Section 2. Quasi-Judicial Hearing Level 2

- (A) Mailed Notice: Notice of evidentiary hearings conducted pursuant to Chapter 3 shall be mailed to the person or entity whose appeal, application, or request is the subject of the hearing; to the owner of the property that is the subject of the hearing if the owner did not initiate the hearing; to the owners of all parcels of land within 100 feet on all sides of the parcel of land that is the subject of the hearing; and to any other persons entitled to receive notice as provided by the local development regulation. The notice must be deposited in the mail at least 10 days, but not more than 25 days, prior to the date of the hearing.

- (B) Within that same time period, the local government shall also prominently post a notice of the hearing on the site that is the subject of the hearing or on an adjacent street or highway right-of-way.

Section 3. Quasi-Judicial Hearing Level 3

- (A) Mailed Notice. Notice of evidentiary hearing conducted pursuant to Chapter 3 shall be mailed to the person or entity whose appeal, application, or request is the subject of the hearing; to the owner of the property that is the subject of the hearing if the owner did not initiate the hearing to all owners of property abutting and to the owners of all parcels of land within 500 feet of the subject parcel twenty five (25) days in advance of the hearing.

- (B) Within that same time period, the local government shall also prominently post a notice of the hearing on the site that is the subject of the hearing or on an adjacent street or highway right-of-way.

- (C) In addition, notice shall be published in a newspaper of general circulation in the area sixty (60) days and again two (2) weeks in advance of the hearing.

- (D) An announcement of the hearing shall be placed on the County's web site sixty (60) days in advance of the hearing, and remain there continuously until the hearing.

Section 4 Legislative Hearing

- (A)** Text Amendment: A notice of the hearing shall be given once a week for two successive calendar weeks in a newspaper having general circulation in the area. The notice shall be published the first time not less than 10 days nor more than 25 days before the date scheduled for the hearing. In computing such period, the day of publication is not to be included but the day of the hearing shall be included.
- (B)** Rezoning:
- (1)** Mailed Notice. –The owners of affected parcels of land and the owners of all parcels of land abutting that parcel of land shall be mailed a notice of the hearing on a proposed zoning map amendment by first-class mail at the last addresses listed for such owners on the county tax abstracts. For the purpose of this section, properties are "abutting" even if separated by a street, railroad, or other transportation corridor. This notice must be deposited in the mail at least 10 but not more than 25 days prior to the date of the hearing.
- (2)** Optional Notice for Large-Scale Zoning Map Amendments. – The first-class mail notice required under subsection (1) of this section is not required if the zoning map amendment proposes to change the zoning designation of more than 50 properties, owned by at least 50 different property owners, and the ordinance administrator elects to use the expanded published notice provided for in this subsection. In this instance, a local government may elect to make the mailed notice provided for in subsection (1) of this section or, as an alternative, elect to publish notice of the hearing as required by G.S. 160D-601, provided that each advertisement shall not be less than one-half of a newspaper page in size. The advertisement is only effective only for property owners who reside in the area of general circulation of the newspaper that publishes the notice. Property owners who reside outside of the newspaper circulation area, according to the address listed on the most recent property tax listing for the affected property, shall be notified according to the provisions of subsection (1) of this section.
- (3)** Posted Notice. – When a zoning map amendment is proposed, the County shall prominently post a notice of the hearing on

the site proposed for the amendment or on an adjacent public street or highway right-of-way. The notice shall be posted within the same time period specified for mailed notices of the hearing. When multiple parcels are included within a proposed zoning map amendment, a posting on each individual parcel is not required but the County shall post sufficient notices to provide reasonable notice to interested persons.

ARTICLE V Special Use Reviews

Section 1. High Impact Land Use (HILU)

- (A) Applicability:** A special use permit shall be required for all High Impact Land Uses as set forth in Chapter 13 Article II.
- (B) Process Type:** Quasi-Judicial – Board of Adjustment
- (C) Required Application Information:** An application for a High Impact Land Special Use review shall be submitted in accordance with Article II Application Filing and Acceptance and the following provisions:
 - (1) High Impact Land Use Review Application**
 - (2)** 2 copies of a site plan, drawn to scale, showing the actual dimensions and shape of the lot to be built upon; the exact sizes and locations on the lot of any buildings already existing; the location and dimensions of the proposed building or alteration; and compliance with the standards of Chapter 13 Article II. The application shall include such other information as may reasonably be required by the Ordinance Administrator, including a description of all existing or proposed buildings or alterations; existing and proposed uses of the buildings and land; conditions existing on the land parcel; and such other matters as may be necessary to determine conformance with, and provide for the enforcement of, this chapter.
 - (3) Developer Authorization Form** if being developed by person(s) other than land owner(s).
- (D) Public Notice:** Quasi-Judicial Hearing Level 3
- (E) Appeals:** Appeals of decisions of the Board of Adjustment shall be subject to review at the instance of any aggrieved party by the Superior Court by proceedings in the nature of certiorari. The appeal to Superior Court must be filed within 30 days of the filing by the Board Clerk of the decision in the office of the Department of Planning & Inspections or the delivery of the notice.

- (F) Permit Validity: A HILU Special Use Permit shall expire if a Building Permit or High Impact Land Use Occupancy Permit for such use is not obtained by the applicant within twelve (12) months from the date of issuance.

Section 2. Wireless Communication Towers

- (A) Applicability: Any wireless facility or wireless support structures not meeting the requirements of Chapter 23 Article II Section 1 or 3 may be permitted upon the granting of a Special Use permit.
- (B) Process Type: Quasi-Judicial - Board of Adjustment
- (C) Required Application Information: An application for a Wireless Communication Towers review shall be submitted in accordance with Article II Application Filing and Acceptance and the following provisions:
 - (1) Wireless Communication Towers Review Application
 - (2) Special Use Permit application form signed by the owner, or the applicant in accordance with (3) below;
 - (3) Non-owner applicants must provide a copy of lease or letter of authorization from the property owner evidencing applicant's authority to pursue the application. Such submissions need not disclose financial lease terms;
 - (4) Written description and scaled drawings of the proposed wireless support structure or wireless facility, including structure height, ground and structure design, and proposed materials;
 - (5) Number of proposed antennas and their height above ground level, including the proposed placement of antennas on the wireless support structure;
 - (6) Line-of-sight diagram or photo simulation, showing the proposed wireless support structure set against the skyline and viewed from at least four (4) directions within the surrounding areas;
 - (7) A statement that the proposed wireless support structure will be made available for collocation to other service providers at commercially reasonable rates, provided space is available and consistent with Chapter 23 Article V Section 1 (A) of this chapter.
- (D) Public Notice: Quasi-Judicial Hearing Level 1

- (E) Appeals: Appeals of decisions of the Board of Adjustment shall be subject to review at the instance of any aggrieved party by the Superior Court by proceedings in the nature of certiorari. The appeal to Superior Court must be filed within 30 days of the filing by the Board Clerk of the decision in the office of the Department of Planning & Inspections or the delivery of the notice.
- (F) Permit Validity: A Wireless Communication Towers development approval issued pursuant to this ordinance expires one year after the date of issuance if the work authorized by the development approval has not been substantially commenced.

Section 3. Large Wind Energy System Review

- (A) Applicability: Large wind energy systems shall be subject to the requirements of Chapter 22 Article IV as well as Chapter 22 Article III, except that the height limits in Chapter 22 Article III Section 1 may be increased if approved as necessary by the Board of Adjustment.
- (B) Process Type: Quasi-Judicial - Board of Adjustment
- (C) Required Application Information: An application for a Large Wind Energy System Review shall be submitted in accordance with Article II Application Filing and Acceptance and the following provisions:
 - (1) Wind Energy System Review Application
 - (2) Documentation as required by Chapter 22 Article IV Section 1.
 - (3) Developer Authorization Form if being developed by person(s) other than land owner(s).
- (D) Public Notice: Quasi-Judicial Level 1
- (E) Appeals: Appeals of decisions of the Board of Adjustment shall be subject to review at the instance of any aggrieved party by the Superior Court by proceedings in the nature of certiorari. The appeal to Superior Court must be filed within 30 days of the filing by the Board Clerk of the decision in the office of the Department of Planning & Inspections or the delivery of the notice.
- (F) Permit Validity: A Large Wind Energy System development approval issued pursuant to this ordinance expires one year after the date of issuance if the work authorized by the development approval has not been substantially commenced.

Section 4. Foscoe Grandfather Special Use Review

- (A)** Applicability: The regulations set forth in Chapter 10 shall apply to all land, every building and every use of land and/or building except bona fide farms as defined in N.C.G.S. 160D-903 within the boundaries of the Foscoe-Grandfather Community.
- (B)** Process Type: Quasi-Judicial - Board of Adjustment
- (C)** Required Application Information: An application for a Special Use Permit Review shall be submitted in accordance with Article II Application Filing and Acceptance and the following provisions:
 - (1)** Foscoe/Grandfather Special Use Permit Application
 - (2)** A site plan as defined in Chapter 7 showing compliance with standards in Chapter 10 Article VI.
 - (3)** Developer Authorization Form if being developed by person(s) other than land owner(s).
 - (4)** Planned Unit Developments will also need the following:
 - a. Preliminary Plat meeting the specifications in Chapter 18 Article V Section 3
 - b. Preliminary Plat Checklist (Chapter 18 Appendix E)
 - c. Adequate assurance of public or community water and sanitary sewer service.
- (D)** Public Notice: Quasi-Judicial Hearing Level 1
- (E)** Appeals: Appeals of decisions of the Board of Adjustment shall be subject to review at the instance of any aggrieved party by the Superior Court by proceedings in the nature of certiorari. The appeal to Superior Court must be filed within 30 days of the filing by the Board Clerk of the decision in the office of the Department of Planning & Inspections or the delivery of the notice.
- (F)** Permit Validity: A Foscoe Grandfather Special Use development approval issued pursuant to this ordinance expires one year after the date of issuance if the work authorized by the development approval has not been substantially commenced.

Article VI Administrative Permit Reviews

Section 1 Foscoe Grandfather Zoning

- (A)** Applicability. The regulations set forth in Chapter 10 shall apply to all land, every building and every use of land and/or building except

bona fide farms as defined in N.C.G.S. 160D-903 within the boundaries of the Foscoe-Grandfather Community.

- (B)** Process Type. Administrative- Ordinance Administrator
- (C)** Required Application Information. An application for a Zoning Permit shall be submitted in accordance with Article II Application Filing and Acceptance and the following provisions:
 - (1)** Zoning Permit Application
 - (2)** Plans, drawn to scale, showing the actual dimensions and shape of the lot to be built upon; the exact sizes and locations on the lot of buildings already existing, if any; and location and dimensions of the proposed building or alteration. The application shall include such other information as lawfully may be required by the Zoning Official including a description of all existing or proposed buildings or alterations; existing or proposed uses of the buildings and land; the number of families, housekeeping units, or rental units the buildings are designed to accommodate; conditions existing on the lot; and such other matters as may be necessary to determine conformance with Chapter 10.
- (D)** Public Notice. None Required.
- (E)** Appeals: Appeals of decisions of the Ordinance Administrator shall be heard by the Board of Adjustment in accordance with Chapter 3.
- (F)** Permit Validity: Zoning Permits shall be valid for 1 year following the date of issuance. Failure to initiate construction, or otherwise begin the permitted use, within this time period shall render the permit void.

Section 2 Electronic Access Gates for Gated Communities

- (A)** Applicability: Applies to the installation of electronic access gates for gated communities.
- (B)** Process Type. Administrative – Ordinance Administrator
- (C)** Required Application Information. An application for an Electronic Access Gate Permit shall be submitted in accordance with Article II Application Filing and Acceptance and the following provisions:
 - (1)** Electronic Gate Permit Application
 - (2)** A detailed plan, including but not limited to, scaled drawings showing the location of the gates, turn radius, dimensions of

the gates, pavement, sidewalks, curbs, etc. Information such as topography lines, vegetation, site triangles, etc.

(3) Documentation of means of emergency access.

(D) Public Notice. None Required.

(E) Appeals: Appeals of decisions of the Ordinance Administrator shall be heard by the Board of Adjustment in accordance with Chapter 3.

(F) Permit Validity: Electronic Gate Permits shall be valid for six (6) months following the date of issuance. Failure to initiate construction, or otherwise begin the permitted use, within this time period shall render the permit void.

Section 3. Signs

(A) Applicability. Except as otherwise provided in Chapter 16 Article III Section 1, no sign may be erected, located, or altered in any manner until a sign permit, and building permit if necessary, has been secured from the Planning and Inspections Department.

(B) Process Type. Administrative – Ordinance Administrator

(C) Required Application Information. An application for a Sign Permit shall be submitted in accordance with Article II Application Filing and Acceptance and the following provisions:

(1) Sign Permit Application

(2) Walls Signs: Drawings showing sign and building dimensions.

(3) Freestanding Signs: Site plan showing proposed location and drawings showing sign dimensions.

(4) Billboards: Survey verifying spacing and setbacks requirements.

(D) Public Notice. None Required.

(E) Appeals: Appeals of decisions of the Ordinance Administrator shall be heard by the Board of Adjustment in accordance with

(F) Permit Validity: Sign Permits shall be valid for six (6) months following the date of issuance. Failure to initiate construction, or otherwise begin the permitted use, within this time period shall render the permit void.

Section 4. Small Wind Energy Systems

(A) Applicability. Applies to a single wind turbine which has a rated capacity of not more than 20 kW.

(B) Process Type. Administrative- Ordinance Administrator

- (C) Required Application Information. An application for a Wind Energy System Permit shall be submitted in accordance with Article II Application Filing and Acceptance and the following provisions:
 - (1) Wind Energy System Permit Application
 - (2) A scaled drawing including tower, base and footing.
 - (3) Details on exterior finish/paint color.
 - (4) A site plan as defined in Chapter 7.
- (D) Public Notice. None Required.
- (E) Appeals: Appeals of decisions of the Ordinance Administrator shall be heard by the Board of Adjustment in accordance with Chapter 3.
- (F) Permit Validity: Small Wind Energy Systems Permit shall be valid for six (6) months following the date of issuance. Failure to initiate construction, or otherwise begin the permitted use, within this time period shall render the permit void.

Section 5. Wireless Communication Towers

- (A) Applicability. Wireless Communication Towers that can be approved administrative are the following:
 - (1) New wireless support structures that are 60 feet or less in height.
 - (2) New wireless support structures that are 100 feet or less in height and separated from residential dwellings by a distance of 300 feet or more.
 - (3) New wireless support structures that are 140 feet or less in height located within commercial or industrial areas and separated from residential dwellings by a distance of 300 feet or more.
 - (4) Concealed wireless facilities that are 140 feet or less in height and separated from residential dwellings by a distance of 300 feet or more.
 - (5) Monopoles or replacement poles located on public property or within utility easements or rights-of-way.
 - (6) COWs, if the use of the COW is either not in response to a declaration of an emergency or disaster by the Governor, or will last in excess of one hundred-twenty (120) days.
 - (7) Substantial modifications.
 - (8) Collocations.

(B) Process Type. Administrative – Ordinance Administrator

(C) Required Application Information.

(1) An application for a New Wireless Communication Tower Permit shall be submitted in accordance with Article II Application Filing and Acceptance and the following provisions:

a) Wireless Communication Towers application form signed by the owner, or the applicant in accordance with item (2) below;

b) Non-owner applicants must provide a copy of a lease or letter of authorization from the property owner evidencing applicant's authority to pursue the application. Such submissions need not disclose financial lease terms; and

c) Site plans detailing proposed improvements which comply with this ordinance. Drawings must depict improvements related to the applicable requirements including property boundaries, setbacks, topography, elevation sketch, and dimensions of improvements.

d) Documentation from a North Carolina licensed professional engineer including calculation of the fall zone and certification that the wireless support structure has sufficient structural integrity to accommodate the required number of additional users as provided in this ordinance. Design of the support structure shall be in accordance with the latest ANSI/EIA/TIA-222 standards. Tower foundation design shall be in accordance with Chapter 18 of the NC Building Code. Grounding and electrical service equipment shall be in accordance with the National Electric Code. Watauga County is located within a Special Wind Region that will impact structural design of wireless structures and foundations.

(2) An application for Other Sites/Facilities Wireless Communication Tower Permit shall be submitted in accordance with Article II Application Filing and Acceptance and the following provisions:

a) Wireless Communication Towers application form signed by the owner, or the applicant in accordance with Chapter 23 Section 4 (C) (1) (b);

- b) For collocations and substantial modifications, written verification from a North Carolina licensed professional engineer certifying that the host support structure is structurally and mechanically capable of supporting the proposed additional antenna or configuration of antennas. Watauga County is located within a Special Wind Region that will impact structural design of wireless structures and foundations.
- c) For substantial modifications, drawings depicting the improvements along with their dimensions.

(D) Public Notice. None Required.

(E) Appeals: Appeals of decisions of the Ordinance Administrator shall be heard by the Board of Adjustment in accordance with Chapter 3

(F) Permit Validity: Sign Permits shall be valid for six (6) months following the date of issuance. Failure to initiate construction, or otherwise begin the permitted use, within this time period shall render the permit void.

Article VII Historic Preservation Reviews

Section 1. Certificate of Appropriateness – Major Works

(A) Applicability: No building, structure, or land shall hereafter be used or occupied and no building, structure or part hereof shall be hereafter erected, reconstructed, moved, demolished, located or the exterior structurally altered except in conformity with regulations set out herein for the Valle Crucis Historic District.

(B) Process Type: Quasi-Judicial – Valle Crucis Historic Preservation Commission

(C) Required Application Information: An application for a Certificate of Appropriateness shall be submitted in accordance with Article II Application Filing and Acceptance and the following provisions:

(1) Certificate of Appropriateness application

(2) Drawings, plans, photos and/or other sufficient to determine compliance with standards

(D) Public Notice: Quasi-Judicial Hearing Level 2

(E) Appeals: Appeals of decisions of the Valle Crucis Historic Preservation Commission shall be subject to review at the instance of any aggrieved party by the Superior Court by proceedings in the nature of certiorari. The appeal to Superior Court must be filed within 30

days of the filing by the Board Clerk of the decision in the office of the Department of Planning & Inspections or the delivery of the notice.

- (F) Permit Validity: A Certificate of Appropriateness development approval issued pursuant to this ordinance expires one year after the date of issuance if the work authorized by the development approval has not been substantially commenced.

Section 2. Certificate of Appropriateness – Minor Works

- (A) Applicability: No building, structure, or land shall hereafter be used or occupied and no building, structure or part hereof shall be hereafter erected, reconstructed, moved, demolished, located or the exterior structurally altered except in conformity with regulations set out herein for the Valle Crucis Historic District. Minor works are defined in Chapter 20 Article II Section 8(B).
- (B) Process Type: Administration- Ordinance Administrator
- (C) Required Application Information: An application for a Certificate of Appropriateness shall be submitted in accordance with Article II Application Filing and Acceptance and the following provisions:
 - (1) Certificate of Appropriateness application
 - (2) Drawings, plans, photos sufficient to determine compliance with standards
- (D) Public Notice: None
- (E) Appeals: Appeals of decisions of the Ordinance Administrator shall be heard by the Board of Adjustment in accordance with Chapter 3.
- (F) Permit Validity: A Certificate of Appropriateness development approval issued pursuant to this ordinance expires one year after the date of issuance if the work authorized by the development approval has not been substantially commenced.

Article VIII Natural Resource Protection Reviews

Section 1. Sedimentation and Erosion Control Plan

- (A) Applicability: To assure that land-disturbing activity undertaken in Watauga County does not result in accelerated erosion and sedimentation, no such land- disturbing activity on development 1 acre or greater in area shall take place until plans for controlling erosion associated with the activity have been reviewed and approved in accordance with the procedures set forth below.

- (B)** Process Type. Administrative – Ordinance Administrator
- (C)** Required Application Information. A Sedimentation and Erosion Control Plan shall be presented to the Ordinance Administrator according to the following provisions:
 - (1)** Sedimentation and Erosion Control Plan Submission Application
 - (2)** Plan Submission: Two copies of the plan shall be filed with the Ordinance Administrator and 1 copy shall be simultaneously submitted to the Watauga County Soil and Water Conservation District at least 30 days prior to the commencement of the proposed activity.
 - (3)** Financial Responsibility and Ownership Form
 - (4)** Environmental Policy Act Document (If needed)
 - (5)** Content: The plan required by this section shall contain architectural and engineering drawings, maps, assumptions, calculations, and narrative statements as needed to adequately describe the proposed development of the tract and the measures planned to comply with the requirements of this article. Plan content may vary to meet the needs of specific site requirements. Detailed guidelines for plan preparation may be obtained from the city on request.
 - (6)** Watauga County Soil and Water Conservation District comments.
- (E)** Public Notification: None required.
- (F)** Appeals: Except as provided in (6) of this subsection, the appeal of a disapproval or approval with modifications of a plan shall be governed by the following provisions:
 - (1)** The disapproval or modification of any proposed plan by the County shall entitle the Person submitting the plan to a public hearing if such Person submits written demand for a hearing within 15 days after receipt of written notice of disapproval or modifications.
 - (2)** A hearing held pursuant to this section shall be conducted by the Watauga County Planning Board within thirty (30) days after the date of the written appeal or request for a hearing.
 - (3)** The Planning Board shall make recommendations to the Board of Commissioners within seven (7) days after the date of the hearing on any plan.
 - (4)** The Board of Commissioners will render its final decision on any plan within five (5) days of receipt of the recommendations from the agency conducting the hearing.

- (5) If the Board of Commissioners upholds the disapproval or modification of a proposed plan following the hearing, the Person submitting the plan shall then be entitled to appeal the County's decision to the Commission as provided in G.S. 113A-61(c) and 15A NCAC 4B .0118(d).
- (6) In the event that a plan is disapproved pursuant to Chapter 8 Article V Section 9, the applicant may appeal the County's disapproval of the plan directly to the Commission.
- (G) Permit Validity: When work under an approved Sedimentation and Erosion Control Plan is not initiated within 3 years following the date of approval, the plan shall be deemed expired.

Section 2. Grading Permit

- (A) Applicability: To assure that land-disturbing activity undertaken in Watauga County does not result in accelerated erosion and sedimentation, no such land- disturbing activity on development 1 acre or greater in area shall take place until plans for controlling erosion associated with the activity have been reviewed and approved in accordance with the procedures set forth below.
- (B) Process Type. Administrative.
- (C) Required Application Information. An application for a Grading Permit shall be submitted in accordance with Article II Application Filing and Acceptance and the following provisions:
 - (1) Grading Permit Application
 - (2) Approved Sedimentation and Erosion Control Plan
 - (3) NCDOT driveway connection permit
 - (4) General Contractors Affidavit as to Status of Workman's Compensation.
 - (5) NC Lien Appointment
- (D) Public Notification: None Required.
- (E) Appeals: Appeals of decisions of the Ordinance Administrator shall be heard by the Board of Adjustment in accordance with Chapter 3.
- (F) Permit Validity: When work under an approved Grading Permit is not initiated within one (1) years following the date of approval, the permit shall be deemed expired.

Section 3 Floodplain Development Permit

- (A) Applicability. This section shall apply to all Special Flood Hazard Areas within the jurisdiction of Watauga County and within the jurisdiction of any other community whose governing body agrees,

by resolution, to such applicability. No structure or land shall hereafter be located, extended, converted, altered, or developed in any way without full compliance with the terms of this section and other applicable regulations.

(B) Process Type. Administrative – Ordinance Administrator

(C) Required Application Information:

(1) Floodplain Development Application

(2) A plot plan drawn to scale which shall include, but shall not be limited to, the following specific details of the proposed floodplain development:

a) the nature, location, dimensions, and elevations of the area of development/disturbance; existing and proposed structures, utility systems, grading/pavement areas, fill materials, storage areas, drainage facilities, and other development;

b) the boundary of the Special Flood Hazard Area as delineated on the FIRM or other flood map as determined in Chapter 9 Article II, Section 2, or a statement that the entire lot is within the Special Flood Hazard Area;

c) flood zone(s) designation of the proposed development area as determined on the FIRM or other flood map as determined in Chapter 9 Article II, Section 2;

d) the boundary of the floodway(s) or non-encroachment area(s) as determined in Chapter 9 Article II, Section 2;

e) the Base Flood Elevation (BFE) where provided as set forth in Chapter 9 Article II, Section 2; Article III, Section 3; or Article IV, Section 4;

f) the old and new location of any watercourse that will be altered or relocated as a result of proposed development; and

g) the certification of the plot plan by a registered land surveyor or professional engineer as determined to be necessary by the Floodplain Administrator.

(3) Proposed elevation, and method thereof, of all development within a Special Flood Hazard Area including but not limited to:

- a) Elevation in relation to NAVD 1988 of the proposed reference level (including basement) of all structures;
 - b) Elevation in relation to NAVD 1988 to which any non-residential structure in Zone AE or A will be floodproofed; and
 - c) Elevation in relation to NAVD 1988 to which any proposed utility systems will be elevated or floodproofed.
- (4) If floodproofing, a Floodproofing Certificate (FEMA Form 086-0-34) with supporting data, an operational plan, and an inspection and maintenance plan that include, but are not limited to, installation, exercise, and maintenance of floodproofing measures,
- (5) A Foundation Plan, drawn to scale, which shall include details of the proposed foundation system to ensure all provisions of this ordinance are met. These details include but are not limited to:
- a) The proposed method of elevation, if applicable (i.e., fill, solid foundation perimeter wall, solid backfilled foundation, open foundation on columns/posts/piers/piles/shear walls); and
 - b) Openings to facilitate automatic equalization of hydrostatic flood forces on walls in accordance with Chapter 9 Article IV, Section 2(D)(4) when solid foundation perimeter walls are used in Zones A, AE, and A I-30.
- (6) Usage details of any enclosed areas below the lowest floor.
- (7) Plans and/or details for the protection of public utilities and facilities such as sewer, gas, electrical, and water systems to be located and constructed to minimize flood damage.
- (8) Certification that all other Local, State and Federal permits required prior to floodplain development permit issuance have been received.
- (9) Documentation for placement of Recreational Vehicles and/or Temporary Structures, when applicable, to ensure that the provisions of Chapter 9 Article IV, Section 2, (F) and (G) of this chapter are met.

(10) A description of proposed watercourse alteration or relocation, when applicable, including an engineering report on the effects of the proposed project on the flood-carrying capacity of the watercourse and the effects to properties located both upstream and downstream; and a map (if not shown on plot plan) showing the location of the proposed watercourse alteration or relocation.

(D) Certification Requirements.

- (1) An Elevation Certificate (FEMA Form 086-0-33) is required prior to the actual start of any new construction.
- (2) An Elevation Certificate (FEMA Form 086-0-33) is required after the reference level is established.
- (3) A final as-built Elevation Certificate (FEMA Form 086-0-33) is required after construction is completed and prior to Certificate of Compliance/Occupancy issuance.
- (4) Floodproofing Certificates. If non-residential floodproofing is used to meet the Regulatory Flood Protection Elevation requirements, a Floodproofing Certificate (FEMA Form 086-0-34), with supporting data, an operational plan, and an inspection and maintenance plan are required prior to the actual start of any new construction. A final Finished Construction Floodproofing Certificate (FEMA Form 086-0-34), with supporting data, an operational plan, and an inspection and maintenance plan are required prior to the issuance of a Certificate of Compliance/Occupancy
- (5) If a manufactured home is placed within Zone A, AE, or AI-3D and the elevation of the chassis is more than 36 inches in height above grade, an engineered foundation certification is required in accordance with the provisions of Chapter 9 Article IV, Section 2(C)(2).
- (6) If a watercourse is to be altered or relocated, a description of the extent of watercourse alteration or relocation; a professional engineer's certified report on the effects of the proposed project on the flood-carrying capacity of the watercourse and the effects to properties located both upstream and downstream; and a map showing the location of the proposed watercourse alteration or relocation shall all

be submitted by the permit applicant prior to issuance of a floodplain development permit.

- (E) Public Notification. None Required.
- (F) Appeals: Appeals of decisions of the Ordinance Administrator shall be heard by the Board of Adjustment in accordance with Chapter 3.
- (G) Permit Validity: Floodplain Development Permits shall be valid for one (1) year following the date of issuance. Failure to initiate construction, or otherwise begin the permitted use, within this time period shall render the permit void.

Section 4. Watershed Development Permits

- (A) Applicability: This shall apply within the area designated as a Public Water Supply Watershed by the N.C. Environmental Management Commission and shall be defined and established on the most recent officially adopted by the NC Environmental Commission version of the map entitled, "Watershed Protection Map of Watauga County North Carolina".
- (B) Process Type: Administrative – Ordinance Administrator
- (C) Required Application Information:
 - (1) Watershed Protection Permit Application
 - (2) Two sets of a Site Plan as defined in Chapter 7 for Commercial or Multi-Family Projects.
- (D) Public Notification. None Required.
- (E) Appeals: Appeals of decisions of the Ordinance Administrator shall be heard by the Board of Adjustment in accordance with Chapter 3.
- (F) Permit Validity: An issued permit shall become null and void if the applicant fails to secure a building permit, record a final plat or initiate construction on the site within one (1) year after the date of approval. In addition, when a Watershed Development Permit is issued in association with a Preliminary Plan or Final Plat, the Watershed Development Permit shall expire if said plan expires, is significantly modified, or is revoked.

Article IX Subdivision Reviews

Applicability: Subdivision approval shall be required before the division of land (for any purpose) into two or more parcels, except as expressly exempted below.

Section 1. Actions Exempt from Subdivision Requirements.

The following shall not be considered a "subdivision" subject to review under this section:

- (A) The combination or recombination of portions of previously subdivided and recorded lots where the total number of lots is not increased and the resulting lots are equal to or exceed the standards of this UDO;
- (B) The division of land into parcels greater than ten acres where no road right-of-way dedication is involved;
- (C) The public acquisition by purchase of strips of land for water or sewer infrastructure or the widening or opening of roads; and
- (D) The division of a site in single ownership whose entire area is no greater than two acres into not more than three lots, where no road right-of-way dedication is involved and where the resultant lots are equal to or exceed the standards of this UDO.
- (E) The division of a tract into parcels in accordance with the terms of a probated will or in accordance with intestate succession under Chapter 29 of the General Statutes.

Section 2. Type of Subdivision

- (A) Minor Subdivision is a subdivision:
 - (1) that requires no variances and consist of not more than ten (10) lots. One phase of a phased development cannot be considered a minor subdivision unless the entire development is not more than 10 lots.
 - (2) Minor subdivisions require minor plat review and final plat approval.
- (B) Major Subdivision
 - (1) All other divisions of land not exempted by Section 1 or Section 2 (A).
 - (2) Major subdivisions require preliminary plat approval and final plat approval.
- (C) Planned Unit Development
 - (1) A "planned unit development" (PUD) is a tract of land under single, corporate, firm, partnership, or association ownership which is planned and developed as an integral unit. It is established in a single development operation or a definitely

programmed series of development operations according to an approved master development plan and a preliminary site plan.

(2) Planned Unit Developments require preliminary plat approval and final plat approval.

(D) Multi-Phased Development

(1) Development containing at least 25 acres;

(2) Subject to a master development plan with committed elements showing type and intensity of use for each phase; and

(3) Development permitting to occur in more than one phase.

(E) Family Subdivision

(1) The division of land solely among members of the same family, which shall include all lineal descendants or ancestors plus brothers, sisters, aunts, uncles, fathers-in-law, mothers-in-law, brothers-in-law, sisters-in-law, nieces, nephews and stepchildren by any method of transfer except where the parties contemplate development for resale, and where the resultant lots are equal to or exceed the standards of the county as shown in this chapter.

(2) Family subdivisions require final plat approval.

(F) Manufactured Home/Recreational Park Trailer Park

(1) The rental of any site or tract of land upon which three (3) or more manufactured homes or recreational park trailers occupied for dwelling or sleeping purposes are located.

(2) Leases of a term longer than ten (10) years shall be constructed as a sale of property.

Section 3. Minor Subdivision Plat Review

(A) Applicability: The procedure for approval of a minor subdivision plat is intended to simplify processing of routine small subdivisions with due regard to protection of the public interest.

(B) Process Type: Administrative – Ordinance Administrator

(C) Required Application Information: An application for a minor subdivision plat review shall be submitted in accordance with Article II Application Filing and Acceptance and the following provisions:

(1) Plat Submission Application

(2) 2 copies of Plat meeting the specifications in Chapter 18 Article V Section 6.

- (D) Public Notice: None Required.
- (E) Appeals: Appeals of decisions of the Ordinance Administrator shall be heard by the Planning Board in accordance with Chapter 3.
- (F) Permit Validity: The approval of the final plat by the Ordinance Administrator shall be on the condition that such plat be recorded in the office of the Register of Deeds within six (6 months) after such approval.

Section 4. Family Subdivision Review

- (A) Applicability: A final plat shall be required for all subdivisions that do not meet the definition of a minor subdivision as set forth in Article VI (A)(2).
- (B) Process Type: Administrative – Ordinance Administrator
- (C) Required Application Information: An application for a Family Subdivision Review shall be submitted in accordance with Article II Application Filing and Acceptance and the following provisions:
 - (1) Final Plat meeting the specifications in Chapter 18 Article V Section 3.
 - (2) Family Subdivision Document.
- (D) Public Notice: None Required.
- (E) Appeals: Appeals of decisions of the Ordinance Administrator shall be heard by the Planning Board in accordance with Chapter 3.
- (F) Permit Validity: The approval of the plat by the Ordinance Administrator shall be on the condition that such plat be recorded in the office of the Register of Deeds within six (6) months after such approval.

Section 5. Planning Board General Submission Requirements

All submissions to the Watauga County Planning Board are required to:

- (A) Submit two (2) paper copies of plat/plan along with other requirements as outlined in applicable Sections 6 – 11 by submission deadline.
- (B) Two weeks prior to meeting and subsequent to staff review an electronic copy will be provided to staff.
- (C) Eight (8) full size copies of plat will be submitted no later than 5:00 p.m. the Friday before the scheduled meeting.

Section 6. Major Subdivision Preliminary Plat Approval

- (A)** Applicability: A preliminary plat shall be required for all subdivisions that do not meet the definition of a minor subdivision as set forth in Article IX Section 2.
- (B)** Process Type: Administrative - Planning Board
- (C)** Required Application Information: An application for a preliminary plat review shall be submitted in accordance with Article II Application Filing and Acceptance and the following provisions:
 - (1)** Plat Submission Application
 - (2)** Master Plan (if applicable)
 - (3)** Preliminary Plat meeting the specifications in Chapter 18 Article V Section 3
 - (4)** Preliminary Plat Checklist (Chapter 18 Appendix E)
 - (5)** Developer Authorization Form if being developed by person(s) other than land owner(s).
- (D)** Public Notice: None Required.
- (E)** Appeals: Appeals of decisions of the Planning Board shall be subject to review at the instance of any aggrieved party by the Superior Court by proceedings in the nature of certiorari. The appeal to Superior Court must be filed within 30 days of the filing by the Board Clerk of the decision in the office of the Department of Planning & Inspections or the delivery of the notice.
- (F)** Permit Validity: Unless a final plat is submitted to the Planning Board within eighteen (18) months from the date on which the preliminary plat was approved, such action on the preliminary plat shall become void and of no effect, and will necessitate the resubmission of the preliminary plat to the Planning Board for consideration. Multi-Phased development as defined in Article IX Section 2 shall be vested for seven (7) years from the time of initial Master Plan approval.

Section 7. Major Subdivision Final Plat Approval

- (A)** Applicability: A final plat shall be required for all subdivisions that do not meet the definition of a minor subdivision as set forth in Article IX Section 2.
- (B)** Process Type: Administrative - Planning Board

- (C) Required Application Information: An application for a final plat review shall be submitted in accordance with Article II Application Filing and Acceptance and the following provisions:
 - (1) Plat Submission Application
 - (2) Final Plat meeting the specifications in Chapter 18 Article V Section 3.
 - (3) Final Plat Checklist (Chapter 18 Appendix F)
 - (4) Road Grade Certification by NC Licensed Surveyor.
 - (5) NCDOT approval of driveway connection. (if applicable)
- (D) Public Notice: None Required.
- (E) Appeals: Appeals of decisions of the Planning Board shall be subject to review at the instance of any aggrieved party by the Superior Court by proceedings in the nature of certiorari. The appeal to Superior Court must be filed within 30 days of the filing by the Board Clerk of the decision in the office of the Department of Planning & Inspections or the delivery of the notice.
- (F) Permit Validity: The approval of the final plat by the Planning Board shall be on the condition that such plat be recorded in the office of the Register of Deeds within ninety (90) days after such approval.

Section 8. Planned Unit Developments (PUD) Preliminary Plat Review

- (A) Applicability: A preliminary plat shall be required for all subdivisions that do not meet the definition of a minor subdivision as set forth in Article IX Section 2.
- (B) Process Type: Administrative - Planning Board
- (C) Required Application Information: An application for a PUD preliminary plat review shall be submitted in accordance with Article II Application Filing and Acceptance and the following provisions:
 - (1) Plat Submission Application
 - (2) Master Plan (if applicable)
 - (3) Preliminary Plat meeting the specifications in Chapter 18 Article V Section 3
 - (4) Preliminary Plat Checklist (Chapter 18 Appendix E)
 - (5) Developer Authorization Form if being developed by person(s) other than land owner(s).
 - (6) Adequate assurance that public or community water and sanitary sewer service.
- (D) Public Notice: None Required.

- (E) Appeals: Appeals of decisions of the Planning Board shall be subject to review at the instance of any aggrieved party by the Superior Court by proceedings in the nature of certiorari. The appeal to Superior Court must be filed within 30 days of the filing by the Board Clerk of the decision in the office of the Department of Planning & Inspections or the delivery of the notice.
- (F) Permit Validity: Unless a final plat is submitted to the Planning Board within eighteen (18) months from the date on which the preliminary plat was approved, such action on the preliminary plat shall become void and of no effect, and will necessitate the resubmission of the preliminary plat to the Planning Board for consideration. Multi-Phased development as defined in Article IX Section 2 shall be vested for seven (7) years from the time of initial Master Plan approval.

Section 9. Planned Unit Developments (PUD) Final Plat Review

- (A) Applicability: A final plat shall be required for all subdivisions that do not meet the definition of a minor subdivision as set forth in Article IX Section 2.
- (B) Process Type: Administrative - Planning Board or Ordinance Administrator
- (C) Required Application Information: An application for a PUD final plat review shall be submitted in accordance with Article II Application Filing and Acceptance and the following provisions:
 - (1) Plat Submission Application
 - (2) Final Plat meeting the specifications in Chapter 18 Article V Section 3.
 - (3) Final Plat Checklist (Chapter 18 Appendix F)
 - (4) Road Grade Certification by NC Licensed Surveyor
 - (5) NCDOT approval of driveway connection (if applicable).
- (D) Public Notice: None Required.
- (E) Appeals: Appeals of decisions of the Ordinance Administrator shall be heard by the Planning Board in accordance with Chapter 3. Appeals of decisions of the Planning Board shall be subject to review at the instance of any aggrieved party by the Superior Court by proceedings in the nature of certiorari. The appeal to Superior Court must be filed within 30 days of the filing by the Board Clerk of the decision in the office of the Department of Planning & Inspections or the delivery of the notice.

- (F) Permit Validity: The approval of the final plat by the Planning Board or Ordinance Administrator shall be on the condition that such plat be recorded in the office of the Register of Deeds within ninety (90) days after such approval.

Section 10. Manufactured Home/Recreational Park Trailer Parks Preliminary Plat Review

- (A) Applicability: No person, firm, or corporation shall commence construction or alteration of a manufactured home/recreational park trailer park within Watauga County without first securing the approval of a preliminary site plan from the Watauga County Planning Board.
- (B) Process Type: Administrative - Planning Board
- (C) Required Application Information: An application for a Manufactured Home/Recreation Park Trailer Park preliminary site plan review shall be submitted in accordance with Article II Application Filing and Acceptance and the following provisions:
 - (1) Plat Submission Application
 - (2) Site Plan drawn to scale including the following:
 - a) Items specified by AppHealthCare.
 - b) Sketch vicinity map of the park's location.
 - c) Proposed streets, street names, rights-of-way, roadway widths, approximate grades, curve radiuses, and proposed drainage facilities.
 - d) Landscaping, buffering, open space plans.
 - e) Designated parking areas.
 - f) AppHealthCare certificate indicating approval of the plan.
- (D) Public Notice: None Required.
- (E) Appeals: Appeals of decisions of the Planning Board shall be subject to review at the instance of any aggrieved party by the Superior Court by proceedings in the nature of certiorari. The appeal to Superior Court must be filed within 30 days of the filing by the Board Clerk of the decision in the office of the Department of Planning & Inspections or the delivery of the notice.
- (F) Permit Validity: Unless a final plat is submitted to the Planning Board within eighteen (18) months from the date on which the preliminary plat was approved, such action on the preliminary plat shall become void and of no effect, and will necessitate the resubmission of the

preliminary plat to the Planning Board for consideration. Multi-Phased development as defined in Article IX Section 2 shall be vested for seven (7) years from the time of initial Master Plan approval.

Section 11. Manufactured Home/Recreational Park Trailer Parks **Final Plat Review**

- (A)** Applicability: No person, firm, or corporation shall commence construction or alteration of a manufactured home/recreational park trailer park within Watauga County without first securing the approval of a preliminary site plan from the Watauga County Planning Board.
- (B)** Process Type: Administrative - Planning Board
- (C)** Required Application Information: An application for a Manufactured Home/Recreation Park Trailer Park final site plan review shall be submitted in accordance with Article II Application Filing and Acceptance and the following provisions:
 - (1)** Plat Submission Application
 - (2)** Site Plan drawn to scale including the following:
 - a)** Sketch vicinity map of the park's location.
 - b)** As-built streets, street names, rights-of-way, and drainage facilities.
 - c)** Designated parking areas.
 - (3)** NCDOT approval of driveway connection (if applicable).
- (D)** Public Notice: None Required.
- (E)** Appeals: Appeals of decisions of the Planning Board shall be subject to review at the instance of any aggrieved party by the Superior Court by proceedings in the nature of certiorari. The appeal to Superior Court must be filed within 30 days of the filing by the Board Clerk of the decision in the office of the Department of Planning & Inspections or the delivery of the notice.

Article X Variances

- (A)** Applicability: The appropriate Board may vary certain requirements of this Ordinance that will not be contrary to the public interest, where, owing to special conditions, a strict application of the provisions of these regulations, will, in an individual case, result in unnecessary hardship. The appropriate Board shall ensure that the

spirit of these regulations shall be observed, public safety secured, and substantial justice done.

(1) No change in permitted uses may be authorized by variance.

(2) It is not intended that variances be granted merely to remove inconveniences or financial burdens that the requirements of this ordinance may impose on property owners in general or to increase the profitability of a proposed development.

(3) In no event shall any Board grant a variance which would conflict with the North Carolina State Building Code or any other state code unless otherwise authorized by duly enacted applicable laws and regulations.

(B) Process Type: Quasi-Judicial

(C) Required Application Information: An application for a variance shall be submitted in accordance with Article II Application Filing and Acceptance and the following provisions:

(1) Variance Application

(2) Survey required for setback variance requests.

(3) Site Plan or other documentation relevant to describing applicant's request.

(D) Public Notice: Quasi-Judicial Hearing Level 1, 2, or 3 depending on applicable Board and Chapter variance is being requested from

(E) Appeals: Appeals of decisions by Quasi-Judicial Boards shall be subject to review at the instance of any aggrieved party by the Superior Court by proceedings in the nature of certiorari. The appeal to Superior Court must be filed within 30 days of the filing by the Board Clerk of the decision in the office of the Department of Planning & Inspections or the delivery of the notice.

Article XI Appeals of Administrative Decisions

(A) Applicability: This process is hereby established to provide an appeal process for parties aggrieved by any administrative order, requirement, decision or determination, made by an administrative officer charged with enforcing the provisions of this ordinance. An appeal of an administrative decision may be taken by any person aggrieved (or by their authorized agent) or may be taken by any officer, department, board or bureau of the county. Such an appeal

shall be made to the county within 30 days of the receipt of the written notice of decision from the county.

- (B) Process Type: Quasi-Judicial
- (C) Required Application Information: An application for an Appeal of Administrative Decision shall be submitted in accordance with Article II Application Filing and Acceptance and the following provisions:
 - (1) Application for Appeal of Determination
 - (2) Any other documentation relevant to applicant's request.
- (D) Public Notice: Quasi-Judicial Hearing Level 1 or 2 depending on applicable Board and regulations variance is being requested.
- (E) Appeals: Appeals of decisions by Quasi-Judicial Boards shall be subject to review at the instance of any aggrieved party by the Superior Court by proceedings in the nature of certiorari. The appeal to Superior Court must be filed within 30 days of the filing by the Board Clerk of the decision in the office of the Department of Planning & Inspections or the delivery of the notice.

Article XII Text Amendments

- (A) Applicability: The County may from time to time amend any part of the text of this ordinance. A request to amend the text of this ordinance may be initiated by the Board of Commissioners, Board of Adjustment, Planning Board, Director, or the general public.
- (B) Process Type: Legislative – Board of Commissioners
- (C) Required Application Information: An application for a Text Amendment shall be submitted in accordance with Article II Application Filing and Acceptance and the following provisions:
 - (1) Application for Text Amendment
 - (2) Any other documentation relevant to applicant's request.
- (D) Public Notice: A distinctive advertisement shall be placed by the County in a local newspaper of general circulation once a week for two successive calendar weeks, the first notice being published not less than ten days nor more than 25 days before the date fixed for the public hearing.
- (E) Appeals: A legislative decision of the Board of Commissioners with regard to a text amendment may be challenged by the filing of a declaratory judgement action in the Superior Court of Watauga County.

Article XIII Rezoning

- (A)** Applicability: Amendments to the Foscoe Grandfather Zoning Map shall be made in accordance with the provisions of this section. A request for a rezoning may be initiated by the Board of Commissioners, Board of Adjustment, Planning Board, Ordinance Administrator, or owner of land within the jurisdiction of the County.
- (B)** Process Type: Legislative - Board of Commissioners
- (C)** Required Application Information: An application for a Zoning Map Amendment shall be submitted in accordance with Article II Application Filing and Acceptance and the following provisions:
 - (1)** Application for Zoning Map Amendments
 - (2)** Any other documentation relevant to applicant's request.
- (D)** Public Notice: Mailed Notice. –The owners of affected parcels of land and the owners of all parcels of land abutting that parcel of land shall be mailed a notice of the hearing on a proposed zoning map amendment by first-class mail at the last addresses listed for such owners on the county tax abstracts. For the purpose of this section, properties are "abutting" even if separated by a street, railroad, or other transportation corridor. This notice must be deposited in the mail at least 10 but not more than 25 days prior to the date of the hearing.
- (E)** Appeals: A legislative decision of the Board of Commissioners with regard to a text amendment may be challenged by the filing of a declaratory judgement action in the Superior Court of Watauga County.

Article XIV Vested Rights

- (A)** Applicability: A vested right establishes the right to undertake and complete the development and use of a property on substantial expenditures as set forth in G.S. § 160D-108.
- (B)** Vested Right Runs with Property. A zoning vested right is not a personal right but shall attach to and run with the applicable property. After approval of a Site-Specific Vesting Plan, all successors to the original landowner shall be entitled to exercise such right while applicable.

(C) Types of Vested Rights. Vested Rights may be granted for the following development activities:

- (1) Site-Specific Vesting Plans**
- (2) Building Permits**
- (3) Multi-phased Developments**
- (4) Development Agreements**

(D) Establishment:

- (1) A vested right is established upon the valid approval, or conditional approval of a site-specific vesting plan. Such a vested right confers upon the landowner the right to undertake and complete the development and use of the property under the terms and conditions of the site-specific development plan, including any amendments thereto.**
- (2) The approving authority may approve a site-specific vesting plan upon such terms and conditions as may reasonably be necessary to protect the public health, safety and welfare.**
- (3) Notwithstanding paragraphs 1 and 2 above, approval of a site-specific vesting plan with the condition that a variance be obtained shall not confer a zoning vested right unless and until the necessary variance is obtained.**
- (4) A site-specific vesting plan shall be deemed approved upon the effective date of the approval authority's decision approving the plan or another date determined upon approval.**
- (5) The establishment of a vested right shall not preclude the application of overlay zoning that imposes additional requirements, but does not affect the allowable type or intensity of use, or ordinances or regulations that are general in nature and are applicable to all property subject to land use regulation by the County, including, but not limited to, building, fire, plumbing, electrical and mechanical codes. Otherwise applicable, new or amended regulations shall become effective with respect to property that is subject to a site-specific development plan upon the expiration or termination of the vested right in accordance with this Ordinance.**
- (6) A vested right obtained under this section is not a personal right, but attaches to and runs with the applicable property. After approval of a site-specific vesting plan, all successors to**

the original landowner shall be entitled to exercise such right while applicable.

- (E)** Application Requirements: An application shall be submitted in accordance with §9.2.2, Application Requirements. In order for a vested right to be established upon approval of a site-specific vesting plan, the applicant must indicate, at the time of application, that a vested right is being sought.
- (F)** Notice and Public Hearings: The County shall hold all required public hearings and give notice in accordance with Article IV Public Notification.
- (G)** Amendment of Plans: An approved site-specific vesting plan may be amended with the approval of the owner and the approval authority as follows: Any substantial modification must be reviewed and approved in the same manner as the original approval. Minor modifications as defined by Ordinance may be approved by the Ordinance Administrator.
- (H)** Continuing Review: Following approval or conditional approval of a statutory vested right, the Ordinance Administrator may make subsequent reviews and require approvals by the County to ensure compliance with the terms and conditions of the original approval, provided that such reviews and approvals are not inconsistent with the original approval. The County may revoke the original approval for failure to comply with applicable terms and conditions of the original approval or the applicable development regulations.
- (I)** Duration and Termination of Vested Right:
 - (1)** A. A vested right for a site-specific vesting plan remains vested for a period of two years unless specifically and unambiguously provided otherwise pursuant to paragraph B below. This vesting shall not be extended to any amendments or modifications to a site-specific development plan unless expressly provided by the approval authority at the time the amendment or modification is approved.
 - (2)** Notwithstanding the provisions of paragraph 1 above, the approval authority may provide that rights shall be vested for a period exceeding two years but not exceeding five years where warranted in accordance with all relevant circumstances, including, but not limited to, the size of the development, density and intensity of the development, economic cycles and market conditions. These determinations shall be in the sound

discretion of the approval authority at the time the site-specific vesting plan is approved.

- (3) A multi-phased development plan as defined in §12.2.3 is vested for the entire development with the land development regulations then in place at the time a site plan approval is granted for the initial phase of the multiple-phased development.
- (4) Upon issuance of a building permit, the expiration provisions of this section and the revocation provisions of G.S. § 160D-1115 and 160-1115 shall apply, except that a permit shall not expire or be revoked because of the running of time while a vested right under this section is outstanding.
- (5) A right vested as provided in this section terminates at the end of the applicable vesting period with respect to buildings and uses for which no valid building permit applications have been filed.

(J) Subsequent Changes Prohibited; Exceptions

A vested right, once established as provided for in this section, precludes any zoning action by the County that would change, alter, impair, prevent, diminish, or otherwise delay the development or use of the property as set forth in an approved site-specific development plan, except under one or more of the following conditions:

- (1) With the written consent of the affected landowner;
- (2) Upon findings, by ordinance after notice and an evidentiary hearing, that natural or man-made hazards on or in the immediate vicinity of the property, if uncorrected, would pose a serious threat to the public health, safety, and welfare if the project were to proceed as was contemplated in the site-specific vesting plan;
- (3) To the extent that the affected landowner received compensation for all costs, expenses, and other losses incurred by the landowner, including, but not limited to, all fees paid in considerations of financing, and all architectural, planning, marketing, legal, and other consulting fees incurred after approval by the County, together with interest as provided in the G.S. §160D-106;

- (4) Upon findings, by ordinance after notice and a evidentiary hearing, that the landowner or the landowner's representative intentionally supplied inaccurate information or made material misrepresentations which made a difference in the approval by the Board of Commissioners of the site specific vesting plan; or
 - (5) Upon the enactment or promulgation of a State or Federal Law or regulation that precludes development as contemplated in the site-specific vesting plan, in which case the County may modify the affected provisions, upon a finding that the change in State or Federal Law has a fundamental effect on the plan, by ordinance after notice and an evidentiary hearing.
- (K) Process to Claim Common Law Vested Right: A person claiming a common law vested right may submit information to substantiate that claim to the Ordinance Administrator, who shall make an initial determination as to the existence of the vested right. The decision of the Ordinance Administrator may be appealed to the Board of Adjustment. In lieu of seeking a determination or pursuing an appeal to the Board of Adjustment, a person claiming a vested right may bring an original civil action as provided in G.S. §160D-1403.1.



AppHealthCare
Caring for our Community

Watauga County Updates

FY26-27 Budget



10A NCAC 46.0201 –Mandated Services

- Adult Health
- Home Health*
- Dental Public Health
- Food, Lodging, and Sanitation
- Sanitary Sewage Collection, Treatment, and Disposal
- Communicable Disease Control
- Vital Records Registration
- Maternal Health
- Child Health*
- Family Planning
- Public Health Laboratory



If staff capacity decreases, we risk the impact of declining caseload, which will result in declining revenue in the following FY. This will further limit ability to serve clients into the future that could lose SNAP benefits.

- Pregnant women and children 0-5 years supplemental nutrition
 - District caseload 98%
 - Alleghany: 408 clients: 96%
 - Ashe: 593 clients: 99%
 - Watauga: 645 clients: 99%
 - Total funding \$345,217
 - Total cost \$471,679
 - Gap \$125,954



This program serves pregnant women and children insured by Medicaid referred by their healthcare provider. New referrals from providers are 26 each month (children) and 56 each month (pregnant women)

Program sustainability will depend on Medicaid funding for these services to Prepaid Health Plans and willingness to continue contract for the services.

- **Care Management for Pregnant women and children 0-5 years**
 - **6 FTE (1 RN, 5 SW)**
 - **Patients receiving care management per month:**
 - **60 children**
 - **94 pregnant women**
 - **Total funding \$434,438**
 - **Total cost \$465,110**

Measles



- ✓ Born before 1957
- ✓ Proof of immunizations -2 MMR
- ✓ Proof of immunity -titer

- [NC DHHS Measles Dashboard](#)
- [NC DHHS Measles Vaccination Dashboard](#)
- [NC Wastewater Monitoring](#)




AppHealthCare
Caring for our Community


Watauga County

FY2025-26


Watauga Primary Care Adult Visits FY23-24 thru 9/30/25




Watauga Child Health Visits FY 23-24 thru 9/30/25




Watauga Family Planning Visits FY23-24 thru 9/30/25




Watauga Behavioral Health Visits FY23-24 thru 9/30/2025




Watauga Medication Assisted Treatment FY23-24 thru 9/30/2025




Watauga Sexually Transmitted Infection Visits FY23-24 thru 9/30/2025




Watauga Tuberculosis Visits FY23-24 thru 9/30/2025



Watauga Breast & Cervical Cancer Control Program FY23-24 thru 9/30/2025



Watauga Nurses General Clinic FY 23-24 thru 9/30/2025






AppHealthCare
Caring for our Community


Funding Analysis

FY2025-26

APPHEALTHCARE ADOPTED FY 25-26 BUDGET




Maternal Health Expense- Revenue-Gap FY25-26




- Community need
- Payer mix
- Sliding fee must go to \$0
- Staffing levels
- DHHS funding from federal sources
- Contracts with local providers AND local hospitals for ultrasounds and visits at 32-36 weeks

Family Planning Expense, Revenue, & Gap FY25-26




- Community need
- Payer mix
- Sliding fee must go to \$0
- Self-report income must be accepted
- Staffing levels
- Visits are lengthy based on state requirements
- DHHS funding from 5 state & federal sources
- Title X funding cut to NC DHHS retroactively
- Title X at risk in future budgets

Child Health Expense-Revenue-Gap FY25-26




- Community need
- Payer mix
- Sliding fee must go to \$0
- Staffing levels
- DHHS funding from federal sources (CDC)

BCCCP Expense Revenue Gap FY25-26




- Awarded state and federal “slots” annually
- Staffing levels
- DHHS funding from federal sources (CDC)
- Contracts with local hospitals for diagnostic radiology

Tuberculosis Expense-Revenue-Gap FY25-26




- Community need
- Staffing levels
- DHHS funding from federal sources (CDC)
- Contracts with local hospitals for chest X-rays needed for diagnostic purposes
- Direct observed therapy
- Isolation/Quarantine housing

STI Expense-Revenue-Gap FY25-26




- Community need
- Quick access required
- Sliding Fee Scale to \$0
- Billing only with patient permission
- Staffing levels
- DHHS funding from federal sources (CDC)

Communicable Disease Expense- Revenue-Gap FY25-26




- Community need
- Staffing levels
- DHHS funding from federal sources
- Any legislative appropriation (none current)

Immunization Expense-Revenue-Gap FY25-26




- Staffing levels
- Community need
- Payer mix
- Clinic productivity
- Coding & Billing
- Vaccine cost
- Some needed for communicable disease prophylaxis
- Vaccines for Children

Dental Services Expense – Revenue- Gap FY25-26



- Community need
- Staffing levels
- Payer mix
- Clinic productivity
- Coding & Billing

Call Center adds capacity to customer service



Funding has not kept pace

- \$223,631 was written off for Sliding Fee Discounts and Bad Debt in 2025 for Watauga County services
- Medicaid funding represents >30% of total funding
- Combined County Allocations represent 10% of total funding
- FY24-25 ended in financial loss and FY25-26 loss expected

What's happening elsewhere?


- According to NC Local Health Department Accreditation Program, using data reported from 2019-2024, here is information about local appropriations (county funds) for LHD budgets:
 - Minimum: 24% (2024) (minimal range across 2019-2024)
 - Median contribution: 41% (ranging from 36% to 42%)
 - Maximum: 62% (2024); (ranging 78% (2020); 70% (2021-23))
- 14% receive less than 25% of their budget from local appropriations
- 57% receive 25-50% of their budget from local appropriations
- 29% receive >50% of their budget from local appropriations
- *AppHealthCare is 2nd to the BOTTOM of the appropriations among medium size health departments from 2019-2024 in local appropriations. Avg: 39%*

County funding is critical

- County allocations could be improved to better align with peers, even with accounting for savings in the district model (alongside other counties in the District)
- The graphic below shows the peer county average is \$2.7 million or \$2.3 million averaged with Watauga's current allocation

Watauga County	54,607	\$	1,080,000
Columbus County	50,453	\$	3,325,059
Hoke County	53,102	\$	2,243,375
Lenoir County	54,917	\$	2,677,575

NC DHHS Funding Amounts FY15-FY26



County advocacy is also critical

- County allocations in the district could be improved to better align with peers. Average contributions by each county would help alleviate the budget gap that exists in costs for required services.
- NC DHHS funding is important, and it is mostly federal funds. It is subject to specific services. NC remains 45th in public health funding according to America's Health Rankings.
- Public health services are largely dependent on Medicaid revenues. If HR1 (OBBA) leads to reduced Medicaid recipients, this may lead to larger needs and less funding.

What Now?


- Hold on filling most positions with attrition.
- Maintain minimum fund balance limit amount: 3 months' expenses
- Advocacy for funding needed public health services
- Identify additional funding in fees (clinical, environmental health)
- Preparing for major reduction in expenses



AppHealthCare

Caring for our Community

www.AppHealthCare.com



UNC Health Appalachian

Leading the way with innovative healthcare in the High Country



Presented by: Nathan Nipper, CEO

UNC Health Appalachian



Watauga Medical Center



Appalachian Regional Behavioral Health Hospital



Cannon Memorial Hospital



Heart & Vascular Center - Watauga



1,550+ Employees



**130+ Employed
Providers**



3 Non-Profit Hospitals



**41 Outpatient Services
and Locations**



**400,000 visits over
the last year**

UNC Health has 18 hospitals across the state


7 hospitals owned and 11 hospitals Managed Service Agreement/Other



Hospitals across the state (18)

Owned Hospitals (7)


Managed/JOA Hospitals (11)



Partnering with UNC Health

A 10 yr managed services agreement provides operational support and strategic direction to ARHS, fostering alignment and collaboration.

- + Access to Epic and Information Services
- + Managed Care Support
- + Professional Billing Services for Medical Offices
- + Organizational Compliance Support
- + Access to Benchmarking for Quality and Service
- + Government affairs support
- + Supply Chain and Pharmacy Services
- + Leadership Connectivity and Forums
- + Potential clinical alignment options



Partnering with UNC Health

What the partnership does not include:


- + Ownership of Assets
- + Governance Control
- + Operational Decision - Making
- + Recruitment of Providers or Staff
- + Compensation and Benefit Plans for Staff
- + Hospital Billing Services
- + Negotiation of Local Contracts
- + Support for Capital Improvement Projects
- + Philanthropic and Fundraising Resources




UNC Health Appalachian by the numbers...

2024
2025

VOLUMES





Stewardship



MARKET


2025 Patient Origin

From 2020 to 2025:
Volumes in our market (Ashe, Avery, Watauga) grew **15.5%**
Market share grew from **47% to 53%**
 40% of visits are from Watauga Co.




2025 Employee Residence

42% of employees reside in Watauga



Challenges: UNC Health Appalachian as a Rural Health System



Workforce & Culture	Access, Capacity & Operations	Market & Community	Financial & Policy Pressures	External & Environmental
<ul style="list-style-type: none"> • Recruitment and staffing • Provider demand vs. supply • High burnout risk • Retention pressure tied to wage / benefits escalation • Housing • Childcare 	<ul style="list-style-type: none"> • ED strain • Complexities of transportation, staffing, resources • Provider recruitment to support desired specialty advancement • Replacement capital to meet demands • Stewardship vs. Reputation 	<ul style="list-style-type: none"> • Expectations for Excellence • Slow rural population growth • Aging population • Social drivers of health exacerbate chronic conditions • Differing opinions of partnership alignment • Competition 	<ul style="list-style-type: none"> • Margin compression • Payer mix challenges • OBBB: <ul style="list-style-type: none"> ○ Lower rates ○ Reduced flexibility ○ Revenue cycle slowing ○ HASP uncertainty • Capital Constraints • CON protections are falling 	<ul style="list-style-type: none"> • Shifting political environment • Continued extreme weather risk • "Mountain Miles" • Infrastructure Vulnerabilities • Cybersecurity threats • Out of industry competition

Solution: Managing expectations and rethinking alignment.
What does our community want in a local health system?

What We're Building for Tomorrow

- + Delivering high -quality, patient -centered care
- + Increasing access to Primary Care and Specialty services
 - 2025: Women's, Pain Mgmt , Urology, Ortho/Spine, Telehealth
 - 2026: Regional providers, Cardiology, Pulmonology/Critical Care
- + Expanding and modernizing technology
 - ✓ da Vinci 5 Surgical Robot
 - ✓ Linear Accelerator
 - ✓ Coronary CT Angiography and imaging at Cannon Memorial
 - ✓ Master Facility Plan for growth and evolution with change
- + Exercising stewardship
- + Enhancing employee retention and transforming workplace culture
- + Developing workforce from high schools and local colleges
- + Rural Medical Education: Existing Family Medicine residency and Physician Assistant program, adding Psychiatry and General Surgery



UNC Health Appalachian

Leading the way with innovative healthcare in the High Country



Presented by: Nathan Nipper, CEO



Watauga County Emergency Services

184 Hodges Gap Rd, Suite D
Boone, NC 28607
Phone 828-264-4235
Fax 828-265-7617



Fire Marshal ♦ Emergency Management ♦ EMS ♦ Communications ♦ County Safety

2026 State of the Department

As we move into FY27, this is a great time to review what 2025 brought to the Department and where we go from here. This year saw continued incredible growth within the Department as we fully on-boarded EMS, completed major work in Helene recovery operations, and overall continued an operations tempo that only seems to increase each year. This document will highlight our successes, as well as opportunities for improvement, with every attempt to maintain brevity as we understand the sheer volume of work of the budget process. Emergency Services comprises five key mission areas: PSAP management (addressing, GIS, etc.), Communications, Fire Marshal, Emergency Management, and Emergency Medical Services (EMS). This document serves as a review of the past year and our goals for continuing to meet the mission.

Communications – Staffing

The Communications Division has continued to become busier as the County grows in population and tourism. The current staff breakdown is 2 Supervisors and 2 Assistant Supervisors, with the 14 remaining positions filling Telecommunicator I or II positions depending on level of training and experience. Additionally, the Communications Chief is a non-console position but fills in regularly.

The Division has made great strides with staffing this year with only 1 vacant position at the time of writing as one of our Assistant Supervisors went out on maternity leave and chose to take a non-shift work position with the Sheriff's Office. The Department has leveraged new recruitment tools and these recruiting efforts have paid off tremendously with the number of applications received.

The telecommunications staff completed hundreds of hours of training in either initial certification or continuing education to maintain their credentials and stay up to date on current



Watauga County Emergency Services

184 Hodges Gap Rd, Suite D
Boone, NC 28607
Phone 828-264-4235
Fax 828-265-7617



Fire Marshal ♦ Emergency Management ♦ EMS ♦ Communications ♦ County Safety

techniques and strategies. Even accounting for the increase from Boone, call volumes continued to outpace that addition with record numbers of calls received, EMD, and EFD calls. Staff is reviewing AI solutions to help manage the influx of spam calls that also inundate the facility; one supervisor in particular has reported 93 spam calls received just at her position in a shift. The performance of our telecommunicators is something to be very proud of and we are looking forward to bringing stability to our staffing in the coming year.

Communications - Infrastructure

This year has also seen great progress in our major tower infrastructure upgrade. Staff works closely with the North Carolina Highway Patrol who manages the State's VIPER radio system to plan for expanding and colocating their facilities with ours in a symbiotic relationship that saves significant cost while expanding the capabilities of both systems. A separate document detailing the progress made was presented at the annual budget retreat and is available for review.

Communications - 911/PSAP Services

Our 911 Services Coordinator, Emily Whichard, joined us this year after the departure of Paul Payne who took a position in the private sector. Emily has over 12 years of experience in 911 communications as a telecommunicator and supervisor. She has done an outstanding job learning this new facet of the PSAP world and has been a welcome addition to the team.

The position continues to work as a crossover employee between Communications and Emergency Management by assisting the Fire Marshal's staff on an as needed basis in running reports for inspection properties, locating property information following a fire, creating maps for fire chiefs, and providing backup support with answering the public's questions.



Watauga County Emergency Services

184 Hodges Gap Rd, Suite D
Boone, NC 28607
Phone 828-264-4235
Fax 828-265-7617



Fire Marshal ♦ Emergency Management ♦ EMS ♦ Communications ♦ County Safety

Fire Marshal

In the past calendar year, the Division investigated 21 different fires including four incendiary fire with three arrests made. These investigations can quickly escalate in man-hour commitment (336 additional hours for investigation beyond the initial fire response this year) if a more complex investigation is required such as evidence analysis by the State Crime Lab, fires that involve injuries or fatalities, criminal activity, or other factors. The Fire Marshal and Assistant Fire Marshal serve alternate weeks on-call for incidents (fires or other significant incidents) regardless of when they occur and I serve as backfill for incidents when they need coverage or if a major incident occurs.

The major piece to the incident response is support of the local fire departments. The FMO staff responded to incidents such as severe medical emergencies, technical rescue incidents, and other types of calls when either the primary agency wasn't available (for example responding as EMTs/Paramedics when EMS is already committed) or to supplement staffing on high acuity events. The FMO is also the oversight authority in the contracts for service with local fire departments and inspects all fire departments at a minimum of once a year for purposes of maintaining the service standard required by the NC Department of Insurance. This piece of our job is highly valued by the fire departments as we supplement staffing not only for the rural departments but also the Town of Boone on significant incidents. All credentialed firefighters attend training monthly with Boone Fire Department during business hours in order to keep skills sharp, learn new techniques, and build relationships that are invaluable on incidents. Staff in this Division completed 284 hours of training in 2025, a significant amount given the competing demands for time.



Watauga County Emergency Services

184 Hodges Gap Rd, Suite D
Boone, NC 28607
Phone 828-264-4235
Fax 828-265-7617



Fire Marshal ♦ Emergency Management ♦ EMS ♦ Communications ♦ County Safety

Incidents	
Structure Fires (Investigated)	21
Other Fire Incidents	108
Hazardous Materials	10
Weather (not counting Helene)	2
Assist EMS/Rescue	42
Total Incidents	162
Total Manhours	473

In addition to the responsibilities of investigating fires and responding to incidents, another primary responsibility of the Fire Marshal is fire prevention which includes fire inspections and education programs. Each year, the office assists with the National Fire Protection Association's Fire Prevention Week which occurs in October, however the fire prevention activities expand the entire month of October and beyond. A few examples of how the office assists the fire departments and community is through classroom education of students, operating the fire safety trailer, and many other outreach opportunities which last year accounted for approximately 207 manhours for different fire prevention programs actively engaged in the community.

The enforcement of the NC Fire Prevention Code is the primary way that the office saves lives every year. The Fire Marshal's Office is responsible for enforcement of the code within all of Watauga County with the exception of the municipal jurisdictions. The fire prevention code offers a required frequency of inspections for existing occupancies which the Division follows and the below table shows inspections both from the fire prevention requirements and permits pulled.



Watauga County Emergency Services

184 Hodges Gap Rd, Suite D
Boone, NC 28607
Phone 828-264-4235
Fax 828-265-7617



Fire Marshal ♦ Emergency Management ♦ EMS ♦ Communications ♦ County Safety

Inspections		Man Hours
Recurring including Re-inspections	992	1488
Vacant Premise Checks	75	112.5
Plan Review	86	258
Fire Systems Inspections	39	97.5
Carbon Monoxide Detectors	71	71
Miscellaneous	43	64.5
NCRRS Inspections	15	22.5
Foster Homes	14	21
Tent Inspections	27	40.5
Fireworks	7	28
Blasting Inspections	74	185
Total Inspections	1443	2388.5

These inspections take an average of a 1.5 hours for each visit based on the type of occupancy, but can sometimes take much longer over multiple visits to the premise. Additionally, the inspection process, especially for new construction, involves many additional hours of office time as the staff reviews code requirements, plans, precedents, previous rulings, and other best practices in order for the intent of the code to be met while also taking into account the needs of our business owners. To assist with the growing inspection load, the Commissioners approved a part-time non-regular budget to assist the Division in maintaining inspection currency and we currently have 1 fire inspector who work various schedules around their full-time employment.

To help recoup the financial investment made into this endeavor, the Commissioners approved a new fee schedule in FY23 and overall business owners have been receptive to this fee schedule. For the calendar year 2025, the office billed for \$21,410 in inspections, with an 89.8% collection rate (up from 68.1% in FY25 and 52.8% in FY24) on billed inspection fees for a total of \$19,230 collected. This



Watauga County Emergency Services

184 Hodges Gap Rd, Suite D
Boone, NC 28607
Phone 828-264-4235
Fax 828-265-7617



Fire Marshal ♦ Emergency Management ♦ EMS ♦ Communications ♦ County Safety

increase in collection rate is due primarily to two factors, the Department's administrative assistant has reached out for second attempts to collect the fees and we have implemented an electronic payment option which has increased payment rates as well. The permit fees (which are collected before the inspection for 100% collection rate) totaled \$11,269.70. This led to a total collection for calendar year 2025 of \$32,679.70 for the Division.

Emergency Management

The Emergency Management Division is how Watauga County meets the requirements of NC General Statute Chapter 166A which requires all 100 Counties to develop an emergency management program. In itself, emergency management is the all-hazard approach to managing incidents in the four phases of their occurrence. These phases include preparation for events we cannot stop, mitigation of the impacts of events where possible, response (either directly or through coordination of resources) to the event, and recovering from the event. The primary responsibility for local emergency management falls to me with close coordination with the Fire Marshal and other partners. In addition to local resources, we work very closely with NC Emergency Management (a division within the Department of Public Safety) as incidents are locally executed, state managed, and federally supported.

Staff this year worked on multiple projects and attended dozens of meetings to support networking, plan for events, and strengthen coordination efforts. A few examples of events supported include Appalachian State University football games and other athletic events as well as various festivals, fairs, and other similar events.

While there were many reported incidents, ones that bear mentioning are the multiple events to support law enforcement such as several missing persons and severe/winter weather events (outside



Watauga County Emergency Services

184 Hodges Gap Rd, Suite D
Boone, NC 28607
Phone 828-264-4235
Fax 828-265-7617



Fire Marshal ♦ Emergency Management ♦ EMS ♦ Communications ♦ County Safety

of Helene) that required close monitoring. Without the close relationships we have developed with those partners the management of these incidents would be much more difficult. While Watauga County received resources this year, we were also able to give resources to our surrounding counties through deployments of equipment or personnel. There were multiple examples of interagency coordination with our local and regional partners. These opportunities to give back where we can to the neighbors who are willing to help us are fulfilling, allow for additional opportunities to support Watauga County operations, and further solidify the relationships that are critical in times of need.

Emergency Medical Services

The largest growth of the Department this year was by far the transition of service from Watauga Medics, Inc. to the establishment of the EMS Division of Watauga County Emergency Services. The transition took the better part of the year, with the official start of service for EMS beginning on December 15th. The Department hired Juan Bowen to serve as our first EMS Chief over the EMS Division and he has hit the ground running to ensure our service is second to none.

From an operations perspective, the Department has on-boarded approximately 80 full-time and part-time staff to cover the 48 FTE shift positions across 4 shifts (24/72 schedule). As full-time staff numbers stabilize, part-time staff will be used primarily to fill in vacation, sick, and other times the shifts may not have a full-time employee present. Already, four of our new EMT hires have graduated paramedic school and are scheduled for their credentialing exams. Finally for operations, we are operating a pilot program with a BLS-level truck to take the load off of the 911 ALS system for convalescent transports. This truck is operated using part-time staff and operates during normal



Watauga County Emergency Services

184 Hodges Gap Rd, Suite D
Boone, NC 28607
Phone 828-264-4235
Fax 828-265-7617



Fire Marshal ♦ Emergency Management ♦ EMS ♦ Communications ♦ County Safety

business hours when the bulk of the transports happen. The truck also supports the 911 system by running Alpha and Omega level calls initially to further conserve ALS resources

Staff also hired Colby Hamby to serve as an Administrative Assistant/Billing Specialist with the Department and she has been an integral part of the transition not only with billing but with many other tasks as needed. Colby is our primary point of contact with EMS MC who serves as our third-party billing agency. From the transition date to the end of the calendar year, there were 168 trips with \$100,952.84 billed for service. An initial collection report will be available in February to begin reviewing collection rates and actual revenue received.

The biggest emphasis with the EMS transition has been to ensure that patient care is our number one priority. This does not mean we do not intend to be as efficient with the budget as possible. To that end, we are reviewing different facets of operations, logistics, and billing to make sure we are good stewards of the public's funds. Beginning with next year's report, a full breakdown of data will be available for the Division's operations. The future of EMS is bright as we work with community partners and invest in one of the most important services we can provide in Emergency Services.

Hurricane Helene

Everyone knows the impact that Hurricane Helene had on Watauga County, so this section is simply to briefly highlight the efforts of the Department in the recovery process. The Department has spent thousands of manhours this year in the recovery process through debris removal, assisting with Individual Assistance across many programs, private road and bridges concerns, managing our Public Assistance projects, coordinating with assisting agencies in making sure their PA projects are also completed, and many other facets of recovery. The County also retained Hagerty Consulting who has



Watauga County Emergency Services

184 Hodges Gap Rd, Suite D
Boone, NC 28607
Phone 828-264-4235
Fax 828-265-7617



Fire Marshal ♦ Emergency Management ♦ EMS ♦ Communications ♦ County Safety

been instrumental in navigating the complexities of the Public Assistance process, especially in the nuances of a Major Disaster that occurred during a federal government transition. While the bulk of the recovery has been completed, there are still many people and groups who still need assistance and the Department stands ready along with our partners to help navigate those needs.

Conclusion

As you can see, this year has been record-breaking with the hurricane and other events (even as I write this, we just finished an EOC activation for an ice storm), however that does not mean we are going to rest in 2026. Looking forward, we are well into the process of constructing a new Emergency Services headquarters, addressing issues found in our own threat/hazard analysis, further developing our personnel to handle anything that comes their way, and expanding our functional capacity in such areas as field communications, community paramedicine, and other tools for supporting our growing community. I hope this document serves to not only provide clarity on the operations of the Emergency Services Department, but also to raise questions that staff or I can answer regarding needs, capacity, or anything else to help budget staff make informed decisions this coming fiscal year.



WATAUGA ECONOMIC DEVELOPMENT
579 Greenway Rd; Suite 101
Boone, NC 28607
828-264-2225

www.boonechamber.com
E-mail: joe@boonechamber.com

MEMORANDUM

TO: County Manager, Board of Commissioners

FROM: Joe Furman

RE: Economic Development update for Board of Commissioners retreat

DATE: January 30, 2026

Thank you for providing time during the Commissioners' pre-budget retreat for an update on economic development activities being undertaken on behalf of Watauga County by the Boone Area Chamber of Commerce. David Jackson, President and CEO, and I will be presenting. While we are often the "faces" of these activities, the entire Chamber staff is involved, hence we attached the Chamber's annual report which recaps many of them.

During our time at the retreat we will report on several subjects, time permitting, including RISE Caldwell-Watauga workforce development program (information attached), housing efforts, childcare advocacy and fundraising, Chamber Foundation efforts and successes, possibilities for collaboration with ASU and NC Innovation, and our participation in exploration of formation of a new regional economic development organization.


Student Recruitment & Career Interest Trends

Thanks to our counselors and community partners RISE has visited all 6 high schools and has placements for Spring from each school



Students are showing interest across multiple career areas, with trends beginning to align with local employer demand.

These early signals help inform where to deepen employer engagement and where additional exposure may be needed.

WHS Senior Symposium & Career Fair



Get ready to explore all the amazing opportunities awaiting your child in high school! Join us for a fun and interactive evening where you can visit various tables and booths to learn about everything from exciting Career and College Promise programs, Advanced Placement courses, and diverse CTE pathways to Athletics, Arts, and comprehensive Student Support Services. It's your chance to gather essential information on High School Basics like GPA and credits, ensuring you have all the tips and tricks to help your rising 9th grader smoothly transition and achieve peak performance. We're excited to help your family make informed decisions as you navigate the climb to high school!



Progress Update



Over the past three months, R.I.S.E. has focused on building the foundation: student interest, employer outreach, educator partnerships, shared tools, and early placements.



Since November 2025

60+ student applications

30+ businesses engaged



Spring 2026 Cohort
32 Students!

- Caldwell County is in Week 3

- Watauga is in progress and starts in 2 weeks



Industries - 46% Healthcare,
15% Trades, 12% Hospitality, 10% Education
Manufacturing, Criminal Justice,
Marketing, & Banking





CALDWELL | WATAUGA
Regional Initiative for Skilled Employment

Executive Summary

Caldwell Community College and Technical Institute has recently launched **RISE (Regional Initiative for Skilled Employment) Caldwell-Watauga** to leverage its partnerships to provide more students in our area with work-based and experiential learning opportunities.

Based on successful work-based learning projects like Surry-Yadkin Works, this initiative will help ensure that residents of Caldwell and Watauga counties can take advantage of these types of learning experiences to develop the skills and resources necessary for success in our area's workforce.

Additionally, this initiative will provide a variety of supports to help eliminate barriers that prevent high school students and adult learners from attaining postsecondary education and workforce credentials. Helping more students pursue postsecondary credentials through work-based learning experiences will also help to advance the educational attainment goals of Caldwell and Watauga counties in support of myFutureNC's 2030 attainment targets and, in doing so, promote the economic vitality of this area and the state more generally.

The mission of Caldwell Community College and Technical Institute (CCC&TI) is to provide educational opportunities for the residents of Caldwell and Watauga counties, and this mission is advanced in large part through strong partnerships with our local school systems, economic development agencies, business and industry, and state partners such as myFutureNC.

Partner Agencies



Caldwell County
NORTH CAROLINA
Economic Development



Participation Targets: Year 1 - Year 3

Caldwell Participant Targets	Watauga Participant Targets	Total Participant Targets
AY 25/26: 25 students	AY 25/26: 20 students	AY 25/26: 45 students
AY 26/27: 50 students	AY 26/27: 40 students	AY 26/27: 90 students
AY 27/28: 75 students	AY 27/28: 60 students	AY 27/28: 135 students
3-year Total: 150 Participants	3-year Total: 120 Participants	3-year Total: 270 Students

RISE Caldwell-Watauga is led by an Executive Board composed of the college's president, the superintendents of Caldwell County and Watauga County school systems, and the economic development directors of Caldwell and Watauga counties.

This board provides oversight to the Executive Director, Career Pathways who facilitates work-based learning opportunities for students in each county by working with business and industry partners to develop pre-apprenticeships, apprenticeships, and internships.

The Executive Director also works with college and high school staff to promote and place students in work-based learning opportunities and coordinate these learning experiences with the educational programming provided by the college and its partnering school systems.

RISE Caldwell-Watauga will help close achievement gaps for underrepresented populations by lessening the financial barriers for students to pursue post-secondary education and credentials.

By including our local school systems, economic development agencies, and business and industry partners in every aspect of its implementation, this initiative is a cross-sector collaboration that encourages the buy-in and support of all key stakeholders.

By intentionally using the potential for work-based and experiential learning to engage and encourage students to pursue postsecondary education and credentials, this initiative takes an innovative approach to increasing educational attainment and supporting workforce development.

The college will utilize several strategies to achieve these participant targets, including:

- *Coordinated promotional efforts to make students aware of the benefits of participating in the initiative.*
- *Regular advising for participating students to ensure the successful completion of their work-based learning experiences.*
- *Financial supports for participating students, including stipends for travel and other expenses associated with participation in the initiative.*
- *Incentives for participating employers.*
- *Coordinated academic programming to provide participants with opportunities to develop professional and leadership skills that enhance their work-based learning.*

For more information contact:

Tara Brossa

Executive Director, RISE Caldwell-Watauga

Caldwell Community College and Technical Institute
2855 Hickory Blvd
Hudson NC 28638
tbrossa@cccti.edu

Find us online at:

<https://www.linkedin.com/company/rise-caldwell-watauga>

or

Scan the Code:





BOONE

AREA CHAMBER OF COMMERCE

2024-2025 ANNUAL REPORT



Connect. Advocate. Educate.

THE BOONE AREA CHAMBER OF COMMERCE

MISSION STATEMENT

To connect business and community partners, to enhance opportunities through advocacy and education, and support continued sustainable economic development within our region.

VISION STATEMENT

The Boone Area Chamber of Commerce is the catalyst for a diverse and engaged local economy, cultivating a thriving community that serves as the economic hub of Northwest North Carolina.

BOONE AREA CHAMBER STAFF

- David Jackson
President/CEO
- Carrie Henderson
Vice President of Events/Chief of Staff
- Natalie Harkey
Vice President of Finance
- Patrick K. Setzer
Vice President of Member Engagement
- Lindsay Cook
Director of Operations
- Emma Faulkner
Director of Communications
- Joe Furman
Director of Economic Development
- Ethan Dodson
Director of Development
- Reggie Hunt
Executive Director, Boone Area Sports Commission
- Jeannine Underdown Collins
Chamber Volunteer



David Jackson, Emma Faulkner, Ethan Dodson, Lindsay Cook, Joe Furman, Carrie Henderson, Natalie Harkey, Patrick Setzer

Table of Contents

Mission, Vision, Staff	2
Letter from the President/CEO & Board Chair	3
Year in Review	4
Awards & Media Statistics	5
BACC Foundation.....	6-7
Helping After Helene.....	8-9
Chamber Advocacy in Action	10-11
Celebrating Members	12-13
Chamber Events	14-15
Programs & Partnerships.....	16-17
Your Membership, Your Investment.....	18
Chamber Partners	19
Finances & Strategic Plan.....	20-21
Looking Ahead	22
Board & Committees	22-23

Dear community member,

On behalf of the Board of Directors and staff of the Boone Area Chamber of Commerce, thank you for your interest and support of our organization. Your investment makes it possible for us to serve as a catalyst for a diverse and engaged local economy, cultivating a thriving community that serves as the economic hub of Northwest North Carolina.

Through both the Chamber and the Boone Area Chamber of Commerce Foundation, we are able to deliver programs that connect members to business opportunities, expand leadership development, support workforce initiatives, and advocate for future investments in our community. These efforts have taken on greater importance as we continue the vital work of helping our community recover from the impact of Hurricane Helene. At the same time, we remain focused on addressing the long-term needs of the High Country—ensuring our region is not only resilient in the face of challenging times but also prepared for the opportunities that will shape our region for decades to come.

Thank you again for your interest in the Boone Area Chamber of Commerce and for supporting the work of our Foundation. We remain committed to strengthening the High Country's business community while protecting and enhancing the quality of life we enjoy in the High Country.

With appreciation,



A handwritten signature in black ink, appearing to be "David Jackson".

David Jackson
President/CEO
Boone Area Chamber of Commerce



A handwritten signature in black ink, appearing to be "Tara Brossa".

Tara Brossa
Chair
Boone Area Chamber of Commerce
Board of Directors



YEAR IN REVIEW

88

New member businesses/organizations during fiscal year 2024-25, up from 74 new members during the previous fiscal year.

30

Ribbon-cuttings between September 2024 and September 2025

3

of those were for #WNCOpenForBusiness

1

was with NC First Lady Anna Stein

5

were comebacks from Helene, including delayed openings or destroyed and rebuilt

1

was with a new neighbor in the Greenway Commons building

9

Business After Hours events

1091

Total *Business After Hours* Attendees

121

Average attendees per event

The largest Business After Hours event was at the **Original Mast General Store** celebrating their 45th anniversary, partnered with Blue Ridge Conservancy.

The second-largest event was at **Shipleigh Farms** in May. They were supposed to host in October of 2024, but it was delayed due to the hurricane.

2024 saw record-breaking attendance for **Spirit of Boone** and the event sold out in 2025.

AWARDS

DOGWOOD AWARD - DECEMBER 2024

The Chamber staff, along with FizzEd and Zionville Ramp Company were honored as Watauga County recipients of the 2024 Dogwood Award. This state-level award recognizes those who are working to improve the health, safety, and well-being of their fellow North Carolinians.



Ethan, Carrie, and David with Governor Josh Stein (then Attorney General) receiving the Dogwood Award.

CACCE COMMUNICATIONS AWARD - APRIL 2025

The Boone Area Chamber received a Communications Excellence Award for the 2024 Spirit of Boone Community Awards & 75th Anniversary Video, showcasing the resilience and vibrancy of our local businesses and leaders.

“After Helene, the Boone Area Chamber of Commerce has been instrumental in helping Boone’s economy get back on its feet. They understand that when our businesses and families succeed, our towns and cities thrive.”

- NC Governor Josh Stein

NC RURAL CENTER - APRIL 2025

President/CEO David Jackson attended the 2025 Rural Summit, hosted by the NC Rural Center, where he was honored with the Community Advocate of the Year award.

NC CHILD - CHAMPION FOR CHILDCARE

Chamber President/CEO David Jackson, Director of Operations Lindsay Cook, and Content Manager Emma Faulkner attended NC Child’s State of the Child conference in Raleigh — a day focused on the well-being of North Carolina’s children and the policies that shape their futures.

The Chamber was recognized at the evening reception as a 2025 Champion of Childcare alongside local Representative Ray Pickett. The award honored the Chamber’s continued advocacy efforts and direct community support.



Emma, David, and Patrick with CACCE Board Members receiving the CACCE Communications Award.

Social Media Statistics

Facebook Reach: 2.7 million
Instagram Reach: 575,900

Fun fact: Total social media reach = larger than the population of Iowa!

Facebook New Followers:
6,300 (Total : 9,700)
Instagram New Followers:
More than doubled
to 9,700

Constant Contact Email Statistics

Average 45% open rate (5% above industry average)

4,458 total email contacts



Left: David with Patrick Woodie, NC Rural Center President & CEO, receiving the Community Advocate of the Year award. Right: David with Representative Ray Pickett as Champion of Childcare recipients.



THE BOONE AREA CHAMBER OF COMMERCE FOUNDATION (BACCF)



The Boone Area Chamber of Commerce Foundation (BACCF) was created to solicit, manage, and distribute funds and resources for the future betterment of Boone, NC, and the Watauga County area. It was the vision of several community leaders to use the funds raised by

this organization to address critical issues like access to childcare for working parents, attainable housing for our growing workforce, and professional development and services for our small businesses.

The first major project funded by the foundation was an important research report about Childcare in Watauga County. This was published on April 13, 2024, and identified gaps in our childcare offerings and the impact on our workforce. As of September 27, 2024, the BACCF had raised just over \$10,000. Just a few days later on September 30, that number had been quadrupled. Donors from across the country saw the High Country in need and stepped up to give in droves to help address the immediate needs. What started as an ambitious yet modest branch of the BACC, was now accelerating into action to address the dire business needs of our community.

“We are deeply grateful to the Boone Area Chamber of Commerce for the incredible support we received following Hurricane Helene. Your hard work and generosity not only provided critical funding in a time of uncertainty but truly saved our new small business from the risk of shutting down, allowing us to continue to serve our community. We know the effort behind making these funds available was immense, and we are so thankful for the stability and hope it gave us as new business owners.”

- Erin Wonder & Tiffany Weitzen of Wonder Pelvic Therapy and Wellness

To our donors, all of whom gave to the BACCF or to other non-profits after Hurricane Helene, you provided immediate relief and set the stage for long-term recovery in our community. Many of you have strong ties to the High Country (we see you App State, CCCTI, and Watauga High School Alumni!) and we thank you for standing with us when it mattered most.

Our foundation will never rest on its laurels and will always be forward acting for our priorities. After distributing more than \$1m into the High Country, the need remains for more funding for small businesses and assistance for our childcare providers. Furthermore, we cannot let this disaster disrupt our workforce development programs and stifle how we advance our own community leaders.

You answered the call before and we ask that you do it again to help propel Boone forward in this upcoming important year.



David, Lindsay, and Ethan tabling at App State's Homegiving football game in October 2024.



BACC staff working together days after Hurricane Helene.

EARLY CHILDCARE DEVELOPMENT AND EDUCATIONAL FUND

The Foundation funded the **Pathways to Accreditation Program** run by the **Children’s Council of Watauga County**, benefiting 59 teachers and 12 center directors.

In October of 2024, the Foundation paid \$206,000 to eight licensed childcare centers in Watauga County to cover tuition for families for the month.

HOPE FOR THE HIGH COUNTRY SMALL BUSINESS RESILIENCY DISASTER GRANT PROGRAM

The Boone Area Chamber of Commerce Foundation, our 501c3 non-profit, has established the High Country Business Resiliency Disaster Grant to help small businesses in Watauga, Ashe, and Avery County recover from the crippling impacts of Hurricane Helene. These emergency grants, not loans, will provide necessary aid to the very businesses that have provided for our communities for generations. Grant applicants do not need to be members of the Boone Area Chamber of Commerce to receive funding.

Among the sobering realities we’ve recently experienced, the Federal Emergency Management Agency (FEMA), says 40% of small businesses do not reopen after a disaster. Thanks to the gifts and support of generous donors, business leaders, and longtime friends of the area, we are position to change that narrative and help sustain the small, independent businesses that make the High Country so unique.

TOTALS:
209 businesses impacted
\$978,500 total in grants given

COUNTY BREAKDOWN:
Ashe: 32
Avery: 45
Watauga: 144

**TOTAL FUNDS
DISTRIBUTED \$1,184,500**

Online:
940 gifts, \$219,290
\$233.54 avg gift
\$100 most frequent

ROUND 1
Concluded on November 4, 2024:
86 businesses, \$344,500

ROUND 2
Concluded on December 12, 2024:
76 businesses, \$114,000

ROUND 3
Concluded on May 13, 2025:
38 businesses, \$120,000
Mountain Bizworks Partnership
23 businesses, \$400,000

Other gifts:
117 gifts, \$1,512,892
\$8,019.10 avg gift
\$1,000 most frequent

1057 TOTAL DONORS

Quotes from Impacted Families:

“This tuition reimbursement has been such a gift to us! Our monthly budget is very tight, and this payment is one of our largest. It allowed us to give more to our friends in need immediately after Helene because we knew that we would have some room in the budget for it. Being able to give a little more was what we wanted to be able to do after such a difficult event for our community and helped lift our spirits in the process! Specifically, we were able to donate to a friend who lost his home in a way we would not have been able to otherwise! So grateful!!”

“We had damage to our home, requiring us to remove walls and restore a damaged oil tank. The waiver helped cover costs that insurance could not assist with.”

“Because of the Boone Chamber Foundation’s generous donation to cover our childcare expenses for the month of October, we were able to offset the expense of our car repairs. This would not have been financially possible for us without their support. THANK YOU SO MUCH”



Left: Lindsay with donated boots to pass out at the annual First Responders Breakfast at Daniel Boone Inn in November 2024. Middle: Board Member Halee Hartley with donations at Pinnacle Storage. Right: Encouraging notes for volunteers and those giving donations.

Helene Donations by the Numbers

SIX 53' TRAILERS OF SUPPLIES OVER A 6 WEEK PERIOD.

Containers held:

5 pallets of generators

- 3 pallets of tools
- 650+ blankets donated by Art of Living
- 10 pallets stacked 7' high with heaters
- 5 pallets stacked with fleece lined blankets
- 2 pallets of outdoor gear
- 20+ pallets of diapers, wipes, and formula - partnered with the Children's Council and Blue Ridge Peds to get them into the community
- 1 pallet emergency water filters
- 250 boxes of battery operated smoke/carbon monoxide detectors for those without power operating propane heaters
- 1 pallet of batteries
- 2 pallets of fuel
- 2 pallets MREs
- 4 pallets of hand sanitizer
- 1 pallet medical grade bandages, gauze, ambulatory aids, etc.



10,000 square foot warehouse donated for use by a community member (prefers to remain anonymous) - we used the space for 8 months



250+ pairs of boots given to first responders, community volunteers, and Helene survivors at the Annual First Responders Breakfast in November 2024



Carrie consults with a volunteer about oil for chainsaws.



The Summit Pickleball courts turned supply warehouse.

MEMBER SPOTLIGHTS: HELENE RECOVERY CHAMBER PARTNERSHIPS


Within several days after Hurricane Helene, we coordinated a partnership with a new Chamber member business that had just opened its operations in Boone: **Pinnacle Storage**. Through the generosity of Pinnacle, we were able to secure three climate-controlled storage units which we primarily used for disaster relief items collected through **WCNC-TV Charlotte** in the aftermath of Helene. WCNC-TV encouraged its viewers to donate new winter clothing items (coats, gloves, hats, socks, etc.) for children of Boone and surrounding High Country communities. More than 3,000 new winter clothing and accessory items were donated by WCNC-TV viewers, and these were delivered to our units at Pinnacle during the second and third week of October 2024, just several weeks following Helene.

During this same time period, **A Cleaner World** of Boone also donated several hundred gently used adult winter coats that we were able to keep in storage and distribute from our units at Pinnacle. As of late summer 2025, nearly all of our children's winter clothing items have been distributed to communities in Watauga, Avery, Ashe, Mitchell, Yancey counties. Further, we were able to work with volunteers and agencies in other areas of Western North Carolina, Eastern Tennessee, and parts of Kentucky to provide support and relief to families in need.

In addition to the storage space provided through Pinnacle, **The Summit Pickleball** in Boone partnered with the Chamber to serve as a large-scale supply warehouse in the weeks following the storm. Co-owners Crystal Smith and Grant Williams temporarily suspended operations and opened their 16,000-square-foot facility to house incoming relief supplies, quickly transforming the courts into a hub for collection and distribution. Donations arrived from across the region and beyond, and with the help of local volunteers, schools, churches, and partner organizations, essential items such as food, clothing, and medical supplies were organized and sent to communities most in need. This partnership not only expanded our storage and distribution capacity but also underscored the role of local businesses as critical anchors in community recovery.



Patrick at Pinnacle Storage with WCNC staff members.



CHAMBER ADVOCACY IN ACTION



The Chamber formed a **Hurricane Helene Long Term Recovery Group** dedicated solely to economic and business recovery in December of 2024. It functions as a subcommittee of the overall **Watauga Long Term Recovery Group**. In addition to the **Hope For The High Country Small Business Resiliency Disaster Grant** program of the Chamber Foundation, the LTRG-Business works to provide information, marketing, and advocacy. Among the first actions recommended by the group was to establish a “landing-page” for business resources including disaster preparedness, economic recovery, and regional coordination. The result is the **Watauga**



Forward page on the Chamber web site. The marketing efforts have primarily been to let prospective visitors know that Watauga County is accessible and open for business; one action was to run a full-page ad in the July issue of *Business North Carolina* magazine. Finally, members of the group have tirelessly advocated for needed assistance to NC and US elected officials as well as to the Blue Ridge Parkway regarding scheduling of repair work.




The Chamber contracted with Watauga County to provide administration and staffing for the County’s economic development function including the Watauga Economic Development Commission (WEDC). This was a return to a similar contractual relationship that existed mid-1990s to early 2000s. The WEDC was reorganized to better represent the entire county by including members appointed by

each of the five local government bodies. The WEDC established priorities of workforce housing, childcare, and workforce development, recognizing that shortages in those areas must be addressed in order to grow the local economy. Hurricane recovery became an overarching priority in October.

Chamber staff members have worked closely with Watauga Housing Council and Watauga Community Housing Trust to explore innovative approaches to address the housing shortage and have consistently communicated to state and local government the need to develop housing that is attainable by the work force. There is a gap in the housing inventory of homes that can be afforded by individuals/families with incomes that exceed 80% of the Area Median Income.

Chamber staff organized several conversations among members and others to discuss employer-led housing solutions and continues to explore possibilities. Childcare continues to be at the top of advocacy activities. In January, the Chamber hosted a childcare “legislative day” attended by elected officials and statewide childcare organizations during which information was shared and local facilities were visited.



Local and state legislatures touring childcare facilities in Watauga County for Childcare Legislative Day in January, 2025.



David Jackson participated in discussions in Raleigh, Atlanta, and Washington DC advocating for funding for child care. Throughout the year, Chamber staff hosted and led the Watauga myFutureNC Attainment Planning Committee. myFutureNC is a statewide non-profit organization established by the NC General Assembly with the mission of increasing the number of adults aged 25-44 who hold post secondary education degrees or certificates, thereby increasing the skills of the work force. Each County has a numerical goal to reach by 2030, Watauga is on-target to do so.



A by-product of the committee’s work was the establishment of a partnership between Watauga and Caldwell Counties’ economic development offices and public school systems with Caldwell Community College & Technical Institute to develop a work-based learning program that will provide opportunities for students to achieve degrees or certificates in the areas of hospitality, health care, and construction and other trades. The primary vehicles for the training will be pre-apprenticeships, and internships. Full launch of the program is scheduled for January, 2026.



STABLE WORKPLACES

STABLE Workplaces is an initiative in Watauga County with a vision of thriving workplaces sustained by a stable workforce. The acronym stands for “Staff Training and Business Leadership for Evolving Workplaces.”

The effort was born out of an event in August of 2022 which convened area agencies and partners alongside Watauga County business owners and employers to discuss the possibility of an ongoing collaborative effort toward more resources in the workplace. The August event built on years of data collection efforts to better understand challenges around workforce development through the perspectives of local stakeholders, including business leaders and staff.

STABLE Workplaces recognizes that the business sector is facing unprecedented recruitment and retention challenges alongside complex challenges among staff, such as family needs, mental health and substance use concerns, and lack of housing. STABLE is exploring ways to better deliver resources to the business sector and other employers through unified messaging, collaborative training efforts, toolkit development and incentivized participation.

In February 2025, the Chamber via the Foundation entered into a training cohort provided by **Family Forward NC** to explore local promotion family-friendly workplaces. This activity fits nicely into the framework of the STABLE initiative.



*Lindsey Sullivan,
AppHealthCare*

The cohort will be completed by the end of 2025 and will result in a strategy to incorporate the knowledge gained into STABLE.

If you have questions about getting involved, reach out to Lindsey Sullivan at info@stableworkplaces.org.

CELEBRATING MEMBERS




Our members are the heart of the Chamber. From ribbon cuttings to signature events and everything in between, we are proud to celebrate the businesses, people, and partnerships that strengthen our community.



Chamber Board, staff, and partners at the iconic Doc Watson Statue for a WNC is Open for Business Ribbon Cutting.

State Leaders in Boone



After paddling on the New River, the First Lady of North Carolina, Anna Stein, joined local outfitters and partners for a WNC Open for Business Week Ribbon Cutting.



Governor Josh Stein holding press conference at Boone Chamber office January 2025 to announce public-private partnership for small business recovery grants.



Lieutenant Governor Rachel Hunt at Vision NWNC



Secretary of Commerce Lee Lilley at Kid Cove in Boone



Sponsors and Summit Partners at the 2nd Annual Fairway Fore Foundation Golf Classic.

EVENTS & PROGRAMS

SPIRIT OF BOONE

September 12, 2024 | Grandview Ballroom, Appalachian State

WATAUGA COUNTY MEET THE CANDIDATES FORUM

September 16, 2024 | The Appalachian Theatre

STATE OF THE COMMUNITY

November 15, 2024 | The Beacon Butcher Bar

EVERGREEN VOICES:

WATAUGA WOMEN IN LEADERSHIP GALA

November 21, 2024 | The Inn at Crestwood

WATAUGA LEADERSHIP CHALLENGE

January 2025-April 2025

9TH ANNUAL HIGH COUNTRY ECONOMIC KICKOFF LUNCHEON

January 16, 2025 | Grandview Ballroom, Appalachian State

9TH ANNUAL 4 UNDER 40 AWARDS

March 26, 2025 | The Appalachian Theatre

FAIRWAY FORE FOUNDATION GOLF CLASSIC

April 30, 2025 | Jefferson Landing

VISION NORTHWEST NORTH CAROLINA

May 22, 2025 | Caldwell Community College & Technical Institute



Finalists and winners at the 9th Annual 4 Under 40 Awards.

PROGRAMS & PARTNERSHIPS

Watauga Leadership Institute (WLI)



The Watauga Leadership Institute (WLI) is a comprehensive leadership development program designed to meet our community's need for the active participation of informed and educated leaders. Graduates of WLI programs enjoy lifelong networking opportunities with over 300 program alumni. The Chamber contracts with **Ridgeline Leadership** and Dr. Jim Street to coordinate curriculum for all WLI programs.

Watauga Leadership Challenge

Watauga Leadership Challenge strikes a balance between understanding leadership and understanding the community. Participants will have the opportunity to interact with business and community leaders who are finding ways to bring people together for change. This class gives participants the opportunity to broaden their understanding of leadership and to see themselves as agents of change in their associations, their places of work, their community, and in their own lives.

Watauga Leadership Development

The Watauga Leadership Development course provides participants the opportunity to take a deeper dive into understanding leadership and the competencies required for effective leadership in work, community, and in life. The program focuses on authentic leadership and covers competencies that are critical in the leadership process.

Watauga Leadership Encore

This cohort-style course offers attendees the opportunity to expand their leadership knowledge, mindset, and skills. Each two-hour session will examine a specialty topic that builds off the core elements of the Watauga Leadership Institute curriculum, while encouraging the self-renewal of your guiding leadership principles.

Participating in Watauga Leadership was a transformative experience that deepened my understanding of community impact, strengthened my leadership skills, and connected me with inspiring local leaders. It is one of the best experiences of my professional career and I would highly recommend this program to anyone who wants a brighter and deeper understanding of the workforce in our community. - Chandler B.

Boone Business Exchange (BBE)

The Boone Business Exchange (BBE) is a business-to-business referral network that provides opportunities for its members to connect with other businesses, share best business practices, and generate referrals.

During each weekly meeting, each group member is provided the opportunity to introduce their business/service/product to the group and the group then breaks out into smaller groups where they can discuss specific referral opportunities one-on-one.



BBE provides opportunities for its members to connect with other businesses, share best business practices, and generate referrals. The group's emphasis is placed on building professional relationships with your fellow members and creating a solid network of referrals and resources for operating your business.

- 32 active member businesses/organizations
- 437 business referrals were made during BBE FY24-25
- Business referrals estimated value of \$1,212,793.78 during the 2024-2025 fiscal year

Watauga Women in Leadership (WWIL)



The mission of Watauga Women in Leadership (WWIL) is to empower High Country women in business and leadership in all stages of their careers. The organization presents events that support women through networking and educational speakers. We hope to enable and grow business, support and mentoring opportunities among professional women in the High Country.

Community outreach/programming is made possible by sponsorships from members/member organizations.

Programmatic themes and coffee connections are geared toward women, but all are welcome. Committee made up the following: Christy Gottfried, Amy Odom, Lindsay Cook, Suzy Greene, Nancy Crawford, Kayla Lasure, and Amanda White.



High Country Young Professionals (HC YoPros)



The High Country Young Professionals, affectionately dubbed “the High Country YoPros,” is a dedicated group of 200+ professional young adults under the age of 40 serving in various industries across the High Country. Born out of the desire to provide a supportive community for young working people, the group’s primary goal is to connect like-minded individuals. These connections foster trust, collaboration, and lasting community ties.

For those who are new to the workforce, recent graduates, or new residents in the High Country, the YoPros offer an invaluable way to establish roots both professionally and personally. Each month, the group highlights and partners with local businesses to host events, offering professional development and providing a direct link to the business community, helping members gain insights, mentorship, and opportunities to thrive in their careers and lives.



Boone Area Sports Commission (BASC)

The Boone Area Sports Commission (BASC) was created in 2019 to enhance the High Country of Northwest North Carolina as a sports tourism destination. The BASC is a 501c3 non-profit organization under the umbrella of the Boone Area Chamber of Commerce.

The BASC is a proud member of the Sports Events and Tourism Association, the premier trade association for the industry in the United States. The Boone and Watauga County Tourism Development Authorities provide a portion of the operational funding to the BASC along with industry contacts that have helped create awareness with event organizers across the State of North Carolina and the Southeast Region.



The BASC works with a variety of partners and all levels of sport. Our staff connects organizers with event-hosting resources, including hotel and restaurant partners, area attractions, and other services provided by members of the Boone Area Chamber of Commerce.



YOUR MEMBERSHIP, YOUR INVESTMENT

As a non-profit membership association, we strive to connect business and community partners and provide opportunities to enhance those connections through thoughtful programming and services focused on advocacy, education, and supporting sustainable economic development in our region. Your membership investment allows you to increase business visibility, build brand awareness, and promote services here locally and in the region. Moreover, your membership gives you access to a wide range of networking opportunities, business referral pathways, advertising and communications marketing platform, online career center listings, leadership development programming, and business advocacy network.

The members and work of the Chamber reflect the needs and values of our local and regional community. Our goal of building successful, sustainable, and long-term business relationships is directly related to Chamber member engagement. We take great pride in seeing our member businesses and organizations thrive and we continuously seek ways and avenues to further enhance our platform of programming, events, and services.

When you invest in a Boone Area Chamber of Commerce membership, you are also investing in your business and helping our community thrive.



SUMMIT PARTNERS



COMMUNITY PARTNERS

PLATINUM



GOLD



FINANCIAL INFORMATION & GOVERNANCE

Revenues

Event Income	\$113,109
General Income	\$203,499
Membership Income	\$433,651
WWIL Income	\$14,945
Special Projects	\$98,373
TOTAL	\$863,577

Expenses

Personnel Expenses	\$510,634
Professional Expenses	\$26,040
Operations Expenses	\$93,244
Special Projects/Events	\$133,354
Building Expenses	\$81,856
TOTAL	\$845,128

Board Rosters

BOONE AREA CHAMBER OF COMMERCE EXECUTIVE COMMITTEE

Tara Brossa, *Caldwell Community College & Technical Institute*
 Mark Gould, *Mast General Store*
 Seth Sullivan, *The Cardinal Food & Spirits*
 Ralph Polk, *DMJPS PLLC*

BOONE AREA CHAMBER OF COMMERCE BOARD OF DIRECTORS

Carrie Afanador, *Immigrant Connection of the High Country*
 Shirley Alexander, *Booneshine Brewing Company Inc.*
 Dr. Harry Davis, *Appalachian State University*
 Talia Freeman, *Beech Mountain Resort*
 Christy Gottfried, *Go Postal in Boone*
 Jim Hamilton, *NC Cooperative Extension*
 Halee Hartley, *Kid Cove*
 Angela Heavner, *180 Float Spa*
 Hal Hood, *LifeStore Bank*
 Nathaniel Johnson, *Granite Insurance*
 Brent Keith, *SkyLine/SkyBest*
 Angus Lamond, *Graystone Lodge*
 Nick London, *VPC Builders, LLC*
 Michael Maybee, *Watauga Opportunities, Inc.*
 Gary Moss, *Walker & Associates-Ameriprise Financial Services, LLC*
 Danielle Neibaur, *The Horton Hotel and Rooftop Lounge*
 Amy Odom, *Appalachian State University*
 Dr. Mark Poarch, *Caldwell Community College & Technical Institute*
 Lyndsi Richardson, *UNC Health Appalachian*
 Dr. Tierra Stark, *Watauga County Schools*
 Omer Tomlinson, *Spectrum Reach*
 Amanda White, *First Horizon Bank*

BOONE AREA CHAMBER OF COMMERCE FOUNDATION BOARD OF DIRECTORS

Chair: Tara Brossa, *Caldwell Community College & Technical Institute*
 Immediate Past Chair: Mark Gould, *Mast General Store*
 Chair Elect: Seth Sullivan, *The Cardinal Food & Spirits*
 Edward Hinson, *SkyLine/SkyBest*
 Amy Crabbe, *Women's Fund of the Blue Ridge*
 Chuck Eycler, *Peak Insurance Group*
 Dr. Leslie Alexander, *Watauga County Schools*
 Dr. Harry Davis, *Appalachian State University*
 Talia Freeman, *Beech Mountain Resort*
 Ralph Polk, *DMJPS*
 James Milner, *Appalachian Commercial Real Estate*

WATAUGA ECONOMIC DEVELOPMENT COMMISSION BOARD OF DIRECTORS

Chair: Pete Gherini, *Blowing Rock Town Council*
 Vice Chair: Lee Rankin, *At-Large Member*
 Weidner Abernathy, *Beech Mountain Town Council*
 Bob Bertini, *Seven Devils Town Council*
 Tim Hodges, *Watauga County Commissioner*
 Eric Plaag, *Boone Town Council*
 Christine Hendren, *Appalachian State University*
 David Jackson, *Boone Area Chamber of Commerce*
 Robin Miller, *Blowing Rock Chamber of Commerce*
 Suzanne Livesay, *At-Large*
 Virginia Wallace, *At-Large*

BOONE AREA SPORTS COMMISSION

Chair: Wright Tilley, *Explore Boone*
 Vice Chair: David Jackson, *Boone Area Chamber of Commerce*
 Secretary: Joe Furman, *Watauga County EDC*
 Tara Brossa, *Caldwell Community College & Technical Institute*
 Amy Davis, *Town of Boone Manager*
 Terese Fogleman, *Chick Fil A*
 Dustin Kerley, *Watauga County Schools*
 Keron Poteat, *Watauga County Parks & Recreation Director*
 Stephen Poulos, *Sports Organization*
 Crystal Smith, *The Summit Pickleball*
 Sarah Strickland, *Appalachian State University Athletics*

Committee Rosters

GOVERNMENT RELATIONS COMMITTEE

Co-Chairs: Mark Gould, Omer Tomlinson
 BACC Liaison: David Jackson
 EDC Liaison: Joe Furman
 Tim Hodges
 David Birtwistle
 Jay Harrill
 Scott Elliott
 Chuck Eyer
 David Martin
 Michael Maybee

WATAUGA WOMEN IN LEADERSHIP (WWIL)

Chair: Christy Gottfried
 BACC Liaison: Lindsay Cook
 Events: Carrie Henderson
 Amanda White
 Suzy Greene
 Amy Odom
 Nancy Crawford
 Kayla Lasure

COMMUNICATIONS COMMITTEE

Chair: Talia Freeman
 BACC Liaison: Emma Faulkner
 Carrie Afanador
 Yolanda Adams
 Angus Lamond
 Nick London

MEMBERSHIP COMMITTEE

Chair: Nathaniel Johnson
 BACC Liaison: Patrick Setzer
 Travis Critcher
 Hal Hood
 Kaylor Meade
 Gary Plaag

HIGH COUNTRY YOUNG PROFESSIONALS COMMITTEE

Chair: Danielle Neibaur
 BACC Liaison: Emma Faulkner
 Katy Willis
 Andrew Ortiz
 Morgan Sturgill

Nathaniel Johnson
 Trevor Moody

WORKFORCE DEVELOPMENT COMMITTEE

Chair: Tara Brossa
 EDC/BACC Liaison: Joe Furman
 Misty Bishop-Price
 Debra Fox
 Scott Hinkson
 Phil Pope
 Toni Deal
 David Koontz

BUSINESS DEVELOPMENT COMMITTEE

Chair: Heidi Ragan
 BACC Liaison: David Jackson
 EDC Liaison: Joe Furman
 Dr. Harry Davis
 James Milner
 Frank "Ham" Wilson
 Michelle Novacek
 Lane Moody

2025-2030 Strategic Plan

OPERATIONAL EXCELLENCE

Create operational excellence by maximizing our resources and evaluating procedures.

- Evaluate and refine the organizational structure and staff roles to expand executive capacity, maximize skillsets, improve efficiency, and create opportunities for long-term growth and advancement.
- Formalize an internal communication plan that ensures consistent messaging by providing staff with clear talking points for member questions and concerns.
- Develop a plan for the use of technology in Chamber-managed facilities and prioritize the training of staff on all systems.
- Establish a defined recruitment strategy for board members and committee members.
- Ensure committees are a valuable asset to the Chamber and have goals and work plans rooted in the organization's strategic priorities.
- Prioritize meaningful, professional development opportunities for Chamber staff and board members to foster growth, strengthen leadership, and enhance our organizational impact.
- Develop the Boone Area Chamber of Commerce Foundation as a reliable third revenue stream through donor relations and event creation, and by solidifying it as the front porch to the Chamber's economic development work within the region.

- Regularly assess and refine member benefits to ensure they remain relevant, valuable, and responsive to the evolving needs and priorities of the business community.
- Create a strategic and sustainable budgeting process with goals that balance dues and non-dues revenue streams.
- Emphasize Chamber board development – continue to evaluate clear roles and expectations for Chamber Board members.

ADVOCATE

Serve as the regional voice for business advocacy by leading important conversations that will move the region forward.

- Create a board-approved public policy agenda, formulated with input from Chamber and community members, that is effectively communicated to both audiences.
- Cultivate relationships with elected officials, candidates, and agency partners at all levels to advance a pro-business agenda and support policies that foster community and economic development.
- Lead and engage in strategic partnerships with regional and statewide organizations to amplify the collective voice of business and advance shared priorities across the High Country and North Carolina.
- Support and guide the business community in their individual advocacy efforts.

2025-2030 Strategic Plan

- Convene and participate in conversations related to continued Helene recovery efforts.
- Work towards community-wide infrastructure improvements to cultivate business growth.
- Celebrate and encourage entrepreneurial efforts in the High Country by connecting resource partners with business growth opportunities.
- Support and guide the business community in their individual advocacy efforts.

COMMUNITY

Actively contribute to developing a vibrant, sustainable community in the High Country.

Community development is business development.

- Remain as the leading voice for economic development across the High Country, bringing visibility, alignment, and momentum to local and regional initiatives.
- Connect the business community with key partners in education, government, and healthcare to align efforts and maximize impact.
- Stay engaged in conversations around critical issues – workforce development, childcare, attainable housing, disaster recovery, and access to essential services.
- Establish the Boone Area Chamber of Commerce Foundation as the secure funding mechanism for community development efforts that create lasting, measurable change.
- Continue to connect businesses, community, and partnerships through strategic communication, storytelling, and advocacy, serving as a voice for local businesses and sharing the stories that shape our community.
- Host intentional events and facilitate meaningful connections, ensuring members have access to timely, relevant information and opportunities to build lasting relationships.

EDUCATE

Build on the success of providing excellent educational opportunities that will provide

Chamber members with the knowledge, strategies, and tools to support their success.

- Encourage community and local government officials to prioritize Watauga County as a leader in educational attainment, early childhood policy, and workforce-centered curriculum alignment.
- Regularly assess the evolving business and community landscape to identify and deliver the

educational programming members need to adapt and thrive.

- Facilitate educational opportunities that build community resilience, including preparedness for economic disruption, natural disasters, and other critical events.
- Work with local education partners and utilize their expertise to enhance connections with the business community.
- Collaborate with local education partners to enhance workforce development through work-based learning and stronger business-to-classroom connections.
- Promote STABLE Workplaces as a framework for creating supportive, resilient, and retention-focused workplace cultures. Use it as a resource to guide employer education, workforce development conversations, and community standards.
- Continuously evaluate and strengthen existing learning and engagement opportunities such as Watauga Leadership Institute, High Country Young Professionals, Watauga Women in Leadership, and other programmatic outreach, with the goal of migrating Watauga Leadership Institute to operate under the Boone Area Chamber of Commerce Foundation.

CONNECT

Enhance value to members by connecting them to the Chamber, to one another, and to the resources and opportunities that support their success.

- Partnerships – define our role as a trusted convener that brings together key stakeholders for meaningful and impactful conversations.
- Foster alignment between members, community partners, and regional organizations by highlighting shared goals and encouraging collaborative strategies.
- Effectively communicate the value and benefits of membership, telling the story of our organization, our members, and our business community. Enable our members to become our best advocates.
- Emphasize personal chamber/member relationships by identifying, maximizing, and increasing touchpoints.
- Continue to evaluate effective ways to onboard and orient new members.

LOOKING AHEAD: 2026 AND BEYOND



Our staff and Board of Directors are dedicated to advancing the needs of our members. We have our eyes fixed on the horizon, eager to lead important conversations around long-term storm recovery, community development, accessible and affordable childcare and housing, while staying focused on emerging topics like transportation funding and workforce development. We also remain committed to developing the next generation of leaders for our region, and will use platforms like Watauga Leadership Institute, High Country Young Professionals, and Watauga Women in leadership to energize the voices of tomorrow.

As we move through the year ahead, we encourage you to stay actively involved in our organization in a way that works best for you and the needs of your business. Attend upcoming programs, take advantage of networking opportunities, provide resources for impactful initiatives, and lend your voice to the conversations shaping our community's future. Your participation ensures our organization continues to be a powerful advocate and trusted resource for our local business community.



579 Greenway Rd Suite 101
Boone, North Carolina 28607
United States
828.264.2225



Our Chamber



The Boone Area Chamber of Commerce is a private, not-for-profit 501(c)(6) organization, and is not affiliated with any municipal or county government. We are a Carolinas Accredited Chamber by CACCE and serve over 750 members across the High Country.

Caldwell Community College and Technical Institute
Watauga Campus Capital Request

Public Safety and Workforce Development Building- \$25 million

- Construction of 30,000 square feet Public Safety and Workforce Development Building to add/expand programs such as EMT/Paramedic, Law Enforcement, Fire/Rescue, additional healthcare programs, and additional technical programs requiring lab space.
- The Watauga Campus of CCC&TI currently has three modular units that are being utilized for classroom instruction/office space. These units are becoming extremely difficult to maintain and will be unusable in the near future, which will impede our ability to deliver critical programs for the community. The recommendation is to remove the modular buildings and construct a permanent facility to meet the current and future instructional programming needs of the region.

County Revenue

School Controlled Furniture & Equipment Budgets	\$57,000
CO Controlled District Wide F&E Budgets	\$39,000
Band/Orchestra Equipment	\$15,000
Arts Programs	\$15,000
Security Cameras	\$10,000
Classroom Presentation Technology	\$80,000
Chromebooks	\$300,000
Garage Equipment	\$10,000
Activity Bus	\$175,000
Vehicle Lift Replacement	\$70,000
HVAC/Sewer Pump Replacements	\$25,000
Maintenance Equipment	\$12,000
Aerial Man Lift on Tracks	\$55,000
Custodial Equipment	\$25,000
Mold Remediation	\$52,000
Discretionary	\$10,000
Total	<u>\$950,000</u>

Lottery Funds

Replace Kitchen/Cafeteria Equipment FY '27	80,000
Pavement & Sidewalk Repair FY '25	80,000
Door/Window Replacements FY '27	22,000
Gym Floor Replacements/Recoat FY '27	28,000
R&R Roof Replacement FY '25	45,000
R&R Roof Replacement FY '27	35,000
R&R Carpet & Tile Replacements FY '27	55,000
R&R Door Access Systems FY '25	60,000
HS Stage ??? If it will qualify? FY '27	60,000
	<u>465,000</u>

County Request from WCS Set-Aside Capital Funds

Baseball Turf	\$1,565,300
Softball Turf	\$669,000
Air Cond.@ GV	\$2,000,000
Electrical Upgrades for CC/ BR/Mabel	\$250,000
	<u>\$4,484,300</u>

County Revenue

School Controlled Furniture & Equipment Budgets	\$60,000
CO Controlled District Wide F&E Budgets	\$45,000
Band/Orchestra Equipment	\$15,500
Arts Programs	\$15,500
Security Cameras	\$10,000
Classroom Presentation Technology	\$80,000
Chromebooks	\$310,000
Garage Equipment	\$11,000
Activity Bus	\$185,000
HVAC/Sewer Pump Replacements	\$26,000
Maintenance Equipment	\$16,000
Custodial Equipment	\$31,000
Mold Remediation	\$55,000
Renovate 2-4 Hall Bathrooms - Blowing Rock	\$95,000
Discretionary	\$10,000
Total	<u>\$965,000</u>

Lottery Funds

Replace Kitchen/Cafeteria Equipment FY '28	85,000
Pavement & Sidewalk Repair FY '28	80,000
Door/Window Replacements FY '28	25,000
Gym Floor Replacements/Recoat FY '28	30,000
R&R Roof Replacement FY '28	80,000
R&R Carpet & Tile Replacements FY '28	55,000
R&R Door Access Systems FY '28	60,000
	<u>415,000</u>

County Request from WCS Set-Aside Capital Funds

Air Cond.@ CC/Mabel	\$4,000,000
	<u>\$4,000,000</u>

County Revenue

School Controlled Furniture & Equipment Budgets	\$60,000
CO Controlled District Wide F&E Budgets	\$45,000
Band/Orchestra Equipment	\$15,500
Arts Programs	\$15,500
Security Cameras	\$10,000
Classroom Presentation Technology	\$80,000
Chromebooks	\$310,000
Garage Equipment	\$11,000
Activity Bus	\$195,000
HVAC/Sewer Pump Replacements	\$26,000
Maintenance Equipment	\$16,000
Maintenance Vehicles	\$130,000
Custodial Equipment	\$31,000
Mold Remediation	\$45,000
Total	<u>\$990,000</u>

Lottery Funds

Replace Kitchen/Cafeteria Equipment FY '29	85,000
Pavement & Sidewalk Repair FY '29	85,000
Door/Window Replacements FY '29	25,000
Gym Floor Replacements/Recoat FY '29	32,000
R&R Roof Replacement FY '29	85,000
R&R Carpet & Tile Replacements FY '29	58,000
R&R Door Access Systems FY '29	60,000
	<u>430,000</u>

County Request from WCS Set-Aside Capital Funds

Air Cond.@ Blowing Rock	\$3,000,000
	<u>\$3,000,000</u>

County Revenue

School Controlled Furniture & Equipment Budgets	\$65,000
CO Controlled District Wide F&E Budgets	\$50,000
Band/Orchestra Equipment	\$16,000
Arts Programs	\$16,000
Security Cameras	\$10,000
Classroom Presentation Technology	\$80,000
Chromebooks	\$320,000
Garage Equipment	\$14,000
HVAC/Sewer Pump Replacements	\$28,000
Maintenance Equipment	\$18,000
Maintenance Vehicles	\$140,000
Custodial Equipment	\$33,000
Lacrosse Field Turf	\$215,000
Total	<u>\$1,005,000</u>

Lottery Funds

Replace Kitchen/Cafeteria Equipment FY '30	87,000
Pavement & Sidewalk Repair FY '30	85,000
Door/Window Replacements FY '30	25,000
Gym Floor Replacements/Recoat FY '30	35,000
R&R Roof Replacement FY '30	85,000
R&R Carpet & Tile Replacements FY '30	58,000
R&R Door Access Systems FY '30	60,000
	<u>435,000</u>

County Request from WCS Set-Aside Capital Funds

\$0

County Revenue

School Controlled Furniture & Equipment Budgets	\$65,000
CO Controlled District Wide F&E Budgets	\$50,000
Band/Orchestra Equipment	\$16,000
Arts Programs	\$16,000
Security Cameras	\$10,000
Classroom Presentation Technology	\$80,000
Chromebooks	\$320,000
Garage Equipment	\$15,000
HVAC/Sewer Pump Replacements	\$28,000
Maintenance Equipment	\$20,000
Maintenance Vehicles	\$65,000
Custodial Equipment	\$35,000
Lights on WHS Tennis Courts	\$63,610
Lacrosse WHS Netting	\$34,136
Track Repairs WHS	\$192,254
Total	<u>\$1,010,000</u>

Lottery Funds

Replace Kitchen/Cafeteria Equipment FY '31	87,000
Pavement & Sidewalk Repair FY '31	85,000
Door/Window Replacements FY '31	25,000
Gym Floor Replacements/Recoat FY '31	35,000
R&R Roof Replacement FY '31	85,000
R&R Carpet & Tile Replacements FY '31	58,000
	<u>375,000</u>

County Request from WCS Set-Aside Capital Funds

\$0